



- Run approximately 120 ft of trac pipe from city meter to flat top stove and fireplace. Gas
- valve will be installed after city meter. Line from city meter to attic will be ran expose in
- Galv. line from attic to fireplace will be ran exposed. Valve will be installed on line for fire
- place. Line for stove will drop in wall. Gas valve box will be installed under flat top stove.
- Permits will be pulled after estimate is approved.
- System will be put on test for inspection after passing system will be hooked up.