

49776

Revised

CAROL CHADWICK, P.E.

Civil Engineer

1208 S.W. Fairfax Glen

Lake City, FL 32025

307.680.1772

ccpewyo@gmail.com

www.carolchadwickpe.com

July 16, 2021

Ironwood Mobile Homes

Contact: Lisa Paul

386.754.8844/386.754.0190

familyhomecenter136@yahoo.com

**re: FHA FOUNDATION DESIGN – 269 SW BOBWHITE GLEN, FORT WHITE, FL
DONALD DAVIES**

I have reviewed the foundation plan and installation data of the above referenced property and find that the pier spacing and longitudinal tie-down locations and spacing, along with the other requirements, are in conformance with FBC 2020, 7th Edition for modular home installation.

The home is to be installed in a non-flood plan designated area, a minimum of 1,000 p.s.f. soil bearing and in accordance with the State of Florida 15C-1 regulations. The following onsite requirements are mandatory in addition to the manufacturer's installation instructions and the State of Florida 15C-1 regulations:

1. The stacked concrete block piers shall be stacked on approved ABS plastic pads per attached plan.
2. Structural skirting shall be installed after the foundation construction is completed.
3. Non-structural members such as axels, wheels, hitches and tongues shall be removed from the structure.

Should you have any questions, please don't hesitate to contact me.

Respectfully,

Carol Chadwick, P.E.



Digitally signed by
 Carol Chadwick
 DN: c=US,
 o=Unaffiliated,
 ou=A01410D0000
 01711349D4A7000
 1621F, cn=Carol
 Chadwick
 Date: 2021.07.16
 11:41:56 -04'00'



