



8/12 PITCH HOUSE  
 10/12 GARAGE/MST BDRM  
 1'-6" O/H

BEARING HEIGHT SCHEDULE

9'-1 1/8"

HANGER SCHEDULE  
 4 - HTU26

- NOTES:
- 1) REFER TO HB 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEER DRAWINGS FOR PERMANENT BRACING REQUIRED.
  - 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V105 FOR ALTERNATE BRACING REQUIREMENTS.
  - 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
  - 4) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
  - 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
  - 6) 5Y4Z TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
  - 7) BEAM/HEADER/INTEL (HDR) TO BE FURNISHED BY BUILDER.



**Builders FirstSource**  
 Jacksonville  
 PHONE: 904-772-6100 FAX: 904-772-1973

Bunnell  
 PHONE: 386-437-3349 FAX: 386-437-3994

Lake City  
 PHONE: 386-755-6894 FAX: 386-755-7973

Sanford  
 PHONE: 407-322-0059 FAX: 407-322-5993

Freeport  
 PHONE: 850-835-4541 FAX: 850-835-6835

Treasure Coast  
 PHONE: 772-468-8160 FAX: 772-468-8181

Tampa  
 PHONE: 813-621-9831 FAX: 813-628-8956

BUILDER: RICHARD KEEN	
LEGAL ADDRESS: LAMBERT RES.	
MODEL: CUSTOM	Revisions: Con. By:
DATE: 11-5-09	DESIGNED BY: K.L.H. Original Reference #: 318492
1st Level Job #:	2nd Level Job #: