



*CJ Custom Carpentry, Inc
222 SW Cross Pointe Ct
Lake City, FL 32024
386-754-6924 Office
CGC151322*

*Gray Collis
187 SW Vera Glen
Lake City, FL 32024*

Guest bath remodel:

Disconnect all plumbing, tear out and haul away existing tub, shower valve and trim, shower tile and substraight, bathroom floor tile, toilet, bath accessories, mirror, light, c-top.

Install new shower valve and trim, curb, new shower drain (drain is not moving), pre-slope shower floor, install new pan, install new hardibacker, waterproof shower walls, drywall repair where needed. Install new tile on shower walls with niche and shower floor. Install new tile on bathroom floor. Install new toilet, new c-top, faucet, new mirror, light, shower door and bathroom accessories. Customer to supply all fixtures.

Window replacement:

Replace 10 windows, size for size.