





STUD ANCHOR TABLE			
TYPICAL TRUSS UPLIFT	ANCHOR BOLT SPACING	SP4 / SPS SPACING	ALTERNATE SP4/SPS/SP6 SPACING
770 LB	48" O.C.	48" O.C.	NA
800 LB	48" O.C.	32" O.C.	NA
1270 LB	32" O.C.	16" O.C.	32" O.C.
1500 LB	32" O.C.	16" O.C.	16" O.C.
2200 LB	LTT01 W/ 50" X 7" WEDGE ANCHOR	NA	(2) HTS20 NAILED TO STUD PACK

NOTE: SP2 TOP & SP1 BOTTOM ALTERNATE FOR SP4/6


NOTE: MINIMUM ANCHOR BOLT SPACING FOR WALLS WITH A HEIGHT GREATER THAN 10'-0" AND LESS THAN 14'-0" SHALL BE 32" O.C.

W1 - SINGLE STORY EXT. WALL SECTION
SCALE: 1/2"=1'-0" REV-22-AUG-03




SYP #2 PT W/ POSTS			
TYPICAL POST UPLIFT	POST BASE ANCHOR	BETWEEN FLOOR STRAPPING	HEADER STRAPPING
555 LB	AB44 W/ (8)-10d & 4" x 8" ATTACHED TO 1" x 8" x 8" COUPLER THRU COLUMN A HEADER WITH 2" WAGNER & NUT TOP	(2) ST421 W/ (8)-10d EA	(2) ST421 W/ (8)-10d EA
720 LB	AB48 W/ (8)-16d & 4" x 8" ATTACHED TO 1" x 8" x 8" COUPLER THRU COLUMN A HEADER WITH 2" WAGNER & NUT TOP	(2) ST421 W/ (8)-10d EA	(2) ST421 W/ (8)-10d EA
2200 LB	AB44 W/ (12)-16d & 2" x 6" BOLTS & 4" x 8" ATTACHED TO 1" x 8" x 8" COUPLER THRU COLUMN A HEADER WITH 2" WAGNER & NUT TOP	(2) ST421 W/ (16)-10d EA	(2) ST421 W/ (16)-10d EA
2200 LB	AB66 W/ (12)-16d & 2" x 6" BOLTS & 4" x 8" ATTACHED TO 1" x 8" x 8" COUPLER THRU COLUMN A HEADER WITH 2" WAGNER & NUT TOP	(2) ST421 W/ (16)-10d EA	(2) ST421 W/ (16)-10d EA
HOLLOW COLUMN			
1500 LB	3" x 8" x 8" ATTACHED TO 1" x 8" x 8" COUPLER THRU COLUMN A HEADER WITH 2" WAGNER & NUT TOP		
2200 LB	3" x 8" x 8" ATTACHED TO 1" x 8" x 8" COUPLER THRU COLUMN A HEADER WITH 2" WAGNER & NUT TOP		


W12 - PORCH HEADER ANCHORS
SCALE: N.T.S. REV-18-JUL-03




F1 - STEM WALL FOUNDATION
SCALE: 1/2"=1'-0" REV-27-MAY-03




F12 - NON-BEARING STEP FOOTING
SCALE: 1/2"=1'-0" REV-10-FEB-03




F2 - PORCH SLAB
SCALE: 1/2"=1'-0" REV-22-AUG-03




F3 - GARAGE DOOR POCKET
SCALE: 1/2"=1'-0" 22-AUG-03



F4 - INTERIOR BEARING FOOTING
SCALE: 1/2"=1'-0" REV-22-AUG-03




F5 - INTERIOR BEARING STEP FOOTING
SCALE: 1/2"=1'-0" REV-22-AUG-03




W13-TYPICAL HEADER SIZING & STRAPPING DETAIL
SCALE: N.T.S. REV-22-AUG-03



F5 - INTERIOR BEARING STEP FOOTING
SCALE: 1/2"=1'-0" REV-22-AUG-03



W13-TYPICAL HEADER SIZING & STRAPPING DETAIL
SCALE: N.T.S. REV-22-AUG-03



F5 - INTERIOR BEARING STEP FOOTING
SCALE: 1/2"=1'-0" REV-22-AUG-03

Load Bearing Header Sizing Methods (BY BUILDER)			
1. Determine header size from FBC 2001, Tables 2308.3 A, B, & C, or 2308.5.	20	28	36
2. Use supplier published data or Southern pine span tables.	Span	NU	Span
3. For engineered lumber beams have suppliers engineer size beam.	2-2x4	3-6	1 3/2 1 2/10
Jack Studs and King Studs (BY BUILDER)	2-2x6	5-5	1 4-8 1 4-2
4. Lookup jack studs from FBC 2001, Tables 2308.3 A, B, & C, or 2308.5.	2-2x8	6-10	1 5-11 2 5-4
5. Use one jack stud for every 3000 lb. vertical load.	2-2x10	8-5	2 7-3 2 6-6
6. Total king plus jack studs = studs needed to be here if no opening was there.	2-2x12	9-9	2 8-5 2 7-6
Header Uplift Connections (BY BUILDER)	3-2x6	8-4	1 7-5 1 6-8
7. Calculate the uplift at each end of the header by summing the moments of all truss uplifts and dividing by the length of the header.	3-2x10	10-6	1 9-1 2 8-2
8. Select header connections from table below or mfg. catalog to connect header to stud (top connection) and stud to foundation (bottom connection).	3-2x12	12-2	2 10-7 2 9-5
	4-2x6	9-2	1 8-4 1 7-6
	4-2x10	11-8	1 10-6 1 9-5
	4-2x12	14-1	1 12-2 2 10-11

Uplift greater than 3885 lb requires engineering design.

N2-GENERAL NOTES:

FOUNDATION: FOR POINT LOADS GRATER THAN 5000 LB OR REPETITIVE TRUSS LOADS GRATER THAN 2000 LB PER TRUSS PROVIDE A THICKENED SLAB OR PAD FOOTING 1'-0" X 1 sq. ft. FOR EVERY 1000 LB OF BEARING REINFORCE WITH #5 @ 8" O.C. EACH WAY

CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS SHALL BE $F_c = 3000$ PSI. WHERE EXCESS WATER IS ADDED TO THE CONCRETE SO THAT ITS SERVICABILITY IS DEGRADED, THE ATTAINMENT OF REQUIRED STRENGTH SHALL NOT RELEASE THE CONTRACTOR FROM PROVIDING SUCH MODIFICATIONS AS MAY BE REQUIRED BY THE ENGINEER TO PROVIDE A SERVICEABLE MEMBER OR SURFACE. ALL CONCRETE SHALL BE VIBRATED. NO REPAIR OR RUBBING OF CONCRETE SURFACES SHALL BE MADE PRIOR TO INSPECTION BY AND APPROVAL OF THE ENGINEER, OWNER OR HIS REPRESENTATIVE.

WELDED WIRE REINFORCED SLAB: 6" x 6" W1 x 4 W1.4 W1.4 = 68KSI WELDED WIRE REINFORCEMENT FABRIC (W.W.M.) CONFORMING TO ASTM A185, LOCATED IN MINIMUM 1" FROM THE SLAB, SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACINGS NOT TO EXCEED 3'.

FIBER CONCRETE SLAB: CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT. FIBER LENGTHS SHALL BE 1/2 INCH TO 2 INCHES IN LENGTH. DOSAGE AMOUNTS SHALL BE FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. SYNTHETIC FIBERS SHALL COMPLY WITH ASTM C 1116. THE MANUFACTURER OR SUPPLIER SHALL PROVIDE CERTIFICATION OF COMPLIANCE WITH ASTM C 1116 WHEN REQUESTED BY THE BUILDING OFFICIAL.

CONTROL JOINTS: WHERE SPECIFIED, SAWIN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 302. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. THE LENGTH / WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1.5 AND TYPICAL SPACING OF CUTS TO BE 12FT. DO NOT CUT WMM OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)


REBAR: ASTM A 615, GRADE 40, DEFORMED BARS, $F_y = 40$ KSI. ALL LAPS SPLICES 40" DB (25" FOR #5 BARS); UNO. ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH ACI 315-95 WITH ACI 315-96 UNLESS NOTED OTHERWISE. ALL TENSION DEVELOPMENT LENGTHS SHALL BE 23 INCHES.

STRUCTURAL CONNECTORS: MANUFACTURERS AND PRODUCT NUMBER FOR CONNECTORS, ANCHORS, AND REINFORCEMENT ARE LISTED FOR EXAMPLE NOT ENDORSEMENT, AN EQUIVALENT DEVICE OF THE SAME OR OTHER MANUFACTURER CAN BE SUBSTITUTED FOR ANY DEVICES LISTED IN THE EXAMPLE TABLES AS LONG AS IT MEETS THE REQUIRED LOAD CAPACITIES. MANUFACTURER'S INSTALLATION INSTRUCTIONS MUST BE FOLLOWED TO ACHIEVE RATED LOADS.


ANCHOR BOLTS: A-307 ANCHOR BOLTS WITH MINIMUM EMBEDMENT AS SPECIFIED IN DRAWINGS BUT NO LESS THAN 7" IN CONCRETE OR REINFORCED BOND BEAM OR 15" IN GROUTED CMU.

WASHERS: WASHERS USED WITH 1/2" BOLTS TO BE 2" x 2" x 9/64"; WITH 5/8" BOLTS TO BE 3" x 3" x 9/64"; WITH 3/4" BOLTS TO BE 3" x 3" x 9/64"; WITH 7/8" BOLTS TO BE 3" x 3" x 5/16"; NO.

NAILS: ALL NAILS ARE COMMON NAILS UNLESS OTHERWISE SPECIFIED OR ACCEPTED BY FBC TEST REPORTS AS HAVING EQUAL STRUCTURAL VALUES.



W10 - TYPICAL GABLE END (X-BRACING)
SCALE: 1/2"=1'-0"



ALTERNATIVE TO BALLOON FRAMING IS GYPSUM CEILING DIAPHRAGM AS SPECIFIED IN THE "WOOD FRAME CONSTRUCTION MANUAL" (WFCM). SEE WFCM TABLE 3.13 AND FIGURE 3.6a. SHONE ABOVE. PROTECT GYPSUM FROM MOISTURE TO PRESERVE STRENGTH OF DIAPHRAGM.

NOTE: EXTEND RAT RUN BRACES GABLE TO GABLE OR A LENGTH EQUAL TO 1/2 OF GABLE WIDTH FOR ROOFS UP TO 7-12 AND 5/8 OF GABLE WIDTH OVER 7-12

W23 - GYPSUM CEILING DIAPHRAGM OPTION - GABLE END WALL
SCALE: N.T.S.

N5 - TRUSS UPLIFT CONNECTOR TABLE			
REV-25-AUG-03			
All connectors are Simpson Strongtie, uno. Select top and bottom connectors from this table or SST catalog to meet truss uplift. Use fasteners as specified.			
Uplift SPF	Uplift SYP	Truss Connector	To Plate / To Truss / Rafter
320	455	H5	4-8d / 4-8d
245	350	H5A	3-8d / 3-8d
535	600	H2.5A	5-8d / 5-8d
620	720	H10	8-10d x 1 1/2" / 8-10d x 1 1/2"
850	990	LTS12	8-8d x 1 1/2" / 8-8d x 1 1/2"
1245	1450	HTS20	10-10d or 12-10d x 1 1/2" / 10-10d or 12-10d x 1 1/2"
1265	1470	H16, H16-2	10-10d x 1 1/2" / 2-10d x 1 1/2"
1785	2050	LG2	14-10d Sinker / 16-16d Sinker
3655	4200	MGT	3/4" Thrd Rod / 22-10d
SPF	SYP	Strap Connector	To One Member / To Other Member
760	885	SP4	6-10d x 1 1/2" / N/A
865	1005	CS20	9-8d or 7-10d / 7-10d
1085	1265	LSTA18-24	7-10d / 7-10d
1170	1360	SPH4	12-10d x 1 1/2" / N/A
1420	1650	CS16	14-8d or 11-10d / 14-8d or 11-10d
SPF	SYP	Column Anchor	To Foundation / To Column / Truss
1160	1350	LTT19	3/4" x 16" AB / 8-16d Sinker
1985	2310	LTT131	3/4" x 16" AB / 8-16d x 1 1/2"
2385	2775	H02A	3/4" x 16" AB / 2-3/4" Bolts
3550	4175	HTT16	3/4" x 16" AB / 16-16d
1975	2300	ABU66	3/4" x 16" AB / 12-16d

Shade Supporting Trusses: The builder is responsible for gravity loads, but you should put an extra 2x4 stud under truss bearing location for each 3000 lb. of reaction. Check the minimum bearing requirements of the truss and top plate (SPF, F1=22p/2238p/2239p).

Manufacturer and product number are listed for example not endorsement. An equivalent device of the same or other manufacturer can be substituted for any devices listed in the example tables as long as it meets the required load capacities. Manufacturer's installation instructions must be followed to achieve rated loads. All connections exposed directly to the weather shall be hot-dipped galvanized after fabrication. Loads are increased for wind duration. Strapping uplift may be reduced proportionally to number of nails. See spec sheet for alternate nail sizes (10d=8d/16d, 10d=11d/8d/16d, 10d=12d/16d/16d). SPF=8d/5d/19p

N4-WIND LOAD DESIGN DATA			
REV-25-AUG-03			
(Wind loads are per FBC 2001, Section 1606.2 for enclosed simple diaphragm buildings with mean roof height less than 60' or the least horizontal dimension; not solid on the upper half of an unobstructed 60' high hill with >10% slope.)			
Basic Wind Speed	110 MPH		
Wind Exposure	B		
Wind Importance Factor	1.0		
Building Category	II		
Internal pressure Coefficient	N/A (Enclosed)		
Building not in the high velocity hurricane zone			
Building not in the wind-borne debris region			
Mean Roof Height	< 30 ft		
Roof Angle	10-45 degrees		
Components And Cladding Wind Pressures (FBC Table1606.2.8&C)			
Zone	Effective Wind Area (ft ²)	Transverse	Longitudinal
10	100		
4	21.8	23.6	18.5
5	21.8	29.1	18.5
22.6			
Total Shear Wall Segments	Transverse	Longitudinal	
Required	46.0'	27.0'	
Actual	119.9'	67.8'	
All exterior walls are type II shear walls			
ACTUAL SHEAR WALL length is the total of all wall segments with full height sheathing and width to height ratio greater than 1:3.5 (plus special shear wall segments if noted) REQUIRED SHEAR WALL length is from WFCM 2001, table 3.17A & 3.17B with table 3.17E adjustment for type II shear wall (or equivalent calculation)			

N3-WINDLOAD ENGINEER'S SCOPE OF WORK: The wind load engineer is engineer of record for compliance of the structure to wind load requirements of FBC 2001, Section 1606. If trusses are used, the wind load engineer is not engineer of record for the trusses and did not design the trusses or delegate to the truss designer.

BUILDER'S RESPONSIBILITY: The builder and owner are responsible for the following, which are specifically not part of the wind load engineer's scope of work.

- * Confirm that the foundation design & site conditions meet gravity load requirements (assume 1000 PSF bearing capacity unless visual observation or soils test proves otherwise)
- * Provide materials and construction techniques, which comply with FBC 2001 requirements for the stated wind velocity and design pressures.
- * Provide a continuous load path from roof to foundation. If you believe the plan omits a continuous load path connection, call the wind load engineer immediately.
- * Verify the truss engineering includes truss design, placement plans, temporary and permanent bracing details, truss-to-truss connections, and load reactions for all bearing locations.
- * Select uplift connectors, walls, columns, and footings based on truss engineering bearing locations and reactions; including interior bearing walls.
- * Size headers for gravity loads; headers sized by the builder for gravity loads will also satisfy wind loads.

DOCUMENT CONTROL AND PRIORITY: Structural requirements on S-1 control unless the building code or architectural sheets have more stringent requirements. Non-structural requirements on architectural sheets control. Specific requirements take precedence over general requirements. Revision control is by the latest signature date and is the responsibility of the builder.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

DIMENSIONS: Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

WINDLOAD ENGINEER: Mark Disoway, PE No.53915

LIMITATION: This design is valid for one building, at specified location. This drawing is not valid for construction unless raised seal is affixed.

REV-27-JUL-04

WINDLOAD ENGINEERING

"EVERYTHING YOU NEED FOR YOUR BUILDING PERMIT"

Mark Disoway P.E.

POB 868, Lake City, FL 32056 Phone: (386) 754-5419

Fax: (386) 754-6749 Email: windloadengineer@bellsouth.net

Location: Lot #5 Russwood Estates S/D, Lake City, FL

Unit 3 Lot #6 208 SW Bethany Place

Columbia County, Lake City Florida 32024

Builder: John Johnson Construction

Designer:

Approved: FLPE#53915

Revisions:

Sheet S-1 of 5 Sheets

Windload Engineering

Job # 509063