

CAROL CHADWICK, P.E.

Civil Engineer

1208 S.W. Fairfax Glen

Lake City, FL 32025

307.680.1772

ccpewyo@gmail.com

www.carolchadwickpe.com

January 20, 2025

Curtis Jones

CJ Custom Carpentry

239.571.0699

permits@cjcustomcarpentry.com

re: ELEVATION LETTER – 545 SW LEGION DRIVE, LAKE CITY, FL

As requested, I inspected the building site for the proposed construction at the above referenced site. Per the flood report by SRWMD, there are no wetlands or floodplains on the site. Refer to the attached site plan by others.

The topography of the site drains to the northeast. The finished floor elevation of the home shall be 8" above the adjacent ground for the entire perimeter of the foundation, except driveways and sidewalks which must be flush with the finished floor elevation. The finished floor of the home will be below required elevation of one foot above the adjacent road.

I certify that the minimum finished floor elevation listed above will protect the structure against water damage from a base flood event, as defined in Article 8 of the Land Development Regulations.

Should you have any questions, please don't hesitate to contact me.

Respectfully,

Carol Chadwick, P.E.

attachments: SRWMD Flood Report & site plan sketch

This item has been digitally signed and sealed by Carol Chadwick, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

CC Job #FL25021