


**INDEX OF SHEETS**

SHEET NO.	DESCRIPTION OF SHEET CONTENTS
A-1	BASIC DATA, DINING ROOMS LAYOUT AND LIFE SAFETY PLAN, FINISHING SCHEDULE, SHEET INDEX
A-2	EXISTING BUILDING BUILD-OUT PLAN / KITCHEN EQUIPMENT PLAN, KITCHEN EQUIPMENT SCHEDULE, ACCESSIBLE RESTROOM DETAILS
A-3	EXISTING BUILDING BUILD-OUT PLAN / KITCHEN EQUIPMENT PLAN, KITCHEN EQUIPMENT SCHEDULE, ACCESSIBLE RESTROOM DETAILS
A-4	UNIT DESIGN DATA, PROJECT LOCATION MAP, NEW ENTRY, CANOPY PLANS, SECTIONS, DETAILS

- FIRE RESISTANCE:**  
 BUILDINGS EXISTING COMMERCIAL  
 PROJECT IS WITHIN FIRE DISTRICT  
 STRUCTURE WILL HAVE AN APPROXIMATE AUTOMATIC FIRE SPRINKLER SYSTEM  
 \*ADJUST TRAVEL DISTANCE TO POINT OF DISCHARGE IS 20'
- EXIT TRAVEL DISTANCE TO POINT OF DISCHARGE IS 20'**
- 0 EXTERIOR BEARING WALLS
  - 1 INTERIOR WALLS
  - 2 SEPARATION WALL
  - 3 COLLUMS
  - 4 BEAMS, GIRDERS, TRUSSES
  - 5 FLOOR SYSTEM
  - 6 ROOF AND ROOF / CEILING
  - 7 ASSEMBLIES

- BUILDING CODE SUMMARY:**  
 REFER TO APPLICABLE 2006 FLORIDA BUILDING CODES  
 WITH LATEST AMENDMENTS 2006 NEC, AND 2006 IRC AND  
 2011 INTERNATIONAL BUILDING CODES BY REFERENCE,  
 AND 2011 FLORIDA ACCESSIBILITY CODE
- EXISTING BUILDING ALTERATION LEVEL: 3**
- USE DESCRIPTION:** COMMERCIAL, A-1 RESTAURANT
- OCCUPANCY CLASSIFICATION:** A-1 RESTAURANT
- CONSTRUCTION TYPE:** TYPE III (5.0" CMU EXTERIOR WALLS)  
 TYPE II (5.0" CMU INTERIOR WALLS)
- ROOF LOADS:** 20 PSF UNIFORM, 160 PSF CONCENTRATED
- SOIL BEARING:** 2,000 PSF
- FLOOD ZONE:** X
- FLORIDA ACCESSIBILITY:**
- 100% ADA COMPLIANT YES
  - AN ACCESSIBLE ENTRANCE YES
  - RAMP TO ENTRANCE YES
  - ACCESSIBLE REST ROOMS YES



**DINING ROOMS SEATING LAYOUT AND LIFE SAFETY PLAN**  
 SCALE: 3/16" = 1'-0"

**LIFE SAFETY LEGEND**

- ➔ PATH OF EXIT TRAVEL
- ➔ POINT OF EXIT DISCHARGE IS 15'
- ➔ POINT OF EXIT DISCHARGE IS 20'
- ➔ EXIT DOOR
- ➔ EXIT SIGN
- ➔ EMERGENCY LIGHT
- ➔ FIRE EXTINGUISHER
- ➔ SMALL MOUNT WITH SIGNAGE


**NOTE**  
 STRUCTURE WILL HAVE AN APPROXIMATE AUTOMATIC FIRE SPRINKLER SYSTEM

**DINING ROOMS SEATING SCHEDULE**

MARK	NO. OF SEATING UNITS	SEATING CAPACITY	NUMBER OF SEATING UNITS	TOTAL SEATING CAPACITY
1	1	2	2	2
2	1	2	2	2
3	1	2	2	2
4	1	2	2	2
5	1	2	2	2
6	1	2	2	2
7	1	2	2	2
8	1	2	2	2
9	1	2	2	2
10	1	2	2	2
11	1	2	2	2
12	1	2	2	2
13	1	2	2	2
14	1	2	2	2
15	1	2	2	2
16	1	2	2	2
17	1	2	2	2
18	1	2	2	2
19	1	2	2	2
20	1	2	2	2
21	1	2	2	2
22	1	2	2	2
23	1	2	2	2
24	1	2	2	2
25	1	2	2	2
26	1	2	2	2
27	1	2	2	2
28	1	2	2	2
29	1	2	2	2
30	1	2	2	2
31	1	2	2	2
32	1	2	2	2
33	1	2	2	2
34	1	2	2	2
35	1	2	2	2
36	1	2	2	2
37	1	2	2	2
38	1	2	2	2
39	1	2	2	2
40	1	2	2	2
41	1	2	2	2
42	1	2	2	2
43	1	2	2	2
44	1	2	2	2
45	1	2	2	2
46	1	2	2	2
47	1	2	2	2
48	1	2	2	2
49	1	2	2	2
50	1	2	2	2
51	1	2	2	2
52	1	2	2	2
53	1	2	2	2
54	1	2	2	2
55	1	2	2	2
56	1	2	2	2
57	1	2	2	2
58	1	2	2	2
59	1	2	2	2
60	1	2	2	2
61	1	2	2	2
62	1	2	2	2
63	1	2	2	2
64	1	2	2	2
65	1	2	2	2
66	1	2	2	2
67	1	2	2	2
68	1	2	2	2
69	1	2	2	2
70	1	2	2	2
71	1	2	2	2
72	1	2	2	2
73	1	2	2	2
74	1	2	2	2
75	1	2	2	2
76	1	2	2	2
77	1	2	2	2
78	1	2	2	2
79	1	2	2	2
80	1	2	2	2
81	1	2	2	2
82	1	2	2	2
83	1	2	2	2
84	1	2	2	2
85	1	2	2	2
86	1	2	2	2
87	1	2	2	2
88	1	2	2	2
89	1	2	2	2
90	1	2	2	2
91	1	2	2	2
92	1	2	2	2
93	1	2	2	2
94	1	2	2	2
95	1	2	2	2
96	1	2	2	2
97	1	2	2	2
98	1	2	2	2
99	1	2	2	2
100	1	2	2	2

**TOTAL SEATING CAPACITY OF ALL UNITS = 152**

FRONT DINING MAXIMUM OCCUPANCY BY CODE = 106 PERSONS ACTUAL SEATING = 86  
 REAR DINING MAXIMUM OCCUPANCY BY CODE = 11 PERSONS ACTUAL SEATING = 66



- Job # 1378750  
 Job Name: Cedar River Seafood - Lake City FL  
 Drawn By: [Name]  
 System Size: ANSUL - 20/30/230 Total FP required 28  
 Hood # 1 Size: 15' Long x 34" Wide x 24" High  
 Hood # 2 14' Long x 34" Wide x 24" High  
 Hood # 3 14' Long x 34" Wide x 24" High  
 Hood # 4 Metal Slow-Off Caps Included.
- NOTES  
 - FIELD PIPE JOISTS AS SHOWN  
 - FIELD VENT, ELZERS, AND NOZZLES SUPPLIED BY GAS VENT,  
 - SALAMANDERS, ETC. IF FLOW PATTERNS IS BLOCKED BY SHELVING,  
 - HANGING OF ELZERS IN SUPPLY LINE FROM RACK TO FIRST NOZZLE  
 - HANGING OF ELZERS UP FROM RACK TO FIRST NOZZLE  
 - FACTORY OPENING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD  
 - APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE  
 - THIS FIRE SYSTEM COMPLETES WITH UL 300 REQUIREMENTS

32376

GENERAL INFORMATION

1. Nozzles must be located 2-8 in. (5-20 cm) into the center of the duct opening, discharging up. See Figure 1.




FIGURE 1  
 000173

2 In installations where a UL listed damper assembly is employed, the duct nozzle can be installed beyond the 8 in. (20 cm) maximum, to a point just beyond the damper assembly that will not interfere with the damper. Exceeding the maximum of 8 in. (20 cm) in this way will not void the UL listing of the system.

3 Previously listed 3 flow number and 5 flow number duct protection detailed in earlier published manual, Part No. 418087-06, can also still be utilized.

DUCT SIZES UP TO 50 IN (127 cm)  
 PERIMETER/ 16 IN (41 cm) DIAMETER

- One 1W nozzle (Part No 419336) = one flow number
- 50 in (127 cm) perimeter maximum
- 16 in. (41 cm) diameter maximum

DUCT SIZES UP TO 100 IN (254 cm)  
 PERIMETER/ 32 IN. (81.3 cm) DIAMETER

- One 2W Nozzle (Part No 419337) = two flow numbers
- 100 in (254 cm) perimeter maximum
- 32 in (81.3 cm) diameter maximum

The chart below shows the maximum protection available from each duct nozzle

Part	Description	No	System	3 0 Gallon	1 5 Gallon
419337	2W Nozzle	Maximum	System	100 in. (254 cm)	Maximum
		Perimeter		100 in. (254 cm)	Perimeter
419336	1W Nozzle	Maximum	System	50 in. (127 cm)	Maximum
		Perimeter		50 in. (127 cm)	Perimeter

SYSTEM DESIGN

The ANSUL R-102 Restaurant Fire Suppression System may be used on a number of different types of restaurant cooking appliances and hood and duct configurations. The design information listed in this section deals with the limitations and parameters of this pre-engineered system. Those individuals responsible for the design of the R-102 system must be trained and hold a current ANSUL certificate in an R-102 training program.

The R-102 and the PIRANHA systems use compatible agents and components, therefore, they may be used together for cooking appliance, hood, and duct protection. The primary ANSUL AUTOMAN Release can be either an R-102 or a PIRANHA ANSUL AUTOMAN Release and can actuate up to two additional R-102 or PIRANHA Regulated Actuators in systems utilizing a 101 remote release, any combination of the maximum number of regulated actuators can be used.

- Both systems must actuate simultaneously
- Each system must be designed and installed per its appropriate manual

- Adjacent appliances requiring protection must be protected with the same type of system, either R-102 or PIRANHA, unless the center-to-center spacing between the adjacent and connecting duct above those appliances cannot be protected with PIRANHA nozzles
- When appliances are protected with R-102 nozzles, the hood and connecting duct above those appliances cannot be protected with PIRANHA nozzles
- Mixing systems in a common plenum is not allowed

One of the key elements for restaurant fire protection is a correct system design. This section is divided into ten sub-sections: Nozzle Placement Requirements, Tank Quantity Requirements, Actuation and Expellant Gas Line Requirements, Distribution Piping Requirements, Detection System Requirements, Manual Pull Station Requirements, Mechanical Gas Valve Requirements, Electrical Gas Valve Requirements, Electrical Switch Requirements, and Pressure Switch Requirements. Each of these sections must be completed before attempting any installation. System design sketches should be made of all aspects of design for reference during installation.

NOZZLE PLACEMENT REQUIREMENTS

This section gives guidelines for nozzle type, positioning, and quantity for duct, plenum, and individual appliance protection. This section must be completed before determining tank quantity and piping requirements.

Duct Protection - Single Nozzle

All duct protection is UL listed without limitation of maximum duct length (unlimited length). This includes all varieties of ductworks both horizontal and vertical including ducts that run at angles to the horizontal and ducts with directional bends.


The R-102 system uses different duct nozzles depending on the size of duct being protected.

**Duct Protection - Multiple Nozzle (Continued)**


▶ **DUCT SIZES GREATER THAN 100 IN. (254 cm) PERIMETER**

- ▶ Ducts over 100 in. (254 cm) perimeter may be modularized using 2W nozzles (Part No. 419337)
- ▶ No round duct option available
- ▶ Follow the design chart to determine maximum module size for each 2W nozzle
- ▶ When determining number of nozzles required, it is sometimes an advantage to check the chart using the shortest side as Side "A" and then recheck it using the longest side as Side "A". This comparison may reveal a need for a lesser quantity of nozzles one way versus the other way.
- ▶ When working with Chart 1, the quantity of nozzles determined must be equally divided within the duct area.


When working with Chart 2, one half of the quantity of nozzles determined must be equally positioned in the top half of the area of the duct and the remaining half of the nozzles must be positioned in the bottom half of the duct area.  
 Example: The duct to be protected has a Side "A" of 40 in. (101.6 cm) and a Side "B" of 60 in. (152.4 cm). Referring to the design chart, this duct requires 4 nozzles. One half of 4 = 2. Therefore, 2 nozzles must be equally positioned in each of the two duct areas. See Figure 3.



**FIGURE 3**




**CHART NO. 1**



**CHART NO. 2**

NOTE: NOZZLE QUANTITIES LISTED IN CHART 2 MUST BE EQUALLY DIVIDED INTO EACH OF THE TWO DUCT MODULES.



006522


**Plenum Protection**

The R-102 system uses the 1W Nozzle (Part No. 419336) or the 1N Nozzle (Part No. 419335) for plenum protection. The 1W nozzle tip is stamped with 1W and the 1N nozzle tip is stamped with 1N, indicating they are one-flow nozzles and must be counted as one flow number each. When protecting a plenum chamber, the entire chamber must be protected regardless of filter length.

**VERTICAL PROTECTION - GENERAL**

- ▶ 1W NOZZLE - PART NO. 419336 - SINGLE AND "V" BANK PROTECTION

One 1W nozzle will protect 4 linear feet (1.2 m) of plenum. The maximum distance from the end of the hood to the first and last nozzle must be no more than 2 ft (0.6 m). After the first nozzle, any additional nozzles must be positioned at a maximum of 4 ft (1.2 m) apart down the entire length of the plenum. The plenum width must not exceed 4 ft (1.2 m). (The 1W nozzle can be used on single or V-bank filter arrangements.) See Figure 6.




**FIGURE 6**  
 000197

When protecting plenums with the 1W nozzle, two options of coverage are available:


- Option 1:** The 1W nozzle must be on the center line of the single or "V" bank filter and positioned within 1-20 in. (2.5-51 cm) above the top edge of the filter. See Figure 7.

Figure 7.



**FIGURE 7**  
 000199


- Option 2:** The 1W nozzle must be placed perpendicular, 8-12 in. (20-30 cm) from the face of the filter and angled to the center of the filter. The nozzle tip must be within 2 in. (5 cm) from the perpendicular center line of the filter. See Figure 8



**FIGURE 8**  
 000200

**HORIZONTAL PROTECTION - OPTION 1**

One 1N nozzle will protect 10 linear feet (3.1 m) of single filter bank plenum. The nozzle(s) must be mounted in the plenum, 2 to 4 in. (5 to 10 cm) from the face of the filter, centered between the filter height dimension, and aimed down the length. The nozzle must be positioned 0-6 in. (0-15 cm) from the end of the hood to the tip of the nozzle. See Figure 9.



**FIGURE 9**

**Appliance Protection**

The following pages detail types of appliance protection. Each design requires several factors: correct nozzle choice, correct nozzle height above hazard, correct nozzle location and correct aiming point.

**Fryer – Single Nozzle Protection**

1. Design requirements for fryers are broken down into two types.

**A. FRYERS WITHOUT DRIPBOARDS**

If the fryer does not include a dripboard, measure the internal depth (horizontal dimension from front to back) and length of the frypot.

**B. FRYERS WITH DRIPBOARDS**

If the fryer includes any dripboard areas, measure both the internal depth and length of the overall hazard area including any dripboard areas

2. Using Table, "Maximum Cooking Area Dimension – Single Nozzle Fryer Protection," determine which nozzle is needed to protect the fryer based on the maximum dimensions listed. A. If the fryer does not include a dripboard, use the maximum dimensions listed in the first column of the table to select the correct nozzle.


B. If the fryer includes any dripboard areas, use both the maximum frypot dimensions in the first column of the table, and the maximum overall dimensions in the second column of the table to select the correct nozzle. None of the maximum dimensions in either column may be exceeded.

3. If either the maximum frypot or the overall sizes are exceeded, an additional nozzle(s) will be required. Refer to the multiple nozzle requirements.


*Example: A fryer with a dripboard. The inside of the frypot without the dripboard measures 18 in. in depth x 18 in. in length (46 cm x 46 cm) and the inside of the overall area including the dripboard measures 18 in. in depth x 24 in. in length (46 cm x 61 cm). From the Table "Maximum Cooking Area Dimension – Single Nozzle Fryer Protection," either the 3N or the 290 nozzle should be selected to protect the fryer, depending on the maximum nozzle height above the fryer and the positioning requirements allowed. Refer to appropriate Figures.*

**Fryer - Single Nozzle Protection (Continued)**  
**Maximum Area Dimensions - Single Nozzle Fryer Protection (Continued)**

Max. Size	Overall Max. Size	Type of Nozzle	Nozzle Height Above Top of Fryer	Nozzle Location
19.5 in. x 19 in.	19.5 in. x 25 3/8 in.	290	13 in. to 16 in. (33 to 41 cm)	See Figure 17
19.5 in. x 19 in.	19.5 in. x 25 3/8 in.	3N	See Figure 18	See Figure 18
18 in. x 18 in.	18 in. x 27 3/4 in.	3N	25 in. to 35 in. (64 cm to 89 cm)	See Figure 19




**FIGURE 17**



**FIGURE 18**

**FIGURE 19**



NOTE: 3N NOZZLE TIP MUST BE LOCATED WITHIN THE PERIMETER OF THE SURFACE AREA WITHIN THE FRONT HALF OF THE FRY POT AND AIMED AT THE CENTER

Fryer - Multiple Nozzle Protection (Continued)

Max. Size Module	Overall	Nozzle Height	Nozzle Location
▶ Full or Split Vat 21 in. x 210 in. <sup>2</sup> (53 cm x 0.14 m <sup>2</sup> )	▶ Full or Split Vat 21 in. x 294 in. <sup>2</sup> (53 cm x 0.19 m <sup>2</sup> )	27 in. to 47 in. (69 cm to 119 cm)	Above Top of Fryer
▶ Full or Split Vat 21 in. x 210 in. <sup>2</sup> (53 cm x 0.14 m <sup>2</sup> )	▶ Full or Split Vat 21 in. x 294 in. <sup>2</sup> (53 cm x 0.19 m <sup>2</sup> )	20 in. to 27 in. (51 to 69 cm)	
▶ Full or Split Vat 21 in. x 210 in. <sup>2</sup> (53 cm x 0.14 m <sup>2</sup> )	▶ Full or Split Vat 21 in. x 294 in. <sup>2</sup> (53 cm x 0.19 m <sup>2</sup> )	13 in. to 16 in. (33 to 41 cm)	
▶ Full or Split Vat 25 3/8 x 370.5 in. <sup>2</sup> (65 cm x 0.24 m <sup>2</sup> )	▶ Full or Split Vat 25 3/8 x 495 in. <sup>2</sup> (65 cm x 0.32 m <sup>2</sup> )	13 in. to 16 in. (33 to 41 cm)	
▶ Full or Split Vat 26 1/2 in. x 203 in. <sup>2</sup> (67 cm x 0.13 m <sup>2</sup> )	▶ Full or Split Vat 26 1/2 in. x 384 1/4 in. <sup>2</sup> (67 cm x 0.25 m <sup>2</sup> )	16 in. to 27 in. (41 to 69 cm)	
▶ Full or Split Vat 25 3/8 x 370.5 in. <sup>2</sup> (65 cm x 0.24 m <sup>2</sup> )	▶ Full or Split Vat 25 3/8 x 495 in. <sup>2</sup> (65 cm x 0.32 m <sup>2</sup> )	See Figure 22	
▶ Full or Split Vat 27 3/4 x 324 in. <sup>2</sup> (70.5 cm x 0.21 m <sup>2</sup> )	▶ Full or Split Vat 27 3/4 x 497 in. <sup>2</sup> (70.5 cm x 0.32 m <sup>2</sup> )	25 in. to 35 in. (64 cm to 89 cm)	
▶ Full or Split Vat 21 in. x 210 in. <sup>2</sup> (53 cm x 0.14 m <sup>2</sup> )	▶ Full or Split Vat 21 in. x 294 in. <sup>2</sup> (53 cm x 0.19 m <sup>2</sup> )	See Figure 21	
▶ Full or Split Vat 21 in. x 210 in. <sup>2</sup> (53 cm x 0.14 m <sup>2</sup> )	▶ Full or Split Vat 21 in. x 294 in. <sup>2</sup> (53 cm x 0.19 m <sup>2</sup> )	See Figure 21	
▶ Full or Split Vat 25 3/8 x 370.5 in. <sup>2</sup> (65 cm x 0.24 m <sup>2</sup> )	▶ Full or Split Vat 25 3/8 x 495 in. <sup>2</sup> (65 cm x 0.32 m <sup>2</sup> )	See Figure 22	
▶ Full or Split Vat 26 1/2 in. x 203 in. <sup>2</sup> (67 cm x 0.13 m <sup>2</sup> )	▶ Full or Split Vat 26 1/2 in. x 384 1/4 in. <sup>2</sup> (67 cm x 0.25 m <sup>2</sup> )	See Figure 22	
▶ Full or Split Vat 25 3/8 x 370.5 in. <sup>2</sup> (65 cm x 0.24 m <sup>2</sup> )	▶ Full or Split Vat 25 3/8 x 495 in. <sup>2</sup> (65 cm x 0.32 m <sup>2</sup> )	See Figure 23	
▶ Full or Split Vat 27 3/4 x 324 in. <sup>2</sup> (70.5 cm x 0.21 m <sup>2</sup> )	▶ Full or Split Vat 27 3/4 x 497 in. <sup>2</sup> (70.5 cm x 0.32 m <sup>2</sup> )	See Figure 23	




FIGURE 21

POSITION NOZZLE TIP ANYWHERE ALONG OR WITHIN THE PERIMETER OF THE MODULE IT IS PROTECTING AND AIM AT THE MIDDLE OF THAT MODULE AREA.




FIGURE 22

290 NOZZLE TIP POSITIONED OVER THE MIDDLE OF THE RESPECTIVE MODULAR AREA ± 3 IN (7.6 cm) FROM THE MIDDLE ALONG THE LONGEST SIDE OF THE MODULE AND ± 1 IN (2.5 cm) FROM THE MIDDLE ALONG THE SHORTEST SIDE OF THE MODULE AND AIMED AT THE MIDDLE OF THE MODULE.

FIGURE 23

3N NOZZLE TIP MUST BE POSITIONED ANYWHERE ALONG OR WITHIN THE PERIMETER OF THE MODULE IT IS PROTECTING AND AIMED AT THE MIDDLE OF THAT RESPECTIVE MODULE AREA.





FIGURE 24

3N NOZZLE TIP MUST BE POSITIONED ANYWHERE ALONG OR WITHIN THE PERIMETER AND FORWARD OF THE RIGHT-TO-LEFT CENTERLINE OF THE COOKING AREA. THE AIMING POINT OF THE NOZZLE MUST BE AT THE DIAGONAL CENTER OF THE MODULAR COOKING AREA.



► Range Protection

The R-102 system uses five different nozzles for the protection of ranges. Two of the design options require a one-flow nozzle and three of the design options require two-flow nozzles.

**NOTICE**

A 13 in. (33 cm) diameter wok pan is the largest wok size that can be protected on ranges.

When protecting hot top ranges, the entire cooking surface must be protected.

► Range Protection 1N (1-Flow) Nozzle – High Proximity

Application

► No Obstructions

Single and multiple burner ranges can be protected using a 1N nozzle, Part No. 419335. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle and must be counted as one flow number.

When using this nozzle for range protection, the maximum length of the burner grates being protected with a single nozzle must not exceed 32 in. (81 cm) and the maximum area of the burner grates must not exceed 384 in.<sup>2</sup> (2477 cm<sup>2</sup>) per nozzle.

When protecting a range, the 1N nozzle must be located a maximum of 10 in. (25.4 cm) from each burner grate centerline and must be aimed at the center of the cooking surface. See Figures 27 and 28.




FIGURE 27




FIGURE 28

**Application**  
 Range Protection 260 (2-Flow) Nozzle - Medium Proximity

**No Obstructions**  
 30 in. to 40 in. (76 cm to 102 cm) above the cooking surface.  
 The medium proximity application uses the 260 nozzle, Part No. 419341.  
 The nozzle tip is stamped with 260 indicating this is a two-flow nozzle and must be counted as two flow numbers.  
 One 260 nozzle will protect a cooking area of 768 in.<sup>2</sup> (4955 cm<sup>2</sup>) with a maximum dimension of 32 in. (81 cm).  
 When using this nozzle for range protection, the nozzle must be pointed vertically down and positioned as shown in Figures 31 and 32.




FIGURE 31




FIGURE 32

**NOTICE**

Four burner grates shown in Figure 32. For single or double burner grates, locate nozzle at center of cooking surface.

Range Protection 260 (2-Flow) Nozzle (With or Without Back Shell/Obstruction)

Single and multiple burner ranges can be protected using a 260 nozzle, Part No. 419341. The nozzle tip is stamped with 260 indicating that it is a two-flow nozzle and must be counted as two flow numbers.

When using the 260 nozzle for range protection with or without back shell or other similarly sized obstruction, the maximum length of burner grates being protected must not exceed 32 in. (81 cm) and the maximum area of the burner grates must not exceed 384 in.<sup>2</sup> (2477 cm<sup>2</sup>). Nozzle must be located on the front edge of the burner grates and aimed at a point 10 in. (25 cm) from the back edge of the burner grates. Nozzle must be mounted 30 to 40 in. (76 to 102 cm) above the hazard surface. See Figure 38.




FIGURE 38

000238a

Range Protection (With or Without Back Shell/Obstruction)

When this type of hazard is equipped with a back shell or other similarly sized obstruction located above the range top, two protection options are available: One requires a 1F nozzle, Part No. 419333, and the other option requires a 260 nozzle, Part No. 419341.

Range Protection 1F (1-Flow) Nozzle (With or Without Back Shell/Obstruction)

Single and multiple burner ranges can be protected using a 1F nozzle, Part No. 419333. The nozzle tip is stamped with 1F indicating that it is a one-flow nozzle and must be counted as one flow number.

When using the 1F nozzle for range protection with or without back shell or other similarly sized obstruction, the maximum length of the burner grates being protected must not exceed 28 in. (71 cm) and the maximum area of the burner grates must not exceed 336 in.<sup>2</sup> (2168 cm<sup>2</sup>). See Figure 37 for nozzle location details.




FIGURE 37

000238b

Griddle Protection 290 (2-Flow) Nozzle - Medium Proximity Application

Option 2a - Nozzle Perimeter Located (Continued)

20 in. to 30 in. (51 cm to 76 cm) above the cooking surface  
 The medium proximity application uses the 290 nozzle, Part No. 419342.  
 The nozzle tip is stamped with 290 indicating this is a two-flow nozzle and must be counted as two flow numbers.

One 290 nozzle will protect a maximum cooking area of 1440 in.<sup>2</sup> (9290 cm<sup>2</sup>) with a maximum dimension of 48 in. (122 cm).

When using this nozzle for griddle protection, the nozzle must be positioned along the cooking surface perimeter to 2 in. (5.1 cm) inside the perimeter, and aimed at the center of the cooking surface. See Figure 45 and 46




FIGURE 45  
 000241




FIGURE 46  
 000243

Griddle Protection 260 (2-Flow) Nozzle - High Proximity Application

Option 2 - Nozzle Perimeter Located

30 in. to 50 in. (76 cm to 127 cm) above the cooking surface.  
 This high proximity application uses the 260 nozzle, Part No. 419341.  
 The nozzle tip is stamped with 260 indicating this is a two-flow nozzle and must be counted as two flow numbers.

One 260 nozzle will protect a maximum cooking area of 1440 in.<sup>2</sup> (9290 cm<sup>2</sup>) with a maximum dimension of 48 in. (122 cm).

When using this nozzle for griddle protection, the nozzle must be positioned along the cooking surface perimeter to 2 in. (5.1 cm) inside perimeter, and aimed at the center of the cooking surface. See Figure 43 and 44.




FIGURE 43  
 000243




FIGURE 44  
 000241

**Griddle Protection 1W (1-Flow) Nozzle - Low Proximity**

Application  
 15 in. to 20 in. (38.1 cm to 50.8 cm) above the cooking surface.  
 The low proximity 1-flow nozzle application for the protection of  
 griddles requires the 1W nozzle, Part No. 419336.

The nozzle tip is stamped with 1W indicating that this is a one-flow  
 nozzle and must be counted as one flow number.

When using the 1W nozzle for low proximity griddle protection with  
 our without obstruction, the maximum length of the cooking sur-  
 face to be protected must not exceed 26 in. (66.0 cm). The nozzle

must be centered at one end of the maximum 26 in. (66.0 cm)  
 length, aimed along a centerline to a point 20 in. (50.8 cm) from  
 the end of the length, protecting a maximum width of 20.5 in.

(52.1 cm).  
 The 1W nozzle tip must be positioned at or below the obstruction,  
 if present. The protected area begins at the point straight down  
 from the nozzle tip. The nozzle can be positioned above the edge

of the hazard area to be protected. See Figures 51 and 52  
 Note: If the hazard area exceeds the single nozzle coverage list-  
 ed above, additional nozzles will be required. The additional noz-  
 zle can be positioned in front at high proximity or at the side at low

proximity.




FIGURE 51





FIGURE 52

**Overhead Chain Broiler Protection (Continued)**

**Example No. 1** - Internal broiler size is 24 in. long x 20 in. wide (61 x 51 cm), with an opening of 16 in. x 16 in. (40.6 x 40.6 cm).  
 To determine minimum opening size, multiply the internal length and the internal width by 0.6:  
 Length of opening - 24 in. x 0.6 = 14.4 in.  
 Width of opening - 20 in. x 0.6 = 12.0 in.  
 (51 cm x 0.6 = 30.5 cm)  
 The minimum allowable opening for overhead protection would be 14.4 in. x 12.0 in. (36.6 x 30.5 cm).  
 This example would be acceptable for overhead protection.


**Example No. 2** - Internal broiler size is 30 in. long x 24 in. wide (76 x 61 cm) with an opening of 22 in. x 12 in. (56 x 30 cm).  
 To determine minimum opening size, multiply internal length and internal width by 0.6:  
 Length of opening - 30 in. x 0.6 = 18.0 in.  
 Width of opening - 24 in. x 0.6 = 14.4 in.  
 (61 cm x 0.6 = 36.6 cm)  
 Minimum allowable opening for overhead protection would be 18 in. x 14.4 in. (45.7 x 36.6 cm).  
 Because this broiler has an opening of 22 in. x 12 in., the 12 in. width is below the minimum allowable calculated dimension of 14.4 in. (36.6 cm) and therefore would not be acceptable for overhead protection.

**Salamander Broiler Protection**  
 The R-102 system uses three different nozzle locations for salamander broiler protection. All of the design options require a one-flow nozzle.  
**Salamander Broiler Protection - 1N (1-Flow) Nozzle Overhead**  
 A salamander broiler with a maximum hazard area (internal broiler chamber) of 16 in. (41 cm) deep x 29 in. (74 cm) wide can be protected using a 1N nozzle, Part No. 419335. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle.  
 The single 1N nozzle must be located directly in line with either vertical edge of the broiler opening, 6 in. (15 cm) to 12 in. (30 cm) in front of the broiler, and 0 in. to 12 in. (30 cm) above the top of the broiler. The nozzle must be aimed at the center of the broiler opening. See Figure 57a.




**FIGURE 57a**  
 008426

**Salamander Broiler Protection - 1F (1-Flow) Nozzle Overhead**  
 A salamander broiler with a maximum hazard area (internal broiler chamber) of 15 in. (38 cm) deep x 31 in. (79 cm) wide can be protected using a 1F nozzle, Part No. 419333. The nozzle tip is stamped with 1F, indicating that this is a one-flow nozzle.  
 The single 1F nozzle must be located directly in line with the center of the broiler opening, 8 in. (20 cm) to 12 in. (30 cm) in front of the broiler and 12 in. (30 cm) to 18 in. (46 cm) above the top of the broiler. The nozzle must be aimed at the center of the top broiler opening when the grate is located in the middle position. The nozzle must be orientated so the nozzle tip flaps are parallel with the grate left to right centerline. See Figure 57b.



**FIGURE 57b**  
 008426

**Salamander Broiler Protection - 1N (1-Flow) Nozzle Local**  
 A salamander broiler with a maximum hazard area (internal broiler chamber) of 15 in. (38 cm) deep x 31 in. (79 cm) wide can be protected using a 1N nozzle, Part No. 419335. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle.  
 The single 1N nozzle must be located above the grate on either vertical edge of the broiler opening. The nozzle must be aimed at the center of the grates. See Figure 57c.



**FIGURE 57c**  
 008426

**Natural Charcoal Broiler Protection**

The R-102 system uses the 1N Nozzle (Part No. 41935) for all natural charcoal broiler protection. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle and must be counted as one flow number.

One 1N nozzle will protect a hazard area which has a maximum length of 24 in. (61 cm) and a total cooking area which does not exceed 288 in.<sup>2</sup> (1858 cm<sup>2</sup>). The nozzle tip must be located 18 to 40 in. (46 to 102 cm) above the hazard surface. When using this nozzle for natural charcoal broiler protection, the nozzle must be positioned anywhere along or within the perimeter of the maximum cooking area and aimed at the center of the cooking surface. See Figure 61.

The coverage of such appliances only applies when the depth of the charcoal does not exceed 4 in. (10 cm)




FIGURE 61

**Lava Rock (Ceramic) Char-Broiler Protection**

The R-102 system uses the 1N Nozzle (Part No. 41935) for all lava rock char-broiler protection. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle and must be counted as one flow number.

One 1N nozzle will protect a hazard which has a maximum length of 24 in. (61 cm) and a total cooking area which does not exceed 312 in.<sup>2</sup> (2013 cm<sup>2</sup>). The nozzle tip must be located 18 to 35 in. (46 to 89 cm) above the hazard surface. When using this nozzle for lava rock (ceramic) char-broiler protection, the nozzle must be positioned anywhere along or within the perimeter of the maximum cooking area and angled to the center. See Figure 60.




FIGURE 60

2. A 1N Nozzle, Part No. 419335, will protect a wok 11 in. (28 cm) minimum diameter up to 24 in. (61 cm) maximum diameter. The wok depth must be no less than 3 in. (8 cm) and no greater than 6 in. (15 cm). The nozzle tip is stamped with 1N indicating that this is a one-flow nozzle and must be counted as one flow number. When using this nozzle, the nozzle must be positioned anywhere along or within the perimeter of the wok, aimed at the center, 30 in. to 40 in. (76 to 102 cm) above the hazard surface, as shown in Figure 65.

**NOTICE**

When using this type of wok protection, only 5 flow numbers are allowed on a 1 1/2 gal (5.7 L) system, and only 11 flow numbers are allowed on a 3 gal (11.4 L) system.




FIGURE 65  
 000261

1. A 260 nozzle, Part No. 419341, will protect a wok 14 in. (36 cm) minimum diameter up to 30 in. (76 cm) maximum diameter. The wok depth must be no less than 3.75 in. (9.5 cm) and no greater than 8 in. (20 cm). The nozzle tip is stamped with 260 indicating that this is a two-flow nozzle and must be counted as two flow numbers. When using this nozzle, the nozzle must be positioned as shown in Figure 64.

NOZZLE MUST BE POSITIONED WITHIN 1 IN. (2 cm) RADIUS OF THE CENTER OF THE WOK, POINTED VERTICALLY DOWN




FIGURE 64  
 000261

Nozzle Application Chart (Continued)

Nozzle Tip  
 Stamping -  
 Flow No.

Nozzle  
 Part No.

Nozzle  
 Heights

Minimum  
 Nozzle  
 Quantity

Maximum Hazard  
 Dimensions

Hazard  
 Fryer (Non-Spill  
 Vat Only)\*

230	419339	27 - 47 in.	1	1	27 - 47 in. Medium Proximity		
245	419340	20 - 27 in.	1	1	20 - 27 in. Medium Proximity		
290	419338	21 - 34 in.	1	1	21 - 34 in. High Proximity		
290	419342	13 - 16 in.	1	1	13 - 16 in. Low Proximity		
3N	419338	25 - 35 in. (64-89 cm)	1	1	25 - 35 in. High Proximity		
290	419342	13 - 16 in.	1	1	13 - 16 in. Low Proximity		
3N	419338	25 - 35 in. (64-89 cm)	1	1	25 - 35 in. High Proximity		
290	419342	13 - 16 in.	1	1	13 - 16 in. Low Proximity		
290	419342	13 - 16 in.	1	1	13 - 16 in. Low Proximity		
290	419342	16 - 27 in.	1	1	16 - 27 in. Medium Proximity		
1N	419335	30 - 40 in. (76 - 102 cm)	1	1	30 - 40 in. High Proximity		
1N	419335	15 - 20 in. (38 - 51 cm)	1	1	15 - 20 in. Low Proximity		
1F	419333	40 - 48 in. (102 - 122 cm) (With Backshell)	1	1	40 - 48 in. Longest Side		
245	419340	40 - 50 in. (102 - 127 cm)	1	1	40 - 50 in. Longest Side (High Proximity)		
260	419341	30 - 40 in. (76 - 102 cm)	1	1	30 - 40 in. Longest Side (Medium Proximity)		

Fryer (Spill or  
 Non-Spill Vat)

Range


\* For multiple nozzle protection of single fryers, see detailed information on Pages 4-10 and 4-11

Nozzle Application Chart (Continued)

Hazard	Maximum Hazard Dimensions	Minimum Nozzle	Nozzle	Nozzle Heights	Part No.	Flow No.	Nozzle Tip Stamping -
Lava-Rock or Natural Charcoal Char-Broiler	Longest Side - 30 in. (76 cm) Area - 720 sq in. (4645 sq cm)	1	14 - 40 in. (36 - 102 cm)	419338	3N		
Wood Fueled Char-Broiler	Longest Side - 30 in (76 cm) Area - 720 sq in. (4645 sq cm)	1	14 - 40 in (36 - 102 cm)	419338	3N		
Upright Broiler	Length - 32.5 in. (82.5 cm) Width - 30 in. (76 cm)	2	-	419334	1/2N		
Salamanca Broiler	Length - 29 in. (74 cm) Width - 16 in. (41 cm)	1	-	419335	1N		
Wok	Length - 31 in. (79 cm) Width - 15 in. (38 cm)	1	-	419333	1F		
	Length - 31 in. (79 cm) Width - 15 in. (38 cm)	1	-	419335	1N		
	Length - 31 in. (79 cm) Width - 15 in. (38 cm)	1	35 - 45 in (89 - 114 cm)	419341	260		
Wok	Length - 24 in (28 - 61 cm) Diameter 30 - 6.0 in (8 - 15.2 cm) Deep		30 - 40 in. (76 - 102 cm)	419335/435672	1N/1NSS		

\* Minimum chain broiler exhaust opening - 12 in x 12 in (31 cm x 31 cm) and not less than 60% of internal broiler size.

32376



Fryer-H w/Drp Board  
High Proximity  
18.00' L x 18.00' D

Fryer-H w/Drp Board  
High Proximity  
18.00' L x 18.00' D

Fryer-H w/Drp Board  
High Proximity  
18.00' L x 18.00' D

Fryer-H w/Drp Board  
High Proximity  
18.00' L x 18.00' D

Range-Hood  
High Proximity  
36.00' L x 24.00' D

Gas Radiant Charbroiler  
High Proximity  
30.00' L x 24.00' D

Upright Broiler  
Low Proximity  
36.00' L x 24.00' D

Upright Broiler  
Low Proximity  
36.00' L x 24.00' D

- NOTES
- FIELD PIPE JOINS AS SHOWN
  - FIELD PIPE NOZZLES SUPPLIED BY GAS
  - RELIEF VALVES & FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
  - MAXIMUM 9' CLIMBS IN SUPPLY LINE FROM TANK TO FIRST NOZZLE
  - MAXIMUM 2' CLIMBS IN EXHAUST LINE FROM HOODS TO FIRST NOZZLE
  - FACTORY PIPING EXTENSIVE A MAXIMUM OF 6' ABOVE THE TOP OF THE HOOD
  - APPLICABLE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE NOT THE OVERALL APPLIANCE SIZE
  - THIS FIRE SYSTEM COMPLETES WITH U.L. 300 REQUIREMENTS
- Job # 1978750  
 Job Name Cedar River Seafood - Lake City FL  
 Drawn By:  
 System Size: ANSI-30/20/30 Total FP required: 88  
 Room # 1 Size: 16' Dia. x 8' High  
 Room # 2 Size: 16' Dia. x 8' High  
 Hood # 1 Metal Blow-Off Caps Included.  
 Hood # 2 14' OD, Long x 54" Wide x 24" High  
 Room # 2 Size: 14' Dia.  
 Hood # 2 Metal Blow-Off Caps Included.

GENERAL INFORMATION

1 Nozzles must be located 2-8 in. (5-20 cm) into the center of the duct opening, discharging up. See Figure 1.




FIGURE 1  
 000173

2 In installations where a UL listed damper assembly is employed, the duct nozzle can be installed beyond the 8 in. (20 cm) maximum, to a point just beyond the damper assembly that will not interfere with the damper. Exceeding the maximum of 8 in (20 cm) in this way will not void the UL listing of the system.

3 Previously listed 3 flow number and 5 flow number duct protection detailed in earlier published manual, Part No 418087-06, can also still be utilized.

DUCT SIZES UP TO 50 IN (127 cm)  
 PERIMETER/ 16 IN. (41 cm) DIAMETER

- One 1W nozzle (Part No. 419336) = one flow number
- 50 in (127 cm) perimeter maximum
- 16 in. (41 cm) diameter maximum

DUCT SIZES UP TO 100 IN (254 cm)  
 PERIMETER/ 32 IN (81.3 cm) DIAMETER

- One 2W Nozzle (Part No. 419337) = two flow numbers
- 100 in (254 cm) perimeter maximum
- 32 in (81.3 cm) diameter maximum

The chart below shows the maximum protection available from each duct nozzle

Part No.	System	3.0 Gallon	System	1.5 Gallon
419337	Maximum	100 in (254 cm)	Maximum	100 in (254 cm)
	Perimeter		Perimeter	
419336	Maximum	50 in. (127 cm)	Maximum	50 in. (127 cm)
	Perimeter		Perimeter	

**SYSTEM DESIGN**

The ANSUL R-102 Restaurant Fire Suppression System may be used on a number of different types of restaurant cooking appliances and hood and duct configurations. The design information listed in this section deals with the limitations and parameters of this pre-engineered system. Those individuals responsible for the design of the R-102 system must be trained and hold a current ANSUL certificate in an R-102 training program.

The R-102 and the PIRANHA systems use compatible agents and components, therefore, they may be used together for cooking appliance, hood, and duct protection. The primary ANSUL AUTOMAN Release can be either an R-102 or a PIRANHA ANSUL AUTOMAN Release and can actuate up to two additional R-102 or PIRANHA Regulated Actuators. In systems utilizing a 101 remote release, any combination of the maximum number of regulated actuators can be used.

- Both systems must actuate simultaneously.
- Each system must be designed and installed per its appropriate manual.
- Adjacent appliances requiring protection must be protected with the same type of system, either R-102 or PIRANHA, R-102 and PIRANHA nozzles is no less than 36 in. (91.4 cm) and connecting duct above those appliances cannot be protected with PIRANHA nozzles.
- Mixing systems in a common plenum is not allowed.

One of the key elements for restaurant fire protection is a correct system design. This section is divided into ten sub-sections: Nozzle Placement Requirements, Tank Quantity Requirements, Actuation and Expellant Gas Line Requirements, Distribution Piping Requirements, Detection System Requirements, Manual Pull Station Requirements, Mechanical Gas Valve Requirements, Electrical Gas Valve Requirements, Electrical Switch Requirements, Pressure Switch Requirements. Each of these sections must be completed before attempting any installation. System design sketches should be made of all aspects of design for reference during installation.

**NOZZLE PLACEMENT REQUIREMENTS**

This section gives guidelines for nozzle type, positioning, and quantity for duct, plenum, and individual appliance protection. This section must be completed before determining tank quantity and piping requirements.

**Duct Protection - Single Nozzle**

All duct protection is UL listed without limitation of maximum duct length (unlimited length). This includes all varieties of ductwork both horizontal and vertical including ducts that run at angles to the horizontal and ducts with directional bends.

The R-102 system uses different duct nozzles depending on the size of duct being protected.

When working with Chart 2, one half of the quantity of nozzles determined must be equally positioned in the top half of the area of the duct and the remaining half of the nozzles must be positioned in the bottom half of the duct area.  
 Example: The duct to be protected has a Side "A" of 40 in. (101.6 cm) and a Side "B" of 60 in. (152.4 cm). Referring to the design chart, this duct requires 4 nozzles. One half of 4 = 2. Therefore, 2 nozzles must be equally positioned in each of the two duct areas. See Figure 3




FIGURE 3

**Duct Protection - Multiple Nozzle (Continued)**

- ▶ DUCT SIZES GREATER THAN 100 IN (254 cm) PERIMETER
- ▶ Ducts over 100 in. (254 cm) perimeter may be modularized using 2W nozzles (Part No. 419337)
- ▶ No round duct option available
- ▶ Follow the design chart to determine maximum module size for each 2W nozzle
- ▶ When determining number of nozzles required, it is sometimes an advantage to check the chart using the shortest side as Side "A" and then recheck it using the longest side as Side "A". This comparison may reveal a need for a lesser quantity of nozzles one way versus the other way.
- ▶ When working with Chart 1, the quantity of nozzles determined must be equally divided within the duct area.




CHART NO. 1





CHART NO. 2

NOTE: NOZZLE QUANTITIES LISTED IN CHART 2 MUST BE EQUALLY DIVIDED INTO EACH OF THE TWO DUCT MODULES.



006522




FIGURE 7

Option 2: The 1W nozzle must be placed perpendicular, 8-12 in. (20-30 cm) from the face of the filter and angled to the center of the filter. The nozzle tip must be within 2 in. (5 cm) from the perpendicular center line of the filter. See Figure 8




FIGURE 8

HORIZONTAL PROTECTION - OPTION 1  
 1N NOZZLE - PART NO. 419335 - SINGLE BANK PROTECTION  
 One 1N nozzle will protect 10 linear feet (3.1 m) of single filter bank plenum. The nozzle(s) must be mounted in the plenum, 2 to 4 in. (5 to 10 cm) from the face of the filter, centered between the filter height dimension, and aimed down the length. The nozzle must be positioned 0-6 in. (0-15 cm) from the end of the hood to the tip of the nozzle. See Figure 9.




FIGURE 9

Plenum Protection  
 The R-102 system uses the 1W Nozzle (Part No. 419336) or the 1N Nozzle (Part No. 419335) for plenum protection. The 1W nozzle tip is stamped with 1W and the 1N nozzle tip is stamped with 1N, indicating they are one-flow nozzles and must be counted as one flow number each. When protecting a plenum chamber, the entire chamber must be protected regardless of filter length.

VERTICAL PROTECTION - GENERAL  
 1W NOZZLE - PART NO. 419336 - SINGLE AND "V" BANK PROTECTION

One 1W nozzle will protect 4 linear feet (1.2 m) of plenum. The maximum distance from the end of the hood to the first and last nozzle must be no more than 2 ft (0.6 m). After the first nozzle, any additional nozzles must be positioned at a maximum of 4 ft (1.2 m) apart down the entire length of the plenum. The plenum width must not exceed 4 ft (1.2 m). (The 1W nozzle can be used on single or V-bank filter arrangements.) See Figure 6




FIGURE 6

When protecting plenums with the 1W nozzle, two options of coverage are available:

Option 1: The 1W nozzle must be on the center line of the single or "V" bank filter and positioned within 1-20 in. (2.5-51 cm) above the top edge of the filter. See Figure 7

**Appliance Protection**

The following pages detail types of appliance protection. Each design requires several factors: correct nozzle choice, correct nozzle height above hazard, correct nozzle location and correct aiming point.

**Fryer – Single Nozzle Protection**

1. Design requirements for fryers are broken down into two types.

**A. FRYERS WITHOUT DRIPBOARDS**

If the fryer does not include a dripboard, measure the internal depth (horizontal dimension from front to back) and length of the frypot.

**B. FRYERS WITH DRIPBOARDS**

If the fryer includes any dripboard areas, measure both the internal depth (horizontal dimension from front to back) and length of the frypot portion, and then measure including any dripboard areas

2. Using Table, "Maximum Cooking Area Dimension – Single Nozzle Fryer Protection," determine which nozzle is needed to protect the fryer based on the maximum dimensions listed. A If the fryer does not include a dripboard, use the maximum dimensions listed in the first column of the table to select the correct nozzle.

B. If the fryer includes any dripboard areas, use both the maximum frypot dimensions in the first column of the table, and the maximum overall dimensions in the second column of the table to select the correct nozzle. None of the maximum dimensions in either column may be exceeded.

3. If either the maximum frypot or the overall sizes are exceeded, an additional nozzle(s) will be required. Refer to the multiple nozzle requirements.

*Example: A fryer with a dripboard. The inside of the frypot without the dripboard measures 18 in. in depth x 18 in. in length (46 cm x 46 cm) and the inside of the overall area including the dripboard measures 18 in. in depth x 24 in. in length (46 cm x 61 cm). From the Table "Maximum Cooking Area Dimension – Single Nozzle Fryer Protection," either the 3N or the 290 nozzle should be selected to protect the fryer, depending on the maximum nozzle height above the fryer and the positioning requirements allowed. Refer to appropriate Figures.*

Fryer - Single Nozzle Protection (Continued)  
 Maximum Area Dimensions - Single Nozzle Fryer Protection (Continued)

Max. Size	Overall Max. Size	Type of Nozzle	Location
19.5 in. x 19 in. (50 cm x 48 cm)	19.5 in. x 25 3/8 in. (50 cm x 65 cm)	290	Above Top of Fryer
19.5 in. x 19 in. (50 cm x 48 cm)	19.5 in. x 25 3/8 in. (50 cm x 65 cm)	3N	Above Top of Fryer
18 in. x 18 in. (46 cm x 46 cm)	18 in. x 27 3/4 in. (46 cm x 70.5 cm)	3N	Above Top of Fryer




FIGURE 17





FIGURE 18

FIGURE 19



NOTE: 3N NOZZLE TIP MUST BE LOCATED WITHIN THE PERIMETER OF THE SURFACE AREA WITHIN THE FRONT HALF OF THE FRY POT AND AIMED AT THE CENTER.



The R-102 system uses five different nozzles for the protection of ranges. Two of the design options require a one-flow nozzle and three of the design options require two-flow nozzles.

**NOTICE**

A 13 in. (33 cm) diameter wok pan is the largest wok size that can be protected on ranges. When protecting hot top ranges, the entire cooking surface must be protected.

**Range Protection 1N (1-Flow) Nozzle - High Proximity**

**Application**

**No Obstructions**

Single and multiple burner ranges can be protected using a 1N nozzle, Part No. 419335. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle and must be counted as one flow number.

When using this nozzle for range protection, the maximum length of the burner grates being protected with a single nozzle must not exceed 32 in. (81 cm) and the maximum area of the burner grates must not exceed 384 in.<sup>2</sup> (2477 cm<sup>2</sup>) per nozzle.

When protecting a range, the 1N nozzle must be located a maximum of 10 in. (25.4 cm) from each burner grate centerline and must be aimed at the center of the cooking surface. See Figures 27 and 28.




FIGURE 27




FIGURE 28

**Range Protection**





FIGURE 32 000766

FIGURE 31



**Application**  
 Range Protection 260 (2-Flow) Nozzle - Medium Proximity

**No Obstructions**  
 30 in. to 40 in. (76 cm to 102 cm) above the cooking surface.

The medium proximity application uses the 260 nozzle, Part No. 419341.

The nozzle tip is stamped with 260 indicating this is a two-flow nozzle and must be counted as two flow numbers.

One 260 nozzle will protect a cooking area of 768 in.<sup>2</sup> (4955 cm<sup>2</sup>) with a maximum dimension of 32 in (81 cm).


When using this nozzle for range protection, the nozzle must be pointed vertically down and positioned as shown in Figures 31 and 32.

**Range Protection 260 (2-Flow) Nozzle (With or Without Back Shelf/Obstruction)**

Single and multiple burner ranges can be protected using a 260 nozzle, Part No. 419341. The nozzle tip is stamped with 260 indicating that it is a two-flow nozzle and must be counted as two flow numbers.

When using the 260 nozzle for range protection with or without back shelf or other similarly sized obstruction, the maximum length of burner grates being protected must not exceed 32 in. (81 cm) and the maximum area of the burner grates must not exceed 384 in.<sup>2</sup> (2477 cm<sup>2</sup>). Nozzle must be located on the front edge of the burner grates and aimed at a point 10 in. (25 cm) from the back edge of the burner grates. Nozzle must be mounted 30 to 40 in. (76 to 102 cm) above the hazard surface. See Figure 38.

**260 NOZZLE**  
 SHELF OR OTHER SIMILARLY SIZED OBSTRUCTION CAN OVERHANG BURNER(S) BY A MAXIMUM OF 11 IN. (28 cm)  
 18 IN. (45.7 cm) MINIMUM  
 30 - 40 IN. (76 - 102 cm)  
 10 IN. (25 cm) FROM BACK OF BURNER GRATES



**FIGURE 38**  
 0002388

**Range Protection (With or Without Back Shelf/Obstruction)**


When this type of hazard is equipped with a back shelf or other similarly sized obstruction located above the range top, two protection options are available: One requires a 1F nozzle, Part No. 419333, and the other option requires a 260 nozzle, Part No. 419341.

**Range Protection 1F (1-Flow) Nozzle (With or Without Back Shelf/Obstruction)**

Single and multiple burner ranges can be protected using a 1F nozzle, Part No. 419333. The nozzle tip is stamped with 1F indicating that it is a one-flow nozzle and must be counted as one flow number.

When using the 1F nozzle for range protection with or without back shelf or other similarly sized obstruction, the maximum length of the burner grates being protected must not exceed 28 in. (71 cm) and the maximum area of the burner grates must not exceed 336 in.<sup>2</sup> (2168 cm<sup>2</sup>). See Figure 37 for nozzle location details.

**1F NOZZLE**  
 SHELF OR OTHER SIMILARLY SIZED OBSTRUCTION CAN OVERHANG BURNER(S) BY A MAXIMUM OF 11 IN. (28 cm)  
 20 IN. (51 cm) MINIMUM  
 40 - 48 IN. (102 - 122 cm)  
 AIM POINT



**FIGURE 37**  
 0002389

IF NOZZLE LOCATED OVER FRONT EDGE OF BURNER GRATE AND ORIENTED SO NOZZLE TIP FLATS ARE PARALLEL WITH BURNER GRATE FRONT TO REAR CENTERLINE AND SHALL BE AIMED AT THE CENTER OF THE COOKING SURFACE.

Gridle Protection 290 (2-Flow) Nozzle - Medium Proximity Application

Option 2a - Nozzle Perimeter Located (Continued)

20 in. to 30 in. (51 cm to 76 cm) above the cooking surface. The medium proximity application uses the 290 nozzle, Part No. 419342.

The nozzle tip is stamped with 290 indicating this is a two-flow nozzle and must be counted as two flow numbers.

One 290 nozzle will protect a maximum cooking area of 1440 in.<sup>2</sup> (9290 cm<sup>2</sup>) with a maximum dimension of 48 in. (122 cm).

When using this nozzle for grille protection, the nozzle must be positioned along the perimeter to 2 in. (5.1 cm) inside the perimeter, and aimed at the center of the cooking surface. See Figure 45 and 46




FIGURE 45 000241




FIGURE 46 000243

Gridle Protection 260 (2-Flow) Nozzle - High Proximity Application

Option 2 - Nozzle Perimeter Located

This high proximity application uses the 260 nozzle, Part No. 419341.

The nozzle tip is stamped with 260 indicating this is a two-flow nozzle and must be counted as two flow numbers.

One 260 nozzle will protect a maximum cooking area of 1440 in.<sup>2</sup> (9290 cm<sup>2</sup>) with a maximum dimension of 48 in. (122 cm).

When using this nozzle for grille protection, the nozzle must be positioned along the cooking surface perimeter to 2 in. (5.1 cm) inside perimeter, and aimed at the center of the cooking surface. See Figure 43 and 44.




FIGURE 43 000243




FIGURE 44 000241

**Griddle Protection 1W (1-Flow) Nozzle - Low Proximity**

The low proximity 1-flow nozzle application for the protection of griddles requires the 1W nozzle, Part No. 419336.

The nozzle tip is stamped with 1W indicating that this is a one-flow nozzle and must be counted as one flow number.

When using the 1W nozzle for low proximity griddle protection without obstruction, the maximum length of the cooking surface to be protected must not exceed 26 in. (66.0 cm). The nozzle must be centered at one end of the maximum 26 in. (66.0 cm) length, aimed along a centerline to a point 20 in. (50.8 cm) from the end of the length, protecting a maximum width of 20.5 in. (52.1 cm).

The 1W nozzle tip must be positioned at or below the obstruction, if present. The protected area begins at the point straight down from the nozzle tip. The nozzle can be positioned above the edge of the hazard area to be protected. See Figures 51 and 52.

**Note:** If the hazard area exceeds the single nozzle coverage listed above, additional nozzles will be required. The additional nozzle can be positioned in front at high proximity or at the side at low proximity.




FIGURE 51




FIGURE 52

**Overhead Chain Broiler Protection (Continued)**

**Example No. 1** - Internal broiler size is 24 in. long x 20 in. wide (61 x 51 cm), with an opening of 16 in. x 16 in. (40.6 x 40.6 cm).

To determine minimum opening size, multiply the internal length and the internal width by 0.6:

Length of opening - 24 in. x 0.6 = 14.4 in.

(61 cm x 0.6 = 36.6 cm)

Width of opening - 20 in. x 0.6 = 12.0 in.

(51 cm x 0.6 = 30.5 cm)

The minimum allowable opening for overhead protection would be 14.4 in. x 12.0 in. (36.6 x 30.5 cm).

This example would be acceptable for overhead protection.

**Example No. 2** - Internal broiler size is 30 in. long x 24 in. wide (76 x 61 cm) with an opening of 22 in. x 12 in. (56 x 30 cm).

To determine minimum opening size, multiply internal length and internal width by 0.6:

Length of opening - 30 in. x 0.6 = 18.0 in.

(76 cm x 0.6 = 45.7 cm)

Width of opening - 24 in. x 0.6 = 14.4 in.

(61 cm x 0.6 = 36.6 cm)

Minimum allowable opening for overhead protection would be 18 in. x 14.4 in. (45.7 x 36.6 cm).


Because this broiler has an opening of 22 in. x 12 in., the 12 in. width is below the minimum allowable calculated dimension of 14.4 in. (36.6 cm) and therefore would not be acceptable for overhead protection.

**Salamander Broiler Protection**

The R-102 system uses three different nozzle locations for salamander broiler protection. All of the design options require a one-flow nozzle.

**Salamander Broiler Protection - 1N (1-Flow) Nozzle Overhead**  
 A salamander broiler with a maximum hazard area (internal broiler chamber) of 16 in. (41 cm) deep x 29 in. (74 cm) wide can be protected using a 1N nozzle, Part No. 419335. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle.

The single 1N nozzle must be located directly in line with either vertical edge of the broiler opening, 6 in. (15 cm) to 12 in. (30 cm) in front of the broiler, and 0 in. to 12 in. (30 cm) above the top of the broiler. The nozzle must be aimed at the center of the broiler opening. See Figure 57a.




**FIGURE 57a**  
 008426

**Salamander Broiler Protection - 1F (1-Flow) Nozzle Overhead**

A salamander broiler with a maximum hazard area (internal broiler chamber) of 15 in. (38 cm) deep x 31 in. (79 cm) wide can be protected using a 1F nozzle, Part No. 419333. The nozzle tip is stamped with 1F, indicating that this is a one-flow nozzle.

The single 1F nozzle must be located directly in line with the center of the broiler opening, 8 in. (20 cm) to 12 in. (30 cm) in front of the broiler and 12 in. (30 cm) to 18 in. (46 cm) above the top of the broiler. The nozzle must be aimed at the center of the top broiler opening when the grate is located in the middle position. The nozzle must be orientated so the nozzle tip flats are parallel with the grate left to right centerline. See Figure 57b.




**FIGURE 57b**  
 008426

**Salamander Broiler Protection - 1N (1-Flow) Nozzle Local**

A salamander broiler with a maximum hazard area (internal broiler chamber) of 15 in. (38 cm) deep x 31 in. (79 cm) wide can be protected using a 1N nozzle, Part No. 419335. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle.

The single 1N nozzle must be located above the grate on either vertical edge of the broiler opening. The nozzle must be aimed at the center of the grates. See Figure 57c.



**FIGURE 57c**  
 008426

**Natural Charcoal Broiler Protection**

The R-102 system uses the 1N Nozzle (Part No. 419335) for all natural charcoal broiler protection. The nozzle tip is stamped with 1N indicating that this is a one-flow nozzle and must be counted as one flow number.

One 1N nozzle will protect a hazard area which has a maximum length of 24 in. (61 cm) and a total cooking area which does not exceed 288 in.<sup>2</sup> (1858 cm<sup>2</sup>). The nozzle tip must be located 18 to 40 in. (46 to 102 cm) above the hazard surface. When using this nozzle for natural charcoal broiler protection, the nozzle must be positioned anywhere along or within the perimeter of the maximum cooking area and aimed at the center of the cooking surface. See Figure 61.

The coverage of such appliances only applies when the depth of the charcoal does not exceed 4 in. (10 cm).




FIGURE 61

**Lava Rock (Ceramic) Char-Broiler Protection**

The R-102 system uses the 1N Nozzle (Part No. 419335) for all lava rock char-broiler protection. The nozzle tip is stamped with 1N, indicating that this is a one-flow nozzle and must be counted as one flow number.

One 1N nozzle will protect a hazard which has a maximum length of 24 in. (61 cm) and a total cooking area which does not exceed 312 in.<sup>2</sup> (2013 cm<sup>2</sup>). The nozzle tip must be located 18 to 35 in. (46 to 89 cm) above the hazard surface. When using this nozzle for lava rock (ceramic) char-broiler protection, the nozzle must be positioned anywhere along or within the perimeter of the maximum cooking area and angled to the center. See Figure 60.




FIGURE 60

2. A 1N Nozzle, Part No. 419335, will protect a wok 11 in. (28 cm) minimum diameter up to 24 in. (61 cm) maximum diameter. The wok depth must be no less than 3 in. (8 cm) and no greater than 6 in. (15 cm). The nozzle tip is stamped with 1N indicating that this is a one-flow nozzle and must be counted as one flow number. When using this nozzle, the nozzle must be positioned anywhere along or within the perimeter of the wok, aimed at the center, 30 in. to 40 in. (76 to 102 cm) above the hazard surface, as shown in Figure 65.

**NOTICE**

When using this type of wok protection, only 5 flow numbers are allowed on a 1 1/2 gal (5.7 L) system, and only 11 flow numbers are allowed on a 3 gal (11.4 L) system.




FIGURE 65  
 000261

**Wok Protection**

The R-102 system uses two different nozzles for the protection of woks.

1. A 260 nozzle, Part No. 419341, will protect a wok 14 in (36 cm) minimum diameter up to 30 in. (76 cm) maximum diameter. The wok depth must be no less than 3.75 in. (9.5 cm) and no greater than 8 in. (20 cm). The nozzle tip is stamped with 260 indicating that this is a two-flow nozzle and must be counted as two flow numbers. When using this nozzle, the nozzle must be positioned as shown in Figure 64.

NOZZLE MUST BE POSITIONED WITHIN 1 IN (2 cm) RADIUS OF THE CENTER OF THE WOK, POINTED VERTICALLY DOWN




FIGURE 64  
 000261

Nozzle Application Chart (Continued)

Flow No.	Stamping - Nozzle Tip	Part No.	Nozzle	Height	Nozzle Quantity	Minimum Nozzle	Dimensions	Hazard	Hazard (Non-Spill Vat Only)*
230	419339	419340	27 - 47 in.	20 - 27 in.	1	1	High Proximity (38 cm x 36 cm) 15 in. x 14 in. (Fry Pot must not exceed 14 in. (36 cm) x 21 in. (53 cm) (with drip board) Maximum Size	Fryer (Non-Spill Vat Only)*	
245	419339	419340	27 - 47 in.	20 - 27 in.	1	1	High Proximity (38 cm x 36 cm) 15 in. x 14 in. (Fry Pot must not exceed 14 in. (36 cm) x 21 in. (53 cm) (with drip board) Maximum Size	Fryer (Non-Spill Vat Only)*	
290	419338	419342	21 - 34 in.	13 - 16 in.	1	1	High Proximity (48.2 cm) (49.5 cm) x 19 in. (Fry pot side must not exceed 19 1/2 in. (with drip board) Maximum Size	Fryer (Non-Spill Vat Only)*	
290	419338	419338	25 - 35 in.	(64-89 cm)	1	1	High Proximity x 27 3/4 in (70.5 cm) 18 in (45.7 cm) (with drip board) Maximum Size	Fryer (Non-Spill Vat Only)*	
290	419342	419342	13 - 16 in.	(33 - 41 cm)	1	1	Low Proximity 14 in. (36 cm) x 21 in. (53 cm) (with drip board) Maximum Size	Fryer (Non-Spill Vat Only)*	
290	419342	419342	16 - 27 in.	(41 - 69 cm)	1	1	14 1/2 in (37 cm) x 26 1/2 in. (67 cm) (with drip board) Maximum Size	Fryer (Non-Spill Vat Only)*	
1N	419335	419335	30 - 40 in.	(76 - 102 cm)	1	1	Longest Side (High Proximity) 32 in. (81 cm) Area - 384 sq. in. (2477 sq cm)	Range	
1N	419335	419335	15 - 20 in.	(38 - 51 cm)	1	1	Longest Side (Low Proximity) 24 in. (61 cm) Area - 432 in. <sup>2</sup> (2787 cm <sup>2</sup> )	Range	
1F	419333	419333	40 - 48 in.	(102 - 122 cm) (With Backshell)	1	1	Longest Side 28 in. (71 cm) Area - 336 sq in. (2168 sq cm)	Range	
245	419340	419340	40 - 50 in.	(102 - 127 cm)	1	1	Longest Side (High Proximity) 28 in. (71 cm) Area - 672 sq in. (4335 sq cm)	Range	
260	419341	419341	30 - 40 in.	(76 - 102 cm)	1	1	Longest Side (Medium Proximity) 32 in. (81 cm) Area - 768 sq in. (4955 sq cm)	Range	

\* For multiple nozzle protection of single fryers, see detailed information on Pages 4-10 and 4-11


Nozzle Application Chart (Continued)

Hazard	Dimensions	Minimum Nozzle Quantity	Nozzle Heights	Nozzle Part No.	Nozzle Tip Flow No. Stamping -
Lava-Rock or Natural Charcoal Char-Broiler	Longest Side - 30 in (76 cm) Area - 720 sq in (4645 sq cm)	1	14 - 40 in. (36 - 102 cm)	419338	3N
Wood Fueled Char-Broiler	Longest Side - 30 in (76 cm) Area - 720 sq in (4645 sq cm)	1	14 - 40 in (36 - 102 cm)	419338	3N
Upright Broiler	Length - 32.5 in (82.5 cm) Width - 30 in (76 cm)	2	-	419334	1/2N
Salamander Broiler	Length - 29 in (74 cm) Width - 16 in (41 cm)	1	-	419335	1N
	Length - 31 in (79 cm) Width - 15 in (38 cm)	1	-	419333	1F
	Length - 31 in (79 cm) Width - 15 in (38 cm)	1	-	419335	1N
Wok	14 in - 30 in (36 - 76 cm) Diameter 3 75 - 8.0 in (9.5 - 20 cm) Deep	1	35 - 45 in (89 - 114 cm)	419341	260
	11 in - 24 in (28 - 61 cm) Diameter 3 0 - 6.0 in (8 - 15.2 cm) Deep		30 - 40 in (76 - 102 cm)	419335/435672	1N/1NSS

\* Minimum chain broiler exhaust opening - 12 in. x 12 in (31 cm x 31 cm) and not less than 80% of internal broiler size

# Lake City Parking & Seafood Restaurant Modifications

1620 W US Highway 90  
Lake City Florida 32025  
for  
Hurst Contracting, Inc.  
P.O. Box 551260  
Jacksonville, FL 32255



VICINITY MAP  
N T S

**ALMOND**  
ENGINEERING  
CONSULTING CIVIL ENGINEERS  
- ENGINEERING - WATER RESOURCES - STORMWATER DESIGN -  
- REGULATORY PERMITTING - PLANNING -  
3609 HENDRICKS AVENUE  
JACKSONVILLE FL 32207  
JACKSONVILLE FL 32207  
3609 HENDRICKS AVENUE  
JACKSONVILLE FL 32207  
JACKSONVILLE FL 32221  
(904) 306-0162 PHONE - (904) 306-2185 FAX  
CERTIFICATE OF AUTHORIZATION NO 27254



Sheet No	Description
1	COVER
2	GENERAL NOTES
3	EXISTING CONDITIONS DEMOLITION
4	EXISTING UTILITIES
5	MASTER SITE PLAN
6	HORIZONTAL CONTROL
7	PAVING GRADING AND DRAINAGE
8	UTILITIES
9	GENERAL DETAILS
10	GENERAL DETAILS
11	LIFE SAFETY PLAN
12	SEDIMENT AND EROSION CONTROL PLAN
13	CONTRACTOR CERTIFICATION SHEET
14	STORM WATER PREVENTION PLAN
15	MAINTENANCE OF TRAFFIC
16	LANDSCAPE PLAN
IR-1	IRRIGATION PLAN

**IF YOU DIG IN FLORIDA**  
CALL US FIRST!  
1-800-432-4770  
SUNSHINE STATE ONE-CALL OF FLORIDA, INC  
IT'S THE LAW

## GENERAL PROJECT INFORMATION

GENERAL  
City Development Number N/A  
Concurrence Application Number N/A  
Property Appraiser Number (RE #) 31-35-17-06214-000  
Zoning Designation MKT  
PUD Ordinance Number N/A  
FRM - Community - Panel X  
Flood Zones (Show in Plans) ZONE XI  
Base Flood Elev (map #1202101222) XXXXXX  
Vertical Datum Used for Project NAVD-88  
JEA Availability Number N/A  
SURWMD Permit Number N/A  
SUBDIVISION  
PSD Number N/A  
City or Private Inspection N/A  
Public or Private Roads N/A  
Subdivision ('911') Disk Provided? N/A  
NON-SUBDIVISION  
Classification System (NAICS) \_\_\_\_\_  
North American Industry \_\_\_\_\_  
ImperVIOUS Area (Sq Ft) \_\_\_\_\_



LAKE CITY PARKING &  
SEAFOOD RESTAURANT  
MODIFICATIONS  
(AE PROJECT #14-03)

**ALMOND**  
ENGINEERING  
CONSULTING CIVIL ENGINEERS



REVISION INFO	DATE	DESC.
SUBMITTAL #1		
SUBMITTAL		





**SITE DATA SUMMARY**

PROJECT SUMMARY:	TOTAL SITE AREA: 50,217.87 SF (1.15 Ac)
EXIST PMWT AREA: 13,766.33 SF (0.316 Ac) (27.4%) (CONC.)	NEW PMWT AREA: 18,808.97 SF (0.604 Ac) (39.45%) (ASPH)
BUILDING AREA: 5,683.95 SF (0.13 Ac) (11.32%)	TOTAL BUILDING AREA: 5,683.95 SF (0.13 Ac) (11.32%)
CITY OF JACKSONVILLE MINIMUM PARKING REQUIREMENTS	
OFF STREET PARKING REQUIREMENTS: STAND ALONE RESTAURANT: 1 SPACES PER 4 SEATS PLUS 1 SPACE PER 2 EMPLOYEES (200 / 4) + (20 / 2) = 60 (USE 60)	
MIN PARKING REQ'D: 60 SPACES REQ'D.	
HANDICAPPED PARKING REQUIREMENTS: * PER FLORIDA STATUTE 316.1955 & 316.1956 * PER A.D.A.G. § 4.1.2 (5)	
TOTAL PARKING REQUIRED ACCESSIBLE SPACES	1-26
26-50	51-75
76-100	101-150
151-200	
PARKING REQ'D: 2 SPACE	
PARKING PROVIDED: 3 SPACE	
TOTAL OFF STREET VEHICLE PARKING:	
PARKING REQ'D: 60 SPACES	
PARKING PROVIDED: 72 SPACES	

**ALMOND ENGINEERING**  
CONSULTING CIVIL ENGINEERS  
3609 HENDRICKS AVENUE JACKSONVILLE, FL 32207  
(904) 306-0162 PHONE (904) 306-2185 FAX


LAKE CITY PARKING & SEAFOOD RESTAURANT MODIFICATIONS

MASTER SITE PLAN



AE JOB NO. 14-03  
DESIGN: E.J.A.  
DRAWN: T.K.B.  
CHECKED: E.J.A.  
START DATE: 4-25-14  
PLOT DATE: 7-31-2014

Professional Engineer Seal for Eric John Almond, License No. 59248, State of Florida.

Date	Review







NOTES:  
1. ALL THE FACILITIES AND ELEMENTS OF THE SITE (INCLUDING ACCESSIBLE ROUTES AND PARKING) SHALL MEET THE REQUIREMENTS OF THE FLORIDA ACCESSIBILITY CODE FOR BUILDING CONSTRUCTION (FACBC), THE AMERICANS WITH DISABILITY ACT ACCESSIBILITY GUIDELINES (ADAAG) ESTABLISHED BY FLORIDA LAW AND THE FAIR HOUSING ACT IF APPLICABLE.

**LEGEND**

- PROJECT BOUNDARY
- EXISTING CONTOURS
- SPOT ELEVATION
- SOIL NUMBERS
- SOIL DIVIDE LINE
- SOIL BEARING LOCATION
- TIME OF CONCENTRATION PATH
- RUNOFF FLOW ARROW
- DRAINAGE DIVIDE
- BRN NODAL AREA NAME & AREA
- JURISDICTIONAL WETLAND AREA

WET-2  
6.15 Ac.  
6  
21.50


NOTE: SEE ARCHITECT LIFE SAFETY PLAN FOR ADA ACCESSIBLE FIRE EXIT

**ALMOND ENGINEERING**  
CONSULTING CIVIL ENGINEERS  
3609 HENRICKS AVENUE, JACKSONVILLE, FL 32207  
(904) 306-0162 PHONE (904) 306-2185 FAX

LAKE CITY PARKING & SEAFOOD RESTAURANT MODIFICATIONS

PAVING, GRADING, AND DRAINAGE

AE JOB NO.: 14-03  
DESIGN: E.J.A.  
DRAWN: T.K.B.  
CHECKED: E.J.A.  
START DATE: 4-25-14  
PLOT DATE: 7-31-2014





**3** SIDEWALK SECTION

NOTES:  
 1 CONCRETE SHALL BE 3000 PSI, MIN SLUMP 5  
 2 SAW CUT CONTROL JOINTS AT SPACING EQUAL TO WIDTH OF SIDEWALK  
 3 INSTALL EXPANSION JOINT AT EVERY FOURTH CONTROL JOINT (25' MAX)

**2** TYPICAL ASPHALT PAVEMENT

NOTE:  
 SOIL ANALYSIS MAY INDICATE THE NEED FOR A THICKER BASE COURSE. THE PAVEMENT THICKNESS MAY BE MODIFIED TO ACCOMMODATE THE BEARING CAPACITY OF VARIOUS SUBGRADES.

**1** CURB & GUTTER

TYPE "A" CURB  
 TYPE "B" CURB  
 TYPE "C" CURB

**6** CURB RAMP W/O LANDING

**5** STANDARD HANDICAP RAMP DETAILS

**7** RAMP DETAIL (SIDEWALK FLUSH W/ CURB)

FDOT-TYPE F  
 FDOT-TYPE B

**9** HANDICAP SIGN AND POST

NOTES:  
 1 TOP PORTION SHALL HAVE A REFLECTIVE BLUE BACKGROUND WITH WHITE REFLECTIVE SYMBOL AND BORDER  
 2 BOTTOM PORTION SHALL HAVE A REFLECTIVE WHITE BACKGROUND WITH BLACK SYMBOL AND BORDER  
 3 FINAL TY SIGN SHALL HAVE A REFLECTIVE BLUE BACKGROUND WITH REFLECTIVE WHITE LEGEND AND BORDER

**8** TRUNCATED DOME

**10** HANDICAP PAVEMENT MARKINGS

**11** STORM SEWER INLET - TYPE "C"

**9** PAVING, GRADING, AND DRAINAGE

**9** PAVING, GRADING, AND DRAINAGE

**JALMOND ENGINEERING**  
 CONSULTING CIVIL ENGINEERS  
 5609 HENDRICKS AVENUE JACKSONVILLE, FL 32207  
 (904) 506-0162 PHONE (904) 506-2185 FAX



LAKE CITY PARKING & SEAFOOD RESTAURANT MODIFICATIONS

GENERAL DETAILS

AE JOB NO.: 14-03  
 DESIGN: E.J.A.  
 DRAWN: T.K.B.  
 CHECKED: E.J.A.  
 START DATE: 4-25-14  
 PLOT DATE: 7-31-2014

ERIC JOHN ALMOND  
 PROFESSIONAL ENGINEER  
 LICENSE NO. 59246






11


**ALMOND**  
 ENGINEERING  
 CONSULTING CIVIL ENGINEERS  
 5609 HENDRICKS AVENUE JACKSONVILLE FL 32207  
 (904) 306-0162 PHONE (904) 306-2185 FAX

LAKE CITY PARKING &  
 SEAFOOD RESTAURANT  
 MODIFICATIONS

LIFE SAFETY PLAN

AE JOB NO.: 14-03  
 DESIGN: E.L.A.  
 DRAWN: T.K.B.  
 CHECKED: E.L.A.  
 START DATE: 4-25-14  
 PLOT DATE: 7-31-2014





IF YOU DIG IN FLORIDA,  
CALL US FIRST!  
1-800-432-4770  
SUNSHINE STATE ONE-CALL OF FLORIDA, INC.  
IT'S THE LAW

**LEGEND**

SILT FENCES TO BE INSTALLED  
BY THE CONTRACTOR

HAY BALES OR SEDIMENT  
FILTER AROUND EACH  
DRAINAGE STRUCTURE

12

**ALMOND**  
ENGINEERING

CONSULTING CIVIL ENGINEERS  
5609 HENRICKS AVENUE JACKSONVILLE, FL 32207  
(904) 506-0162 PHONE (904) 506-2185 FAX

LAKE CITY PARKING &  
SEAFOOD RESTAURANT  
MODIFICATIONS

SEDIMENT AND EROSION  
CONTROL PLAN

AE JOB NO.: 14-03  
DESIGN: E.L.A.  
DRAWN: T.K.B.  
CHECKED: E.L.A.  
START DATE: 1-25-14  
PLOT DATE: 7-31-2014

**ERIC JOHN ALMOND**  
Professional Engineer  
No. 59246










STATE OF FLORIDA  
Professional Engineer

Date	Revision



SEDIMENT AND EROSION CONTROL NOTES

1. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING SILT FROM SITE IF NOT RESISTANT ON SWALES AT COMPLETION OF CONSTRUCTION.  
 2. THE SITE CONTRACTOR IS RESPONSIBLE FOR REMOVING THE TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AFTER COMPLETION OF CONSTRUCTION AND ONLY AREAS HAVE BEEN STABILIZED.  
 3. ADDITIONAL PROTECTION - ON-SITE PROTECTION IN ADDITION TO THE ABOVE MUST BE PERMITTED TO PREVENT SILT TO LEAVE THE PROJECT DURING ALL WEATHER CONDITIONS OR ACCIDENTS.  
 4. CONTRACTOR SHALL INSURE THAT ALL DRAINAGE STRUCTURES, PIPES, ETC. ARE CLEANED OUT AND WORKING PROPERLY AT TIME OF ACCEPTANCE.  
 5. WIRE MESH SHALL BE LAID OVER THE DROP INLET SO THAT THE WIRE EXTENDS A MINIMUM OF 1 FOOT BEYOND EACH SIDE OF THE INLET.  
 6. WIRE MESH SHALL BE USED FOR CONSTRUCTION NOT COVERED BY THE OWNERS NOTICE OF INTENT PERMIT.  
 7. IF THE STONE FILTER BECOMES CLOGGED WITH SEDIMENT SO THAT IT IS PULLED AWAY FROM THE INLET, CLEANED AND REPLACED.  
 8. BALES SHALL BE EITHER WIRE-BOUND OR STRUNG TOGETHER WITH THE PINNERS ORIENTED AROUND THE SIDE RATHER THAN OVER AND UNDER THE BALES.  
 9. BALES SHALL BE PLACED LENGTHWISE IN A SINGLE ROW SURROUNDING THE INLET, WITH THE ENDS OF ADJACENT BALES PRESSED TOGETHER.  
 10. THE FILTER BARRIER SHALL BE ENTRENCHED AND BACKFILLED AFTER THE BALES ARE STAPLED TO THE EXCAVATED SOIL.  
 11. EACH BALE SHALL BE SECURELY ANCHORED AND HELD IN PLACE BY AT LEAST TWO STAKES OR REBARS DRIVEN THROUGH THE BALE.  
 12. LOOSE STRAW SHOULD BE WEDGED BETWEEN BALES TO PREVENT WATER FROM ENTERING BETWEEN BALES.  
 13. STRAW BALE BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL.  
 14. END RUNS AND UNDERCUTTING BENEATH BALES.  
 15. NECESSARY REPAIRS TO BARRIERS OR REPLACEMENT OF BALES SHALL BE ACCOMPLISHED PROMPTLY.  
 16. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH RAINFALL.  
 17. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE STRAW BALE OR FILTER BARRIERS AND OR SILT FENCES NO LONGER REQUIRED SHALL BE APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.  
 18. RAINFALL ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.  
 19. SHOW THE METHOD OF FILTER BARRIER DECOMPOSITION OR DISPOSAL OF THE BALE.  
 20. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NEEDED.  
 21. SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP AND IN SUCH A MANNER THAT IT WILL NOT ERODE.  
 22. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING THE BEST EROSION AND SEDIMENT CONTROL MEASURES AS OUTLINED IN THE PLAN AND SPECIFICATIONS AND CHAIRMAN.  
 23. REFER TO THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (F.D.E.P.) CHAPTER 62-280 AND WATER MANAGEMENT FROM THE STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL REGULATION (F.D.E.R.) CHAPTER 6.  
 24. EROSION AND SEDIMENT CONTROL BARRIERS SHALL BE PLACED ADVANTAGE TO ALL METAL AND AREAS WHERE THERE IS POTENTIAL FOR TYPICAL CONSTRUCTION.  
 25. SOIL SHALL BE PLACED IN AREAS WHICH MAY REQUIRE IMMEDIATE EROSION PROTECTION TO ENSURE WATER QUALITY STANDARDS ARE MAINTAINED.  
 26. ANY DISCHARGE FROM DEWATERING ACTIVITY SHALL BE FILTERED AND TRANSPORTATION OF SUSPENDED SOLIDS TO THE RECEIVING OUTFALL.  
 27. DRAINAGE PIPES SHALL NOT EXCEED THE CAPACITY OF THAT WHICH WATER MANAGEMENT DISTRICT.  
 28. ALL DISTURBED AREAS SHALL BE GRASSED, FERTILIZED AND MULCHED UNTIL A PERMANENT VEGETATION COVER IS ESTABLISHED.  
 29. SLOPE SHALL NOT BE STEEPER TO RECEIVE STAKED SOLID SOIL.  
 30. ALL DISTURBED EROSION AND SEDIMENT CONTROL SHALL REMAIN IN PLACE UNTIL AFTER COMPLETION OF CONSTRUCTION AND REMOVED ONLY WHEN AREAS HAVE BEEN STABILIZED.  
 31. THE PLAN INDICATES THE MINIMUM EROSION AND SEDIMENT MEASURES REQUIRED FOR THIS PROJECT. THE CONTRACTOR IS RESPONSIBLE FOR MEETING ALL APPLICABLE RULES, REGULATIONS AND WATER QUALITY GUIDELINES AND MAY NEED TO INSTALL ADDITIONAL CONTROLS.  
 32. THE CONTRACTOR SHALL BE REQUIRED TO RESPOND TO ALL WATER QUALITY AND SEDIMENTATION CONTROL MEASURES TO COMPLY WITH THE COMPLIANCE SHALL BE PART OF THE CONTRACT.  
 33. EROSION AND SEDIMENT CONTROL BARRIERS SHALL BE PLACED ADVANTAGE TO ALL METAL AND AREAS WHERE THERE IS POTENTIAL FOR TYPICAL CONSTRUCTION.  
 34. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING A PERMANENT STAND OF SOIL AND/OR GRASS PER THE CONTRACT DOCUMENTS AND MEETING THE NPDES FINAL STABILIZATION REQUIREMENTS.





**ALMOND ENGINEERING**  
 CONSULTING CIVIL ENGINEERS  
 5409 HENDRICKS AVENUE JACKSONVILLE, FL 32207  
 (904) 306-0162 PHONE (904) 306-2188 FAX

LAKE CITY PARKING & SEAFOOD RESTAURANT MODIFICATIONS

STORM WATER PREVENTION PLAN


AE JOB NO.: 14-03  
 DESIGN: E.J.A.  
 DRAWN: T.K.B.  
 CHECKED: E.J.A.  
 START DATE: 4-25-14  
 PLOT DATE: 7-31-2014





- FDOT NOTES**
- No lane closures from 4:00pm to 6:30pm
  - All work performed within the Florida Department of Transportation Right-of-Way Manual shall conform to the most current edition of the following publications:
    - Standard Specifications for Road and Bridge Construction (English)
    - FDOT Standards Index (English)
    - FDOT Plans Prep Manual
    - FDOT Flexible Pavement Design Manual for New Construction and Pavement Rehabilitation
  - Should a conflict arise between the details shown in the plans and the Department of Transportation Standards the Engineer/ Permittee shall immediately confer with the Department's Engineer in order to resolve the discrepancy. In no case will anything less than the Department's minimum standard be allowed.
  - All traffic striping and markings are to be lead-free, non-solvent based thermoplastic
  - Removal of existing striping shall be accomplished using the "hydro-blast" method. If this process damages/scars pavement, then the pavement shall be milled and resurfaced per FDOT Standards.
  - Existing paved shoulder shall be removed full depth prior to widening of the roadway
  - All curb and gutter and sidewalk will be removed and replaced joint to joint.
  - All disturbed area within the Department of Transportation right of way will be restored to original or better condition by grading and sodding the area disturbed (Bermuda in rural, centpede in utility strips).
  - Burning of material and/or debris is prohibited within FDOT right-of-way.
  - All lanes must be opened for traffic during an evacuation notice of a hurricane or other catastrophic event and shall remain open for the duration of the evacuation or event.

LAST REVISION 07/10/10  
 DESCRIPTION: FDOT 2014 DESIGN STANDARDS  
 TWO-LANE, TWO-WAY WORK WITHIN THE TRAVEL WAY  
 INDEX NO. 603  
 SHEET 2 OF 2



AE JOB NO.: 14-03  
 DESIGN: E.J.A.  
 DRAWN: T.K.B.  
 CHECKED: E.J.A.  
 START DATE: 4-26-14  
 PLOT DATE: 7-31-2014

MAINTENANCE OF TRAFFIC  
 LAKE CITY PARKING &  
 SEAFOOD RESTAURANT  
 MODIFICATIONS

**ALMOND**  
 ENGINEERING  
 CONSULTING CIVIL ENGINEERS  
 3609 HENDRICKS AVENUE JACKSONVILLE, FL 32207  
 (904) 308-0162 PHONE (904) 308-2185 FAX



