

ADDENDUM NO. 5
TO THE DRAWINGS AND PROJECT MANUAL
FOR
FIRE STATION
RACE TRACK LANE, LAKE CITY, FL
COLUMBIA COUNTY BOARD OF COUNTY COMMISSION

ARCHITECT'S PROJECT NO. 0715

CRAIG SALLEY & ASSOCIATES, ARCHITECTS, GAINESVILLE, FLORIDA

This Addendum shall be considered part of the Contract Documents for the above mentioned Project as though it has been issued at the same time and incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall govern and take precedence. **Bidders are hereby notified that they shall acknowledge receipt of this Addendum on their Bid Proposal Form.**

1. **PROJECT MANUAL, SECTION 02200 – EARTHWORK:** Refer to Paragraph 3.09 – DISPOSAL OF EXCESS EXCAVATING MATERIALS and revise as follows:
 - A. Waste all excess excavated material not required for backfill or filling **on site**, to agree with Note 10 on Sheet C-1.

2. **PROJECT MANUAL, SECTION 15064 – PLASTIC PIPE AND FITTINGS, DRAWINGS, SHEET C-2 – SITE PLAN AND DRAWINGS, SHEET FP-1 – FIRE PROTECTION/SPRINKLER SYSTEM:**
 - A. Clarification on Certification/Licensing required for installing the Fire Protection Water Supply Line: The backflow device is called out on Civil Drawings C-2 and Detail B. The fire protection water supply line from the City installed tap, through the backflow preventer and to the building shall be installed by a State Certified and Licensed Fire Protection Contractor. **A Utility Contractor License is not sufficient.**
 - B. Clarification: Refer to Section 15064 for the specification for below grade PVC fire protection pipe specification.

END OF WRITTEN ADDENDUM