

**ADDENDUM #1  
BID NO. 2009-V**

**Issue Date: August 28, 2009**

**Project: Ellisville Water System Improvement – Expansion to US 441**

This ADDENDUM is issued to institute the included changes, additions and/or deletions to the Plans and Specifications for the construction of the **ELLISVILLE WATER SYSTEM IMPROVEMENTS – EXPANSION TO HWY 441** for **COLUMBIA COUNTY** and hereby becomes a part of said Plans and Specifications. Where an item on the original Plans and Specifications is amended, voided, or superseded by a modification contained in the ADDENDUM, the provisions of such item not specifically amended, voided, or superseded shall remain in effect.

**Bid Documents**

The Bid Form (Bid Schedule) has been revised. The revised Bid Schedule is attached to this addendum.

**Each bid submitted in response to this Request for Bids shall include an acknowledgement of this addendum.**

**COLUMBIA COUNTY  
ELLISVILLE WATER SYSTEM  
BID SCHEDULE**

| <b>1.0 WATER SYSTEM IMPROVEMENTS</b>  |    | <b>Unit</b> | <b>Quantity</b> | <b>Unit Price</b> | <b>Total</b> |
|---|----|-------------|-----------------|-------------------|--------------|
| 12" C-900 (DR-18) PVC Water Main(blue)<br>Installed, including fittings, tracer wire &<br>1.1 appurtenances | LF | 15,300      |                 |                   |              |
| 1.2 12" Gate Valve & Valve Box  | EA | 27          |                 |                   |              |
| 6" C-900 (DR-18) PVC Water Main(blue)<br>Installed, including fittings, tracer wire &<br>1.3 appurtenances  | LF | 3,510       |                 |                   |              |
| 1.4 6" Gate Valve & Valve Box   | EA | 6           |                 |                   |              |
| 1.5 Fire Hydrant Assembly Installed   | EA | 18          |                 |                   |              |
| Jack & Bore 24" Steel Casing (.35" wt) including<br>1.6 12" DIP carrier pipe                                | LF | 65          |                 |                   |              |
| 1.7 12" Directional Bore  | LF | 1,050       |                 |                   |              |
| 1.8 Driveway Repair (Gravel)  | SF | 2,140       |                 |                   |              |
| 1.9 Traffic Control (FDOT Index 600)  | LS | 1           |                 |                   |              |
| 1.10 Testing (Pressure and Bac'T)   | LS | 1           |                 |                   |              |
| <b>WATER SYSTEM IMPROVEMENTS TOTAL =</b>  |    |             |                 |                   |              |
| <b>2.0 ENVIRONMENTAL</b>  |    | <b>Unit</b> | <b>Quantity</b> | <b>Unit Price</b> | <b>Total</b> |
| 2.1 Silt Fencing  | LF | 2000        |                 |                   |              |
| 2.2 Tree Protection   | LF | 200         |                 |                   |              |
| 2.3 Right of Way Restoration, Seed and Mulch  | SY | 7,650       |                 |                   |              |
| 2.4 Right of Way Restoration, Sod   | SF | 74,560      |                 |                   |              |
| 2.5 Inlet Protection  | EA | 5           |                 |                   |              |
| <b>ENVIRONMENTAL TOTAL =</b>  |    |             |                 |                   |              |
| <b>3.0 PROFESSIONAL SERVICES BY CONTRACTOR</b>  |    | <b>Unit</b> | <b>Quantity</b> | <b>Unit Price</b> | <b>Total</b> |
| 3.1 Project Layout  | LS | 1           |                 |                   |              |
| 3.2 Certified As-Built by RLS   | LS | 1           |                 |                   |              |
| 3.3 Soil Testing by PE  | LS | 1           |                 |                   |              |
| <b>SERVICES TOTAL =</b>   |    |             |                 |                   |              |
| <b>4.0 START-UP</b>   |    | <b>Unit</b> | <b>Quantity</b> | <b>Unit Price</b> | <b>Total</b> |
| 4.1 Mobilization  | LS | 1           |                 |                   |              |
| 4.2 Insurance   | LS | 1           |                 |                   |              |
| <b>START-UP TOTAL =</b>   |    |             |                 |                   |              |
| <b>TOTAL AMOUNT of BASE BID =</b>   |    |             |                 |                   |              |