

**ADDENDUM #3
BID NO. 2009-W**

Issue Date: September 9, 2009

Project: Ellisville Water System Improvement – Expansion to I-75 North

This ADDENDUM is issued to institute the included changes, additions and/or deletions to the Plans and Specifications for the construction of the **ELLISVILLE WATER SYSTEM IMPROVEMENTS – EXPANSION TO I-75 NORTH** and hereby becomes a part of said Plans and Specifications. Where an item on the original Plans and Specifications is amended, voided, or superseded by a modification contained in the ADDENDUM, the provisions of such item not specifically amended, voided, or superseded shall remain in effect.

ADDITION OF ALTERNATE #1

The following work is hereby added to the bidding requirements:

Bid Alternate #1 - 300 feet of 12" Water Main Directional Bore under I-75

This item is being added as an alternate to the Jack and Bore Operation identified in the plans and construction documents.

The evaluation of bids will be based upon the BASE BID Amount. A revised version of the bid form is attached to this Addendum.

Each bid submitted in response to this Request for Bids shall include an acknowledgement of this addendum.

**COLUMBIA COUNTY
WATER SYSTEM IMPROVEMENTS I-75 NORTH**

BID SCHEDULE

1.0 WATER SYSTEM IMPROVEMENTS	Unit	Quantity	Unit Price	Total
12" C-900 (DR-18) PVC Water Main(blue) Installed, including fittings, tracer wire & 1.1 appurtenances	LF	12,719	_____	_____
1.2 12" Gate Valve & Valve Box	EA	15	_____	_____
6" C-900 (DR-18) PVC Water Main(blue) Installed, including fittings, tracer wire & 1.3 appurtenances	LF	5175	_____	_____
1.4 6" Gate Valve & Valve Box	EA	8	_____	_____
1.5 Fire Hydrant Assembly Installed	EA	19	_____	_____
1.6 12" DIP carrier pipe Jack & Bore 24" Steel Casing (.35" wt) including Connect to Existing PVC, Transition Coupling	LF	300	_____	_____
1.7 including Fittings	EA	1	_____	_____
1.8 Valve including Fittings Connect to Existing PVC, Tapping Sleeve &	EA	1	_____	_____
1.9 Cut & Patch Roadway	SF	280	_____	_____
1.10 3/4" Short Service Assembly Installed, Including Service Saddle, Corp Stop, and Meter	EA	29	_____	_____
1.11 3/4" Long Service Assembly Installed, Including Service Saddle, Corp Stop, Roadway Crossing and Meter	EA	20	_____	_____
1.12 "This item removed from bid schedule"			N/A	N/A
1.13 Traffic Control (FDOT Index 600)	LS	1	_____	_____
1.14 Testing (Pressure and Bac'T)	LS	1	_____	_____
WATER SYSTEM IMPROVEMENTS TOTAL =				
2.0 ENVIRONMENTAL	Unit	Quantity	Unit Price	Total
2.1 Silt Fencing	LF	2000	_____	_____
2.2 Tree Protection	LF	200	_____	_____
2.3 Right of Way Restoration, Seed and Mulch	SY	1000	_____	_____
2.4 Right of Way Restoration, Sod	SF	2500	_____	_____
2.5 Inlet Protection	EA	15	_____	_____
ENVIRONMENTAL TOTAL =				
3.0 PROFESSIONAL SERVICES BY CONTRACTOR	Unit	Quantity	Unit Price	Total
3.1 Project Layout	LS	1	_____	_____
3.2 Certified As-Built by RLS	LS	1	_____	_____
3.3 Soil Testing by PE	LS	1	_____	_____
SERVICES TOTAL =				
4.0 START-UP	Unit	Quantity	Unit Price	Total
4.1 Mobilization	LS	1	_____	_____
4.2 Insurance	LS	1	_____	_____
START-UP TOTAL =				
TOTAL AMOUNT of BASE BID =				
5.0 BID ALTERNATE NO. 1	Unit	Quantity	Unit Price	Total
5.0 Directional Bore 12" Water main under I-75	LF	300	_____	_____
BID ALTERNATE NO. 1				
TOTAL AMOUNT of BASE BID + ALTERNATE NO. 1=				