

2012-8

ADDENDUM #2

CHANGES:

1. Bid Documents pages 2 of 10 (Bid Proposal Sheet) shall be replaced with the newly revised sheet. (See attached)

Modifications were made to items 11-13 adding quantities along with a change to the units, and a Miscellaneous Asphalt pay item was added for item 13 replacing Guardrail-flared.

2. Bid Documents notes were added to Bid Documents page 3 of 10. (See attached)

Note #10, Price and payment for removal of existing guardrail shall be included in the cost under item 110-3, Removal of Existing Structure (Bridge).

Note #11, Items 11-13 may be increased, decreased, or omitted as directed by Engineer.

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2012-8
County Road 131 – NW Falling Creek Road

BID PROPOSAL

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
	ROADWAY				
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	Rework Existing Roadway	LF	25400		
4	Limerock Material	CY	6270		
5	Borrow Material	CY	2400		
6	Asphaltic Concrete - SP 12.5 (150 LBS/SY average)	TN	4650		
7	Asphaltic Concrete - SP 9.5 (110 LBS/SY average)	TN	3455		
8	Cross Drain Pipe Extensions	LS	1		
9	Shoulder	LS	1		
10	Intersections and Driveways	SY	1920		
11	Guardrail - End Anchorage	EA	4		
12	Guardrail - Tangent	LF	132		
13	Miscellaneous Asphalt	TN	100		
14	Sod	SY	20000		
15	Seed and Mulch	LS	1		
16	Pavement Markings	LS	1		
17	Staked Silt Fence	LF	500		
18	RCP - 24"	LF	392		
19	RCP - 30"	LF	168		
20	RCP - 54"	LF	168		
21	RCP (Arched) - 36" x 23"	LF	112		
22	Concrete Mitered End Section 24"	EA	16		
23	Concrete Mitered End Section 30"	EA	6		
24	Concrete Mitered End Section 54"	EA	6		
			ROADWAY TOTAL		
	BRIDGE				
110-3	Removal of Existing Structure (Bridge)	LS	1		
400-2-4	Class II Concrete (Superstructure)	CY	93.5		
400-2-5	Class II Concrete (Substructure)	CY	25		
400-2-10	Class II Concrete (Approach Slabs)	CY	21		
400-7	Bridge Deck Grooving	SY	356		
400-147	Composite Neoprene Pads	CF	1.45		
415-1-4	Reinforcing Steel (Superstructure)	LB	26406		
415-1-5	Reinforcing Steel (Substructure)	LB	4012		
415-1-9	Reinforcing Steel (Approach Slabs)	LB	4706		
455-35-5	Piling, Steel (HP 14x73)	LF	514		
458-1-11	Bridge Deck Expansion Joint, New Construction	LF	154.2		
460-2	Structural Steel - New / Widening	LS	1		
530-1	Riprap (Sand-Cement)	CY	8.2		
			BRIDGE TOTAL		
			TOTAL AMOUNT OF BID		

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2012-8
County Road 131 – NW Falling Creek Road

NOTES:

1. Item 2 includes all elements required for MOT and includes temporary centerline delineation
2. Item 3 includes trenching, limerock placement, mixing, shaping, compacting, finishing, and priming for placement of asphalt
3. Item 4 is estimated at 4 inches (loose measure), but may be increased, decreased, or omitted as directed by Engineer.
4. Item 7 Includes approximately 40 tons placed at the SR 25 (US441) intersection
5. Item 14 includes centerline, edge lines, stop bars at all intersections, and railroad markings. Two applications are required for all final striping
6. ALL INCIDENTAL WORK INCLUDE IN ABOVE ITEMS
7. All unit price and total spaces must be filled in to correlate with each item.
8. Items 18-21 will be decided upon once mixing has taken place. Contractor shall receive approval from Engineer before ordering concrete pipe.
9. Items 18-21 may be increased, decreased, or omitted as directed by Engineer.
10. Price and payment for removal of existing guardrail shall be included in the cost under item 110-3, Removal of Existing Structure (Bridge).
11. Items 11-13 may be increased, decreased, or omitted as directed by Engineer.

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the unit prices on the previous page:

FIRM _____

BY _____
President

(Seal)

ATTEST _____