

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2013-10
SW Hope Henry Street-Roadway Improvements**

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor, and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	Grading	LS	1		
4	Borrow Material	CY	500		
5	Limerock (8")	SY	1370		
6	Side Drain Pipe, (21" X 15" X 32') , CMP	EA	6		
7	Driveways	LS	1		
8	Asphaltic Concrete SP 9.5 (Leveling)	TN	205		
9	Asphaltic Concrete SP 9.5 (Surface)	TN	565		
10	Sod Strip 30"	SY	1,600		
11	Painted Pavement Markings	LS	1		
12	Mitered End Sections	EA	12		
13	Silt Fence, Type 3	LF	500		

TOTAL

Item 2 (Maintenance of Traffic) -includes all elements required for MOT, construction staking, and includes temporary centerline delineation.

Item 3 (Grading) -shall includes removing asphalt maintenance strip, trenching (2' 3" each side), and finish grading shoulder

Item 5(Limerock 8") -includes limerock material transported, placed, and compacted for 2'3" widening on each side of roadway (8" thickness)

Item 7(Driveways) -shall include 6" limerock base and 1 1/2" of SP 9.5 asphaltic concrete for (6) non paved driveways estimated at 40 sy each.

Item 8 (Asphaltic Concrete SP 9.5 Leveling) - Average spread rate shall be 75 lb/sy

Item 9 (Asphaltic Concrete SP 9.5 Surface) - Average spread rate shall be 165lb/sy and does include 11 tons for existing driveways to be resurfaced

Item 10(Sod Strip 30") -includes all areas disturbed, edge of pavement sod strip, and around mitered end sections. Areas disturbed outside normal widening practices shall be paid for by contractor.

Item 11(Painted Pavement Markings) -shall include stop bars and centerline/edgeline striping (2 coats each).

All items (unit) may be increased, decreased, or omitted as directed by the Engineer at no cost to the County.

All materials and construction shall conform to both the requirements of the latest FDOT Standard Specifications for Road and Bridge Construction and the latest FDOT Design Standards.

ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS

ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM

FIRM _____ (Seal)

BY _____
President

ATTEST _____