

**2013-9**

**ADDENDUM #1**

Item I. under General (Page 3), General Requirements

**THAT READS:**

**I. General.**

Project consists of mixing and widening existing 18' roadway to 22' for a distance of +/- 5.08 miles. The new 22' roadway will be reconstructed in two lifts. The existing pavement is limerock base and asphaltic concrete. Pavement cores are attached for general information.

**SHALL BE CHANGED TO:**

**I. General.**

Project consists of mixing and widening existing 20' roadway to 22' for a distance of +/- 5.08 miles. The new 22' roadway will be reconstructed in two lifts. The existing pavement is limerock base and asphaltic concrete. Pavement cores are attached for general information.