

- 1) Pay Item note for item 690-100 on Plan Sheet S3 states all existing Signal Equipment is to be removed including Poles, Foundations, etc... Is this note intended to only reference the Pay Items shown on the Plan Sheet which will no longer be required ie: existing Traffic Signals, Signal Cable, Flashing Controller Cabinet, and the existing Concrete Strain Poles, Span Wire, Electric Service will remain. Please clarify.

This pay item is intended to only cover the items which will no longer be needed for the new signal system. The strain poles, span wire and electric service can remain.

- 2) Could you let us know which type (name brand) Traffic Controller is required by the maintaining agency, ie: Naztec, Econolite, Eagle, etc... if any.

No preference.

- 3) Pay Item 630-2-12 (Directionally Bored Conduit) does not appear to be required for this work, was the item intended be 630-2-11 (Conduit Underground Trenched). Please clarify.

Change the 630-2-12 item to 630-2-11.

- 4) There is no Pay Item for Pull Boxes (635-2-11) but there does appear to be the need for these items. Please clarify.

Add a quantity of four (4), pay item 635-2-11 (pull boxes) to the bid.