

Addendum

Fort White Community Center
 New Restroom Building
 Fort White, Florida

Project

1642

Architect's Project Number

March 3, 2017

Date

Page 1 of 1

Pages

N/A

Attachments

Three

Addendum Number

This Addendum shall be considered part of the Contract Documents and shall be incorporated integrally into them. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall take precedence. Bidders shall acknowledge receipt of this Addendum on their Bid Form.

1. **DRAWINGS, SHEET M2 – DETAILS:** Refer to Note 5. Round sheet metal duct shall be acceptable.
2. **DRAWINGS, SHEET M2 – DETAILS:** Please take note of the float switch shown in the drain pan of the Air Handler Detail 1/M2.
3. **DRAWINGS, SHEET P1 – SUPPLY PLAN, SANITARY PLAN AND RISERS:** Add floor drains with trap primers in the Storage Room 102 and the Mechanical/Electrical Room 104.
4. **DRAWINGS, SHEET P1 – SUPPLY PLAN, SANITARY PLAN AND RISERS:** Add one hot water only bibb in the Mechanical/Electrical Room 104, locate adjacent to the cold water hose bibb. Provide a red engraved label above the hose bibb with the words "CAUTION: HOT WATER" engraved in minimum 1" high letters, mounted on wall above the hose bibb.
5. **DRAWINGS, SHEET P2 – DETAILS AND SCHEDULES:** Fixture Schedule: All flush valves shall be SLOAN only, no other manufacturers will be accepted.
6. **DRAWINGS, SHEET E1 – ELECTRICAL PLAN, RISER, SPECIFICATIONS AND SCHEDULES:** Provide 2#10 with ground to each hand dryer added in Addendum Two. The breakers are already on the panel schedules. The hand dryers will be in the original location of the paper towel dispensers, except the ones on the toilet partition will be relocated to the CMU wall adjacent to the wall hung sink.

END OF ADDENDUM