

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
COLUMBIA COUNTY PROJECT NUMBER 2019-01
Plantation Park Roadway and Water Main Construction

The undersigned, as bidder, hereby declares that he has examined the contract documents and informed himself fully in regard to all conditions pertaining to the work to be done; that he has examined the specifications for the work and other contract documents relative thereto; and that he has satisfied himself relative to the work to be performed.

The bidder agrees, if this bid is accepted, to contract with the Columbia County Board of County Commissioners to furnish everything necessary to complete the work covered by this bid and other contract documents for the Columbia County Board of County Commissioners. The Contractor assumes full responsibility for all quantities used in his/her bid. The contractor shall coordinate his construction with all proposed utilities on the site.

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	12" Water Main - c900 including restraints	LF	7038		
4	12" Gate Valve with Box	EA	19		
5	8" Water Main - c900 including restraints	LF	2355		
6	8" Gate Valve with Box	EA	6		
7	Fire Hydrant Assembly	EA	8		
8	12"x12"x8" Tee	EA	2		
9	12"x12"x12" Tee	EA	2		
10	8"x8"x8" Tee	EA	1		
11	8"x6" adapter	EA	1		
12	Service Lateral (1")	EA	9		
13	Double Service Lateral (1.5")	EA	8		
14	12" x 12.25 degree bend	EA	2		
15	12" x 22.5 degree bend	EA	2		
16	8" x 12.25 degree bend	EA	1		
17	8" x 22.5 degree bend	EA	4		
18	8" x 90 degree bend	EA	3		
19	Testing (Pressure and BacT)	LS	1		
20	As built survey	LS	1		
21	Asphaltic Conc. SP 12.5 structural	TN	344		
				BASE TOTAL:	

Because of funding restraints, the County may self perform the following items. However, the County desires the Contractor to perform the following items if budget allows.

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
A1	Silt Fence	LF	3000		
A2	Borrow	CY	1000		
A3	Subsoil Excavation	CY	333		
A4	Limerock Base(6")	SY	4746		
A5	Turnout Construction	SY	635		
A6	Commercial Stabilizing Material	CY	231		
A7	Stablizing Roadway and Shoulder	SY	5830		
A9	Seed and Mulch	LS	1		
A10	Sod	SY	1458		
A11	Retroreflective Pavement Markings	EA	200		
A12	Painted Pavement Markings	LS	1		
A13	Cross Drain, 14"x23" ERCP	LF	96		
A14	Side Drain 15"x24" ABCCMP	LF	572		
A15	Mitered End Section (18")	EA	30		
A16	Sign Single Post	EA	7		
				ALTERNATE BID:	
				Contractor Signature	