

1. With adding the limerock and 2.75" of asphalt how will the tie end to the existing concrete driveways be addressed?

Please replace original line item sheet with attached.

Saw cut driveways at +/- 13' from centerline. 10' traffic lane pavement will be placed at 2% cross slope and an asphalt transition from edge of pavement to concrete joint will be required.

See Note for Item 14.

2. Will the white edgelines be required since we're in a subdivision?

No edgeline striping is required.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2020-11**  
**SW Huntington Glen**

**BID PROPOSAL**

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	Silt Fence	LF	160		
4	Mixing Existing Pavement (10")	SY	3825		
5	Finishing Mixed Base and Shoulder	SY	5250		
7	Borrow	CY	50		
8	Subsoil Excavation	CY	850		
9	Asphaltic Conc. SP 9.5 - Surface	TN	275		
10	Asphaltic Conc. SP 12.5 - Structural	TN	330		
11	Seed and Mulch	LS	1		
12	Sod - 42"	SY	1240		
13	Painted Pavement Markings	LS	1		
14	Driveway Aprons	EA	20		

**TOTAL:**

Note for Item 14

Saw cut driveways at +/- 13' from roadway centerline. Remove concrete, replace with 6" of limerock and 1.5" of asphalt at engineers direction. This item may be increased, decreased or omitted.

Contractor Name (PRINT): \_\_\_\_\_

Contactore Signature: \_\_\_\_\_