

2020-11

SW Hunting Glen

Addendum 2

Please replace previous line item sheet with the attached.

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2020-11
SW Huntington Glen

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	Silt Fence	LF	160		
4	Mixing Existing Pavement (10")	SY	3825		
5	Finishing Mixed Base and Shoulder	SY	5250		
6	Limerock Material	TN	635		
7	Borrow	CY	50		
8	Subsoil Excavation	CY	850		
9	Asphaltic Conc. SP 9.5 - Surface	TN	275		
10	Asphaltic Conc. SP 12.5 - Structural	TN	330		
11	Seed and Mulch	LS	1		
12	Sod - 42"	SY	1240		
13	Painted Pavement Markings	LS	1		
14	Driveway Aprons	EA	20		

TOTAL:

Note for Item 14

Saw cut driveways at +/- 13' from roadway centerline. Remove concrete, replace with 6" of limerock and 1.5" of asphalt at engineer's direction. This item may be increased, decreased or omitted.

Contractor Name (PRINT): _____

Contractor Signature: _____