

**Bid No. 2021-04
CR 252 Sidewalk (LAP)**

**Addendum 1
Revised Bid Schedule**

Please see attached revised Bid Schedule.

BID SCHEDULE

BID No. 2021-04 – CR 252 (LAP)

ITEM NO.	FDOT PAY ITEM #	DESCRIPTION	EST QUANTITY	UNIT	UNIT PRICE	AMOUNT BID (EXT TOTAL)
1	0101- 1-	MOBILIZATION	1	LS		
2	0102- 1-	TRAFFIC CONTROL	1	LS		
3	0102- 60-	WORK ZONE SIGN	1260	ED		
4	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	5850	ED		
5	0104- 10- 3	SEDIMENT BARRIER	1470	LF		
6	0110-1-1	CLEARING AND GRUBBING	1	LS		
7	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	715	CY		
8	0120- 71-	REGULAR EXCAVATION (3R PROJECTS ONLY)	1	LS		
9	0285-701-	OPTIONAL BASE, BASE GROUP 01	195	SY		
10	0285-706-	OPTIONAL BASE, BASE GROUP 06	72	SY		
11	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	28.7	TN		
12	0425- 1-531	INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	1	EA		
13	0425- 2- 41	MANHOLES, P-7, <10'	1	EA		
14	0425- 3- 61	JUNCTION BOXES, J-7, <10'	1	EA		
15	0430-174-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"SD	104	LF		
16	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	10	LF		
17	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL,ROUND, 24"S/CD	19	LF		

ITEM NO.	FDOT PAY ITEM #	DESCRIPTION	EST QUANTITY	UNIT	UNIT PRICE	AMOUNT BID (EXT TOTAL)
18	0430-984-121	MITERED END SECTION, OPTIONAL ROUND, 12" SD	4	EA		
19	0515-1-2	PIPE HANDRAIL – GUIDERAIL, ALUMINUM	48	LF		
20	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	1752	SY		
21	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	102	SY		
22	0527- 2-	DETECTABLE WARNINGS	90	SF		
23	0570- 1- 2	PERFORMANCE TURF, SOD	4398	SY		
24	0700- 1- 50	SINGLE POST SIGN, RELOCATE	4	AS		
25	0701- 18101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	0.032	GM		
26	0710- 90	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	1	LS		
27	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	237	LF		
28	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	75	LF		
29	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	259	LF		
30	0711- 16-101	THERMOPLASTIC, STANDARD, OTHER SURFACE, WHITE, SOLID, 6"	0.050	GM		
31	0711- 16-201	THERMOPLASTIC, STANDARD, OTHER SURFACE, YELLOW, SOLID, 6"	0.019	GM		
TOTAL BID AMOUNT						

NOTE: This bid is a unit price bid based on estimated quantities. Final payment shall be based upon actual field measurement of quantities.

List of Unit Abbreviations:

SY Square Yards	GL Gallons	SD Side Drain
LS Lump Sum	MG Thousand Gallons	ED Each Day
CY Cubic Yards	GM Gross Miles	CD Cross Drain
EA Each	LF Linear Feet	AS Assembly
TN Tons	NM Net Miles	RCP Reinforced Concrete Pipe
HR Hour	PI Per Intersection	AC Acre

Bidder: _____ Company: _____

Address: _____

Authorized Signature: _____ Title: _____

Clearly Print Signature: _____ Title: _____

PHONE: _____ FAX: _____ DATE: _____

Email Address: _____