

**Bid No. 2021-08
CR 242A (East)**

**Addendum 1
Revised Bid Proposal and Pay Item Notes**

There have been changes made to pages 2 and 3 of the solicitation. Please see the attached revised Bid Proposal and Pay Item Notes.

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2021-08
CR 242 A (East)

BID PROPOSAL

THE UNDERSIGNED hereby propose to furnish all materials, labor and supervision for the construction of the subject project including conformance with the construction requirements and specifications for the following unit prices:

	ITEM	UNIT	QUANTITY	UNIT COST	TOTAL
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	Silt Fence	LF	515		
4	Borrow	CY	385		
5	Subsoil Excavation	CY	1500		
6	Limerock Material	TN	2200		
7	Mixing Existing Pavement, +/- 10" Depth	SY	4900		
8	Finishing Mixed Section, Base and Shoulder	SY	15500		
9	Asphaltic Conc. SP 9.5 - Surface	TN	945		
10	Asphaltic Conc. SP 12.5 - Structural	TN	1140		
11	Resurfacing County Paved Intersections	TN	100		
12	Resurfacing Driveways	TN	125		
13	Driveway Construction	SY	80		
14	Seed and Mulch	LS	1		
15	Sod - 42"	SY	4002		
16	Retroreflective Pavement Markings	EA	325		
17	Painted Pavement Markings	LS	1		

TOTAL: _____

Contractor Name (PRINT): _____

Contractor Signature: _____

COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS
PROJECT NUMBER 2021-08
CR 242 A (East)

PAY ITEM NOTES:

Maintenance of Traffic	Shall include all elements required by FDOT standards and include temporary centerline/stop bar delineation at all non-working times, stationing/offsets, and any edge of pavement reclamation where required.
Silt Fence	Shall be placed at all areas of potential stormwater runoff as directed by engineer.
Limerock Material	Shall include limerock placed by a mechanical spreader with adjustable screed to monitor and verify the limerock mat thickness before mixing begins. Limerock shall have a spread rate of 350 lbs./SY and shall be monitored by a qualified QC inspector.
Mixing	Average Depth shall be +/- 10" at engineer's direction and shall be achieved with a milling machine or engineer approved equivalent.
Finishing Mixed Base	Includes all required construction layouts, scarifying, shaping, shoulder clipping, compacting, finishing, sod placement, and priming for placement of asphalt. Any excess material along shoulder may require relocation at engineer's direction.
Borrow	Shall be placed on shoulder at direction of engineer to provide a safe edge of pavement condition
Subsoil Excavation	Item includes cost to remove 2' of unsuitable material and replace with suitable fill in 6" lifts meeting density requirements
Asphalt SP 12.5 - Structural	Includes placement of SP 12.5 @ +/-165 lb/sy.
Asphalt SP 9.5 - Surface	Includes placement of SP 9.5 @ ± 137.5 lbs/SY. To maintain level access to driveways, an apron may be required at certain driveway locations and will be paid for under this item.
Driveway Resurfacing	Item includes cost to prepare, place Asphalt SP 9.5 over existing paved driveways.
Driveway Construction	Item includes the excavation, compaction of subgrade, 6" limerock base material, base construction and placement of SP 9.5 asphalt pavement for all turnouts.
Seed and Mulch	Shall be placed at all disturbed areas not sodded, as directed by the engineer.
Sod	Includes cost to place 42" sod strip along edge of pavement and in areas directed by the engineer.
Painted Pavement Markings	Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline striping - (2 COATS EACH ITEM)

ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.

- **ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.**
- **ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM**