

**Bid No. 2021-09  
NW Hillcrest Street**

**Addendum 2  
Revised Bid Documents**

There have been changes to various pages of the solicitation. Please see the attached revised Notice to Contractors, Bid Proposal, Pay Item Notes, and General Requirements.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2021-09**  
**SW Hillcrest Street**

**NOTICE TO CONTRACTORS**

Notice is hereby given that sealed bids will be received in the Columbia County Manager's office until **2:00 P.M.** on **July 27, 2021**, for Columbia County Project No. **2021-09**. This office is located on the second floor of the Courthouse Annex at 135 Hernando Avenue, Room 203 Lake City FL 32055.

This project includes levelling and resurfacing SW Hillcrest Street from SW Wendy Ter. to US 441, a distance of 0.6 miles, with placement of asphalt in two layers: (1) Levelling at 75 lbs/SY and (2) Surface at 137.5 lbs/SY. The county roadway is a rural roadway section 18' wide (2 – 9' travel lanes)

Scope of work includes minor shoulder work, grading, asphaltic concrete pavement, erosion control, grassing, painted pavement markings, and incidental items.

The Bid Forms and Construction specifications may be obtained from the County's web site at <http://www.columbiacountyfla.com/PurchasingBids.asp>. Deadline for questions regarding construction plans, specifications, and/or bid documents must be received before **2:00 P.M.** on **July 23, 2021**. The successful bidder will be required to furnish the County Manager with a 5% bid bond with submittal, and if selected, furnish the County Manager with a performance bond and proof of liability insurance prior to commencing work.

The Columbia County Commission reserves the right to reject any or all bids and to add to the contract or delete from the contract to stay within their funding capabilities.

---

Rocky Ford  
Chair - Columbia County Board of County Commissioners



**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2021-09**  
**SW Hillcrest Street**

<b>PAY ITEM NOTES:</b>	
Maintenance of Traffic	Shall include all elements required by FDOT standards and include temporary centerline/stop bar delineation at all non-working times, stationing/offsets, and any edge of pavement reclamation where required.
Silt Fence	Shall be placed at all areas of potential stormwater runoff as directed by engineer.
Borrow	Shall be placed on shoulder at direction of engineer to provide a safe edge of pavement condition
Asphalt SP 9.5 - Levelling	Includes placement of SP 9.5 @ +/-75 lb/sy.
Asphalt SP 9.5 - Surface	Includes placement of SP 9.5 @ ± 165 lbs/SY. To maintain level access to driveways, an apron may be required at certain driveway locations and will be paid for under this item.
Paved County Intersections	Inlcudes placement of SP 9.5 @ +/- 165 lbs/SY on all county paved roadway intersections.
Seed and Mulch	Shall be placed at all disturbed areas not sodded, as directed by the engineer.
Sod	Includes cost to place 42" sod strip along edge of pavement and in areas directed by the engineer.
Painted Pavement Markings	Shall include striping the roadway back to existing layout and shall include stop bars at all stop conditions, centerline striping - (2 COATS EACH ITEM)
Sign - Single Post	Includes cost to constuct signs at engineer's direction: 2 - stop ahead signs (W3-1), 2 - Speed Limit 35 MPH signs (R2-1), 1 - right curve ahead (W1-2), and 1 - left curve ahead (W1-2)

- **ALL ITEMS MAY BE INCREASED, DECREASED, OR OMITTED AS DIRECTED BY THE ENGINEER.**
- **ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO BOTH THE REQUIREMENTS OF THE LATEST FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST FDOT DESIGN STANDARDS.**
- **ALL INCIDENTAL WORK INCLUDED IN THESE ITEMS. ALL UNIT PRICE AND TOTAL SPACES MUST BE FILLED IN TO CORRELATE WITH EACH ITEM**

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2021-09**  
**SW Hillcrest Street**

**General Requirements**

**I. General.**

This project includes levelling and resurfacing SW Hillcrest Street from SW Wendy Ter. to US 441, a distance of 0.6 miles, with placement of asphalt in two layers: (1) Levelling at 75 lbs/SY and (2) Surface at 137.5 lbs/SY. The county roadway is a rural roadway section 18' wide (2 – 9' travel lanes)

Scope of work includes minor shoulder work, grading, asphaltic concrete pavement, erosion control, grassing, painted pavement markings, and incidental items.

**II. Contract Time**

The contract time shall be **60 calendar days** from the date of contract execution. The contractor will be required to return executed contract to Esther Chung, Columbia County Purchasing Director and Chad Williams, Columbia County Engineer, within 14 days of Board approval. Time can be extended by mutual agreement of both parties. Liquidated damages shall be based on FDOT specifications. No work is allowed on Saturdays, Sundays, and/or County designated holidays.

**III. Construction and Materials**

All construction methods and materials shall conform to the requirements of the latest edition of the Florida Department of Transportation Design Standards and Florida Department of Transportation Standard Specifications for Road and Bridge Construction.

**IV. Roadway Construction Requirements**

**Levelling and Resurfacing Operations**

- Install permanent construction signs prior to any work beginning on each end of project and any County connector roads.
- Install Silt Fence as directed by Engineer prior to any earthwork activities.
- Clean roadway surface, haul away debris, square all corners and edges and apply tack coat per FDOT standards.

**COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS**  
**PROJECT NUMBER 2021-09**  
**SW Hillcrest Street**

- Place 1<sup>st</sup> course (levelling) of asphaltic concrete (SP 9.5 at 75 lb/sy). Temporary centerline striping is required.
- **CENTERLINE DELINEATION SHALL BE REQUIRED AT ALL NON-WORKING TIMES INCLUDING ONCE BOTH LANES HAVE BEEN MILLED, USING RPM'S.**
- Place borrow material and final dress as directed by Engineer.
- Place 42" wide sod strip as directed by Engineer
- Place 2<sup>nd</sup> course of asphaltic concrete (SP 9.5 at 137.5 lb/sy) to provide +/- 18 feet roadway surface.)
- Paint 1<sup>st</sup> coat of permanent centerline, and stop bars. Install raised pavement markings (RPM's).
- 2<sup>nd</sup> and final application of painted pavement markings is required. M.O.T. crew is required to prevent paint tracking.

**V. Maintenance of Traffic**

Contractor shall provide Maintenance of Traffic and it shall conform to the requirements of the latest edition of the Florida Department of Transportation Design Standards.

Flagging will be required and only one traffic lane may be closed between the hours of **8:30 A.M. to 4:30 P.M.** only.

All construction signage shall be provided by the contractor.

**CENTERLINE DELINEATION SHALL BE REQUIRED AT ALL NON-WORKING TIMES.**

**VI. Compensation**

Payment shall be made on a monthly basis on work completed with 10% retainage. Contractor invoice shall include Columbia County Invoice Cover Sheet (see attached).