

ADDENDUM NO 2
2023-02
Birley Road Reconstruction

The following change to Unit Price Schedule

Unit Price Schedule

1.

BID TABULATION FOR BIRLEY ROAD						
Pay Item No.	Pay Item Description	Quantity	Units	Unit Price	Total Cost	
101-1	Mobilization	1	LS			
101-2	Maintenance of Traffic	1	LS			
104-1-3	Sediment Barrier	6500	LF			
110-1	Clearing & Grubbing	9.6	AC			
110-4-10	Removal of Existing Concrete Pavement	311	SY			
110-7-1	Mailboxes, Furnish and Install	39	EA			
120-1	Regular Excavation	2866	CY			
120-6	Embankment	7264	CY			
210-1	Reworking Limerock Base	50024.6	SY			
210-2	Limerock, New Material for Reworking Base	2785	CY			
285-70-8	Optional Base Group 8	9264	SY			
286-1	Turnout Construction	4043	SY			
334-1-13	Superpave Asphaltic Conc. Traffic C	7652	TN			
430-174-118	Pipe Culvert, Optional Material, Round 18" S/CD	380	LF			
430-982-125	Mitered End Section, Opt, Round, 18" S/CD	10	EA			
522-2	Concrete Sidewalk and Driveways, 6" Thick	517.2	SY			
546-71-1	Raised Rumble Strip Set - Permanent	8	PS			
570-1-1	Performance Turf	22233	SY			
571-1-2	Performance Turf, Sod	13220	SY			
700-1-11	Single Post Sign, F&I Ground Mount, Up to 12 SF	33	AS			
700-1-60	Single Post Sign, Remove	23	AS			
705-11-1	Tubular, Flexible Delineator	10	EA			
706-1-3	Retroreflective Raised Pavement Markers	417	EA			
710-90	Painted Pavement Markings, Final Surface	1	LS			
*	Painted Pavement Markings, White, Solid, 24" For Stop Line	133	LF			
*	Painted Pavement Markings, White, Solid, 6"	6.24	GM			
*	Painted Pavement Markings, Yellow, Solid 6"	3.76	GM			
*	Painted Pavement Markings, Yellow, Skip 6"	1.49	GM			
		GRAND TOTAL				

Company Name: _____

END OF ADDENDUM NO. 2
(Please acknowledge receipt of Addendums)