

ADDENDUM NO 4
ITB 2025-06
HOWELL ROAD AND ELLISVILLE ACCESS ROAD

Answers to Questions

1) In drawing - Access Rd Plan & Profile - Sheet no 17, concrete sidewalk thickness has been mentioned as 6" thick. But as per the bid form there is not enough quantity shown in 6". Please confirm whether the access road sidewalk is 4" or 6" thick. **The sidewalk along access road is 4" thick.**

2) In drawing - Drainage Structure details - Sheet no 51, S-305 and S-306 are shown but not able to locate those in the plan. Can you please help identify it? **S-305 and S-306 are to be omitted from the plans.**

3) In Bid form - Optional base group quantity has been mentioned as 2351 SY (which is completely for the access road shoulder pavement). There is optional base group 1 shown for the RD21 turnouts as well. If we add that there will be an increase in the quantity. **The optional base group for turnout construction, RD21 is included in the turnout.**

4) OBG 10(6.5") – The FDOT page is kind of conflicting about this with the information. I just wanted to know that you were just wanting 6.5" of Lime rock for this and nothing extra with the sub base. **Please see the callout on typical section 4, the base is to be constructed as black base, B-12.5 per FDOT Specifications.**

5) Sheet 51 Drainage Details – We can't find a S-305 or S3-06. Just wanted to make sure that they are omitted... **S-305 and 306 have been removed from the project.**

6) Sheet 17 – I believe this quantity matches for the sidewalks to be 4" thick and not 6" as per the sidewalk detail. Please verify thickness. **Please bid the concrete ramps at STA 100+40 RT/LT as 4" Concrete ramps.**

7) Is there an area identified for construction staging area or property set aside we can use possibly from Sun Stop or something? **No additional staging areas are being provided.**

8) Bid Form, page 12, Pay Item No. 430-982-638, for a mitered-end section of an elliptical 36" CD pipe requires 2 each.

Please see sheet 13.

9) However, there is no 36" elliptical CD pipe shown on the drawings. Please provide location and/or confirm if these items are required. **Please see sheet 13.**

10) Sheet 15 – It appears that removal of various 18" CMP and structures are not noted for removal. Please verify. **The removal of existing drainage structures is included in the cost of Clearing and Grubbing, 110-1.**

END OF ADDENDUM NO. 4

(Please acknowledge receipt of Addendums)