

**ADDENDUM NO 2
ITB 2025-13
ELLISVILLE – FDOT WASTEWATER INTERCONNECT**

Questions and Answers

1. Can we get some clarification on the portable generator? I see it says 72 hour run time? Is that correct, and are we rating that run time on 100% load? It's looking like a 300 gallon tank for that long of a run time. standard tanks are 100 gallons.
 - a. 24 hours @ 100% load, 100 gallon tank is acceptable.
2. Generator type-towable or fixed?
 - a. Towable/portable.
3. Generator tank size-towable has 24 hours not 72 hours.
 - a. 24 hours @ 100% load.
4. Transfer switch- ATS or MTS?- ATS will need 2-wire start connections from gen to ATS.
 - a. ATS. Provide start wires from generator.
5. Generator size? Drawings say 40KW, Bid specs sheet say 25KVA .
 - a. 40kW.
6. Can you verify that the intent is to run the Wastewater line down the roadway edge to avoid the large tree line removal or if the intent is for the tree line to be removed in the process?
 - a. The intent of installing the Wastewater line along the roadway edge is to minimize impact to the existing trees, but some tree removal or root pruning may be needed based on site conditions (as may be seen during site visit). This section of the forcemain may be adjusted as needed to avoid existing trees, but it is generally clear enough (as can be seen during site visit) for construction as shown in the Project drawings.
7. We have been unable to gain access to the site via the contact email provided on the bid sheets. Can we verify the extent of tree removal down the south property line from Giles Martin to the DOT Station or can we get access to verify?
 - a. The intent of installing the Wastewater line along the roadway edge is to minimize impact to the existing trees, but some tree removal or root pruning may be needed based on site conditions (as may be seen during site visit). This section of the forcemain may be adjusted as needed to avoid existing trees, but it is generally clear enough (as can be seen during site visit) for construction as shown in the Project drawings.
8. Does anyone have any dimensions for the existing bar screen that needs to be replicated for the proposed discharge?
 - a. The dimensions of the existing manual bar screen shall be field confirmed by

contractor. For bidding purposes, this bar screen is nominally 24-inches wide by 48-inches long.

9. We are looking to get in a bid for this project; however, I am unable to locate any specs or diagrams for the MOT needs. Will you please provide specs or additional details on what you are looking for from an MOT perspective for this bid?
 - a. MOT shall comply with FDOT Standard Index 102-603, latest edition.
10. Is there a preference on whether the products used for this project are Domestic or Foreign?
 - a. No
11. When requesting the Bid Bond, should it be made out to both Columbia County and Florida Department of Transportation as both are owners of this project?
 - a. Columbia County Board of County Commissioners
12. Article 3- Qualifications of Bidder: in 3.01 it states that after submitting bid within 10 days of owner's request you would need to submit (D) Subcontract/supplier qualification information but in section 3.03 it states to submit following information with its bid (D) Subcontractor and supplier qualification information. Does our subcontractor need to fill out Appendix H- Schedule B- Previous Experience with Similar projects?
 - a. Contractor will complete
13. Will you please provide specs or additional details on what you are looking for from an MOT perspective for this bid?
 - a. MOT shall comply with FDOT Standard Index 102-603, latest edition.

* Note that the graphic scales shown for Sheets C-7 through C-13 of the Project drawings are incorrect. The written dimensions where shown shall govern. *