

Bid Proposal for Client Name: Shirley Woodham

Address: 7770 SW State Road 247

City, State and Zip: Lake City, FL 32024

USE LEAD SAFE WORK PRACTICES

386-628-1854

Site Built - 1960

Walk Thru Date:

March 21, 2013

Contractor Name:

George Prescott Construction Inc

Contractor Address:

8024 W Benue St. JAX FL 32220

Contractor Ph #

904-781-7381

Item #	Description	Material	Labor
1	Install ____ Air Filters - AC / HEAT - Size	REQUIRED MEASURES	
2	Install ____ Low Flow Showerhead		
3	Install ____ Aerators		
4	Install Water Heater Wrap		
5	X Install Water Line Insulate HWH		15.00 20.00
6	Install Caulk:	MEASURES NOT TO EXCEED \$500 L & M FLOOR & WALL REPAIRS NOT TO EXCEED \$500 L & M	
7	Replace ____ Exterior Doors; finish, replace rotten wood, if necessary:		
8	Minor Ceiling Repairs - Location:		
9	Minor Floor Repair - Location:		
10	Minor Wall Repair - Location:		
11	Install ____ Thresholds <i>EXT in 58.00 3.00 15.00</i>		
12	X Install Weather stripping: ACCESS. (3) DOORS & SWEEPS		75.00 65.00
13	X Replace 8 windows, caulk and finish, replace rotten wood, if necessary		1440.00 800.00
14	Repair ____ window, caulk and finish, replace rotten wood, if necessary		
15	Service Central Cooling/Heating	WEATHERIZATION MEASURES	
16	Replace Central Cooling/Heating - W/HEAT PUMP		
17	Install Thermostat		
18	Install Window Unit Cooling Only:		
19	110 - ____ BTU's 220 - ____ BTU's		
20	Install RVS Cycle Cooling/Heating Unit: HEAT PUMP		
21	110 - ____ BTU's 220 - ____ BTU's		
22	Install Gas Furnace		
23	Install Space Heater		
24	Repair Duct System:		
25	Install ____ Gas Space Heaters <i>5 Baffles 2' to cut</i>		
26	X Install Attic Insulation 1608 sq ft R-30 ROLL OUT & LID <i>No blown in.</i>		1420.00 600.00
27	Install Floor Insulation ____ sq ft R-		
28	Install MH Roof Coating		
29	Install ____ Solar Screens		
30	X ATTIC Ventilation: LOWER		35.00 35.00
31	X Install 20 CFL Bulbs: not to exceed \$100.00 Labor & Material		30.00 20.00
32	Install 18 cu ft Energy Star Refrigerator - Not to exceed \$825.00 L & M		
33	X Repair Water Heater RUN VALVE TO EXT. <i>6" 2" Eve GET. 4" x 8"</i>		
34	Replace ____ gal Water Heater w/pan and pop off relief to exterior		
35	X Install 5 Smoke Alarms: MUST BE UL 217 STANDARD BATTERY	HEALTH & SAFETY NOT TO EXCEED \$500.00 L & M	125.00 20.00
36	X Install 3 CO Alarms: MUST BE UL-2034-05 OF LAS 6-96 BATTERY		210.00 20.00
37	X Stove Venting: RANGE HOOD V.T.R. 3 Joints		175.00 70.00
38	Electrical Repair:		

TOTAL Mat & Lab \$3500.00 \$160.00
GRAND TOTAL L & M \$5120.00

NOTE: TOTAL Job can not exceed \$5,000 Labor & Materials excluding Health & Safety

Signature:

[Signature]

Date:

3/22/13

COvent