

DATE 10/07/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023695

APPLICANT KIMMY EDGLEY PHONE 752-0580

ADDRESS 590 SW ARLINGTON BLVD LAKE CITY FL 32025

OWNER JAMES & DEBORAH STEPHENSON PHONE 752-0580

ADDRESS 231 SW BONANZA GLEN LAKE CITY FL 32025

CONTRACTOR DOUG EDGLEY PHONE 752-0580

LOCATION OF PROPERTY 90W, TL ON SISTERS WELCOME RD, TL ON BUSINESS POINT DR,
8TH LOT ON LEFT

TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 114100.00

HEATED FLOOR AREA 2282.00 TOTAL AREA 4361.00 HEIGHT .00 STORIES 1

FOUNDATION CONC WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB

LAND USE & ZONING RMF-1 MAX. HEIGHT 25

Minimum Set Back Requirments: STREET-FRONT 20.00 REAR 15.00 SIDE 10.00

NO. EX.D.U. 0 FLOOD ZONE X PP DEVELOPMENT PERMIT NO. _____

PARCEL ID 13-4S-16-02952-208 SUBDIVISION SOUTHERN APPROACHES

LOT 8 BLOCK _____ PHASE _____ UNIT _____ TOTAL ACRES _____

000000838 _____ RR28211326 _____

Culvert Permit No. _____ Culvert Waiver _____ Contractor's License Number _____ Applicant/Owner/Contractor _____

CULVERT 05-0082 BK JH Y

Driveway Connection _____ Septic Tank Number _____ LU & Zoning checked by _____ Approved for Issuance _____ New Resident _____

COMMENTS: ONE FOOT ABOVE THE ROAD,

Check # or Cash 1304

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power _____ Foundation _____ Monolithic _____
date/app. by _____ date/app. by _____ date/app. by _____

Under slab rough-in plumbing _____ Slab _____ Sheathing/Nailing _____
date/app. by _____ date/app. by _____ date/app. by _____

Framing _____ Rough-in plumbing above slab and below wood floor _____
date/app. by _____ date/app. by _____

Electrical rough-in _____ Heat & Air Duct _____ Peri. beam (Lintel) _____
date/app. by _____ date/app. by _____ date/app. by _____

Permanent power _____ C.O. Final _____ Culvert _____
date/app. by _____ date/app. by _____ date/app. by _____

M/H tie downs, blocking, electricity and plumbing _____ Pool _____
date/app. by _____ date/app. by _____

Reconnection _____ Pump pole _____ Utility Pole _____
date/app. by _____ date/app. by _____ date/app. by _____

M/H Pole _____ Travel Trailer _____ Re-roof _____
date/app. by _____ date/app. by _____ date/app. by _____

BUILDING PERMIT FEE \$ 575.00 CERTIFICATION FEE \$ 21.81 SURCHARGE FEE \$ 21.81

MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$.00 WASTE FEE \$ _____

FLOOD DEVELOPMENT FEE \$ _____ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ 25.00 TOTAL FEE 718.62

INSPECTORS OFFICE [Signature] CLERKS OFFICE CH

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction


PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Application for Onsite Sewage Disposal System
Application Permit. Part II Site Plan
Application Number: 05-0082

ALL PLANS MUST BE APPROVED BY THE COUNTY HEALTH UNIT

STEPHENSON, 04-2540



1 inch = 40 feet

Site Plan Submitted By Paul L. [Signature] Date 1/17/05
Plan Approved ☒ Not Approved ☐

By M. J. [Signature] Columbia CPHU

Notes: _____

COLUMBIA COUNTY FLORIDA DEPARTMENT OF BUILDING AND ZONING

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 13-4S-16-02952-208

Building permit No. 000023695

Use Classification SFD, UTILITY

Fire: 11.84

Permit Holder DOUG EDGLEY

Waste: 24.50

Owner of Building JAMES & DEBORAH STEPHENSON

Total: 36.34

Location: 231 SW BONANZA GLEN(SOUTHERN APPROACHES, LOT 8)

Date: 08/10/2006



[Signature]
Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)

**Columbia County Building Department
Culvert Permit**

**Culvert Permit No.
000000838**

DATE 10/07/2005 PARCEL ID # 13-4S-16-02952-208
APPLICANT KIMMY EDGLEY PHONE 752-0580
ADDRESS 590 SW ARLINGTON BLVD LAKE CITY FL 32025
OWNER JAMES & DEBORAH STEPHENSON PHONE 752-0580
ADDRESS 231 SW BONANZA GLEN LAKE CITY FL 32025
CONTRACTOR EDGLEY CONSTRUCTION PHONE 752-0580
LOCATION OF PROPERTY 90W, TL ON SISTERS WELCOME RD, TL ON BUSINESS POINT DR, TL ON
BONANZA GLEN, 8TH LOT ON LEFT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT SOUTHERN APPROACHES 8

SIGNATURE

Kimmy Edgley

INSTALLATION REQUIREMENTS



Culvert size will be 18 inches in diameter with a total length of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
 - b) the driveway to be served will be paved or formed with concrete.
- Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.



Culvert installation shall conform to the approved site plan standards.



Department of Transportation Permit installation approved standards.



Other _____

**ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALLATION OF THE CULVERT.**

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00



OCT-07-2005 04:17

FIRST FEDERAL OPERATIONS

James + Deborah Stephenson
Building Permit # 23695
386 754 7155 P.01/01

THIS INSTRUMENT WAS PREPARED BY:
FIRST FEDERAL SAVINGS BANK OF FLORIDA
4705 WEST U.S. HIGHWAY 90
P.O. BOX 2029
LAKE CITY, FLORIDA 32056

PERMIT NO. _____

TAX FOLIO NO. _____

NOTICE OF COMMENCEMENT

STATE OF ~~FLORIDA~~ Michigan
COUNTY OF Calhoun

The undersigned hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

1. Description of property: Lot 8, SOUTHERN APPROACHES, UNIT 1, a subdivision according to the plat thereof as recorded in Plat Book 6, Page 88 of the public records of Columbia County, Florida.
2. General description of improvement: Construction of Dwelling
3. Owner information:
 - a. Name and address: James G. Stephenson and Deborah G. Stephenson
18130 Homer Road, Marshall MI, 49068
 - b. Interest in property: Fee Simple
 - c. Name and address of fee simple title holder (if other than Owner): NONE
4. Contractor (name and address): Edgley Construction
5. Surety:
 - a. Name and address: _____
 - b. Amount of bond: _____
6. Lender: FIRST FEDERAL SAVINGS BANK OF FLORIDA
4705 WEST U.S. HIGHWAY 90
P. O. BOX 2029
LAKE CITY, FLORIDA 32056
7. Persons within the State of Florida designated by Owner upon whom notices or other document may be served as provided by Section 713.13 (1) (a) 7., Florida Statutes: NONE
8. In addition to himself, Owner designates PAULA HACKER of FIRST FEDERAL SAVINGS BANK OF FLORIDA, 4705 West U.S. Highway 90 / P. O. Box 2029, Lake City, Florida 32056 to receive a copy of the Lienor's Notice as provided in Section 713.13 (1) (b), Florida Statutes.
9. Expiration date of notice of commencement (the expiration date is 1 year from the date of recording unless a different date is specified).

James G. Stephenson
Borrower Name
Deborah G. Stephenson
Co-Borrower Name

The foregoing instrument was acknowledged before me this 24th day of May 2005 by James G. Stephenson & Deborah G. Stephenson, who is personally known to me or who has produced driver's license for identification.

Susan J. Rhoades
Notary Public
My Commission Expires: Sept 26, 2006 Calhoun County, Michigan

SUSAN J. RHOADES
Notary Public, Calhoun County, MI
My Commission Expires Sept 26, 2006

Inst:2005013022 Date:05/13/2005 Time:14:18
DE, P. DeWitt Cason, Columbia County B:1048 P:2184

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name: **502044StephensonRes**
Address: **231 SW Bonanza Glen**
City, State: **Lake City, FL**
Owner: **Stephenson**
Climate Zone: **North**

Builder: **Edgley Const.**
Permitting Office: **Columbia**
Permit Number: **23695**
Jurisdiction Number: **221000**

- | | | |
|--|--------------------------------|-----------------------|
| 1. New construction or existing | New | ___ |
| 2. Single family or multi-family | Single family | ___ |
| 3. Number of units, if multi-family | 1 | ___ |
| 4. Number of Bedrooms | 3 | ___ |
| 5. Is this a worst case? | Yes | ___ |
| 6. Conditioned floor area (ft ²) | 2282 ft ² | ___ |
| 7. Glass area & type | Single Pane | Double Pane |
| a. Clear glass, default U-factor | 0.0 ft ² | 205.5 ft ² |
| b. Default tint, default U-factor | 0.0 ft ² | 0.0 ft ² |
| c. Labeled U-factor or SHGC | 0.0 ft ² | 0.0 ft ² |
| 8. Floor types | | |
| a. Slab-On-Grade Edge Insulation | R=0.0, 250.0(p) ft | ___ |
| b. N/A | | ___ |
| c. N/A | | ___ |
| 9. Wall types | | |
| a. Face Brick, Wood, Exterior | R=13.0, 1451.0 ft ² | ___ |
| b. Frame, Wood, Exterior | R=13.0, 60.0 ft ² | ___ |
| c. Frame, Wood, Adjacent | R=13.0, 356.0 ft ² | ___ |
| d. N/A | | ___ |
| e. N/A | | ___ |
| 10. Ceiling types | | |
| a. Under Attic | R=30.0, 2367.0 ft ² | ___ |
| b. N/A | | ___ |
| c. N/A | | ___ |
| 11. Ducts | | |
| a. Sup: Unc. Ret: Unc. AH: Interior | Sup. R=6.0, 200.0 ft | ___ |
| b. Sup: Unc. Ret: Unc. AH: Interior | Sup. R=6.0, 40.0 ft | ___ |

- | | | |
|-------------------------|--|-----|
| 12. Cooling systems | | |
| a. Central Unit | Cap: 35.0 kBtu/hr | ___ |
| | SEER: 10.00 | ___ |
| b. Central Unit | Cap: 10.0 kBtu/hr | ___ |
| | SEER: 10.00 | ___ |
| c. N/A | | ___ |
| 13. Heating systems | | |
| a. Electric Heat Pump | Cap: 35.0 kBtu/hr | ___ |
| | HSPF: 7.00 | ___ |
| b. Electric Heat Pump | Cap: 10.0 kBtu/hr | ___ |
| | HSPF: 7.00 | ___ |
| c. N/A | | ___ |
| 14. Hot water systems | | |
| a. Electric Resistance | Cap: 40.0 gallons | ___ |
| | EF: 0.89 | ___ |
| b. N/A | | ___ |
| c. Conservation credits | | ___ |
| | (HR-Heat recovery, Solar | |
| | DHP-Dedicated heat pump) | |
| 15. HVAC credits | | ___ |
| | (CF-Ceiling fan, CV-Cross ventilation, | |
| | HF-Whole house fan, | |
| | PT-Programmable Thermostat, | |
| | MZ-C-Multizone cooling, | |
| | MZ-H-Multizone heating) | |

Glass/Floor Area: 0.09

Total as-built points: 29048

Total base points: 32907

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Evan Beamsley

DATE: 3/2/05

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____

DATE: _____



SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BSPM = Points Floor Area											
				Type/SC	Overhang Ornt Len Hgt		Area X SPM X SOF = Points				
.18	2282.0	20.04	8231.6	Double, Clear	N	0.0	0.0	20.0	19.20	1.00	384.0
				Double, Clear	N	6.5	8.5	20.0	19.20	0.75	289.3
				Double, Clear	N	6.5	5.5	12.0	19.20	0.68	157.2
				Double, Clear	E	1.5	5.5	10.0	42.06	0.90	377.0
				Double, Clear	E	1.5	6.5	15.0	42.06	0.93	584.6
				Double, Clear	S	0.0	0.0	30.0	35.87	1.00	1076.0
				Double, Clear	S	1.5	6.5	15.0	35.87	0.88	471.7
				Double, Clear	S	9.5	6.5	60.0	35.87	0.48	1023.7
				Double, Clear	S	9.5	8.5	20.0	35.87	0.50	361.4
				Double, Clear	W	1.5	2.5	3.5	38.52	0.67	90.5
				As-Built Total:		205.5			4815.3		
WALL TYPES Area X BSPM = Points				Type		R-Value		Area X SPM = Points			
Adjacent	356.0	0.70	249.2	Face Brick, Wood, Exterior		13.0		1451.0	0.35		507.9
Exterior	1511.0	1.70	2568.7	Frame, Wood, Exterior		13.0		60.0	1.50		90.0
				Frame, Wood, Adjacent		13.0		356.0	0.60		213.6
Base Total:	1867.0		2817.9	As-Built Total:				1867.0	811.4		
DOOR TYPES Area X BSPM = Points				Type				Area X SPM = Points			
Adjacent	20.0	2.40	48.0	Exterior Insulated				60.0	4.10		246.0
Exterior	100.0	6.10	610.0	Exterior Insulated				40.0	4.10		164.0
				Adjacent Insulated				20.0	1.60		32.0
Base Total:	120.0		658.0	As-Built Total:				120.0	442.0		
CEILING TYPES Area X BSPM = Points				Type		R-Value		Area X SPM X SCM = Points			
Under Attic	2282.0	1.73	3947.9	Under Attic		30.0		2367.0	1.73 X 1.00		4094.9
Base Total:	2282.0		3947.9	As-Built Total:				2367.0	4094.9		
FLOOR TYPES Area X BSPM = Points				Type		R-Value		Area X SPM = Points			
Slab	250.0(p)	-37.0	-9250.0	Slab-On-Grade Edge Insulation		0.0		250.0(p)	-41.20		-10300.0
Raised	0.0	0.00	0.0								
Base Total:			-9250.0	As-Built Total:				250.0	-10300.0		
INFILTRATION Area X BSPM = Points								Area X SPM = Points			
	2282.0	10.21	23299.2					2282.0	10.21		23299.2

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT						
Summer Base Points: 29704.6				Summer As-Built Points: 23162.9						
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points
				23162.9		0.778	(1.090 x 1.147 x 0.91)	0.341	1.000	6995.4
				23162.9		0.222	(1.090 x 1.147 x 0.91)	0.341	1.000	1998.7
29704.6		0.4266	12672.0	23162.9		1.00	1.138	0.341	1.000	8994.1

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt	Area X WPM X WOF = Points					
.18	2282.0	12.74	5233.1	Double, Clear	N	0.0	0.0	20.0	24.58	1.00	491.6
				Double, Clear	N	6.5	8.5	20.0	24.58	1.02	498.9
				Double, Clear	N	6.5	5.5	12.0	24.58	1.02	301.0
				Double, Clear	E	1.5	5.5	10.0	18.79	1.04	195.7
				Double, Clear	E	1.5	6.5	15.0	18.79	1.03	290.5
				Double, Clear	S	0.0	0.0	30.0	13.30	1.00	398.9
				Double, Clear	S	1.5	6.5	15.0	13.30	1.09	218.2
				Double, Clear	S	9.5	6.5	60.0	13.30	3.25	2590.0
				Double, Clear	S	9.5	8.5	20.0	13.30	2.92	777.4
				Double, Clear	W	1.5	2.5	3.5	20.73	1.11	80.3
				As-Built Total:		205.5			5842.4		
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	356.0	3.60	1281.6	Face Brick, Wood, Exterior	13.0		1451.0	3.17		4606.9	
Exterior	1511.0	3.70	5590.7	Frame, Wood, Exterior	13.0		60.0	3.40		204.0	
				Frame, Wood, Adjacent	13.0		356.0	3.30		1174.8	
Base Total:	1867.0		6872.3	As-Built Total:		1867.0		5985.7			
DOOR TYPES Area X BWPM = Points				Type			Area X WPM = Points				
Adjacent	20.0	11.50	230.0	Exterior Insulated			60.0	8.40		504.0	
Exterior	100.0	12.30	1230.0	Exterior Insulated			40.0	8.40		336.0	
				Adjacent Insulated			20.0	8.00		160.0	
Base Total:	120.0		1460.0	As-Built Total:		120.0		1000.0			
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	2282.0	2.05	4678.1	Under Attic	30.0		2367.0	2.05 X 1.00		4852.4	
Base Total:	2282.0		4678.1	As-Built Total:		2367.0		4852.4			
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	250.0(p)	8.9	2225.0	Slab-On-Grade Edge Insulation	0.0		250.0(p)	18.80		4700.0	
Raised	0.0	0.00	0.0								
Base Total:			2225.0	As-Built Total:		250.0		4700.0			
INFILTRATION Area X BWPM = Points				Area X WPM = Points							
	2282.0	-0.59	-1346.4	2282.0 -0.59 -1346.4							

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT						
Winter Base Points:		19122.1		Winter As-Built Points:				21034.1		
Total Winter Points	X	System Multiplier	= Heating Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points
				21034.1		0.778	(1.069 x 1.169 x 0.93)	0.487	1.000	9262.1
				21034.1		0.222	(1.069 x 1.169 x 0.93)	0.487	1.000	2646.3
19122.1		0.6274	11997.2	21034.1		1.00	1.162	0.487	1.000	11908.5

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT						
WATER HEATING										
Number of Bedrooms	X	Multiplier	= Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Multiplier X Credit	= Total Multiplier
3		2746.00	8238.0	40.0	0.89	3		1.00	2715.15	1.00 8145.4
				As-Built Total:						8145.4

CODE COMPLIANCE STATUS

BASE						AS-BUILT					
Cooling Points	+	Heating Points	+	Hot Water Points	= Total Points	Cooling Points	+	Heating Points	+	Hot Water Points	= Total Points
12672		11997		8238	32907	8994		11908		8145	29048

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 85.0

The higher the score, the more efficient the home.

Stephenson, 231 SW Bonanza Glen, Lake City, FL,

1. New construction or existing	New	___	12. Cooling systems	
2. Single family or multi-family	Single family	___	a. Central Unit	Cap: 35.0 kBtu/hr ___
3. Number of units, if multi-family	1	___		SEER: 10.00 ___
4. Number of Bedrooms	3	___	b. Central Unit	Cap: 10.0 kBtu/hr ___
5. Is this a worst case?	Yes	___		SEER: 10.00 ___
6. Conditioned floor area (ft ²)	2282 ft ²	___	c. N/A	___
7. Glass area & type	Single Pane	Double Pane		___
a. Clear glass, default U-factor	0.0 ft ²	205.5 ft ²	13. Heating systems	
b. Default tint, default U-factor	0.0 ft ²	0.0 ft ²	a. Electric Heat Pump	Cap: 35.0 kBtu/hr ___
c. Labeled U-factor or SHGC	0.0 ft ²	0.0 ft ²		HSPF: 7.00 ___
8. Floor types			b. Electric Heat Pump	Cap: 10.0 kBtu/hr ___
a. Slab-On-Grade Edge Insulation	R=0.0, 250.0(p) ft	___		HSPF: 7.00 ___
b. N/A	___	___	c. N/A	___
c. N/A	___	___		___
9. Wall types			14. Hot water systems	
a. Face Brick, Wood, Exterior	R=13.0, 1451.0 ft ²	___	a. Electric Resistance	Cap: 40.0 gallons ___
b. Frame, Wood, Exterior	R=13.0, 60.0 ft ²	___		EF: 0.89 ___
c. Frame, Wood, Adjacent	R=13.0, 356.0 ft ²	___	b. N/A	___
d. N/A	___	___		___
e. N/A	___	___	c. Conservation credits	___
10. Ceiling types			(HR-Heat recovery, Solar	
a. Under Attic	R=30.0, 2367.0 ft ²	___	DHP-Dedicated heat pump)	
b. N/A	___	___	15. HVAC credits	___
c. N/A	___	___	(CF-Ceiling fan, CV-Cross ventilation,	
11. Ducts			HF-Whole house fan,	
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 200.0 ft	___	PT-Programmable Thermostat,	
b. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 40.0 ft	___	MZ-C-Multizone cooling,	
	___	___	MZ-H-Multizone heating)	
	___	___		

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____

Date: _____

Address of New Home: _____

City/FL Zip: _____



**NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 889-482-4824.*

Energy Gauge (Version: FLR2PB v3.4)

Documentary Stamps: + BK 0929 PG 2399
 Total: \$
 Prepared by and return to:

01-12022

01 JUN 27 AM 8:48

TITLE OFFICES, LLC

2015 S. 1ST ST.,
 LAKE CITY, FL. 32025
 SE File #01Y-04090DH/

OFFICIAL RECORDS

Property Appraisers Parcel I.D. Number(s):
 02952-208

Documentary Stamp \$192.50
 Intangible Tax
 P. DOWITT CANNON
 Clerk of Court
 By mkc D.C.



Grantee(s) S.S.#(s): 371-48-1123 + 377-58-0390

WARRANTY DEED

THIS WARRANTY DEED made and executed the 15th day of June, 2001, by
 A & R OF LAKE CITY, INC., a corporation existing under the laws of Florida, and having its principal place
 of business at P.O. BOX 1733, LAKE CITY, FL 32056, hereinafter called the Grantor, to JAMES G. STEPHENSON
 and DEBORAH G. STEPHENSON, HIS WIFE, whose post office address is: 18130 HOMER RD. MARSHALL, MI
49068-9736, hereinafter called the Grantee:

(Wherever used herein the terms "first party" and "second party" shall include singular and plural, heirs, legal representatives,
 and assigns of individuals, and the successors and assigns of corporations, wherever the context so admits or requires.)

WITNESSETH: That the Grantor, for and in consideration of the sum of TEN DOLLARS (\$10.00) and other
 valuable considerations, receipt whereof is hereby acknowledged, by these presents does grant, bargain, sell, alien, remise,
 release, convey and confirm unto the Grantee all that certain land situate, lying and being in COLUMBIA County, State
 of Florida, viz:

**LOT 8, SOUTHERN APPROACHES, UNIT 1, A SUBDIVISION ACCORDING TO PLAT THEREOF
 RECORDED IN PLAT BOOK 6, PAGE 88, PUBLIC RECORDS OF COLUMBIA COUNTY, FLORIDA.**

Subject to Restrictions, Reservations and Easements of Record.
TOGETHER with all the tenements, hereditaments and appurtenances thereto belonging or in anywise
 appertaining.

TO HAVE AND TO HOLD the same in fee simple forever.

AND the Grantor hereby covenants with said Grantee that the Grantor is lawfully seized of said land in fee simple;
 that the Grantor has good right and lawful authority to sell and convey said land, and hereby warrants the title to said land
 and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances
 subsequent to December 31, 2000

IN WITNESS WHEREOF, the said Grantor has caused these presents to be executed in its name, and its corporate
 seal to be hereunto affixed, by its proper officers thereunto duly authorized, the day and year first above written.

Signed, sealed and delivered
 in the presence of:

A & R OF LAKE CITY, INC.

Dawn Wilson Herringshaw
 Witness Signature
 Printed Name: DAWNA HERRINGSHAW

BY: Audrey S. Bullard
AUDREY S. BULLARD, Vice President

Brenda Bankham Sykes
 Witness Signature
 Printed Name: Brenda Bankham Sykes

Address: P.O. BOX 1733
LAKE CITY, FL 32056

ATTEST: Secretary

(CORPORATE SEAL)

HALL'S PUMP & WELL SERVICE, INC.

SPECIALIZING IN 4"-6" WELLS



DONALD AND MARY HALL
OWNERS

PHONE (904) 752-1854
FAX (904) 755-7022
~~XXXX NORTH FIRST STREET~~
LAKE CITY, FLORIDA 32055
904 NW Main Blvd.

June 12, 2002

NOTICE TO ALL CONTRACTORS

Please be advised that due to the new building codes we will use a large capacity diaphragm tank on all new wells. This will insure a minimum of one (1) minute draw down or one (1) minute refill. If a smaller diaphragm tank is used then we will install a cycle stop valve which will produce the same results.

If you have any questions please feel free to call our office anytime.

Thank you,

A handwritten signature in cursive script, appearing to read "Donald D. Hall".
Donald D. Hall
DDH/jk

COLUMBIA COUNTY 9-1-1 ADDRESSING

263 NW Lake City Ave. * P. O. Box 2949 * Lake City, FL 32056-2949

PHONE: (386) 752-8787 * FAX: (386) 758-1365 * Email: ron_croft@columbiacountyfla.com

*Sal -
this is for stephenson*

Addressing Maintenance

To maintain the Countywide addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for assigning and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Service Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County.

DATE ISSUED: January 28, 2005

ENHANCED 9-1-1 ADDRESS:

231 SW BONANZA GLN (LAKE CITY, FL 32025)

Addressed Location 911 Phone Number: NOT AVAIL.

OCCUPANT NAME: NOT AVAIL.

OCCUPANT CURRENT MAILING ADDRESS: _____

PROPERTY APPRAISER MAP SHEET NUMBER: 71A

PROPERTY APPRAISER PARCEL NUMBER: 13-4S-16-02952-208

Other Contact Phone Number (If any): _____

Building Permit Number (If known): _____

Remarks: LOT 8, SOUTHERN APPROACHES, UNIT 1, S/D

Address Issued By: _____

Ron Croft
Columbia County 9-1-1 Addressing Department

COLUMBIA COUNTY
9-1-1 ADDRESSING

Residential System Sizing Calculation

Summary

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North


3/2/2005

Location for weather data: Gainesville - Defaults: Latitude(29) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(51gr.)			
Winter design temperature	31 F	Summer design temperature	93 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	39 F	Summer temperature difference	18 F
Total heating load calculation	37631 Btuh	Total cooling load calculation	33543 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	119.6 45000	Sensible (SHR = 0.75)	141.6 33750
Heat Pump + Auxiliary(0.0kW)	119.6 45000	Latent	115.9 11250
		Total (Electric Heat Pump)	134.2 45000

WINTER CALCULATIONS

Winter Heating Load (for 2282 sqft)


Load component		Load	
Window total	206 sqft	5816	Btuh
Wall total	1867 sqft	5254	Btuh
Door total	120 sqft	2021	Btuh
Ceiling total	2367 sqft	3077	Btuh
Floor total	250 ft	7900	Btuh
Infiltration	274 cfm	11771	Btuh
Subtotal		35839	Btuh
Duct loss		1792	Btuh
TOTAL HEAT LOSS		37631	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 2282 sqft)

Load component		Load	
Window total	206 sqft	6338	Btuh
Wall total	1867 sqft	2999	Btuh
Door total	120 sqft	1217	Btuh
Ceiling total	2367 sqft	3361	Btuh
Floor total		0	Btuh
Infiltration	240 cfm	4754	Btuh
Internal gain		3000	Btuh
Subtotal(sensible)		21669	Btuh
Duct gain		2167	Btuh
Total sensible gain		23836	Btuh
Latent gain(infiltration)		8326	Btuh
Latent gain(internal)		1380	Btuh
Total latent gain		9706	Btuh
TOTAL HEAT GAIN		33543	Btuh



EnergyGauge® System Sizing based on ACCA Manual J.

PREPARED BY:

DATE: 3/2/05

System Sizing Calculations - Winter

Residential Load - Component Details

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 39.0 F

3/2/2005

Window	Panes/SHGC/Frame/U	Orientation	Area X	HTM=	Load
1	2, Clear, Metal, DEF	N	20.0	28.3	566 Btuh
2	2, Clear, Metal, DEF	N	20.0	28.3	566 Btuh
3	2, Clear, Metal, DEF	N	12.0	28.3	340 Btuh
4	2, Clear, Metal, DEF	E	10.0	28.3	283 Btuh
5	2, Clear, Metal, DEF	E	15.0	28.3	424 Btuh
6	2, Clear, Metal, DEF	S	30.0	28.3	849 Btuh
7	2, Clear, Metal, DEF	S	15.0	28.3	424 Btuh
8	2, Clear, Metal, DEF	S	60.0	28.3	1698 Btuh
9	2, Clear, Metal, DEF	S	20.0	28.3	566 Btuh
10	2, Clear, Metal, DEF	W	3.5	28.3	99 Btuh
Window Total			206		5816 Btuh
Walls	Type	R-Value	Area X	HTM=	Load
1	Frame - Exterior	13.0	1451	3.1	4498 Btuh
2	Frame - Exterior	13.0	60	3.1	186 Btuh
3	Frame - Adjacent	13.0	356	1.6	570 Btuh
Wall Total			1867		5254 Btuh
Doors	Type		Area X	HTM=	Load
1	Insulated - Exter		60	18.3	1100 Btuh
2	Insulated - Exter		40	18.3	733 Btuh
3	Insulated - Adjac		20	9.4	188 Btuh
Door Total			120		2021 Btuh
Ceilings	Type	R-Value	Area X	HTM=	Load
1	Under Attic	30.0	2367	1.3	3077 Btuh
Ceiling Total			2367		3077 Btuh
Floors	Type	R-Value	Size X	HTM=	Load
1	Slab-On-Grade Edge Insul	0	250.0 ft(p)	31.6	7900 Btuh
Floor Total			250		7900 Btuh
Infiltration	Type	ACH X	Building Volume	CFM=	Load
	Natural	0.80	20538(sqft)	274	11771 Btuh
	Mechanical			0	0 Btuh
Infiltration Total				274	11771 Btuh

Totals for Heating	Subtotal	35839 Btuh
	Duct Loss(using duct multiplier of 0.05)	1792 Btuh
	Total Btuh Loss	37631 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

3/2/2005

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)

System Sizing Calculations - Summer

Residential Load - Component Details

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults)

Summer Temperature Difference: 18.0 F

3/2/2005

Window	Type	Overhang	Window Area(sqft)			HTM		Load		
	Panes/SHGC/U/InSh/ExSh Omt		Len	Hgt	Gross	Shaded	Unshaded		Shaded	Unshaded
1	2, Clear, DEF, N, N	N	0	0	20.0	0.0	20.0	22	22	440 Btuh
2	2, Clear, DEF, N, N	N	6.5	8.5	20.0	0.0	20.0	22	22	440 Btuh
3	2, Clear, DEF, N, N	N	6.5	5.5	12.0	0.0	12.0	22	22	264 Btuh
4	2, Clear, DEF, N, N	E	1.5	5.5	10.0	0.0	10.0	22	72	720 Btuh
5	2, Clear, DEF, N, N	E	1.5	6.5	15.0	0.0	15.0	22	72	1080 Btuh
6	2, Clear, DEF, N, N	S	0	0	30.0	0.0	30.0	22	37	1110 Btuh
7	2, Clear, DEF, N, N	S	1.5	6.5	15.0	15.0	0.0	22	37	330 Btuh
8	2, Clear, DEF, N, N	S	9.5	6.5	60.0	60.0	0.0	22	37	1320 Btuh
9	2, Clear, DEF, N, N	S	9.5	8.5	20.0	20.0	0.0	22	37	440 Btuh
10	2, Clear, DEF, N, N	W	1.5	2.5	3.5	1.2	2.3	22	72	194 Btuh
	Window Total				206					6338 Btuh
Walls	Type	R-Value		Area		HTM		Load		
1	Frame - Exterior	13.0		1451.0		1.7		2525 Btuh		
2	Frame - Exterior	13.0		60.0		1.7		104 Btuh		
3	Frame - Adjacent	13.0		356.0		1.0		370 Btuh		
	Wall Total			1867.0					2999 Btuh	
Doors	Type	R-Value		Area		HTM		Load		
1	Insulated - Exter			60.0		10.1		608 Btuh		
2	Insulated - Exter			40.0		10.1		406 Btuh		
3	Insulated - Adjac			20.0		10.1		203 Btuh		
	Door Total			120.0					1217 Btuh	
Ceilings	Type/Color	R-Value		Area		HTM		Load		
1	Under Attic/Dark	30.0		2367.0		1.4		3361 Btuh		
	Ceiling Total			2367.0					3361 Btuh	
Floors	Type	R-Value		Size		HTM		Load		
1	Slab-On-Grade Edge Insulation	0.0		250.0 ft(p)		0.0		0 Btuh		
	Floor Total			250.0					0 Btuh	
Infiltration	Type	ACH		Volume		CFM=		Load		
	Natural	0.70		20538		240.1		4754 Btuh		
	Mechanical					0		0 Btuh		
	Infiltration Total						240		4754 Btuh	

Internal gain	Occupants	Btuh/occupant	Appliance	Load
	6	X 300 +	1200	3000 Btuh

Manual J Summer Calculations

Residential Load - Component Details (continued)

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

3/2/2005

Totals for Cooling	Subtotal	21669 Btuh
	Duct gain(using duct multiplier of 0.10)	2167 Btuh
	Total sensible gain	23836 Btuh
	Latent infiltration gain (for 51 gr. humidity difference)	8326 Btuh
	Latent occupant gain (6 people @ 230 Btuh per person)	1380 Btuh
	Latent other gain	0 Btuh
	TOTAL GAIN	33543 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(U - Window U-Factor or 'DEF' for default)
(InSh - Interior shading device: none(N), Blinds/Daperies(B) or Roller Shades(R))
(ExSh - Exterior shading device: none(N) or numerical value)
(Ornt - compass orientation)

COLUMBIA COUNTY, FLORIDA
BUILDING AND ZONING DEPART.
P.O. BOX 1529
LAKE CITY, FL 32056-1529



Fax

To: EDGLEY CONSTRUCTION	From: BRIAN L. KEPNER, COUNTY PLANNER
Fax: 752.4904	Pages: 3 (Including cover sheet)
Phone:	Date: 10 JUNE 05
Re: Flood Prone Lot	CC:

☐ Urgent ☐ For Review ☐ Please Comment ☐ Please Reply ☐ Please Recycle

• **Comments:**

I have received information from an adjoining property owner that Lot 8 of Southern Approaches, Unit 1 Subdivision did have standing water back during the hurricanes of 2004. Attached are additional requirement that will need to be submitted before a building permit can be issued.

Brian

District No. 1 - Ronald Williams
District No. 2 - Dewey Weaver
District No. 3 - George Skinner
District No. 4 - Jennifer Flinn
District No. 5 - Elizabeth Porter



BOARD OF COUNTY COMMISSIONERS • COLUMBIA COUNTY

May 11, 2005

M E M O

TO: Who It May Concern

FR: Dale Williams, County Manager

RE: Flood Prone Lots – Additional Permitting Requirements

This is to advise that lots or acreage which have been identified as “flood prone” are subject to the following additional requirements prior to an application for a development permit through the county Building Department:

The applicant for a development permit shall submit in addition to all other required submittals a grading plan for the lot or acreage in which the development order is applied for. The grading plan shall be signed and sealed by a registered professional engineer. The grading plan shall show proposed changes from natural ground elevation, if any including the amount of fill material to be added to the site. The grading plan shall clearly demonstrate that the natural flow of water shall not be altered nor will adjoining properties be negatively impacted by the proposed development. The grading plan shall also establish the lowest habitable floor elevation and building location on the lot or acreage.

In addition to the above, all “flood prone” lots or acreage shall require a letter from the Suwannee River Water Management District or a competent licensed professional stating that the lot is not defined as a wetland in accordance with Florida Law.

For the purposes of these additional permitting requirements “flood prone” is defined as those lots and / or acreage that can be demonstrated on existing maps as flood prone or in which personal testimony will establish as having a history of flooding.

BOARD MEETS FIRST THURSDAY AT 7:00 P.M.
AND THIRD THURSDAY AT 7:00 P.M.

May 11, 2005

Page 2

Any party that is subject to these additional permitting requirements and believes they are inappropriately applied in a given application may appeal to the Board of County Commissioners. Appeals shall be made in writing and shall be mailed to:

Columbia County Commissioners
Post Office Box 1529
Lake City, Florida 32056-1529

DW/cnb

XC: Board of County Commissioners
John Kerce, Chief Building Official
Brian Kepner, County Planner
Marlin Feagle, County Attorney
John Colson, P.E.

□

Floor Plan including:

- ☒ a) Rooms labeled and dimensioned
- ☒ b) Shear walls
- ☒ c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown) *see NOT 4*
- ☒ d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with *NONE SHOWN* hearth
- ☒ e) Stairs with dimensions (width, tread and riser) and details of guardrails and *NONE SHOWN* handrails
- ☒ f) Must show and identify accessibility requirements (accessible bathroom) ✓

Foundation Plan including:

- ☒ a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- ☒ b) All posts and/or column footing including size and reinforcing
- ☒ c) Any special support required by soil analysis such as piling
- ☒ d) Location of any vertical steel *NONE SHOWN*

Roof System:

- ☒ a) Truss package including:
 - see note 5* 1. Truss layout and truss details signed and sealed by FI. Pro. Eng.
 - 2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- ☒ b) Conventional Framing Layout including:
 - 1. Rafter size, species and spacing
 - 2. Attachment to wall and uplift
 - 3. Ridge beam sized and valley framing and support details
 - 4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections including:

- ☒ a) Masonry wall
 - 1. All materials making up wall
 - 2. Block size and mortar type with size and spacing of reinforcement
 - 3. Lintel, tie-beam sizes and reinforcement
 - 4. Gable ends with rake beams showing reinforcement or gable truss and wall bracing details
 - 5. All required connectors with uplift rating and required number and size of fasteners for continuous tie from roof to foundation
 - 6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with resistance rating)
 - 7. Fire resistant construction (if required)
 - 8. Fireproofing requirements
 - 9. Shoe type of termite treatment (termicide or alternative method)
 - 10. Slab on grade
 - a. Vapor retardant (6mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
 - 11. Indicate where pressure treated wood will be placed
 - 12. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
 - a. Vapor retardant (6Mil. Polyethylene with joints lapped 6 inches and sealed
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment
- g) Arc Fault Circuits (AFCI) in bedrooms

HVAC information

- a) Manual J sizing equipment or equivalent computation
- b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)

Gas System Type (LP or Natural) Location and BTU demand of equipment

Disclosure Statement for Owner Builders

*****Notice Of Commencement Required Before Any Inspections Will Be Done**

Private Potable Water

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

Columbia County Building Permit Application

CK #1304 Revised 9-23-04

For Office Use Only Application # 0505-24 Date Received 05/06/05 By JW Permit # 838/23695
Application Approved by - Zoning Official BLK Date 02/10/05 Plans Examiner OKJTH Date 5-27-05
Flood Zone X per plot Development Permit N/A Zoning RMF-1 Land Use Plan Map Category Res. Mod. Den.
Comments no new work done to 1st inspection

Applicants Name KIMMY EDGLEY Phone 386-752-0580
Address 590 SW ARLINGTON BLVD, SUITE 105, LAKE CITY FL 32025
Owners Name JAMES G. AND DEBORAH G. STEPHENSON Phone 386-752-0580
911 Address 231 SW BONANZA GLEN, LAKE CITY FL 32025
Contractors Name EDGLEY CONSTRUCTION CO. Phone 386-752-0580
Address 590 SW ARLINGTON BLVD, SUITE 105, LAKE CITY FL 32025
Fee Simple Owner Name & Address JAMES G. AND DEBORAH G. STEPHENSON
Bonding Co. Name & Address N/A
Architect/Engineer Name & Address MARK DISOSWAY P.E., P.O. BOX 868, LAKE CITY FL 32056
Mortgage Lenders Name & Address FFSB, P.O. BOX 2029, LAKE CITY FL 32056-2029
Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
Property ID Number 13-4S-16-02952-208 Estimated Cost of Construction \$200,000.00
Subdivision Name SOUTHERN APPROACHES Lot 8 Block Unit 1 Phase
Driving Directions HWY 90 WEST, TL ON SISTERS WELCOME ROAD, TL ON BUSINESS POINT
DRIVE, TL ON BONANZA GLEN, 8th LOT ON LEFT

Type of Construction RESIDENTIAL HOME & HANGAR Number of Existing Dwellings on Property N/A
Total Acreage .505 Lot Size Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
Actual Distance of Structure from Property Lines - Front 40 Side 11'-5" Side 11'-5" Rear 78' 11"
Total Building Height 25' 8" Number of Stories 1 Heated Floor Area 2282 Roof Pitch 6/12
4361

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Kimmy Edgley - Agent
Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA

Sworn to (or affirmed) and subscribed before me
this 6th day of may 2005.
Personally known ✓ or Produced Identification

Douglas C. Clark
Contractor Signature
Contractors License Number RR2828211326
Competency Card Number 5364
NOTARY STAMP/SEAL


Jean Clark
Notary Signature
NOTARY PUBLIC
JAN CLARK
MY COMMISSION # DD 181635
EXPIRES: March 28, 2007
Bonded Thru Budget Notary Services

X
Glazed Inswing Unit

COP-WL-JH4141-02

WOOD-EDGE STEEL DOORS

APPROVED ARRANGEMENT:



Note:
Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".

Single Door
Maximum unit size = 3'0" x 6'8"

Design Pressure
+40.5/-40.5
Limited water unless special threshold design is used.

Large Missile Impact Resistance
Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

Warnock Hersey



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see MAD-WL-MA0001-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see MID-WL-MA0001-02.

APPROVED DOOR STYLES:

1/4 GLASS:



100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:



105 Series*




106, 160 Series*




129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite
Masonite International Corporation

WOOD-EDGE STEEL DOORS

APPROVED DOOR STYLES:

3/4 GLASS:



404 Series



410 Series




450 Series


FULL GLASS:



109 Series



114, 120, 122
Series



152 Series



149 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Johnson
EntrySystems™

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from

Masonite®
Masonite International Corporation

XX

Glazed Inswing Unit

COP-WL-JH4142-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:**

Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Note:

Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

Double Door

Maximum unit size = 6'0" x 6'8"

Design Pressure**+40.5/-40.5**

Limited water unless special threshold design is used.

Large Missile Impact Resistance**Hurricane protective system (shutters) is REQUIRED.**

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0002-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0002-02.

APPROVED DOOR STYLES:**1/4 GLASS:**

100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:

105 Series*





106, 160 Series*



129 Series*



200 Series*

12 R/L, 23 R/L, 24 R/L
Series*

107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

1

Johnson™
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from
Masonite®
Masonite International Corporation

XX

Glazed Inswing Unit

COP-WL-JH4142-02

WOOD-EDGE STEEL DOORS**APPROVED DOOR STYLES:****3/4 GLASS:**


404 Series




410 Series



450 Series

FULL GLASS:

109 Series

114, 120, 122
Series

152 Series



149 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. – License Number 56533



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

2

Johnson™
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from

Masonite®
Masonite International Corporation

WOOD-EDGE STEEL DOORS

APPROVED ARRANGEMENT:



Single Door with 2 Sidelites
Maximum unit size = 9'0" x 6'8"

Design Pressure

+40.5/-40.5

Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

Warnock Hersey



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itsmasonite.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Note:

Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see MAD-WL-MA0004-02 or MAD-WL-MA0007-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see MID-WL-MA0004-02.

APPROVED DOOR STYLES:

1/4 GLASS:



100 Series



133, 135 Series



136 Series




680 Series



822 Series

1/2 GLASS:




105 Series*



106, 160 Series*



129 Series*



200 Series*




12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite®
Masonite International Corporation

WOOD-EDGE STEEL DOORS

APPROVED DOOR STYLES:

3/4 GLASS:



404 Series



410 Series




450 Series

FULL GLASS:



109 Series



114, 120, 122 Series



152 Series



149 Series



300 Series

APPROVED SIDELITE STYLES:



680 Series



129 Series



200 Series



12R, 12L, 23R,
23L, 24R, 24L Series




450 Series



152 Series



149 Series



109 Series



120, 122 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab and sidelite panels glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

Kurt L Balthaz

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533



Test Data Review Certificate #3026447A and COP Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from

Masonite International Corporation

WOOD-EDGE STEEL DOORS

APPROVED ARRANGEMENT:



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Note:
Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

Double Door with 2 Sidelites
Maximum unit size = 12'0" x 6'8"

Design Pressure
+40.5/-40.5

Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see MAD-WL-MA0005-02 or MAD-WL-MA0008-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see MID-WL-MA0005-02.

APPROVED DOOR STYLES:

1/4 GLASS:



100 Series



133, 135 Series



136 Series




680 Series




822 Series


1/2 GLASS:



105 Series*




106, 160 Series*




129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L
Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from
Masonite
Masonite International Corporation



APPROVED FOR FABRICATION:
DATE:

ELECTRICAL
230V-1φ

DRAWN: 09-09-02-

CUSTOMER: TYPICAL

40'-6" x 14'-3" BI-FOLD DOOR
W.L. 110 MPH

**WELL-BUILT.
INDUSTRIES**

PLAN

FACE OF DOOR
COLUMNS ON SAME
VERTICAL PLANE AS
STUB COLUMNS

HEIGHT TO HINGE ATTACHMENT
POINT
14'-9"

HEIGHT TO BOTTOM OF STUB
COLUMN
14'-3"

CLEAR OPENING HEIGHT
12'-0"

ACTUAL DOOR FRAME DIMENSION
14'-3"

3"

3"

F.F.

CLEAR OPENING WIDTH

DOOR WIDTH

FACE OF DOOR.
COLUMNS ON SAME
VERTICAL PLANE AS
STUB COLUMNS

ACTUAL DOOR FRAME DIMENSION

CLEAR OPENING HEIGHT

HEIGHT TO BOTTOM OF STUB
COLUMN

HEIGHT TO HINGE ATTACHMENT POINT

• ५ •

CLEAR OPENING WIDTH

DOOR WIDTH

STUB COLUMN ELEVATION

N.T.S.

APPROVED FOR FABRICATION

DATE _____

TYPICAL

WELL-BUILT

WELL BILT INDUSTRIES

1 Well Bilt Road
PO Box 100
Williston, FL 32696-0100
phone (352) 528-5566 toll-free (800) 940-BILT
fax (352) 528-5614
E-mail MWellBilt@aol.com
Web-Site wellbiltdoors.com

WEIGHTS AND BALANCE

Date :

To :

From : Merle Loock, Office Manager

Company :

Fax:

Phone :

TYPICAL

PROJECT:

DOOR DOWN AND LOCKED

BI-FOLD DOOR CLEAR OPENING SIZE

40'-0" X 12'-0"

ACTUAL DOOR SIZE

40'-6" X 14'-3

DEAD WEIGHT

2,020 LBS.

LOCKS/OPTIONS

INCLUDED IN ABOVE WEIGHT

SHEETING WEIGHT, EXTERIOR
(ESTIMATE 1 # per sq. ft.)

577 LBS.

DEAD WEIGHT TOTAL

2,600 LBS.

VERTICAL COLUMN WIND LOAD TRANSFER

75 %

HEADER LOAD TRANSFER

25 %

HORIZONTAL COMPONENT, 2.0 X'S DEAD WEIGHT

5,200 LBS.

HINGE POINTS, WEIGHT EACH (5)

1,040 LBS. HORIZONTAL

520 LBS. VERTICAL

HORIZONTAL COMPRESSION ON EACH
VERTICAL COLUMN

2,600 LBS.

THANK YOU FOR YOUR INTEREST IN WELL BILT INDUSTRIES


BD-104

CLEARANCE REQ'D @ OPEN
POSITION

5 1/2" *
APPROX.

TOP OF DOOR
(CLOSED)

* CLEARANCE DIMENSION
BASED ON FRAME AND
SHEETING DIMENSIONS SHOWN



1 1/2"
CHANNEL &
SHEETING
(BY OTHERS)

2" x 4"
TOP DOOR
FRAME MEMBER

DRAWN 10-02-98
CUSTOMER

OPEN DOOR CLEARANCE - TYPICAL

WIEL-BILT
INDUSTRIES

CONTINUOUS WELD PERIMETER
OF HINGE TO BUILDING STEEL

BUILDING HEADER OR
STUB DOWN

PLUG WELD HOLES

APPROX. 2"

TOP OF DOOR

5 1/4"

1 1/4"

WELL BILT INDUSTRIES

TEL: 352-528-5566 FAX: 352-528-5614

**HINGE MOUNTING INSTALLATION
DETAILS**

DRAWN:
K. MARTIN



DATE:
05-24-04

BD - 112

**INSTRUCTIONS WHEN INSTALLING
DOOR**

REMOVE RETAINER PLATE SCREW FROM
BOTH ENDS OF DOOR.
SLIDE SHAFT OUT FAR ENOUGH TO
REMOVE ANTI SAIL LUG.

WHEN DOOR IS PERMANENTLY
ATTACHED TO BUILDING - REVERSE
PROCEDURE.



WELL BILT INDUSTRIES

TEL: 352-528-5566 FAX: 352-528-5614

**ANTI SAIL INSTALLATION
DETAILS**

DRAWN:
K.MARTIN

DATE:
02-03-04

WEATHER SEAL BY WELL BILT
INSTALLED BY OTHERS

HINGE MOUNTING STUB DOWN
BY OTHERS

SHEETING BY OTHERS

WEATHERSEAL BY WELLBILT
INSTALLED BY OTHERS

FINISHED FLOOR

ALTERNATE

SECTION

DRAWN: K. MARTIN

DATE: 11-16-04

BI-FOLD SHEETING INSTALLATION

WELL BILT INDUSTRIES

TEL: 352-528-5566 FAX: 352-528-5614

**AAMA/NWWDA 101/I.S.2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.

**SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window**

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.


Mark A. Hess, Technician

MAH:nlb

Allen H. Reeves
1 APRIL 2002



Architectural Testing

AAMA/NWDA 101/LS.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWDA 101/LS.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen M. Reum
1 APRIL 2002



Test Specimen Description: (Continued)

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

Allen N. Reeves
1 APRIL 2002



Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max

Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.

	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.02" 0.02"	0.18" max. 0.18" max.
---------	---	----------------	--------------------------

Allen N. Reeves
1 APRIL 2002



Test Specimen Description: (Continued)

Paragraph	Title of Test - Test Method	Results	Allowed
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 588-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.47"*	0.26" max.
	@ 47.2 psf (negative)	0.46"*	0.26" max.

*Exceeds L/175 for deflection, but passes all other test requirements.

Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds)	
@ 67.5 psf (positive)	0.05"
@ 70.8 psf (negative)	0.05"

Allen N. Reeves
1 APRIL 2002




Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.



For ARCHITECTURAL TESTING, INC:


Mark A. Hess
Technician


MAH:nlb
01-41134.01


Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002







1 TYPICAL OVERALL PANEL
SCALE: 1/4\"/>




2 WINDLOCK CHANNEL SUTURE
SCALE: 1/4\"/>




3 WINDLOCK
SCALE: 1/4\"/>




4 BOTTOM STIFFENER & ANGLE (TYPE A)
SCALE: 1/4\"/>




5 BOTTOM STIFFENER & TUBE (TYPE B)
SCALE: 1/4\"/>




A TYPICAL PANEL
SCALE: 1/4\"/>



C PLAN VIEW
SCALE: 1/4\"/>



B SIDE ELEVATION
SCALE: 1/4\"/>



D DOOR MOUNTING BRACKET DETAIL
SCALE: 1/4\"/>

1. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
2. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
3. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
4. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
5. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
6. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
7. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
8. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
9. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
10. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
11. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
12. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
13. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
14. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.
15. THE PRODUCT EVALUATION DOCUMENTS, MANUFACTURE AND QUALITY CONTROL, SHALL BE PROVIDED TO THE ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE START OF CONSTRUCTION.

FLORIDA BUILDING CODE

2022

02-292

1/23

ROLL-UP DOOR

1/23

KREZEVICH & ASSOCIATES, INC.

CONSULTING ENGINEERS - PRODUCT DESIGN

1/23

3100

26 ga.



SUPERIMPOSED LOAD DIAGRAM
SCALE: 3" = 1'-0"

 k_a

Report No: 95-029

23 August 1995

Test Date: 17 August 1995

TESTS ON ROLL DOWN DOORS

Client:

Door & Building Components, Inc.
4310 Industrial Access Road
Douglasville, Georgia 30134

General: Uniform Static Air Pressure Loading, per ASTM E-330

Testing witnessed by:

John W. Knezevich, P.E. Knezevich & Ass.
Don Mills, Product Engineer for D.B.C.I.
Bill Mathews, President J. B. Mathews
George Dotzler, CTC Test Engineer

Statement of Conformance: This is a general statement and does not supersede the specific product descriptions in this report. The specimens are in conformance with drawings provided by the manufacturer, labeled:

ROLL - UP DOOR

D.B.C.I.

Door & Building Components, Inc.
4310 Industrial Access Road
Douglasville, Georgia 30134

Date: 8-23-95 Drawing # 95-430

Description of Test Specimen: The specimen was a roll down door manufactured by Door & Building Components, Inc. . This door was installed covering a nominal opening 16'-0" wide by 16'-0" high. The door was constructed of painted galvanized steel sheet (mic'd @ 0.0240" w/ galvanized, w/o paint). The specimens channel guides were secured to the steel jamb (1/4" steel plate) of the test chamber with 9/16" hex head self threading 3/8" x 1" screws at 4" on center. These channel guides were as shown in detail 2 "Windlock Channel Guide" of the manufacturers supplied drawings. The left guide fastenings were secured through the 1-1/2" x 1-1/2" angle typically used for concrete installations. The right channel guide did not include this feature (the 1-1/2" x 1-1/2" angle) and the fastenings were secured through the center of the 1" protruding flange as shown detail 2. The door's bottom bar was as shown in detail 5 "Bottom Stiffener & Angle (Type B)" in the manufacturers drawings. Before testing this door was fully functional.

Reports pertain to the samples tested only and
may not be reproduced without permission.
CTC95029 : 23 August 1995 · Page 1 of 2

CONSTRUCTION TESTING CORPORATION

13873 N.W. 19th Ave. Miami, Florida 33054

Phone: (305) 685-6657 Fax: (305) 685-6659

Static Wind Loading / Manner of Testing:

Loads applied to the specimen (10 seconds durations in loading cycles greater than 40 seconds) were at levels specified by the client's Consulting Engineer. Polyethylene film (2 mil) and tape were used to seal air leakage during loads. The film and tape were used in a manner that did not influence the results. Deflection gauges were mounted at each jamb to record deflections along the center line of the door. The deflection readings are as follows:

		Left		Center		Right		Net @ Center Line		
Load	Load	Delta	Delta	Delta	Delta	Delta	Delta	Delta	Delta	Percent
PSF	In. H2O	@ Load	@ Rec'y	@ Load	@ Rec'y	@ Load	@ Rec'y	@ Load	@ Rec'y	Recovery
0.0	0.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	NA
15.6	3.0	0.500	0.063	11.438	0.188	0.500	0.016	10.938	0.148	98.6
20.8	4.0	0.531	0.063	12.063	0.125	0.516	0.156	11.539	0.016	99.9
26.0	5.0	0.531	0.031	13.000	0.063	0.563	0.031	12.453	0.031	99.7
31.2	6.0	0.583	0.031	13.750	0.125	0.625	0.063	13.156	0.078	99.4
38.5	7.4	0.625	0.125	14.938	0.313	0.750	0.063	14.250	0.219	98.5
45.5	8.8	0.688	0.156	18.250	0.750	0.875	0.063	15.469	0.641	95.9
52.5	10.1	NR	NR	NR	NR	NR	NR	NR	NR	NR

As loading was initiated it momentarily rose to approximately 55 PSF then immediately reduced to the desired level.

The correct load was held for approximately 4 seconds when the windlocks failed at the center of the right jamb.

SUMMARY

One roll down door specimen manufactured by DBCI was wind loaded in accordance with ASTM E-330 under the supervision of the clients consulting engineer. Loads were chosen to prove the adequacy of the product to sustain a design load of 25.5 PSF. In fact the sustained test load of 45.5 PSF proved the product to a design load of 30.3 PSF.

Respectfully submitted,

CONSTRUCTION TESTING CORPORATION.

(Dade County Certification # 95-0419.02)

Report by George Dotzler:

George Dotzler

Test witnessed & report reviewed


by John W. Knezevich, P.E.

Reports pertain to the samples tested only and
may not be reproduced without permission.

CTC95029 - 21 August 1995 - Page 2 of 2




5 SUPERIMPOSED LOAD DIAGRAM
SCALE: $1'' = 1'-9''$



ALCOHOL NOTES:

1. EMBROIDERED LENGTH DOES NOT INCLUDE STITCHES FINISH.
2. FOR HOLLOW NASGONY, FILL ALL CELLS WITHIN B" OF THE ARMCHOR W/ 2500 PSI GROUT.
3. ARMCHORS SHALL BE INSTALLED IN ACCORDANCE W/ MANUFACTURERS SPECIFICATIONS.

[illegible]

STANDARD BUILDING CODE

V.A. MONTGOMERY
FACED WITH THE
MILITARY
JAN 19 2001

The image shows a document from the Federal Bureau of Investigation (FBI). At the top, the words "FEDERAL BUREAU OF INVESTIGATION" are printed in a bold, sans-serif font. Below the title, there is a grid of boxes, some of which contain text. The text is somewhat blurry and difficult to read, but it appears to be a form or a report. The document is oriented horizontally and is the central focus of the image.







ROLL - UP DOOR

DAVE

DAVE & SON, INC., THE ROLL-UP DOOR CO.
4225 Lombard Avenue So.
Buckhannon, W. Va. 26031

KNEZEVICH & ASSOCIATES, INC.
CONSULTING ENGINEERS - PRODUCT TESTING
1000 N. W. 10th Ave., Suite 100 - Fort Lauderdale, FL 33304
TELEPHONE 366-0000 • FAX 366-0000 • E-MAIL K&A@AOL.COM
WWW.KNEZEVICH.COM • 1-800-451-4514





304 VIBRA-COLOR COATING

INTERIOR ELEVATION

SIDE ELEVATION

1. THIS DOOR IS DESIGNED IN ACCORDANCE WITH THE STANDARD BUILDING CODE, 1991 EDITION, INCLUDING 1992 PAINT STANDARDS REQUIREMENTS.
2. THIS DOOR HAS BEEN TESTED IN ACCORDANCE WITH THE STANDARD BUILDING CODE, 1991 EDITION, AND ASHRAE 15-1989 TO VERIFY A RATING OF 15 MINUTES OF PROTECTION AGAINST FIRE.
3. THE DOOR IS DESIGNED TO WITHSTAND A WIND LOAD OF 150 PSF.
4. THE DOOR IS DESIGNED TO WITHSTAND A SEISMIC LOAD OF 0.15 G.
5. THE DOOR IS DESIGNED TO WITHSTAND A CORROSION RATE OF 0.001 IN/100 HRS.
6. THE DOOR IS DESIGNED TO WITHSTAND A TEMPERATURE RANGE OF -40°F TO 180°F.
7. THE DOOR IS DESIGNED TO WITHSTAND A VIBRATION LEVEL OF 0.05 IN/100 HRS.
8. THE DOOR IS DESIGNED TO WITHSTAND A NOISE LEVEL OF 50 DBA.
9. THE DOOR IS DESIGNED TO WITHSTAND A LIGHT TRANSMITTANCE OF 10%.
10. THE DOOR IS DESIGNED TO WITHSTAND A WEIGHT OF 100 LBS.

ROLL-UP DOOR

D.B.C.I.

2001 S. BAYVIEW AVENUE

420 INDUSTRIAL ACCESS ROAD

DOUGLASSVILLE, GA 30135

770-542-2200

KNEZEVICH & ASSOCIATES, INC.

ENGINEERING, PLANNING & PROJECT TESTING

675 MOYAM DRIVE

1000 SPRING FORD RD

PO BOX 1200

SPRINGFIELD, MA 01102

Copyright 1992 KNEZEVICH & ASSOCIATES, INC.

K

This door shall not be used as a master

Exp. 12-31-1993

Static Wind Loading / Manner of Testing:

Loads applied to the specimen (10 seconds durations in loading cycles greater than 40 seconds) were at levels specified by the client's Consulting Engineer. Polyethylene film (2 mil) and tape were used to seal air leakage during loads. The film and tape were used in a manner that did not influence the results. Deflection gauges were mounted at each jamb to record deflections along the center line of the door. The deflection readings are as follows:

		Left		Center		Right		Net @ Center Line		
Load	Load	Delta	Delta	Delta	Delta	Delta	Delta	Delta	Delta	Percent
PSF	In. H ₂ O	@ Load	@ Rec'y	@ Load	@ Rec'y	@ Load	@ Rec'y	@ Load	@ Rec'y	Recovery
0.0	0.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	NA
15.6	3.0	0.313	0.000	7.525	0.094	0.406	0.000	7.266	0.064	98.7
20.8	4.0	0.313	0.016	8.063	0.094	0.438	0.000	7.628	0.086	98.9
26.0	5.0	0.313	0.016	8.625	0.188	0.500	0.000	8.219	0.180	97.8
31.2	6.0	0.375	0.016	9.125	0.219	0.531	0.000	8.672	0.211	97.6
38.5	7.4	0.375	0.016	9.750	0.125	0.594	0.031	9.266	0.102	98.9
45.5	8.8	0.408	0.016	10.531	0.172	0.688	0.063	9.984	0.133	98.7
52.5	10.1	0.469	0.031	11.266	0.563	0.813	0.188	10.625	0.453	95.7
61.1	11.8	0.938	NR	14.875	NR	1.250	NR	13.731	NR	NR

Load was held for 9 seconds at this level when the wind locks failed at the left center jamb.

Impact Manner of Testing: In accordance with Dade County Test Protocol PA 201-94 (rev 2) **IMPACT TEST PROCEDURE.**

This testing was performed as an experiment for the research and development of this product for Dade County Product Approval. One door assembly was tested, this was installed as previously described. It was impacted twice with a 9.0 lb. 2x4 of No. 2 Southern Pine in locations as indicated in the document "Answers to questions most frequently asked about the new impact test" (by Jaime Gascon of DCPC) and a third time in a location specified by the clients engineer.

Impact Test Results

Shot	Impact Location	Impact Coordinates Rt(in), Up(in)	Firing Pressure in Hg	Impact Velocity Ft / Sec	Results
1	Right Bottom Corner	140, 12	9.88	49.6	No Penetration
2	Panel center @ Midspan	72, 33.5	10.00	50.2	No Penetration
3	Panel seam @ Midspan	73, 42.5	10.00	49.5	No Penetration

SUMMARY


One roll down door specimen manufactured by DBCI was wind loaded in accordance with ASTM E-330 under the supervision of the clients consulting engineer. Loads were chosen to prove the adequacy of the product to sustain a design load of 25.5 PSF. In fact the product sustained a test load of 52.5 PSF adequate to prove a design load of 35 PSF.

Following wind loading undamaged portions of the specimen were subjected to three impacts in accordance with Dade County Test Protocol PA 201-94 (ver 2.0). None of these impacts resulted in the penetration of the specimen.


Respectfully submitted,

CONSTRUCTION TESTING CORPORATION.
(Dade County Certification # 95-0419.02)

Report by George Dotzler :

 8-23-95


Test witnessed & report reviewed
by John W. Knezevich, P.E. :



Reports pertain to the samples tested only and
may not be reproduced without permission.
CTC95028 : 23 August 1995 : Page 3 of 3

Sun-Tek Manufacturing, Inc.
10303 General Drive
Orlando, FL 32824

Ph 407-859-2117
Fax 407-859-6607



IMPACT RATED PRODUCTS

MODEL	LARGEST SIZE	SMALLEST SIZE	DADE APPROVAL #	DESIGN PRESSURE	TEST PRESSURE POSITIVE	TEST PRESSURE NEGATIVE	WIND SPEED MPH (calculated)
MD-CMA	2246	1414	00-0224.08	37 PSF +	110 PSF	74 PSF	120.22
CMA-D	4889	3030	00-1024.03	60 PSF +	180 PSF	120 PSF	256.2
CM TUBE(SITOM)	21"	10"	99-0823.03	65 PSF +	195 PSF	130 PSF	276.9
H8F	4646	2222	01-0620.04	60 PSF +	180 PSF	120 PSF	256.2
ISFG	4849	1430		60 PSF +	120 PSF	120 PSF	153.09
ICMG	4949	1430		60 PSF +	120 PSF	120 PSF	153.09

MODEL	LARGEST SIZE	SMALLEST SIZE	NCTL TEST REPORT	DESIGN PRESSURE	TEST PRESSURE POSITIVE	TEST PRESSURE NEGATIVE	WIND SPEED MPH
SF TUBE(SIT)	21"	10"	210-2195-1,2,3	110	165	165	253

(TESTED TO AND PASSED DADE COUNTY PROTOCOL PA201, PA202, PA203)

AAMA TESTED TO SPEC 1000-00 and/or 1005.1-07 VOLUNTARY SPECIFICATION FOR SKYLIGHTS

MODEL	LARGEST SIZE	SMALLEST SIZE	NCTL TEST REPORT	DESIGN PRESSURE	TEST PRESSURE POSITIVE	TEST PRESSURE NEGATIVE	WIND SPEED MPH
CMG	4949	1430	210-2731-1	60	172	129	163.9
FGC	4949	1430	210-2677-1	60	172	129	163.9
SFA	4646	1414	210-2732-1	73	110	110	169
SF	4646	1414	210-2769-1	89	133.5	133.5	186
CM/CMA	4646	1414	210-2147-1	84	133.5	133.5	186

06/02/00 A.N.G.

WIND LOAD CALCULATIONS FOR SUN-TEK SKYLIGHTS
AS DETERMINED BY PHYSICAL TESTING

Method of calculation:
Square Root of Tested Pounds Per Square Foot
Divided by .00256

Model	Size	PSF	Wind Load
SFA	4848	62	155.8
TP	4848	55	148.8
SF	4848	62	155.8
CM	4848	62	155.8
FGC	4848	117	213.8
CMG	4848	100	187.6
FHP	4848	100	187.6
TG	4848	80	187.5
VGC	4848	110	207.3
TUBE	21"	165	253.8

(24x48) (24x24)

TEST RESULTS

Title of Test	
Air Infiltration - ASTM E283	Measured
Water Resistance - ASTM E547	Measured
WTP = 12.00 pcf	Measured
5.0 gpm/ft²	Measured
1.57 pcf (15 mph)	Measured
0.01 cfm/ft²	Measured
0.30 cfm/ft²	Measured
No Leakage	Measured
No Leakage	Measured
Allowed	Measured
Allowed	Measured

AMA 1600.86
Paragraph No. 2.3
8.3
AMA 1605.1-87
Paragraph No. 4.42

Title of Test & Method
Uniform Load Structural
Positive Load
111.0 pcf (Deflection)
Location:

A
B
C
D
E

111.0 pcf (Permanent Set)
Location:

A
B
C
D
E

Negative Load
111.0 pcf (Deflection)
Location:

A
B
C
D
E

111.0 pcf (Permanent Set)
Location:

A
B
C
D
E
F
G

0.05"
0.01"
0.01"
0.02"
0.01"
0.01"
0.05"

0.317"
0.317"
0.317"
0.317"
0.317"
0.317"
0.317"

0.00"
0.00"
0.00"
0.02"
0.01"

0.317"
0.317"
0.317"
0.317"
0.317"

Dome inverted no permanent damage
Dome inverted no permanent damage
Dome inverted no permanent damage
Dome inverted no permanent damage
Dome inverted no permanent damage

1/17/02
[Signature]

NATIONAL CERTIFIED TESTING LABORATORIES

1464 GEMINI BOULEVARD • ORLANDO, FLORIDA 32837
PHONE (407) 240-1388 • FAX (407) 240-2882

STRUCTURAL PERFORMANCE TEST REPORT

Report No: NCTL-210-2732-1
Test Date: 11/12/01
Report Date: 11/13/01
Expiration Date: 11/13/05

Client: Sun-Tek Manufacturing, Inc.

10308 General Drive
Orlando, FL 32834

Test Specimen: Sun-Tek Manufacturing Model-SFA Fixed Aluminum Polycarbonate Dome Skylight (SKP-R +87.74)

Test Specification: AAMA 1600-00 "Voluntary Specifications for Skylights" AAMA 1605.1-87; "Uniform Load Test Procedure for Plastic Glazed Skylights by Uniform Static Air Pressure Difference."

TEST SPECIMEN DESCRIPTION

General: The test specimen was a fixed aluminum skylight with polycarbonate double dome measuring 54-3/8" wide by 64-3/8" high overall. The skylight was sandwiched glazed using butyl glazing tape bedding with a silicone sealant between the inner polycarbonate dome, all compressed with an extruded aluminum retainer screwed to the exterior perimeter using twelve (12) (#6 x 3/4" self-tapping) screws. The main frame measured 0.080" thick and the inner polycarbonate flat liner sheet measured 0.060" thick. The main frame was of welded mitered corner construction. The specimen was self-flashing mounted using twelve (12) 1-1/4" spiral ring shanked nails (see fastener diagram) to a mock-up roof section employing a 46-1/2" x 46-1/2" opening. The roof section was built to 8:12 pitch slope.

Glazing: The skylight was sandwich glazed using Sun-Tek Skylight's STS 1000 Skylight sealant silicone bedding between the inner polycarbonate flat liner sheet and the outer polycarbonate dome. The outer polycarbonate dome measured 0.060" thick.

Weatherseals: No weatherstripping employed.

Weeps: N/A

Interior & Exterior Surface Finish: Mill-Finish.

PROFESSIONALS IN THE SCIENCE OF TESTING

Bob Bock
11/16

Jun. 20 2003 06:14AM P3

FAX NO. : +386 758 4735

FROM : LAKE CITY INDUSTRIES

19.03.16.05 FAX 407 880 8807

SUN THE SKYLIGHTS

0003

Sun Test Industries

NCTI-210-2732-1

TEST COMPLETED 11/12/01


The test specimen model "SPS" with a double and triple dome meets the performance levels specified in AAMA 1600-00 specification (rating SFP-R+37,-74) Models "SFAF", "SFAW" and "SFAFW" with double and triple dome qualifies with rating of SFP-R+37,-74)

ailed drawings were available for laboratory records and comparison to the test specimen at time of this report. A copy of this report along with representative sections of the test specimen will be retained by NCTI for a period of four (4) years. The results obtained apply only to the specimen tested. No conclusions of any kind regarding the adequacy or inadequacy of the polycarbonate in the test specimen may be drawn from this test. This report does not constitute certification of the product which may only be granted by a certification program validator.

NATIONAL CERTIFIED TESTING LABORATORIES

DANIEL D. CONVERS
Laboratory Manager

Copy to Bob
11/12/01



1000 General Drive Orlando Florida 32824

**SUN-TEK
SKYLIGHTS**

PART NAME	VERT. ASSY	REV	SFAF-001A	DATE	JM 10-16-94
-----------	------------	-----	-----------	------	-------------



Offices
PE 2/1/98
Nov 27, 1994

REV	DATE	DESCRIPTION


APPROVED AS SHOWN WITH THE
SUN-TEK SKYLIGHTS SPEC.
SUN-TEK SKYLIGHTS SPEC.
SUN-TEK SKYLIGHTS SPEC.
SUN-TEK SKYLIGHTS SPEC.

1/17/02
Boyd

TEST DATE: 1-12-01
COMPANY: Sun-Tek
JOB NO.: NCT-210-2132
NATIONAL CERTIFIED
TESTING LABORATORIES

The test specimen was mounted to the
test truck using
screws located at location shown

NOTE: ALL DIMENSIONS NOMINAL & TYPICAL



FASTENER LOCATIONS

ASTM HERITAGE 30 AR®

LAMINATED ASPHALT SHINGLES

PRODUCT DATA



Manufactured in Tuscaloosa, AL.

ASTM HERITAGE 30 AR® shingles feature a double-layer fiberglass mat construction with a random-cut sawtooth design.

The two layers of mat are coated with asphalt and then laminated together and surfaced with mineral granules that will help protect against discoloration caused by algae. A self-sealing strip of asphalt helps provide added wind resistance.

USES

For application to roof decks with inclines of not less than 2 inches per foot. For slopes between 2 inches and 4 inches per foot, refer to wrapper instructions.

ADVANTAGES

- 30 year limited warranty, 5 year FULL START, limited transferability, winds up to 70 MPH
- Affordable upgrade from 3-tab shingles
- Superior fire resistance compared to organic shingles
- Rustic beauty of wood shakes
- Shadowtone feature adds depth and dimensional appearance
- Algae resistant granules to protect against discoloration in areas where extreme humidity is a problem
- 10 year limited warranty against discoloration caused by certain algae growth

CERTIFICATIONS

UL Class A Fire Rating
UL Wind Resistant

ASTM D 3018, Type I
ASTM E 108, Class A
ASTM D 3161 Type I (modified to 110 mph)
ASTM D 3462

Fed. Spec.: Exceeds SS-S-001534,
Class A, Type I


COLORS

Classic Heritage Colors:

- | | | |
|------------------|----------------|-----------------------|
| • Weathered Wood | • Oxford Grey | • Olde English Pewter |
| • Rustic Cedar | • Shadow Grey | • Glacier White |
| • Rustic Hickory | • Desert Sand | • Rustic Evergreen |
| • Driftwood | • Rustic Black | |


PRODUCT DATA*

Shingle size	12" X 37"
Exposure	5"
Shingles per square	78
Bundles per square	3



*All values stated as nominal

CAUTION: The National Institute for Occupational Safety and Health (NIOSH) has concluded that fumes of heated asphalt are a potential occupational carcinogen. Do not heat or burn this product.



TAMKO
ROOFING PRODUCTS

TAMKO® is a registered trademark of
TAMKO Roofing Products, Inc.

Visit our Web Site at www.tamko.com

01/2002

Central District	220 West 4th St., Joplin, MO	64801	800-641-4691
Northeast District	4500 Tamko Dr., Frederick, MD	21701	800-368-2055
Southeast District	2300 35th St., Tuscaloosa, AL	35401	800-228-2656
Southwest District	7910 S. Central Exp., Dallas, TX	75216	800-443-1834
Western District	5300 East 43rd Ave., Denver, CO	80216	800-530-8868

Alpine Engineered Products, Inc.

1950 Marley Drive Haines City, FL 33844

Florida Engineering Certificate of Authorization Number: 567

Florida Certificate of Product Approval # FL1999

Page 1 of 1 Document ID:1SLV215-Z0704162250

Truss Fabricator: W.B. Howland

Job Identification: 2220-/EDGLEY// STEPHENSON/HANGE /EDGELY CONSTRUCTION -- , **

Truss Count: 31

Model Code: Florida Building Code 2001

Truss Criteria: ANSI/TPI-1995;ANSI/TPI-1995(STD)

Engineering Software: Alpine Software,Version 7.11.0116.20.

Structural Engineer of Record:

Address:

Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration

Floor - N/A

Wind - 110 MPH ASCE 7-98 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1-1995 Section 2.2
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR215

Details: BRCLBSUB-CNBRGBLK-A11030EC-GBLLETIN

Seal Date: 04/04/2005

-Truss Design Engineer-

James F. Collins Jr.

Florida License Number: 52212

1950 Marley Drive

Haines City, FL 33844

#	Ref	Description	Drawing#	Date
1	90435--A-1		05094030	04/04/05
2	90436--A-2		05094020	04/04/05
3	90437--A-3		05094021	04/04/05
4	90438--A-4		05094022	04/04/05
5	90439--A-5		05094023	04/04/05
6	90440--A-6		05094024	04/04/05
7	90441--A-7		05094025	04/04/05
8	90442--A-8		05094026	04/04/05
9	90443--A-9		05094031	04/04/05
10	90444--A-10		05094027	04/04/05
11	90445--A-11		05094028	04/04/05
12	90446--A-12		05094032	04/04/05
13	90447--A-13		05094033	04/04/05
14	90448--A-14		05094034	04/04/05
15	90449--A-15		05094035	04/04/05
16	90450--A-16		05094036	04/04/05
17	90451--A-17		05094037	04/04/05
18	90452--A-18		05094038	04/04/05
19	90453--A-19		05094039	04/04/05
20	90454--AGDR-1		05094040	04/04/05
21	90455--AGDR-2		05094041	04/04/05
22	90456--AGDR-3		05094049	04/04/05
23	90457--GE1		05094042	04/04/05
24	90458--GE2		05094043	04/04/05
25	90459--GE3		05094044	04/04/05
26	90460--GEGDR1		05094045	04/04/05
27	90461--GEGDR2		05094050	04/04/05
28	90462--GEGDR3		05094046	04/04/05
29	90463--H2A		05094047	04/04/05
30	90464--M1		05094029	04/04/05
31	90465--MGDR1		05094048	04/04/05




Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #2 N

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 4-4-3.





PLT TYP. Wave TPI/R

Design Crit: TPI-1995(STD)

7.1

Scale = .375"/Ft.


 Alpine Engineered Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567	**WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. TRUSSES IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		TC LL	20.0 PSF	REF	R215--	90435
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEER PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		TC DL	10.0 PSF	DATE	04/04/05	
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEER PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		BC DL	10.0 PSF	DRW	HCUSR215	05094030
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEER PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		BC LL	0.0 PSF	HC-ENG	EC/AP	
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEER PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		TOT.LD.	40.0 PSF	SEQN-	130851	
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEER PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		DUR.FAC.	1.25	FROM	CDM	
IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEER PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OF FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI (A900) TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN MADISON, WI 53719. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		SPACING	24.0"	JREF-	1SLV215_Z07		



110 mph wind, 30.00 ft mean hgt., ASCE 7-98, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 4-4-3.



Design Crit: TPI-1995 (STD)

7.18

Scale = .375"/Ft.

WARNING THUSSES REQUIRE EXTREME CARE IN ABOLITION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO U.S.S.I. (U.S. STEEL INSTITUTE), PUBLISHED BY IPT (TRUSS PLATE INSTITUTE), 583 P. O. BOX 100, SUITE 200, MADISON, WI 53710, FOR SAFETY PRACTICES PRIOR TO OPERATION. THESE CONDITIONS ARE NECESSARY TO PREVENT PERSONAL INJURY. IF THESE CONDITIONS ARE VIOLATED, THE USER ASSUMES ALL LIABILITY. THE TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

REF	R215--	90436
DATE	04/04/05	

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR.
PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN;
THE TRUSS IN CONFORMANCE WITH TPI; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES,
CONNECTED CONDITIONS WITH UNDESIRABLE PROVISIONS OF NON-NATIONAL DESIGN SPEC, BY APRAFA) AND TPI).
ALPINE
APPLY
FORCES
PLATES TO EACH FACE OF TRUSS AND JOINTS, AS SHOWN ON SHEETS [W-670-S] GALV. STEEL
AN INSPECTION OF PLATES FOLLOWED BY (F), SHALL BE PER AMER #3 OF TP1-2002 SEC. 3.3.1
REPAIRING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT
DESIGN SHOWN. THE SUBMITTALS AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE
BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

DRW	HCUSR215	0509402
HC-ENG	EC/AP	
SEQN-	130857	
FROM	CDM	
JREF-	1\$LV215	707
SPACING	24.0"	

Haines City, FL 33844
FL Certificate of Authorization # 567

Apr 04 '05

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

(A) Continuous lateral bracing equally spaced on member.

Deflection meets L/240 live and L/180 total load.


Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 9'-0".

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



1'-4'-0"

17'-3'-11"

10'-4'-10"

17'-3'-11"

45'-0'-0" Over 2 Supports

R=1885 U-432 W=6"

R=1885 U=432 W=6"


PLT TYP. Wave TPI/R

Design Crit: TPI-1995(STD)

7.1

Scale = .125"/Ft.

TC LL	20.0 PSF	REF R215--	90438
TC DL	10.0 PSF	DATE	04/04/05
BC DL	10.0 PSF	DRW HCUSR215	05094022
BC LL	0.0 PSF	HC-ENG EC/AP	*
TOT.LD.	40.0 PSF	SEON-	130666
DUR.FAC.	1.25	FROM	CDM
SPACING	24.0"	JREF-	1SLV215_Z07



Apr 04 '05

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 581 D'ORFORD DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS TO THIS DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. THE DESIGNER'S DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE 2010/166A (W-16S/A) ASTM A653 GRADE 40/50, 48/50, 50/50, 55/50, 60/50, 65/50, 70/50, 75/50, 80/50, 85/50, 90/50, 95/50, 100/50, 105/50, 110/50, 115/50, 120/50, 125/50, 130/50, 135/50, 140/50, 145/50, 150/50, 155/50, 160/50, 165/50, 170/50, 175/50, 180/50, 185/50, 190/50, 195/50, 200/50, 205/50, 210/50, 215/50, 220/50, 225/50, 230/50, 235/50, 240/50, 245/50, 250/50, 255/50, 260/50, 265/50, 270/50, 275/50, 280/50, 285/50, 290/50, 295/50, 300/50, 305/50, 310/50, 315/50, 320/50, 325/50, 330/50, 335/50, 340/50, 345/50, 350/50, 355/50, 360/50, 365/50, 370/50, 375/50, 380/50, 385/50, 390/50, 395/50, 400/50, 405/50, 410/50, 415/50, 420/50, 425/50, 430/50, 435/50, 440/50, 445/50, 450/50, 455/50, 460/50, 465/50, 470/50, 475/50, 480/50, 485/50, 490/50, 495/50, 500/50, 505/50, 510/50, 515/50, 520/50, 525/50, 530/50, 535/50, 540/50, 545/50, 550/50, 555/50, 560/50, 565/50, 570/50, 575/50, 580/50, 585/50, 590/50, 595/50, 600/50, 605/50, 610/50, 615/50, 620/50, 625/50, 630/50, 635/50, 640/50, 645/50, 650/50, 655/50, 660/50, 665/50, 670/50, 675/50, 680/50, 685/50, 690/50, 695/50, 700/50, 705/50, 710/50, 715/50, 720/50, 725/50, 730/50, 735/50, 740/50, 745/50, 750/50, 755/50, 760/50, 765/50, 770/50, 775/50, 780/50, 785/50, 790/50, 795/50, 800/50, 805/50, 810/50, 815/50, 820/50, 825/50, 830/50, 835/50, 840/50, 845/50, 850/50, 855/50, 860/50, 865/50, 870/50, 875/50, 880/50, 885/50, 890/50, 895/50, 900/50, 905/50, 910/50, 915/50, 920/50, 925/50, 930/50, 935/50, 940/50, 945/50, 950/50, 955/50, 960/50, 965/50, 970/50, 975/50, 980/50, 985/50, 990/50, 995/50, 1000/50, 1005/50, 1010/50, 1015/50, 1020/50, 1025/50, 1030/50, 1035/50, 1040/50, 1045/50, 1050/50, 1055/50, 1060/50, 1065/50, 1070/50, 1075/50, 1080/50, 1085/50, 1090/50, 1095/50, 1100/50, 1105/50, 1110/50, 1115/50, 1120/50, 1125/50, 1130/50, 1135/50, 1140/50, 1145/50, 1150/50, 1155/50, 1160/50, 1165/50, 1170/50, 1175/50, 1180/50, 1185/50, 1190/50, 1195/50, 1200/50, 1205/50, 1210/50, 1215/50, 1220/50, 1225/50, 1230/50, 1235/50, 1240/50, 1245/50, 1250/50, 1255/50, 1260/50, 1265/50, 1270/50, 1275/50, 1280/50, 1285/50, 1290/50, 1295/50, 1300/50, 1305/50, 1310/50, 1315/50, 1320/50, 1325/50, 1330/50, 1335/50, 1340/50, 1345/50, 1350/50, 1355/50, 1360/50, 1365/50, 1370/50, 1375/50, 1380/50, 1385/50, 1390/50, 1395/50, 1400/50, 1405/50, 1410/50, 1415/50, 1420/50, 1425/50, 1430/50, 1435/50, 1440/50, 1445/50, 1450/50, 1455/50, 1460/50, 1465/50, 1470/50, 1475/50, 1480/50, 1485/50, 1490/50, 1495/50, 1500/50, 1505/50, 1510/50, 1515/50, 1520/50, 1525/50, 1530/50, 1535/50, 1540/50, 1545/50, 1550/50, 1555/50, 1560/50, 1565/50, 1570/50, 1575/50, 1580/50, 1585/50, 1590/50, 1595/50, 1600/50, 1605/50, 1610/50, 1615/50, 1620/50, 1625/50, 1630/50, 1635/50, 1640/50, 1645/50, 1650/50, 1655/50, 1660/50, 1665/50, 1670/50, 1675/50, 1680/50, 1685/50, 1690/50, 1695/50, 1700/50, 1705/50, 1710/50, 1715/50, 1720/50, 1725/50, 1730/50, 1735/50, 1740/50, 1745/50, 1750/50, 1755/50, 1760/50, 1765/50, 1770/50, 1775/50, 1780/50, 1785/50, 1790/50, 1795/50, 1800/50, 1805/50, 1810/50, 1815/50, 1820/50, 1825/50, 1830/50, 1835/50, 1840/50, 1845/50, 1850/50, 1855/50, 1860/50, 1865/50, 1870/50, 1875/50, 1880/50, 1885/50, 1890/50, 1895/50, 1900/50, 1905/50, 1910/50, 1915/50, 1920/50, 1925/50, 1930/50, 1935/50, 1940/50, 1945/50, 1950/50, 1955/50, 1960/50, 1965/50, 1970/50, 1975/50, 1980/50, 1985/50, 1990/50, 1995/50, 2000/50, 2005/50, 2010/50, 2015/50, 2020/50, 2025/50, 2030/50, 2035/50, 2040/50, 2045/50, 2050/50, 2055/50, 2060/50, 2065/50, 2070/50, 2075/50, 2080/50, 2085/50, 2090/50, 2095/50, 2100/50, 2105/50, 2110/50, 2115/50, 2120/50, 2125/50, 2130/50, 2135/50, 2140/50, 2145/50, 2150/50, 2155/50, 2160/50, 2165/50, 2170/50, 2175/50, 2180/50, 2185/50, 2190/50, 2195/50, 2200/50, 2205/50, 2210/50, 2215/50, 2220/50, 2225/50, 2230/50, 2235/50, 2240/50, 2245/50, 2250/50, 2255/50, 2260/50, 2265/50, 2270/50, 2275/50, 2280/50, 2285/50, 2290/50, 2295/50, 2300/50, 2305/50, 2310/50, 2315/50, 2320/50, 2325/50, 2330/50, 2335/50, 2340/50, 2345/50, 2350/50, 2355/50, 2360/50, 2365/50, 2370/50, 2375/50, 2380/50, 2385/50, 2390/50, 2395/50, 2400/50, 2405/50, 2410/50, 2415/50, 2420/50, 2425/50, 2430/50, 2435/50, 2440/50, 2445/50, 2450/50, 2455/50, 2460/50, 2465/50, 2470/50, 2475/50, 2480/50, 2485/50, 2490/50, 2495/50, 2500/50, 2505/50, 2510/50, 2515/50, 2520/50, 2525/50, 2530/50, 2535/50, 2540/50, 2545/50, 2550/50, 2555/50, 2560/50, 2565/50, 2570/50, 2575/50, 2580/50, 2585/50, 2590/50, 2595/50, 2600/50, 2605/50, 2610/50, 2615/50, 2620/50, 2625/50, 2630/50, 2635/50, 2640/50, 2645/50, 2650/50, 2655/50, 2660/50, 2665/50, 2670/50, 2675/50, 2680/50, 2685/50, 2690/50, 2695/50, 2700/50, 2705/50, 2710/50, 2715/50, 2720/50, 2725/50, 2730/50, 2735/50, 2740/50, 2745/50, 2750/50, 2755/50, 2760/50, 2765/50, 2770/50, 2775/50, 2780/50, 2785/50, 2790/50, 2795/50, 2800/50, 2805/50, 2810/50, 2815/50, 2820/50, 2825/50, 2830/50, 2835/50, 2840/50, 2845/50, 2850/50, 2855/50, 2860/50, 2865/50, 2870/50, 2875/50, 2880/50, 2885/50, 2890/50, 2895/50, 2900/50, 2905/50, 2910/50, 2915/50, 2920/50, 2925/50, 2930/50, 2935/50, 2940/50, 2945/50, 2950/50, 2955/50, 2960/50, 2965/50, 2970/50, 2975/50, 2980/50, 2985/50, 2990/50, 2995/50, 3000/50, 3005/50, 3010/50, 3015/50, 3020/50, 3025/50, 3030/50, 3035/50, 3040/50, 3045/50, 3050/50, 3055/50, 3060/50, 3065/50, 3070/50, 3075/50, 3080/50, 3085/50, 3090/50, 3095/50, 3100/50, 3105/50, 3110/50, 3115/50, 3120/50, 3125/50, 3130/50, 3135/50, 3140/50, 3145/50, 3150/50, 3155/50, 3160/50, 3165/50, 3170/50, 3175/50, 3180/50, 3185/50, 3190/50, 3195/50, 3200/50, 3205/50, 3210/50, 3215/50, 3220/50, 3225/50, 3230/50, 3235/50, 3240/50, 3245/50, 3250/50, 3255/50, 3260/50, 3265/50, 3270/50, 3275/50, 3280/50, 3285/50, 3290/50, 3295/50, 3300/50, 3305/50, 3310/50, 3315/50, 3320/50, 3325/50, 3330/50, 3335/50, 3340/50, 3345/50, 3350/50, 3355/50, 3360/50, 3365/50, 3370/50, 3375/50, 3380/50, 3385/50, 3390/50, 3395/50, 3400/50, 3405/50, 3410/50, 3415/50, 3420/50, 3425/50, 3430/50, 3435/50, 3440/50, 3445/50, 3450/50, 3455/50, 3460/50, 3465/50, 3470/50, 3475/50, 3480/50, 3485/50, 3490/50, 3495/50, 3500/50, 3505/50, 3510/50, 3515/50, 3520/50, 3525/50, 3530/50, 3535/50, 3540/50, 3545/50, 3550/50, 3555/50, 3560/50, 3565/50, 3570/50, 3575/50, 3580/50, 3585/50, 3590/50, 3595/50, 3600/50, 3605/50, 3610/50, 3615/50, 3620/50, 3625/50, 3630/50, 3635/50, 3640/50, 3645/50, 3650/50, 3655/50, 3660/50, 3665/50, 3670/50, 3675/50, 3680/50, 3685/50, 3690/50, 3695/50, 3700/50, 3705/50, 3710/50, 3715/50, 3720/50, 3725/50, 3730/50, 3735/50, 3740/50, 3745/50, 3750/50, 3755/50, 3760/50, 3765/50, 3770/50, 3775/50, 3780/50, 3785/50, 3790/50, 3795/50, 3800/50, 3805/50, 3810/50, 3815/50, 3820/50, 3825/50, 3830/50, 3835/50, 3840/50, 3845/50, 3850/50, 3855/50, 3860/50, 3865/50, 3870/50, 3875/50, 3880/50, 3885/50, 3890/50, 3895/50, 3900/50, 3905/50, 3910/50, 3915/50, 3920/50, 3925/50, 3930/50, 3935/50, 3940/50, 3945/50, 3950/50, 3955/50, 3960/50, 3965/50, 3970/50, 3975/50, 3980/50, 3985/50, 3990/50, 3995/50, 4000/50, 4005/50, 4010/50, 4015/50, 4020/50, 4025/50, 4030/50, 4035/50, 4040/50, 4045/50, 4050/50, 4055/50, 4060/50, 4065/50, 4070/50, 4075/50, 4080/50, 4085/50, 4090/50, 4095/50, 4100/50, 4105/50, 4110/50, 4115/50, 4120/50, 4125/50, 4130/50, 4135/50, 4140/50, 4145/50, 4150/50, 4155/50, 4160/50, 4165/50, 4170/50, 4175/50, 4180/50, 4185/50, 4190/50, 4195/50, 4200/50, 4205/50, 4210/50, 4215/50, 4220/50, 4225/50, 4230/50, 4235/50, 4240/50, 4245/50, 4250/50, 4255/50, 4260/50, 4265/50, 4270/50, 4275/50, 4280/50, 4285/50, 4290/50, 4295/50, 4300/50, 4305/50, 4310/50, 4315/50, 4320/50, 4325/50, 4330/50, 4335/50, 4340/50, 4345/50, 4350/50, 4355/50, 4360/50, 4365/50, 4370/50, 4375/50, 4380/50, 4385/50, 4390/50, 4395/50, 4400/50, 4405/50, 4410/50, 4415/50, 4420/50, 4425/50, 4430/50, 4435/50, 4440/50, 4445/50, 4450/50, 4455/50, 4460/50, 4465/50, 4470/50, 4475/50, 4480/50, 4485/50, 4490/50, 4495/50, 4500/50, 4505/50, 4510/50, 4515/50, 4520/50, 4525/50, 4530/50, 4535/50, 4540/50, 4545/50, 4550/50, 4555/50, 4560/50, 4565/50, 4570/50, 4575/50, 4580/50, 4585/50, 4590/50, 4595/50, 4600/50, 4605/50, 4610/50, 4615/50, 4620/50, 4625/50, 4630/50, 4635/50, 4640/50, 4645/50, 4650/50, 4655/50, 4660/50, 4665/50, 4670/50, 4675/50, 4680/50, 4685/50, 4690/50, 4695/50, 4700/50, 4705/50, 4710/50, 4715/50, 4720/50, 4725/50, 4730/50, 4735/50, 4740/50, 4745/50, 4750/50, 4755/50, 4760/50, 4765/50, 4770/50, 4775/50, 4780/50, 4785/50, 4790/50, 4795/50, 4800/50, 4805/50, 4810/50, 4815/50, 4820/50, 4825/50, 4830/50, 4835/50, 4840/50, 4845/50, 4850/50, 4855/50, 4860/50, 4865/50, 4870/50, 4875/50, 4880/50, 4885/50, 4890/50, 4895/50, 4900/50, 4905/50, 4910/50, 4915/50, 4920/50, 4925/50, 4930/50, 4935/50, 4940/50, 4945/50, 4950/50, 4955/50, 4960/50, 4965/50, 4970/50, 4975/50, 4980/50, 4985/50, 4990/50, 4995/50, 5000/50, 5005/50, 5010/50, 5015/50, 5020/50, 5025/50, 5030/50, 5035/50, 5040/50, 5045/50, 5050/50, 5055/50, 5060/50, 5065/50, 5070/50, 5075/50, 5080/50, 5085/50, 5090/50, 5095/50, 5100/50, 5105/50, 5110/50, 5115/50, 5120/50, 5125/50, 5130/50, 5135/50, 5140/50, 5145/50, 5150/50, 5155/50, 5160/50, 5165/50, 5170/50, 5175/50, 5180/50, 5185/50, 5190/50, 5195/50, 5200/50, 5205/50, 5210/50, 5215/50, 5220/50, 5225/50, 5230/50, 5235/50, 5240/50, 5245/50, 5250/50, 5255/50, 5260/50, 5265/50, 5270/50, 5275/50, 5280/50, 5285/50, 5290/50, 5295/50, 5300/50, 5305/50, 5310/50, 5315/50, 5320/50, 5325/50, 5330/50, 5335/50, 5340/50, 5345/50, 5350/50, 5355/50, 5360/50, 5365/50, 5370/50, 5375/50, 5380/50, 5385/50, 5390/50, 5395/50, 5400/50, 5405/50, 5410/50, 5415/50, 5420/50, 5425/50, 5430/50, 5435/50, 5440/50, 5445/50, 5450/50, 5455/50, 5460/50, 5465/50, 5470/50, 5475/50, 5480/50, 5485/50, 5490/50, 5495/50, 5500/50, 5505/50, 5510/50, 5515/50, 5520/50, 5525/50, 5530/50, 5535/50, 5540/50, 5545/50, 5550/50, 5555/50, 5560/50, 5565/50, 5570/50, 5575/50, 5580/50, 5585/50, 5590/50, 5595/50, 5600/50, 5605/50, 5610/50, 5615/50, 5620/50, 5625/50, 5630/50, 5635/50, 5640/50, 5645/50, 5650/50, 5655/50, 5660/50, 5665/50, 5670/50, 5675/50, 5680/50, 5685/50, 5690/50, 5695/50, 5700/50, 5705/50, 5710/50, 5715/50, 5720/50, 5725/50, 5730/50, 5735/50, 5740/50, 5745/50, 5750/50, 5755/50, 5760/50, 5765/50, 5770/50, 5775/50, 5780/50, 5785/50, 5790/50, 5795/50, 5800/50, 5805/50, 5810/50, 5815/50, 5820/50, 5825/50, 5830/50, 5835/50, 5840/50, 5845/50, 5850/50, 5855/50, 5860/50, 5865/50, 5870/50, 5875/50, 5880/50, 5885/50, 5890/50, 5895/50,

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

(A) Continuous lateral bracing equally spaced on member.

Deflection meets L/240 live and L/180 total load.


Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 8-0-0.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



PLT TYP. Wave TPI\R

Design Crit: TPI-1995(STD)

7.1

FL/-/5/-/-/R/- Scale = .125"/Ft.

TC LL	20.0 PSF	REF	R215-- 90439
TC DL	10.0 PSF	DATE	04/04/05
BC DL	10.0 PSF	DRW	HCUSR215 05094023
BC LL	0.0 PSF	HC-ENG	EC/AP
TOT.LD.	40.0 PSF	SEQN-	130672
DUR.FAC.	1.25	FROM	CDM
SPACING	24.0"	JREF-	1SLV215_Z07

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

JAMES F. COLLINS, P.E.
No. 0052218
STATE OF FLORIDA
PROFESSIONAL ENGINEER
APR 04 '05

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST PRACTICES (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 567 CORDARIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6200 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DETAILING OR FABRICATION OF THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF THE TRUSS. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/ASA) AND TPI. CONNECTOR PLATES ARE MADE OF 2018/16GA (H/H/S/S) ASTM A653 GRADE 40/60 (H, R/H/S) GALV. STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

In lieu of structural panels use purlins to brace all flat TC @ 24" OC.


Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 6-0-0.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



PLT TYP. Wave TPI\R

Design Crit: TPI-1995(STD)

7.1

Scale = .125"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 7-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D-0000100 DP-- SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE NATIONAL BUILDING SPECIFICATIONS. ALPINE CONNECTOR PLATES ARE MADE OF 20/10/16GA W-10/S/13 ASME A573 GRADE 40/60 (OR K/10/S) GALV. STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-1. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. A SEAL ON THIS DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) 1 SEC. 2.

ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



TC LL	20.0 PSF	FL/-/5/-/-/R/-	Scale = .125"/Ft.
TC DL	10.0 PSF	REF R215-- 90441	
BC DL	10.0 PSF	DATE 04/04/05	
BC LL	0.0 PSF	DRW HCUSR215 05094025	
TOT.LD.	40.0 PSF	HC-ENG EC/AP	
DUR.FAC.	1.25	SEON- 130684	
SPACING	24.0"	FROM CDM	
		JREF- 1SLV215_207	

Top chord 2x4 SP #2 N :T3, T6 2x4 SP SS:
 Bot chord 2x4 SP #2 N
 Webs 2x4 SP #2 N
 :Lt Splice Block 2x4 SP #2 N:

Deflection meets L/240 live and L/180 total load.


WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 5'-0.0.



PLT TYP. Wave TPI\R


Design Crit: TPI-1995(STD)

7.1


Scale = .125"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BECS 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'AMORE DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LB, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN AND FABRICATION OF THIS TRUSS. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIAA) AND TPI. CORRECTOR PLATES ARE MADE OF 2010/16GA (4-1/2\"/>



FL Certificate of Authorization # 567



TC LL	20.0 PSF	REF	R215-- 90442
TC DL	10.0 PSF	DATE	04/04/05
BC DL	10.0 PSF	DRW	HCUSR215 05094026
BC LL	0.0 PSF	HC-ENG	EC/AP
TOT.LD.	40.0 PSF	SEQN-	130690
DUR.FAC.	1.25	FROM	CDM
SPACING	24.0"	JREF-	1SLV215_Z07

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

In lieu of rigid ceiling use purlins to brace BC @ 24" OC

Plates sized for a minimum of 3.00 sq.in./piece.


Refer to DWG PIGBACK0204 for piggyback details.

Top chord of supporting truss under piggyback to be braced @ 24" O.C., unless otherwise specified.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=2.0 psf.

Deflection meets L/240 live and L/180 total load.

The overall height of this truss excluding overhang is 1-7-3.



R=77 PLF U=40 PLF W=4-5-0 R=13 U=180 W=7.826"

2-2-8 2-2-8

6-4-10 Over 3 Supports

0-11-13 2-2-8 0-11-13

PLT TYP. Wave TPI\R

Design Crit: TPI-1995(STD)


7.1

16 FL/-/5/-/1-/R/-

Scale = .375"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC317-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS TO THIS DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE 2010 INTERNATIONAL BUILDING CODE (IBC) AND THE 2010 ALPINE DESIGN CRITERIA. CORRECTOR PLATES ARE MADE OF 2010/1866 (M/A/S/E) ASTM A573 GRADE 60/60. CORRECTOR PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1604-7. ANY INSPECTION OF PLATES FOLLOWED BY (U) SHALL BE PER ABX 43 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567



TC LL	20.0 PSF	REF	R215--	90443
TC DL	10.0 PSF	DATE	04/04/05	
BC DL	2.0 PSF	DRW	HCUSR215	05094031
BC LL	0.0 PSF	HC-ENG	EC/AP	
TOT.LD.	32.0 PSF	SEON-	43126	
DUR.FAC.	1.25	FROM	CDM	
SPACING	24.0"	JREF-	1SLV215_207	

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N


The overall height of this truss excluding overhang is 10'-1-3".

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.



R=1134 U=290 H=Simpson LUS26
w/ (4) 10d Common, 0.148"x3.0" nails in Truss
w/ (4) 10d Common, 0.148"x3.0" nails in Girder
Girder is (2)2X6 min. So.Pine

PLT TYP. Wave TPI\R


Design Crit: TPI-1995(STD)

7.1

FL/-/5/-/R/-

Scale = .1875"/Ft.

REF	R215 - 90447
DATE	04/04/05
DRW	HCUSR215 05094033
HC-ENG	EC/AP
SEQN	130751
FROM	CDM
JREF	1SLV215_Z07



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 583 D-000010 DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD INSTITUTE OF AMERICA, 6300 ENTERPRISE LANE, SUITE 100, WILSONVILLE, IN 46093) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORDS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR THE DESIGN, FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&P) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/10/16GA (0.011/0.015) ASTM A653 GRADE 40/60 (H, K/H, S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMEX A3 OF TPI-2002 SEC.3. A SEAL OR THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Top chord 2x4 SP #2 N
 Bot chord 2x4 SP #2 N
 Webs 2x4 SP #2 N
 :Lt Bearing Leg 2x4 SP #2 N:

(A) Continuous lateral bracing equally spaced on member.


In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 8-5-1.



PLT TYP. Wave TPI\|R


Design Crit: TPI-1995(STD)

7.1

Scale = .25"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ORFORD DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERING PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN ACCORDANCE WITH THIS DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. DESIGNER'S PLATES ARE MADE OF 2018/16GAL. ALUMINUM. CONNECTOR PLATES ARE MADE OF 2018/16GAL. ALUMINUM. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1000-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANSI A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



FL Certificate of Authorization # 567



TC LL	20.0 PSF	FL / - / 5 / - / - / R / -	REF R215 -- 90449
TC DL	10.0 PSF		DATE 04/04/05
BC DL	10.0 PSF		DRW HCUSR215 05094035
BC LL	0.0 PSF		HC-ENG EC/AP
TOT.LD.	40.0 PSF		SEON - 130787
DUR.FAC.	1.25		FROM CDM
SPACING	24.0"		JREF - 1SLV215_207


110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.
Plates sized for a minimum of 3.00 sq.in./piece.

(A) Continuous lateral bracing equally spaced on member.

In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

The overall height of this truss excluding overhang is 6-11-1.



PLT TYP. Wave TPI\R

Design Crit: TPI-1995(STD)

7.1

Scale = .25"/Ft.


****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'OROTARIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN ACCORDANCE WITH TPI-1995 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'OROTARIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED, SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN ACCORDANCE WITH TPI-1995 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'OROTARIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED, SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR.



Alpine Engineered Products, Inc.
1950 Manley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567



TC LL	20.0 PSF	REF	R215 --	90450
TC DL	10.0 PSF	DATE	04/04/05	
BC DL	10.0 PSF	DRW	HCUSR215	05094036
BC LL	0.0 PSF	HC-ENG	EC/AP	
TOT.LD.	40.0 PSF	SEON-	130813	
DUR.FAC.	1.25	FROM	CDM	
SPACING	24.0"	JREF-	1SLV215_207	

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N
:Lt Bearing Leg 2x4 SP #2 N:

(A) Continuous lateral bracing equally spaced on member.


In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

The overall height of this truss excluding overhang is 3-11-1.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.



PLT TYP. Wave TPI/R


Design Crit: TPI-1995(STD)

7.1


Scale = .25"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO DESIGN 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 6000 ENTERPRISE LN, MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AIA/PAJ AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/16GA (4-H/5/8) ASTM A653 GRADE 40/60 (IN. K/H-5) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY IT SHALL BE LEFT ABANDONED BY TPI-2002/CEC-3. A SEAL ON THIS DESIGN SHALL BE PLACED ON THE BOTTOM CHORD FOR THE TRUSS. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



TC LL	20.0 PSF	REF	R215--	90452
TC DL	10.0 PSF	DATE	04/04/05	
BC DL	10.0 PSF	DRW	HCUSR215	05094038
BC LL	0.0 PSF	HC-ENG	EC/AP	
TOT.LD.	40.0 PSF	SEON	130827	
DUR.FAC.	1.25	FROM	CDM	
SPACING	24.0"	JREF	1SLV215_207	


Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N
Left Bearing Leg 2x4 SP #2 N:

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.

The overall height of this truss excluding overhang is 3.0-3.

plates sized for a minimum of 3.00 sq. in./piece.



PLT_TYP. Wave TPI\IR

Design Crit: TPI-1995 (STD)

Scale = .25"/Ft.

*****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO DESG 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PAPER INSTITUTE, 583 S. MONROIE DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO BE INSTALLATION CONTRACTOR. ANY FAILURE TO BUILD THE PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE DESIGN IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING A BRACING OF TROUSSES, TROUSSES COMING WITH APPLICABLE PROVISIONS OF THIS REGULATION OR 49CFR 171.10, 171.11, 171.12, 171.13, 171.14, 171.15, 171.16, 171.17, 171.18, 171.19, 171.20, 171.21, 171.22, 171.23, 171.24, 171.25, 171.26, 171.27, 171.28, 171.29, 171.30, 171.31, 171.32, 171.33, 171.34, 171.35, 171.36, 171.37, 171.38, 171.39, 171.40, 171.41, 171.42, 171.43, 171.44, 171.45, 171.46, 171.47, 171.48, 171.49, 171.50, 171.51, 171.52, 171.53, 171.54, 171.55, 171.56, 171.57, 171.58, 171.59, 171.60, 171.61, 171.62, 171.63, 171.64, 171.65, 171.66, 171.67, 171.68, 171.69, 171.70, 171.71, 171.72, 171.73, 171.74, 171.75, 171.76, 171.77, 171.78, 171.79, 171.80, 171.81, 171.82, 171.83, 171.84, 171.85, 171.86, 171.87, 171.88, 171.89, 171.90, 171.91, 171.92, 171.93, 171.94, 171.95, 171.96, 171.97, 171.98, 171.99, 171.100, 171.101, 171.102, 171.103, 171.104, 171.105, 171.106, 171.107, 171.108, 171.109, 171.110, 171.111, 171.112, 171.113, 171.114, 171.115, 171.116, 171.117, 171.118, 171.119, 171.120, 171.121, 171.122, 171.123, 171.124, 171.125, 171.126, 171.127, 171.128, 171.129, 171.130, 171.131, 171.132, 171.133, 171.134, 171.135, 171.136, 171.137, 171.138, 171.139, 171.140, 171.141, 171.142, 171.143, 171.144, 171.145, 171.146, 171.147, 171.148, 171.149, 171.150, 171.151, 171.152, 171.153, 171.154, 171.155, 171.156, 171.157, 171.158, 171.159, 171.160, 171.161, 171.162, 171.163, 171.164, 171.165, 171.166, 171.167, 171.168, 171.169, 171.170, 171.171, 171.172, 171.173, 171.174, 171.175, 171.176, 171.177, 171.178, 171.179, 171.180, 171.181, 171.182, 171.183, 171.184, 171.185, 171.186, 171.187, 171.188, 171.189, 171.190, 171.191, 171.192, 171.193, 171.194, 171.195, 171.196, 171.197, 171.198, 171.199, 171.200, 171.201, 171.202, 171.203, 171.204, 171.205, 171.206, 171.207, 171.208, 171.209, 171.210, 171.211, 171.212, 171.213, 171.214, 171.215, 171.216, 171.217, 171.218, 171.219, 171.220, 171.221, 171.222, 171.223, 171.224, 171.225, 171.226, 171.227, 171.228, 171.229, 171.230, 171.231, 171.232, 171.233, 171.234, 171.235, 171.236, 171.237, 171.238, 171.239, 171.240, 171.241, 171.242, 171.243, 171.244, 171.245, 171.246, 171.247, 171.248, 171.249, 171.250, 171.251, 171.252, 171.253, 171.254, 171.255, 171.256, 171.257, 171.258, 171.259, 171.260, 171.261, 171.262, 171.263, 171.264, 171.265, 171.266, 171.267, 171.268, 171.269, 171.270, 171.271, 171.272, 171.273, 171.274, 171.275, 171.276, 171.277, 171.278, 171.279, 171.280, 171.281, 171.282, 171.283, 171.284, 171.285, 171.286, 171.287, 171.288, 171.289, 171.290, 171.291, 171.292, 171.293, 171.294, 171.295, 171.296, 171.297, 171.298, 171.299, 171.300, 171.301, 171.302, 171.303, 171.304, 171.305, 171.306, 171.307, 171.308, 171.309, 171.310, 171.311, 171.312, 171.313, 171.314, 171.315, 171.316, 171.317, 171.318, 171.319, 171.320, 171.321, 171.322, 171.323, 171.324, 171.325, 171.326, 171.327, 171.328, 171.329, 171.330, 171.331, 171.332, 171.333, 171.334, 171.335, 171.336, 171.337, 171.338, 171.339, 171.340, 171.341, 171.342, 171.343, 171.344, 171.345, 171.346, 171.347, 171.348, 171.349, 171.350, 171.351, 171.352, 171.353, 171.354, 171.355, 171.356, 171.357, 171.358, 171.359, 171.360, 171.361, 171.362, 171.363, 171.364, 171.365, 171.366, 171.367, 171.368, 171.369, 171.370, 171.371, 171.372, 171.373, 171.374, 171.375, 171.376, 171.377, 171.378, 171.379, 171.380, 171.381, 171.382, 171.383, 171.384, 171.385, 171.386, 171.387, 171.388, 171.389, 171.390, 171.391, 171.392, 171.393, 171.394, 171.395, 171.396, 171.397, 171.398, 171.399, 171.400, 171.401, 171.402, 171.403, 171.404, 171.405, 171.406, 171.407, 171.408, 171.409, 171.410, 171.411, 171.412, 171.413, 171.414, 171.415, 171.416, 171.417, 171.418, 171.419, 171.420, 171.421, 171.422, 171.423, 171.424, 171.425, 171.426, 171.427, 171.428, 171.429, 171.430, 171.431, 171.432, 171.433, 171.434, 171.435, 171.436, 171.437, 171.438, 171.439, 171.440, 171.441, 171.442, 171.443, 171.444, 171.445, 171.446, 171.447, 171.448, 171.449, 171.450, 171.451, 171.452, 171.453, 171.454, 171.455, 171.456, 171.457, 171.458, 171.459, 171.460, 171.461, 171.462, 171.

REF R215-- 90453	20.0 PSF
DATE 04/04/05	10.0 PSF
DRW HCUSR215 0509403	10.0 PSF
HC-ENG EC/AP	0.0 PSF
SEQN- 130835	40.0 PSF
FROM CDM	1.25
JREF- 151V215 707	24.0"

Top chord 2x4 SP #2 N
Bot chord 2x6 SP #2 N
Webs 2x4 SP #2 N

SPECIAL LOADS

----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC - From 60 PLF at 0.00 to 60 PLF at 12.67
BC - From 20 PLF at 0.00 to 20 PLF at 12.67
BC - 1134 LB Conc. Load at 2.06, 4.06, 6.06, 8.06, 10.06
12.06

Deflection meets L/240 live and L/180 total load.


Plates sized for a minimum of 3.00 sq.in./piece.

2 COMPLETE TRUSSES REQUIRED

Nailing Schedule: (0.131x3.0 g_nails)
Top Chord: 1 Row @ 12" o.c.
Bot Chord: 2 Rows @ 6" o.c. (Each Row)
Webs : 1 Row @ 4" o.c.
Use equal spacing between rows and stagger nails
in each row to avoid splitting.

110 mph wind, 15.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC
DL=5.0 psf.

The overall height of this truss excluding overhang is 3-6-3.



PLT TYP. Wave TPI\R

Design Crit: TPI-1995(STD)

7.1

FL/-/5/-/-/R/- Scale = .375"/Ft.


ALPINE

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO UCS 1-01 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 583 D'ORFORD DR., SUITE 200, MADISON, WI 53719, AND MICA (WOOD TRUSS CONSTRUCTION MANUAL), PUBLISHED BY THE NATIONAL WOOD TRUSS ASSOCIATION, 1000 N. W. 10TH AVE., SUITE 100, MIAMI, FL 33136, FOR SAFETY PRACTICES. TRUSSES SHALL BE PROPERLY ATTACHED TO THE STRUCTURE. ALL TRUSSES SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF THESE TRUSSES SHALL BE THE RESPONSIBILITY OF THE INSTALLER. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AIA/ASA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2010/166A (M/U/S/P) ASTM A563 GRADE 40/60 (M, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



REF	R215--	90454
DATE	04/04/05	
DRW	HCUSR215	05094040
HC-ENG	EC/AP	
SEQN	130757	
FROM	CDM	
JREF	1SLV215_207	

JREF- 1SLV215_Z07

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #2 N

See DWGS A11030EC1103 & GBLETTIN1103 for more requirements.


Plates sized for a minimum of 3.00 sq.in./piece.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF THE ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, AND SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO THE GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/240 live and L/180 total load.

The overall height of this truss excluding overhang is 4'-0"-4".



R-80 PLF U-23 PLF W-16-0-0

Note: All Plates Are 2X4 Except As Shown.

PLT TYP. Wave TPI\

Design Crit: TPI-1995(STD)

7.1


FL/-5/-/-R/-

Scale = .375"/Ft.


REF	R215--	90457
DATE	04/04/05	
DRW	HCUSR215	05094042
HC-ENG	EC/AP	
SEQN-	130726	
FROM	LB	
JREF-	1SLV215_Z07	

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO RES 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ORFORD DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE DR., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. ANY FAILURE TO BUILD TO THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. ANY FAILURE TO BUILD TO THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. ANY FAILURE TO BUILD TO THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR.



Alpine Engineered Products, Inc.
1950 Manley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567




	Top chord	2x4	SP	#2	N
Bot chord	2x4	SP	#2	Dense	
Webbs	2x4	SP	#2	N	

See DWGS A11030EC1103 & GBLLETIN1103 for more requirements.

Plates sized for a minimum of 3.00 sq.in./piece.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF THE ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, AND SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO THE GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.



R=80 PLF U=23 PLF W=12-8-0

Note: All Plates Are 2X4 Except As Shown.

PLT TYP. Wave TPI\R	Design Crit: TPI-1995(STD)		7.17 APR 04 '05	FL / - / 5 / - / R / -	Scale = .375" / Ft.
			No. 0052212	TC LL	20.0 PSF
			STATE OF FLORIDA PROFESSIONAL ENGINEER	TC DL	10.0 PSF
				BC DL	10.0 PSF
				BC LL	0.0 PSF
				TOT.LD.	40.0 PSF
				DUR.FAC.	1.25
				SPACING	24.0"
				REF	R215 -- 90458
				DATE	04/04/05
				DRW	HCSR215 05094043
				HC-ENG EC/AP	
				SEQN-	130721
				FROM	LB
				JREF-	1SLV215_Z07

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCS1-T-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 501 GORDON DR., SUITE 200, MADISON, WI 53719, AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, SUITE 100, FARMINGTON, CT 06031) FOR ADDITIONAL INFORMATION. UNLESS OTHERWISE INDICATED, ALL TRUSS CHORDS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERING PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DAMAGE OR LOSS OF LIFE OR PROPERTY DUE TO FAILURE OF BUILDINGS OR EQUIPMENT. THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIAPP) AND IPTL (ALPINE TRUSS LOADS). CORRELATOR PLATES ARE MADE OF 20/10/16GA. (20/10/16 GA.) ASTM A653 GRADE 40/60 (40, K/60.5) GALV. STEEL. APPLY PLATES TO EACH FACE OF IPPSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ABEX A3 OF IP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE ITPSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

See DWGS A11030EC1103 & GBLLETIN1103 for more requirements.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.


THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF THE ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, AND SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO THE GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) 1x4 "L" brace. 80% length of web member. Same species & grade or better. Attach with 8d Box or Gun (0.113"x2.5",min.) nails @ 6" OC.

The overall height of this truss excluding overhang is 9-9-4.

+ MEMBER TO BE LATERALLY BRACED FOR HORIZONTAL WIND LOADS. BRACING SYSTEM TO BE DESIGNED AND FURNISHED BY OTHERS.



Note: All Plates Are 2X4 Except As Shown.

PLT TYP. Wave TPI\|R

Design Crit: TPI-1995 (STD)

7.1

Scale = .1875"/Ft.

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"

REF R215-- 90459

DATE 04/04/05

DRW HCUSR215 05094044

HC-ENG EC/AP

SEQN- 130732

FROM LB

JREF- 1SLV215_Z07



ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC1 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 O'DONOHIO DR., SUITE 200, MADISON, WI 53719) AND MCA (WOOD TRUSS COUNCIL OF AMERICA, 6000 ENTERPRISE LN MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. ANY FAILURE TO BUILD THE TRUSS IN ACCORDANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. THE DESIGNER CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AF&PA) AND TPI. ALPINE CORRELATOR PLATES ARE MADE OF 20/18/16GA (W/H/S/E) ASTM A653 GRADE 40/60 (W, V/A/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL OF PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

Gable end supports 8" max rake overhang.

In lieu of structural panels use purlins to brace all flat TC @ 24" OC.

Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 4-3-11.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF THE ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, AND SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO THE GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.


See DWGS A11030EC1103 & GBLLETIN1103 for more requirements.

Deflection meets L/240 live and L/180 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

+ MEMBER TO BE LATERALLY BRACED FOR HORIZONTAL WIND LOADS. BRACING SYSTEM TO BE DESIGNED AND FURNISHED BY OTHERS.

6



R=951 U=217 W=6"

1-4-0

7-11-0 1-1-2

28-6-3

7-5-11

45-0-0 Over 2 Supports

Note: All Plates Are 2x4 Except As Shown.

PLT TYP. Wave TPI\|R

Design Crit: TPI-1995(STD)

FL/-/5/-/-/R/-

Scale = .1875"/Ft.

 Alpine Engineering Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567	**WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D-ORDERIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6500 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		7.1	FL/-/5/-/-/R/-	TC LL	20.0 PSF	REF	R215 -	90461	
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERING PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AIA 605 NATIONAL DESIGN SPEC, BY AIA/PA AND TPI. CONNECTOR PLATES ARE MADE OF 2010/1666 (A-10/5/8) ASH 6053 GRADE 40/60 (A, K/H-5) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.				TC DL	10.0 PSF	DATE	04/04/05		
					BC DL	10.0 PSF	DRW	HCUSR215	05094050	
					BC LL	0.0 PSF	HC-ENG	EC/AP		
					TOT.LD.	40.0 PSF	SEQN -	43102		
								DUR.FAC.	1.25	FROM
					SPACING	24.0"	JREF -	1SLV215_Z07		



Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=2.0 psf.

Gable end supports 8" max rake overhang.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC

Plates sized for a minimum of 3.00 sq.in./piece.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF THE ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, AND SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO THE GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.


2 COMPLETE TRUSSES REQUIRED

Nailing Schedule: (0.131x3.0_g_nails)
Top Chord: 1 Row @ 12" o.c.
Bot Chord: 1 Row @ 12" o.c.
Webs : 1 Row @ 4" o.c.
Use equal spacing between rows and stagger nails in each row to avoid splitting.

See DWGS A11030EC1103 & GBLLETIN1103 for more requirements.

Deflection meets L/240 live and L/180 total load.

The overall height of this truss excluding overhang is 1'-7.3".



5-1-0 Over 3 Supports

PLT TYP. Wave TPI\

Design Crit: TPI-1995(STD)

7.1

FL/-/5/-/-/R/-

Scale = .375"/Ft.


****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ORFORD DR., SUITE 200, MADISON, WI 53719), AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6800 WINTERPARK BLVD., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO CONSTRUCTION. ALL TRUSSES MUST BE PROPERLY BRACED AND RIGID CEILING. ALL TRUSSES SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING A BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC, BY AISC) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/166A (U-N/S/X) ASTM A653 GRADE 40/60 (U, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567



Apr 04 '05

TC LL	20.0 PSF	REF	R215--	90462
TC DL	10.0 PSF	DATE	04/04/05	
BC DL	2.0 PSF	DRW	HCUSR215	05094046
BC LL	0.0 PSF	HC-ENG	EC/AP	
TOT.LD.	32.0 PSF	SEQN-	43121	
DUR.FAC.	1.25	FROM	CDM	
SPACING	24.0"	JREF-	1SLV215_Z07	

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=2.0 psf.


In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.

Deflection meets L/240 live and L/180 total load.

The overall height of this truss excluding overhang is 1-0-0.

Refer to DWG PIGBACKB0204 for piggyback details.

Top chord of supporting truss under piggyback to be braced @ 24" O.C., unless otherwise specified.



6-4-10 Over 3 Supports

PLT TYP.: Wave TPI\R

Design Crit: TPI-1995 (STD)

FL/-/5/-/-/R/-

Scale = .5"/Ft.

WARNING: TRUSSES REQUIRING EXPERTISE CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING PLATE AND BRACING. REFER TO BECS 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSSING PLATE INSTITUTE, 5620 D'AMORE DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6200 ENTERPRISE DR., SUITE 100, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED TOP CHORD SHALING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALTHOUGH ENGINEERS AND ARCHITECTS SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI-1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONDITIONS WITH APPLICABLE PROVISIONS OF AISC NATIONAL DESIGN SPEC., BY AREA) AND TPI-1, ALPHABETICALLY LISTED, SHALL BE THE RESPONSIBILITY OF THE USER. THE FOLLOWING INFORMATION IS PROVIDED FOR YOUR INFORMATION:

PLATES TO EACH FACE OF THUSSED AND UNLESS OTHERWISE LOCATED ON THIS POSITION PER DRAWINGS 160A-Z.

ANY INSPECTION OF PLATES FOLLOWED BY (3) SHALL BE PER AMERICAN A3 OF TPI-1-2002 SEC.2. A SEAL ON THIS DRAWING INDICATES THE ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE USER. Engineering Department



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
Fl. Certificate of Authorization # 567

Haines City, FL 33844
FL Certificate of Authorization # 567

Top chord 2x4 SP #2 N
Bot chord 2x4 SP #2 N
Webs 2x4 SP #2 N


The overall height of this truss excluding overhang is 4-4-3.

110 mph wind, 30.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.



R=297 U=180 H=Simpson LUS24
w/ (2) 10d Common, 0.148"x3.0" nails in Truss
w/ (4) 10d Common, 0.148"x3.0" nails in Girder
Girder is (1)2x6 min. So.Pine

8-0-0 Over 2 Supports



ALPINE Alpine Engineered Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567	Design Crit: TPI-1995(STD)		Scale = .375"/Ft.	
	7.1		FL/-/5/-/-/R/-	
	WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 593 O'NEILL RD., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.		TC LL	20.0 PSF
	IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC. BY AISC) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/T6G6 (W./H./S./R) ASTM A563 GRADE 40/60 (U, V/H/S) GALV. STEEL. APPLY TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AISC/TPI 1 SEC. 2.		TC DL	10.0 PSF
			BC DL	10.0 PSF
			BC LL	0.0 PSF
			TOT.LD.	40.0 PSF
			DUR.FAC.	1.25
			SPACING	24.0"
			REF	R215-- 90464
		DATE	04/04/05	
		DRW	HCUSR215 05094029	
		HC-ENG	EC/AP	
		SEQN	130842	
		FROM	CDM	
		JREF	1SLV215_Z07	

ALPINE

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization #567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST PRACTICES (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 5650 W. 13TH AVE., SUITE 100, DENVER, CO 80202, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CORRECTIONS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC., BY AISC) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/16GA (4-H/S) ASTM A653 GRADE 40/60 (4. K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AISC/TPI 1 SEC. 2.

Top chord 2x4 SP #2 N
Bot chord 2x6 SP #2 N
Webs 2x4 SP #2 N

110 mph wind, 15.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC
DL=5.0 psf.

IT IS THE RESPONSIBILITY OF THE BUILDING DESIGNER TO
VERIFY AND APPROVE THE LOADING.

SPECIAL LOADS


----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC - From 60 PLF at 0.00 to 60 PLF at 8.00
BC - From 20 PLF at 0.00 to 20 PLF at 8.00
BC - 633 LB Conc. Load at 1.94, 3.94, 5.94

Right end vertical not exposed to wind pressure.

Deflection meets L/240 live and L/180 total load.

Plates sized for a minimum of 3.00 sq.in./piece.

The overall height of this truss excluding overhang is 4-4-3.



PLT TYP. Wave TPI\R

Design Crit: TPI-1995(STD)

7.1

FL/-5/-/-R/-

Scale = .375"/Ft.

 Alpine Engineered Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567	 Apr 04 '05		HANDING, SHIPPING, INSTALLING AND BRACING, TYPING, AND T	
--	--	--	--	--



Apr 04 '05

CLB WEB BRACE SUBSTITUTION

THIS DETAIL IS TO BE USED WHEN CONTINUOUS LATERAL BRACING (CLB) IS SPECIFIED ON AN ALPINE TRUSS DESIGN BUT AN ALTERNATIVE WEB BRACING METHOD IS DESIRED.

NOTES:

THIS DETAIL IS ONLY APPLICABLE FOR CHANGING THE SPECIFIED CLB SHOWN ON SINGLE PLY SEALED DESIGNS TO T-BRACING OR SCAB BRACING.

ALTERNATIVE BRACING SPECIFIED IN CHART BELOW MAY BE CONSERVATIVE. FOR MINIMUM ALTERNATIVE BRACING, RE-RUN DESIGN WITH APPROPRIATE BRACING.

WEB MEMBER SIZE	SPECIFIED CLB BRACING	T OR L-BRACE	ALTERNATIVE BRACING SCAB BRACE
2X3 OR 2X4	1 ROW	2X4	1-2X4
2X3 OR 2X4	2 ROWS	2X6	2-2X4
2X6	1 ROW	2X4	1-2X6
2X6	2 ROWS	2X6	2-2X4(*)
2X8	1 ROW	2X6	1-2X8
2X8	2 ROWS	2X6	2-2X6(*)


T-BRACE, L-BRACE AND SCAB BRACE TO BE SAME SPECIES AND GRADE OR BETTER THAN WEB MEMBER UNLESS SPECIFIED OTHERWISE ON ENGINEER'S SEALED DESIGN.

(*) CENTER SCAB ON WIDE FACE OF WEB. APPLY (1) SCAB TO EACH FACE OF WEB.

T-BRACING
OR
L-BRACING:


APPLY TO EITHER SIDE OF WEB
NARROW FACE

ATTACH WITH 16d NAILS AT 6" O.C.
BRACE IS A MINIMUM 80% OF WEB
MEMBER LENGTH



SCAB BRACING:

APPLY SCAB(S) TO WIDE FACE OF WEB.
NO MORE THAN (1) SCAB PER FACE.
ATTACH WITH 10d OR .128"x3" GUN
NAILS AT 6" O.C. BRACE IS A MINIMUM
80% OF WEB MEMBER LENGTH




WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31-003 BUILDING CONSTRUCTION SAFETY INFORMATION PUBLISHED BY THE NATIONAL PLATE INSTITUTE, 583 DUDDELDORF DR., SUITE 200, HANSDEN, IL 63719, AND AISC 1600 TRUSS CODE OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BRACE OR BRACING OF TRUSSES SHALL BE THE RESPONSIBILITY OF THE INSTALLER. TRUSS BRACING OF TRUSSES: DESIGN CONNECTIONS ARE MADE OF 2018/1664 (24H/24) ASTM A572 GRADE 40/50 (A36/H43) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWING 1604-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF THE PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS. CONCURRENT DESIGN OF THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.



ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA



THIS DRAWING REPLACES DRAWING 579.640	PSF	CLB SUBST.
TC LL	PSF	DATE 11/26/03
TC DL	PSF	DRWG BRCLESUB1103
BC DL	PSF	-ENG MLH/KAR
BC LL	PSF	
TOT. LD.	PSF	
DUR. FAC.		
SPACING		

BEARING BLOCK NAIL SPACING DETAIL

MAXIMUM NUMBER OF NAIL LINES PARALLEL TO GRAIN

NAIL TYPE	CHORD SIZE				
	2X4	2X6	2X8	2X10	2X12
8d BOX (0.113"x2.5")	3	6	9	12	15
10d BOX (0.128"x3")	3	5	7	10	12
12d BOX (0.128"x3.25")	3	5	7	10	12
16d BOX (0.135"x3.5")	3	5	7	10	12
20d BOX (0.148"x4")	2	4	5	6	8
8d COMMON (0.131"x2.5")	3	5	7	10	12
10d COMMON (0.148"x3")	2	4	6	8	10
12d COMMON (0.148"x3.25")	2	4	6	8	10
16d COMMON (0.162"x3.5")	2	4	6	8	10
0.120"x2.5" GUN	3	6	8	11	14
0.131"x2.5" GUN	3	5	7	10	12
0.120"x3.0" GUN	3	6	8	11	14
0.131"x3.0" GUN	3	5	7	10	12

MINIMUM NAIL SPACING DISTANCES

NAIL TYPE	DISTANCES		
	A	B*	C**
8d BOX (0.113"x2.5")	3/4"	1 3/8"	1 3/4"
10d BOX (0.128"x3")	7/8"	1 5/8"	2"
12d BOX (0.128"x3.25")	7/8"	1 5/8"	2"
16d BOX (0.135"x3.5")	7/8"	1 5/8"	2 1/8"
20d BOX (0.148"x4")	1"	1 7/8"	2 1/4"
8d COMMON (0.131"x2.5")	7/8"	1 5/8"	2"
10d COMMON (0.148"x3")	1"	1 7/8"	2 1/4"
12d COMMON (0.148"x3.25")	1"	1 7/8"	2 1/4"
16d COMMON (0.162"x3.5")	1"	2"	2 1/2"
0.120"x2.5" GUN	3/4"	1 1/2"	1 7/8"
0.131"x2.5" GUN	7/8"	1 5/8"	2"
0.120"x3.0" GUN	3/4"	1 1/2"	1 7/8"
0.131"x3.0" GUN	7/8"	1 5/8"	2"


MINIMUM SPACING FOR SINGLE BEARING BLOCK IS SHOWN. DOUBLE NAIL SPACINGS AND STAGGER NAILING FOR TWO BLOCKS. GREATER SPACING MAY BE REQUIRED TO AVOID SPLITTING.

- A - EDGE DISTANCE AND SPACING BETWEEN STAGGERED ROWS OF NAILS (6 NAIL DIAMETERS)
- B - SPACING OF NAILS IN A ROW (12 NAIL DIAMETERS)
- C - END DISTANCE (15 NAIL DIAMETERS)

IF NAIL HOLES ARE PREBORED, SOME SPACING MAY BE REDUCED BY THE AMOUNTS GIVEN BELOW:

- * SPACING MAY BE REDUCED BY 50%
- ** SPACING MAY BE REDUCED BY 33%

BEARING BLOCK TO BE SAME SIZE AND SPECIES AS BOTTOM CHORD. BLOCKS MAY BE ANY GRADE WITHIN THE SPECIES. PROVIDED THE COMPRESSION PERPENDICULAR TO GRAIN VALUE (Fc-perp) IS AT LEAST THAT OF THE CHORD.



DRAWING REPLACES DRAWING B139 AND CNBRGLK0699



WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI TRUSS PRODUCTS, INC., 10000 W. 11TH AVENUE, SUITE 100, DENVER, CO 80231, FOR A COMPLETE LIST OF TRUSS COUNCIL OF AMERICA (COTAC) MEMBER COMPANIES AND A LIST OF TRUSS COUNCIL OF AMERICA (COTAC) MEMBER COMPANIES. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY REVISIONS TO THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS NATIONAL DESIGN SPEC. FOR WOOD CONSTRUCTION. ALPINE CORP. TRUSS DIVISION, 10000 W. 11TH AVENUE, SUITE 100, DENVER, CO 80231, FOR A COMPLETE LIST OF TRUSS COUNCIL OF AMERICA (COTAC) MEMBER COMPANIES AND A LIST OF TRUSS COUNCIL OF AMERICA (COTAC) MEMBER COMPANIES. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.



ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

REF	BEARING BLOCK
DATE	11/26/03
DRWG	CNBRGLK1103
-ENG	SJP/KAR

2x4 GABLE VERTICAL SPACING		BRACE GRADE	NO BRACES	(1) 1x4 "L" BRACE *				(1) 2x4 "L" BRACE *				(2) 2x4 "L" BRACE **				(1) 2x6 "L" BRACE *				(2) 2x6 "L" BRACE *			
				GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B				
12" O.C.	SPF	#1 / #2	3' 8"	6' 4"	6' 6"	7' 6"	7' 8"	8' 11"	9' 2"	11' 9"	12' 1"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"		
		#3	3' 7"	5' 5"	5' 5"	7' 2"	7' 2"	8' 11"	8' 11"	11' 2"	11' 2"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STUD	3' 7"	5' 5"	5' 5"	7' 1"	7' 1"	8' 11"	8' 11"	11' 1"	11' 1"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
	HF	STANDARD	3' 7"	4' 8"	4' 8"	6' 1"	6' 1"	8' 3"	8' 3"	9' 6"	9' 6"	12' 11"	12' 11"	12' 11"	12' 11"	12' 11"	12' 11"	12' 11"	12' 11"	12' 11"			
		#1	4' 0"	6' 4"	6' 10"	7' 6"	8' 1"	8' 11"	9' 7"	11' 9"	12' 8"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		#2	3' 11"	6' 4"	6' 10"	7' 6"	8' 1"	8' 11"	9' 7"	11' 9"	12' 8"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
16" O.C.	SP	#3	3' 9"	5' 7"	5' 7"	7' 4"	7' 4"	8' 11"	9' 5"	11' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STUD	3' 9"	5' 6"	5' 6"	7' 3"	7' 3"	8' 11"	9' 5"	11' 4"	11' 4"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"				
		STANDARD	3' 8"	4' 9"	4' 9"	6' 3"	6' 3"	8' 5"	8' 5"	9' 9"	9' 9"	13' 3"	13' 3"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"				
	DFL	#1 / #2	4' 2"	7' 3"	7' 5"	8' 7"	8' 10"	10' 3"	10' 6"	13' 5"	13' 10"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		#3	4' 1"	6' 8"	6' 8"	8' 7"	8' 7"	10' 3"	10' 3"	13' 5"	13' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STUD	4' 1"	8' 0"	8' 0"	8' 7"	8' 7"	10' 3"	10' 3"	13' 5"	13' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
24" O.C.	SPF	STANDARD	4' 1"	5' 8"	5' 8"	7' 6"	7' 6"	10' 1"	10' 1"	11' 8"	11' 8"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		#1	4' 7"	7' 3"	7' 9"	8' 7"	9' 3"	10' 3"	11' 0"	13' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"				
		#2	4' 6"	7' 3"	7' 9"	8' 7"	9' 3"	10' 3"	11' 0"	13' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"				
	HF	#3	4' 4"	6' 10"	6' 10"	8' 7"	9' 0"	10' 3"	10' 9"	13' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STUD	4' 4"	6' 9"	6' 9"	8' 7"	8' 11"	10' 3"	10' 9"	13' 5"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STANDARD	4' 2"	5' 10"	5' 10"	7' 8"	7' 8"	10' 3"	10' 4"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
32" O.C.	SPF	#1 / #2	4' 7"	8' 0"	8' 2"	9' 5"	9' 8"	11' 3"	11' 7"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		#3	4' 6"	7' 8"	7' 8"	9' 5"	9' 5"	11' 3"	11' 3"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STUD	4' 6"	7' 8"	7' 8"	9' 5"	9' 5"	11' 3"	11' 3"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
	HF	STANDARD	4' 6"	6' 7"	6' 7"	8' 8"	8' 8"	11' 3"	11' 3"	13' 6"	13' 6"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		#1	5' 1"	8' 0"	8' 7"	9' 5"	10' 2"	11' 3"	12' 1"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		#2	4' 11"	8' 0"	8' 7"	9' 5"	10' 2"	11' 3"	12' 1"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
48" O.C.	SP	#3	4' 9"	7' 11"	7' 11"	9' 5"	9' 11"	11' 3"	11' 10"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STUD	4' 9"	7' 9"	7' 9"	9' 5"	9' 11"	11' 3"	11' 10"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			
		STANDARD	4' 7"	6' 9"	6' 9"	8' 10"	8' 10"	11' 3"	11' 7"	13' 10"	13' 10"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"	14' 0"			

DIAGONAL BRACE OPTION:
VERTICAL LENGTH MAY BE
DOUBLED WHEN DIAGONAL
BRACE IS USED. CONNECT
DIAGONAL BRACE FOR 700#
AT EACH END. MAX WEB
TOTAL LENGTH IS 14'

VERTICAL LENGTH SHOWN
IN TABLE ABOVE.

CONNECT DIAGONAL AT
MIDPOINT OF VERTICAL WEB.



ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

GABLE TRUSS DETAIL NOTES:

LIVE LOAD DEFLECTION CRITERIA IS L/240.

PROVIDE UPLIFT CONNECTIONS FOR 100 PLF OVER
CONTINUOUS BEARING (5 PSF TC DEAD LOAD)

GABLE END SUPPORTS LOAD FROM 4' 0"

OUTLOOKERS WITH 2' 0" OVERHANG, OR 12"
PLYWOOD OVERHANG

ATTACH EACH "L" BRACE WITH 10d NAILS

* FOR (1) "L" BRACE SPACE NAILS AT 2" O.C.


IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.
 ** FOR (2) "L" BRACES: SPACE NAILS AT 3" O.C.

IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.

"L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

GABLE VERTICAL PLATE SIZES	
VERTICAL LENGTH	NO SPICE
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR
PEAK, SPICE, AND HEEL PLATES.



REFER TO CHART ABOVE FOR COVER LENGTH

ANALYSING... TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND REACTING. REFER TO THE FOLLOWING FOR CONSEQUENT SAFE AND EFFICIENT PRACTICES. THE TECHNICAL PLATE, THIS INSTITUTE, 583 RIDGEPOINTE PL., SUITE 200, MADISON, WI 53719, AND VTCA-1000 TRUSS COUNCIL OF AMERICA, 63000 ENTERPRISE LN, MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPHINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN AND FAILURE TO BUILD THE TRUSSES IN CONFORMANCE WITH TPT. BE FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THIS NATIONAL DESIGN SPEC. BY AISC AND TPT. ALPHINE CONNECTOR PLATES ARE MADE OF 2010/180A 50/50/50 ASTM A563 GRADE 40/60 C/K/H/51 GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PLATES AS SHOWN. IF ANY DEVIATION FROM THIS DESIGN IS FOLLOWED BY IT, SHALL BE THE DESIGNER'S RESPONSIBILITY. THE PROFESSIONAL ENGINEER'S DESIGN SHALL BE THE BASIS FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPT 1 SEC. 2.

REF	ASCE7-98-GABI1030
DATE	11/26/03
DRWG	A11030EC1103
-ENG	

MAX. TOT. LD. 60 PSF

MAX. SPACING 24.0"

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name:	502044StephensonRes	Builder:	Edgley Const.
Address:	231 SW Bonanza Glen	Permitting Office:	
City, State:	Lake City, FL	Permit Number:	
Owner:	Stephenson	Jurisdiction Number:	
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 35.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 10.00
4. Number of Bedrooms	3	b. Central Unit	Cap: 10.0 kBtu/hr
5. Is this a worst case?	Yes		SEER: 10.00
6. Conditioned floor area (ft²)	2282 ft²	c. N/A	
7. Glass area & type	Single Pane Double Pane	13. Heating systems	
a. Clear glass, default U-factor	0.0 ft² 205.5 ft²	a. Electric Heat Pump	Cap: 35.0 kBtu/hr
b. Default tint, default U-factor	0.0 ft² 0.0 ft²		HSPF: 7.00
c. Labeled U-factor or SHGC	0.0 ft² 0.0 ft²	b. Electric Heat Pump	Cap: 10.0 kBtu/hr
8. Floor types			HSPF: 7.00
a. Slab-On-Grade Edge Insulation	R=0.0, 250.0(p) ft	c. N/A	
b. N/A		14. Hot water systems	
c. N/A		a. Electric Resistance	Cap: 40.0 gallons
9. Wall types			EF: 0.89
a. Face Brick, Wood, Exterior	R=13.0, 1451.0 ft²	b. N/A	
b. Frame, Wood, Exterior	R=13.0, 60.0 ft²	c. Conservation credits	
c. Frame, Wood, Adjacent	R=13.0, 356.0 ft²	(HR-Heat recovery, Solar	
d. N/A		DHP-Dedicated heat pump)	
e. N/A		15. HVAC credits	
10. Ceiling types		(CF-Ceiling fan, CV-Cross ventilation,	
a. Under Attic	R=30.0, 2367.0 ft²	HF-Whole house fan,	
b. N/A		PT-Programmable Thermostat,	
c. N/A		MZ-C-Multizone cooling,	
11. Ducts		MZ-H-Multizone heating)	
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 200.0 ft		
b. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 40.0 ft		

Glass/Floor Area: 0.09

Total as-built points: 29048

Total base points: 32907

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Evan Beamsley

DATE: 3/2/06

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____

DATE: _____



SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X SPM X SOF = Points				
.18	2282.0	20.04	8231.6	Double, Clear	N	0.0	0.0	20.0	19.20	1.00	384.0
				Double, Clear	N	6.5	8.5	20.0	19.20	0.75	289.3
				Double, Clear	N	6.5	5.5	12.0	19.20	0.68	157.2
				Double, Clear	E	1.5	5.5	10.0	42.06	0.90	377.0
				Double, Clear	E	1.5	6.5	15.0	42.06	0.93	584.6
				Double, Clear	S	0.0	0.0	30.0	35.87	1.00	1076.0
				Double, Clear	S	1.5	6.5	15.0	35.87	0.88	471.7
				Double, Clear	S	9.5	6.5	60.0	35.87	0.48	1023.7
				Double, Clear	S	9.5	8.5	20.0	35.87	0.50	361.4
				Double, Clear	W	1.5	2.5	3.5	38.52	0.67	90.5
				As-Built Total:		205.5			4815.3		
WALL TYPES											
Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Adjacent	356.0	0.70	249.2	Face Brick, Wood, Exterior	13.0		1451.0	0.35		507.9	
Exterior	1511.0	1.70	2568.7	Frame, Wood, Exterior	13.0		60.0	1.50		90.0	
				Frame, Wood, Adjacent	13.0		356.0	0.60		213.6	
Base Total:				1867.0		2817.9			As-Built Total:		
									1867.0		
									811.4		
DOOR TYPES											
Area X BSPM = Points				Type			Area X SPM = Points				
Adjacent	20.0	2.40	48.0	Exterior Insulated			60.0	4.10		246.0	
Exterior	100.0	6.10	610.0	Exterior Insulated			40.0	4.10		164.0	
				Adjacent Insulated			20.0	1.60		32.0	
Base Total:				120.0		658.0			As-Built Total:		
									120.0		
									442.0		
CEILING TYPES											
Area X BSPM = Points				Type	R-Value		Area X SPM X SCM = Points				
Under Attic	2282.0	1.73	3947.9	Under Attic	30.0		2367.0	1.73 X 1.00		4094.9	
Base Total:				2282.0		3947.9			As-Built Total:		
									2367.0		
									4094.9		
FLOOR TYPES											
Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Slab	250.0(p)	-37.0	-9250.0	Slab-On-Grade Edge Insulation	0.0		250.0(p)	-41.20		-10300.0	
Raised	0.0	0.00	0.0								
Base Total:				-9250.0		As-Built Total:			250.0		
									-10300.0		
INFILTRATION											
Area X BSPM = Points						Area X SPM = Points					
2282.0 10.21 23299.2						2282.0 10.21 23299.2					

SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT									
Summer Base Points: 29704.6				Summer As-Built Points: 23162.9									
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component	X	Cap Ratio	X	Duct Multiplier (DM x DSM x AHU)	X	System Multiplier	X	Credit Multiplier	= Cooling Points
				23162.9		0.778		(1.090 x 1.147 x 0.91)		0.341		1.000	6995.4
				23162.9		0.222		(1.090 x 1.147 x 0.91)		0.341		1.000	1998.7
29704.6		0.4266	12672.0	23162.9		1.00		1.138		0.341		1.000	8994.1

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points				
.18	2282.0	12.74	5233.1	Double, Clear	N	0.0	0.0	20.0	24.58	1.00	491.6
				Double, Clear	N	6.5	8.5	20.0	24.58	1.02	498.9
				Double, Clear	N	6.5	5.5	12.0	24.58	1.02	301.0
				Double, Clear	E	1.5	5.5	10.0	18.79	1.04	195.7
				Double, Clear	E	1.5	6.5	15.0	18.79	1.03	290.5
				Double, Clear	S	0.0	0.0	30.0	13.30	1.00	398.9
				Double, Clear	S	1.5	6.5	15.0	13.30	1.09	218.2
				Double, Clear	S	9.5	6.5	60.0	13.30	3.25	2590.0
				Double, Clear	S	9.5	8.5	20.0	13.30	2.92	777.4
				Double, Clear	W	1.5	2.5	3.5	20.73	1.11	80.3
				As-Built Total:				205.5	5842.4		
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	356.0	3.60	1281.6	Face Brick, Wood, Exterior	13.0		1451.0	3.17	4606.9		
Exterior	1511.0	3.70	5590.7	Frame, Wood, Exterior	13.0		60.0	3.40	204.0		
				Frame, Wood, Adjacent	13.0		356.0	3.30	1174.8		
Base Total:	1867.0		6872.3	As-Built Total:		1867.0		5985.7			
DOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	20.0	11.50	230.0	Exterior Insulated			60.0	8.40	504.0		
Exterior	100.0	12.30	1230.0	Exterior Insulated			40.0	8.40	336.0		
				Adjacent Insulated			20.0	8.00	160.0		
Base Total:	120.0		1460.0	As-Built Total:		120.0		1000.0			
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	2282.0	2.05	4678.1	Under Attic	30.0		2367.0	2.05 X 1.00	4852.4		
Base Total:	2282.0		4678.1	As-Built Total:		2367.0		4852.4			
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	250.0(p)	8.9	2225.0	Slab-On-Grade Edge Insulation	0.0		250.0(p)	18.80	4700.0		
Raised	0.0	0.00	0.0								
Base Total:			2225.0	As-Built Total:		250.0		4700.0			
INFILTRATION Area X BWPM = Points						Area X WPM		= Points			
	2282.0	-0.59	-1346.4			2282.0		-0.59 -1346.4			

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT						
Winter Base Points:		19122.1		Winter As-Built Points:					21034.1	
Total Winter Points	X System Multiplier	=	Heating Points	Total Component	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	=	Heating Points
				21034.1	0.778	(1.069 x 1.169 x 0.93)	0.487	1.000		9262.1
				21034.1	0.222	(1.069 x 1.169 x 0.93)	0.487	1.000		2646.3
19122.1	0.6274		11997.2	21034.1	1.00	1.162	0.487	1.000		11908.5

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

BASE				AS-BUILT					
WATER HEATING									
Number of Bedrooms	X	Multiplier	= Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Multiplier X Credit = Total Multiplier
3		2746.00	8238.0	40.0	0.89	3		1.00	2715.15
				As-Built Total:					8145.4

CODE COMPLIANCE STATUS

BASE					AS-BUILT				
Cooling Points	+	Heating Points	+	Hot Water Points = Total Points	Cooling Points	+	Heating Points	+	Hot Water Points = Total Points
12672		11997		8238	32907		8994		11908
									8145
									29048

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: 231 SW Bonanza Glen, Lake City, FL,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 85.0

The higher the score, the more efficient the home.

Stephenson, 231 SW Bonanza Glen, Lake City, FL,

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 35.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 10.00
4. Number of Bedrooms	3	b. Central Unit	Cap: 10.0 kBtu/hr
5. Is this a worst case?	Yes		SEER: 10.00
6. Conditioned floor area (ft ²)	2282 ft ²	c. N/A	
7. Glass area & type	Single Pane Double Pane	13. Heating systems	
a. Clear glass, default U-factor	0.0 ft ² 205.5 ft ²	a. Electric Heat Pump	Cap: 35.0 kBtu/hr
b. Default tint, default U-factor	0.0 ft ² 0.0 ft ²		HSPF: 7.00
c. Labeled U-factor or SHGC	0.0 ft ² 0.0 ft ²	b. Electric Heat Pump	Cap: 10.0 kBtu/hr
8. Floor types			HSPF: 7.00
a. Slab-On-Grade Edge Insulation	R=0.0, 250.0(p) ft	c. N/A	
b. N/A		14. Hot water systems	
c. N/A		a. Electric Resistance	Cap: 40.0 gallons
9. Wall types			EF: 0.89
a. Face Brick, Wood, Exterior	R=13.0, 1451.0 ft ²	b. N/A	
b. Frame, Wood, Exterior	R=13.0, 60.0 ft ²	c. Conservation credits	
c. Frame, Wood, Adjacent	R=13.0, 356.0 ft ²	(HR-Heat recovery, Solar	
d. N/A		DHP-Dedicated heat pump)	
e. N/A		15. HVAC credits	
10. Ceiling types		(CF-Ceiling fan, CV-Cross ventilation,	
a. Under Attic	R=30.0, 2367.0 ft ²	HF-Whole house fan,	
b. N/A		PT-Programmable Thermostat,	
c. N/A		MZ-C-Multizone cooling,	
11. Ducts		MZ-H-Multizone heating)	
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 200.0 ft		
b. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 40.0 ft		

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



**NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStar™ designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/462-4824.*

Energy Gauge Version: FLR2PB v3.4)

Residential System Sizing Calculation

Summary

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North


3/2/2005

Location for weather data: Gainesville - Defaults: Latitude(29) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(51gr.)			
Winter design temperature	31 F	Summer design temperature	93 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	39 F	Summer temperature difference	18 F
Total heating load calculation	37631 Btuh	Total cooling load calculation	33543 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	119.6 45000	Sensible (SHR = 0.75)	141.6 33750
Heat Pump + Auxiliary(0.0kW)	119.6 45000	Latent	115.9 11250
		Total (Electric Heat Pump)	134.2 45000

WINTER CALCULATIONS

Winter Heating Load (for 2282 sqft)


Load component		Load
Window total	206 sqft	5816 Btuh
Wall total	1867 sqft	5254 Btuh
Door total	120 sqft	2021 Btuh
Ceiling total	2367 sqft	3077 Btuh
Floor total	250 ft	7900 Btuh
Infiltration	274 cfm	11771 Btuh
Subtotal		35839 Btuh
Duct loss		1792 Btuh
TOTAL HEAT LOSS		37631 Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 2282 sqft)

Load component		Load
Window total	206 sqft	6338 Btuh
Wall total	1867 sqft	2999 Btuh
Door total	120 sqft	1217 Btuh
Ceiling total	2367 sqft	3361 Btuh
Floor total		0 Btuh
Infiltration	240 cfm	4754 Btuh
Internal gain		3000 Btuh
Subtotal(sensible)		21669 Btuh
Duct gain		2167 Btuh
Total sensible gain		23836 Btuh
Latent gain(infiltration)		8326 Btuh
Latent gain(internal)		1380 Btuh
Total latent gain		9706 Btuh
TOTAL HEAT GAIN		33543 Btuh



EnergyGauge® System Sizing based on ACCA Manual J.
PREPARED BY: *[Signature]*
DATE: 3/2/05

System Sizing Calculations - Winter

Residential Load - Component Details

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 39.0 F

3/2/2005

Window	Panes/SHGC/Frame/U	Orientation	Area X	HTM=	Load
1	2, Clear, Metal, DEF	N	20.0	28.3	566 Btuh
2	2, Clear, Metal, DEF	N	20.0	28.3	566 Btuh
3	2, Clear, Metal, DEF	N	12.0	28.3	340 Btuh
4	2, Clear, Metal, DEF	E	10.0	28.3	283 Btuh
5	2, Clear, Metal, DEF	E	15.0	28.3	424 Btuh
6	2, Clear, Metal, DEF	S	30.0	28.3	849 Btuh
7	2, Clear, Metal, DEF	S	15.0	28.3	424 Btuh
8	2, Clear, Metal, DEF	S	60.0	28.3	1698 Btuh
9	2, Clear, Metal, DEF	S	20.0	28.3	566 Btuh
10	2, Clear, Metal, DEF	W	3.5	28.3	99 Btuh
Window Total			206		5816 Btuh
Walls	Type	R-Value	Area X	HTM=	Load
1	Frame - Exterior	13.0	1451	3.1	4498 Btuh
2	Frame - Exterior	13.0	60	3.1	186 Btuh
3	Frame - Adjacent	13.0	356	1.6	570 Btuh
Wall Total			1867		5254 Btuh
Doors	Type		Area X	HTM=	Load
1	Insulated - Exter		60	18.3	1100 Btuh
2	Insulated - Exter		40	18.3	733 Btuh
3	Insulated - Adjac		20	9.4	188 Btuh
Door Total			120		2021 Btuh
Ceilings	Type	R-Value	Area X	HTM=	Load
1	Under Attic	30.0	2367	1.3	3077 Btuh
Ceiling Total			2367		3077 Btuh
Floors	Type	R-Value	Size X	HTM=	Load
1	Slab-On-Grade Edge Insul	0	250.0 ft(p)	31.6	7900 Btuh
Floor Total			250		7900 Btuh
Infiltration	Type	ACH X	Building Volume	CFM=	Load
	Natural	0.80	20538(sqft)	274	11771 Btuh
	Mechanical			0	0 Btuh
Infiltration Total				274	11771 Btuh

Totals for Heating	Subtotal	35839 Btuh
	Duct Loss(using duct multiplier of 0.05)	1792 Btuh
	Total Btuh Loss	37631 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

3/2/2005

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(Frame types - metal, wood or insulated metal)

(U - Window U-Factor or 'DEF' for default)

(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)

System Sizing Calculations - Summer

Residential Load - Component Details

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults)

Summer Temperature Difference: 18.0 F

3/2/2005

Window	Type	Overhang	Window Area(sqft)			HTM		Load		
	Panes/SHGC/U/InSh/ExSh Ornt		Len	Hgt	Gross	Shaded	Unshaded		Shaded	Unshaded
1	2, Clear, DEF, N, N	N	0	0	20.0	0.0	20.0	22	22	440 Btuh
2	2, Clear, DEF, N, N	N	6.5	8.5	20.0	0.0	20.0	22	22	440 Btuh
3	2, Clear, DEF, N, N	N	6.5	5.5	12.0	0.0	12.0	22	22	264 Btuh
4	2, Clear, DEF, N, N	E	1.5	5.5	10.0	0.0	10.0	22	72	720 Btuh
5	2, Clear, DEF, N, N	E	1.5	6.5	15.0	0.0	15.0	22	72	1080 Btuh
6	2, Clear, DEF, N, N	S	0	0	30.0	0.0	30.0	22	37	1110 Btuh
7	2, Clear, DEF, N, N	S	1.5	6.5	15.0	15.0	0.0	22	37	330 Btuh
8	2, Clear, DEF, N, N	S	9.5	6.5	60.0	60.0	0.0	22	37	1320 Btuh
9	2, Clear, DEF, N, N	S	9.5	8.5	20.0	20.0	0.0	22	37	440 Btuh
10	2, Clear, DEF, N, N	W	1.5	2.5	3.5	1.2	2.3	22	72	194 Btuh
Window Total						206				6338 Btuh
Walls	Type	R-Value		Area		HTM		Load		
1	Frame - Exterior	13.0		1451.0		1.7		2525 Btuh		
2	Frame - Exterior	13.0		60.0		1.7		104 Btuh		
3	Frame - Adjacent	13.0		356.0		1.0		370 Btuh		
Wall Total					1867.0			2999 Btuh		
Doors	Type	R-Value		Area		HTM		Load		
1	Insulated - Exter			60.0		10.1		608 Btuh		
2	Insulated - Exter			40.0		10.1		406 Btuh		
3	Insulated - Adjac			20.0		10.1		203 Btuh		
Door Total					120.0			1217 Btuh		
Ceilings	Type/Color	R-Value		Area		HTM		Load		
1	Under Attic/Dark	30.0		2367.0		1.4		3361 Btuh		
Ceiling Total					2367.0			3361 Btuh		
Floors	Type	R-Value		Size		HTM		Load		
1	Slab-On-Grade Edge Insulation	0.0		250.0 ft(p)		0.0		0 Btuh		
Floor Total					250.0			0 Btuh		
Infiltration	Type	ACH		Volume		CFM=		Load		
	Natural	0.70		20538		240.1		4754 Btuh		
	Mechanical					0		0 Btuh		
Infiltration Total						240		4754 Btuh		

Internal gain	Occupants	Btuh/occupant	Appliance	Load
	6	X 300 +	1200	3000 Btuh

Manual J Summer Calculations

Residential Load - Component Details (continued)

Stephenson
231 SW Bonanza Glen
Lake City, FL

Project Title:
502044StephensonRes

Class 3 Rating
Registration No. 0
Climate: North

3/2/2005

Totals for Cooling	Subtotal	21669 Btuh
	Duct gain(using duct multiplier of 0.10)	2167 Btuh
	Total sensible gain	23836 Btuh
	Latent infiltration gain (for 51 gr. humidity difference)	8326 Btuh
	Latent occupant gain (6 people @ 230 Btuh per person)	1380 Btuh
	Latent other gain	0 Btuh
	TOTAL GAIN	33543 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(U - Window U-Factor or 'DEF' for default)
(InSh - Interior shading device: none(N), Blinds/Daperies(B) or Roller Shades(R))
(ExSh - Exterior shading device: none(N) or numerical value)
(Ornt - compass orientation)

23695



Cal-Tech Testing, Inc.

- Engineering
- Geotechnical
- Environmental

LABORATORIES

P.O. Box 1625 • Lake City, FL 32056-1625
6919 Distribution Avenue S., Unit #5 • Jacksonville, FL 32257

Tel. (386) 755-3633 • Fax (386) 752-5456
Tel. (904) 262-4046 • Fax (904) 262-4047

JOB NO.: 05-590
DATE TESTED: 11-15-2005
DATE REPORTED: 11-16-2005

REPORT OF IN-PLACE DENSITY TEST

PROJECT:	Stevenson Residence, Cannon Creek Airpark		
CLIENT:	Dale's Excavation, 6139 SW SR-47, Lake City, FL 32024		
GENERAL CONTRACTOR:	Dale's Excavation, 6139 SW SR-47, Lake City, FL 32024		
EARTHWORK CONTRACTOR:	Dale's Excavation, 6139 SW SR-47, Lake City, FL 32024		
INSPECTOR:	P Geiger		
ASTM METHOD		SOIL USE	
(D-2922) Nuclear		BUILDING FILL	
SPECIFICATION REQUIREMENTS: 95%			

TEST NO.	TEST LOCATION	TEST DEPTH	WET DENSITY (lb/ft ³)	MOISTURE PERCENT	DRY DENSITY (lb/ft ³)	PROCTOR TEST NO.	PROCTOR VALUE	% MAXIMUM DENSITY
1	36'E X 28'S OF NW CORNER	0-12"	112.6	5.7	106.5	1	109.6	97.2%
2	27' E X 40'S OF NW CORNER	0-12"	113.5	7.9	105.2	1	109.6	96.0%

REMARKS: The Above Tests Meet Specification Requirements.

PROCTORS				
PROCTOR NO.	SOIL DESCRIPTION	MAXIMUM DRY UNIT WEIGHT (lb/ft ³)	OPT. MOIST.	TYPE
1	Grey Sand w/Limerock	109.6	9.8	MODIFIED (ASTM D-1557)

Respectfully Submitted,
CAL-TECH TESTING, INC.

Linda M. Creamer
Linda M. Creamer
President - CEO

Reviewed By:

John D. [Signature]
Date: 11/22/05
Florida Registration No: 52612

The test results presented in this report are specific only to the samples tested at the time of testing. The tests were performed in accordance with generally accepted methods and standards. Since material conditions can vary between test locations and change with time, sound judgement should be exercised with regard to the use and interpretation of the data.