



REINFORCING			
T	W		
1 STORY	20"	16"	3-#5


1. THICKNESS OF FOOTING INCLUDES THICKNESS OF SLAB.



SECTION S1 1/2"=1'-0"



BASIC TRUSS DESIGN 1/8"=1'-0"



NOTE: CONTRACTOR SHALL VERIFY ALL PERTINENT INFORMATION PRIOR TO CONSTRUCTION. ALL BEAMS, GIRDERS, BLOCKING, ETC. SHALL BE DESIGNED AND LOCATED BY OTHERS. ADDITIONAL BLOCKING, BEAMS, PIER SUPPORTS, ETC. AS NEEDED FOR LOAD BEARING PURPOSES SHALL BE DETERMINED BY CONTRACTOR PRIOR TO CONSTRUCTION.


CONTRACTOR TO VERIFY ALL DIMENSIONS AND REPORT DISCREPANCIES TO SPIERS DRAFTING SERVICE PRIOR TO CONSTRUCTION.

CONTRACTOR TO COMPLY WITH ALL BUILDING CODES AND ORDINANCES OF COLUMBIA COUNTY, FLORIDA.

PROPOSED RESIDENCE FOR:
TROY POOLE


Original Paper Size
34"x22"

SPIERS DRAFTING SERVICE		
850-836-4446		Ponce De Leon, FL
SCALE: 1/4"=1'-0"		DRAWN BY: LBS
DATE:		
FOUNDATION PLAN		
PLAN # 071023 R		1 OF 5



SQUARE FOOTAGE INFORMATION		
HEATED AREA	1872	sq ft
COVERED PORCHES	980	sq ft
TOTAL SQ. FT.	2852	sq ft

NOTE:
8' CEILING HT. THROUGHOUT HOUSE UNLESS OTHERWISE NOTED.
6" EXTERIOR WALLS
UTILIZE FINK TRUSS OVER BEDROOMS FOR STORAGE. SEE OWNER.
ROOF WILL BE CONSTRUCTED BY A TRUSS MANUFACTURER USING PRE-ENGINEERED ROOF TRUSSES
TRUSSES SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER WHO IS LICENCED BY THE STATE OF FL
TRUSSES SHALL BE DESIGNED FOR 140 MILE PER HOUR WIND SPEED.



Original Paper Size
34"x22"

CONTRACTOR TO VERIFY ALL DIMENSIONS AND REPORT DISCREPANCIES TO SPIERS DRAFTING SERVICE PRIOR TO CONSTRUCTION.
CONTRACTOR TO COMPLY WITH ALL BUILDING CODES AND ORDINANCES OF COLUMBIA COUNTY, FLORIDA.


PROPOSED RESIDENCE FOR:
TROY POOLE

SPIERS DRAFTING SERVICE		
850-836-4446	Ponce De Leon, FL	
SCALE: 1/4"=1'-0"		DRAWN BY: LBS
DATE:		
FLOOR PLAN		
PLAN # 071023 R		2 OF 5



FRONT ELEVATION


1/4"=1'-0"



LEFT ELEV.


1/8"=1'-0"

PITCH:	
MAIN ROOF	7:12
FRONT GABLE	10:12
REAR PORCH	3:12
OVERHANG:	12"




RIGHT ELEV.

1/8"=1'-0"



REAR ELEV.

1/8"=1'-0"




Original Paper Size
34"x22"

CONTRACTOR TO VERIFY ALL DIMENSIONS
AND REPORT DISCREPANCIES TO SPIERS
DRAFTING SERVICE PRIOR TO CONSTRUCTION.


CONTRACTOR TO COMPLY WITH ALL BUILDING
CODES AND ORDINANCES OF COLUMBIA
COUNTY, FLORIDA.

PROPOSED RESIDENCE FOR:
TROY POOLE

SPIERS DRAFTING SERVICE	
850-836-4446	Ponce De Leon, FL
SCALE: AS SHOWN	DRAWN BY: LBS
DATE:	
ELEVATIONS	
PLAN # 071023 R	3 OF 5




CABINET ELEVATIONS 1/4"=1'-0"



NOTE: MECHANICAL PLAN IS TO SHOW HEATED AREAS ONLY.
MECHANICAL CONTRACTOR SHALL DETERMINE ADEQUATE SIZE
OF HEAT/COOL UNIT, AS WELL AS EXACT SIZE AND LOCATION
OF CEILING REGISTERS.

LEGEND

- CEILING HUNG LIGHT FIXTURE
- WALL HUNG LIGHT FIXTURE
- RECESSED DOWNLIGHT
- PENDANT DOWNLIGHT
- CEILING LIGHT/EXHAUST FAN COMB.
- EXHAUST FAN
- WALL RECEPTICLE
- WATER-PROOF RECEPTICLE
- 220 VOLT RECEPTICLE
- FLOOR RECEPTICLE
- GAS VALVE
- SWITCH
- 3-WAY SWITCH
- 4-WAY SWITCH
- SMOKE DETECTOR
- CARBON MONOXIDE DETECTOR
- GROUND-FAULT CIRCUIT INTERRUPTER
- HOSE BIB
- WATER LINE FOR ICE MAKER




Original Paper Size
34"x22"

CONTRACTOR TO VERIFY ALL DIMENSIONS
AND REPORT DISCREPANCIES TO SPIERS
DRAFTING SERVICE PRIOR TO CONSTRUCTION.

CONTRACTOR TO COMPLY WITH ALL BUILDING
CODES AND ORDINANCES OF COLUMBIA
COUNTY, FLORIDA.

PROPOSED RESIDENCE FOR:
TROY POOLE


SPIERS DRAFTING SERVICE		
850-836-4446		Ponce De Leon, FL
SCALE: 1/4"=1'-0"		DRAWN BY: LBS
DATE:		
ELECTRICAL/MECHANICAL PLANS, CABINET ELEVATIONS		
PLAN # 071023 R		4 OF 5



TYPICAL SECTIONS

(NOT TO SCALE)

NOTE: VERIFY PERTINENT INFORMATION PRIOR TO CONSTRUCTION & USE ONLY THOSE DETAILS THAT APPLY TO PLANS AND ARE REQUIRED BY CODES



Original Paper Size

34"x22"

(850-836-4446)

SPIERS DRAFTING SERVICE
Ponce De Leon, FL

SCALE: AS SHOWN	DRAWN BY: JCS
DATE:	
TYPICAL SECTIONS	
PLAN #	LAST PAGE

STRUCTURAL NOTES:

GENERAL:

1. NO PROVISION OF ANY REFERENCED STANDARD SPECIFICATION, MANUAL OR CODE (WHETHER OR NOT SPECIFICALLY INCORPORATED BY REFERENCE IN THE CONTRACT DOCUMENTS) SHALL BE EFFECTIVE TO CHANGE THE DUTIES AND RESPONSIBILITIES OF OWNER, CONTRACTOR, ENGINEER, SUPPLIER, OR ANY OF THEIR CONSULTANTS, AGENTS, OR EMPLOYEES FROM THOSE SET FORTH IN THE CONTRACT DOCUMENTS. NOR SHALL IT BE EFFECTIVE TO ASSIGN TO THE STRUCTURAL ENGINEER OF RECORD OR ANY OF THE STRUCTURAL ENGINEER OF RECORD'S CONSULTANTS, AGENTS, OR EMPLOYEES ANY DUTY OR AUTHORITY TO SUPERVISE OR DIRECT THE FURNISHING OR PERFORMANCE OF THE WORK OR ANY DUTY OR AUTHORITY TO UNDERTAKE RESPONSIBILITIES CONTRARY TO THE PROVISIONS OF THE CONTRACT DOCUMENTS.

2. CONTRACT DOCUMENTS INCLUDE, BUT ARE NOT LIMITED TO, THE STRUCTURAL DOCUMENTS (DRAWINGS AND SPECIFICATIONS), BUT DO NOT INCLUDE SHOP DRAWINGS, VENDOR DRAWINGS, OR MATERIAL PREPARED AND SUBMITTED BY THE CONTRACTOR.

3. REFERENCE TO STANDARD SPECIFICATIONS OF ANY TECHNICAL SOCIETY, ORGANIZATION, OR ASSOCIATION OR TO CODES OF LOCAL OR STATE AUTHORITIES, SHALL MEAN THE LATEST STANDARD, CODE, SPECIFICATION OR TENTATIVE SPECIFICATION ADOPTED AT THE DATE OF TAKING BIDS, UNLESS SPECIFICALLY STATED OTHERWISE.

4. CONTRACT DOCUMENTS SHALL GOVERN IN THE EVENT OF A CONFLICT WITH THE CODE OF PRACTICE OR SPECIFICATIONS OF AISC, PCI, AASCI, SJI OR OTHER STANDARDS, WHERE A CONFLICT OCCURS WITHIN THE CONTRACT DOCUMENTS, THE STRICTEST REQUIREMENT SHALL GOVERN.

5. MATERIAL, WORKMANSHIP, AND DESIGN SHALL CONFORM TO THE REFERENCED BUILDING CODE.

6. CONTRACTOR SHALL COORDINATE THE STRUCTURAL DOCUMENTS WITH THE ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND CIVIL DOCUMENTS. ARCHITECT/STRUCTURAL ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCY OR OMISSION, FOR DIMENSIONS NOT SHOWN ON THE STRUCTURAL DRAWINGS SEE THE ARCHITECTURAL DRAWINGS.

7. CONTRACTOR SHALL OBTAIN AND COORDINATE EDE OF SLAB DIMENSIONS, OPENING LOCATIONS AND DIMENSIONS, DERESSED SLAB LOCATIONS AND EXTENTS, SLAB SLOPES, CURB LOCATIONS, AND CMU WALL DIMENSIONS, ARCHITECT/STRUCTURAL ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCY OR OMISSION.

8. CONTRACTOR SHALL VERIFY EXISTING DIMENSIONS, ELEVATIONS, AND SITE CONDITIONS BEFORE STARTING WORK. ARCHITECT/STRUCTURAL ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCY.

9. CONTRACTOR HAS SOLE RESPONSIBILITY FOR MEANS, METHODS, SAFETY, TECHNIQUES, SEQUENCES, AND PROCEDURES OF CONSTRUCTION.

10. THE STRUCTURE IS STABLE ONLY IN ITS COMPLETED FORM. TEMPORARY SUPPORTS REQUIRED FOR STABILITY DURING ALL INTERMEDIATE STAGES OF CONSTRUCTION SHALL BE DESIGNED, FURNISHED, AND INSTALLED BY THE CONTRACTOR. CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTIBILITY ANALYSIS, AND ERECTION PROCEDURES, INCLUDING DESIGN AND ERECTION OF FALSEWORK, TEMPORARY BRACING, ETC.

11. CONTRACTOR HAS SOLE RESPONSIBILITY TO COMPLY WITH ALL OSHA REGULATIONS.

12. REPRODUCTION OF STRUCTURAL DRAWINGS FOR SHOP DRAWINGS IS NOT PERMITTED. ELECTRONIC DRAWING FILES WILL NOT BE PROVIDED TO THE CONTRACTOR.

13. SUBMIT SHOP DRAWINGS WHICH ADEQUATELY DEPICT THE STRUCTURAL ELEMENTS AND CONNECTIONS SHOWN IN THE CONTRACT DOCUMENTS. REVIEW OF SHOP DRAWINGS SHALL BE FOR CONFORMANCE WITH THE CONTRACT DOCUMENTS REGARDING ARRANGEMENT AND SIZES OF MEMBERS AND THE CONTRACTOR'S INTERPRETATION OF THE DESIGN LOADS AND CONTRACT DOCUMENT DETAILS. REVIEW OF SUBMITTALS OR SHOP DRAWINGS BY THE ARCHITECT/STRUCTURAL ENGINEER DOES NOT RELIEVE THE CONTRACTOR OF THE SOLE RESPONSIBILITY TO REVIEW AND CHECK ALL SUBMITTALS AND SHOP DRAWINGS BEFORE SUBMITTING TO THE STRUCTURAL ENGINEER. REVIEW OF SUBMITTALS OR SHOP DRAWINGS BY THE ARCHITECT/STRUCTURAL ENGINEER DOES NOT RELIEVE THE CONTRACTOR OF FULL RESPONSIBILITY FOR COMPLIANCE WITH THE CONTRACT DOCUMENTS.

14. CONTRACTOR REMAINS SOLELY RESPONSIBLE FOR ERRORS AND OMISSIONS ASSOCIATED WITH THE PREPARATION OF SHOP DRAWINGS AS THEY PERTAIN TO MEMBER SIZES, DETAILS, AND DIMENSIONS SPECIFIED IN THE CONTRACT DOCUMENTS.

15. WHERE A SECTION OR DETAIL IS SHOWN OR DETAILED FOR ONE CONDITION, IT SHALL APPLY TO ALL SIMILAR AND LIKE CONDITIONS. DETAILS LABELED "TYPICAL" ON THE STRUCTURAL DRAWINGS APPLY TO ALL SITUATIONS OCCURRING ON THE PROJECT THAT ARE THE SAME OR SIMILAR. THE CONTRACTOR SHALL CONSIDER ALL OF THE CONTRACT DOCUMENTS IN DETERMINING SIMILAR AND LIKE CONDITIONS.

16. SIGNATURE AND REGISTRATION SEAL OF THE STRUCTURAL ENGINEER THAT MAY BE AFFIXED TO THESE DRAWINGS RELATES ONLY TO THE STRUCTURAL DESIGN OF THE PROJECT.
3. ESTIMATED DEFLECTIONS (IN INCHES) ARE AS FOLLOWS:

ROOF MEMBERS:

FLOOR MEMBERS:

WHERE: L = SPAN LENGTH (IN INCHES) BETWEEN CENTERLINES OF SUPPORTS; FOR CANTILEVERS, L IS TWICE THE LENGTH OF THE CANTILEVER.

4. SPECIAL INSPECTIONS:

4.1. THE FOLLOWING TYPES OF WORK REQUIRE SPECIAL INSPECTION:

FOUNDATION ANCHORS & REINFORCING STEEL

SHEARWALL CONSTRUCTION

DIAPHRAM NAILING AND HOLDOWN ATTACHMENT

5. NO PROVISIONS HAVE BEEN MADE FOR FUTURE HORIZONTAL OR VERTICAL EXPANSION.
- CODE/DESIGN CRITERIA CONT:
1. CAST-IN-PLACE CONCRETE:

2. MINIMUM CONCRETE COVERAGE OF REINFORCEMENT: FOOTINGS: 3" BOTTOM AND 3" SIDES.

3. EARTH SUPPORTED SLAB: 4 INCHES THICK REINFORCED WITH 6 X 6 X W2.1 X W2.1 W.W.F. THE SLAB SHALL BE PLACED OVER POLYETHYLENE VAPOR BARRIER OF NOT LESS THAN .006 INCH NOMINAL THICKNESS. IN LIEU OF WELDED WIRE FABRIC, CONCRETE SLAB CAN BE TREATED WITH SYNTHETIC REINFORCING FIBERS AS MANUFACTURED BY FIBERMESH COMPANY AND IN ACCORDANCE WITH ASTM STANDARD SPECIFICATION FOR FIBER REINFORCED CONCRETE AND SHOTCRETE C1116. THE DOSAGE SHALL BE ONE AND ONE HALF 1 1/2 POUNDS FIBERS PER CUBIC YARD OF CONCRETE.

4. ANCHOR BOLTS IN CMU BLOCKS SHALL CONFORM TO ASTM A36 AND SHALL BE 3" OR 5/8" DIAMETER WITH 7" MIN. DEPTH IN CONCRETE.

5. DETAIL REINFORCING IN ACCORDANCE WITH A.C.I. 315. REINFORCING SHALL NOT BE WELDED, EXCEPT AS SHOWN WHERE ASTM A708 BARS ARE USED.

6. CONCRETE SHALL HAVE THE FOLLOWING MINIMUM SPECIFIED 28-DAY COMPRESSIVE STRENGTH:

NORMAL WEIGHT STRUCTURAL CONCRETE:

FOOTINGS, PEDESTALS

SLABS-ON-GRADE

3,000 PSI

3,000 PSI

7. REFER TO ARCHITECTURAL DRAWINGS FOR MOLDS, GROOVES, ORNAMENTS, CLIPS OR GROUNDS REQUIRED TO BE ENCASED IN CONCRETE, AND FOR LOCATION OF FLOOR FINISHES AND SLAB DEPRESSIONS.

8. CONSTRUCTION JOINT LOCATIONS SHALL BE APPROVED BY THE STRUCTURAL ENGINEER. NO HORIZONTAL CONSTRUCTION JOINTS ARE PERMITTED EXCEPT THOSE SHOWN ON THE STRUCTURAL DRAWINGS.

9. DEFECTIVE AREAS IN CONCRETE INCLUDING, BUT NOT LIMITED TO, HONEY-COMBING, SPALLS, AND CRACKS WITH WIDTHS EXCEEDING 0.01 INCH SHALL BE REPAIRED. EXTENT OF DEFECTIVE AREA TO BE DETERMINED BY THE STRUCTURAL ENGINEER.

EXTERIOR WINDOWS & DOORS:

NOTES:

1. THIS STRUCTURE IS DESIGNED AS AN ENCLOSED BUILDING IN ACCORDANCE WITH FLORIDA BUILDING CODE CHAPTER 16. ALL WINDOWS AND EXTERIOR DOORS SHALL BE RATED FOR 140 MPH WIND PRESSURE.

2. FOR THIS ENCLOSED BUILDING, DESIGN PRESSURES ARE INDICATED ON THE WIND LOAD TABLE THIS SHEET.

3. TO COMPLY WITH THE FLORIDA BLDG. CODE, 2023 RESIDENTIAL SHUTTERS OR IMPACT RESISTANT GLAZING ARE REQUIRED.

4. SHUTTERS OR IMPACT RESISTANT GLAZING MUST HAVE FLORIDA PRODUCT APPROVAL NUMBERS.

WOOD:

1. STRUCTURAL GLUED LAMINATED TIMBER SHALL BE PRODUCED IN ACCORDANCE WITH THE AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC). MINIMUM ALLOWABLE BENDING STRESS SHALL BE 2,400 PSI (DRY CONDITIONS).

2. PROVIDE DRESSED SEASONED LUMBER, S4S, WITH A MAXIMUM MOISTURE CONTENT OF 19% AT TIME OF DRESSING AS LISTED BELOW.

3. INTERIOR AND EXTERIOR LOAD-BEARING WALLS: SOUTHERN PINE, NO. 2 GRADE.

4. LINTELS, FLOOR JOISTS AND BEAMS: SOUTHERN PINE, NO. 2 GRADE WOOD IN CONTACT WITH CONCRETE OR MASONRY SHALL BE FOUNDATION GRADE PRESSURE-TREATED. USE GALVANIZED NAILS IN PRESSURE-TREATED WOOD.

ENGINEERED LUMBER PRODUCTS

1. PARALLEL STRAND LUMBER (PSL) SHALL HAVE THE FOLLOWING MINIMUM ALLOWABLE STRESSES AND PROPERTIES:

ALLOWABLE BENDING STRESS

COMPRESSION PERPENDICULAR TO GRAIN

COMPRESSION PARALLEL TO GRAIN

HORIZONTAL SHEAR

MODULUS OF ELASTICITY

FB = 2900 PSI

FCPR = 850 PSI

FCPR = 2900 PSI

FV = 290 PSI

E = 2,000,000 PSI

2. LAMINATED VENEER LUMBER (LVL) SHALL HAVE THE FOLLOWING MINIMUM ALLOWABLE STRESSES AND PROPERTIES:

ALLOWABLE BENDING STRESS

COMPRESSION PERPENDICULAR TO GRAIN

COMPRESSION PARALLEL TO GRAIN

HORIZONTAL SHEAR

MODULUS OF ELASTICITY

FB = 2600 PSI

FCPR = 750 PSI

FCPR = 2310 PSI

FV = 285 PSI

E = 1,900,000 PSI

3. LAMINATED STRAND LUMBER (LSL) SHALL HAVE THE FOLLOWING MINIMUM ALLOWABLE STRESSES AND PROPERTIES:

ALLOWABLE BENDING STRESS

COMPRESSION PERPENDICULAR TO GRAIN

COMPRESSION PARALLEL TO GRAIN

HORIZONTAL SHEAR

MODULUS OF ELASTICITY

FB = 1700 PSI

FCPR = 650 PSI

FCPR = 1400 PSI

FV = 285 PSI

E = 1,300,000 PSI

STRUCTURAL PANELS

1. FLOOR PANELS SHALL BE CONSTRUCTED WITH TONGUE AND GROOVE A/RATED STURD-I-FLOOR. FLOOR PANELS SHALL BE GLUED AND NAILED.

2. WALL PANELS SHALL BE CONSTRUCTED WITH A/RATED SHEATHING. NAIL PANELS w/10d COMMON NAILS AT 3" O.C. ALONG SUPPORTED PANEL EDGES AND AT 10" O.C. AT INTERMEDIATE SUPPORTS. FOR SHEAR WALLS, USE 10d NAILS @ 3" O.C.

3. ROOF PANELS SHALL BE CONSTRUCTED WITH 5/8" A/RATED SHEATHING.

PLYWOOD SHEATHING:

1. EACH CONSTRUCTION AND INDUSTRIAL PANEL SHALL BE IDENTIFIED WITH THE APPROPRIATE TRADEMARK OF THE AMERICAN PLYWOOD ASSOCIATION AND SHALL MEET THE REQUIREMENTS OF THE LATEST EDITION OF U.S. PRODUCT STANDARDS PS 1 OR PRP-180 PERFORMANCE STANDARDS. ALL PANELS WHICH HAVE ANY EDGE OR SURFACE PERMANENTLY EXPOSED TO WEATHER SHALL BE CLASSIFIED EXTERIOR.

2. PANEL ROOF WALL AND FLOOR SHEATHING SHALL BE 3/4" THICK APA STRUCTURAL 1 RATED SHEATHING EXP 2 (UNLESS OTHERWISE NOTED ON PLANS). SHEATHING PERMANENTLY EXPOSED TO WEATHER SHALL BE CLASSIFIED EXTERIOR.

3. NAIL PANELS WITH 10d COMMON NAILS AT 3" O.C. ALONG SUPPORTED PANEL EDGES AND 6 O.C. AT INTERMEDIATE SUPPORTS, OR AS INDICATED ON PLANS.

4. ALL BEARING STUD WALLS SHALL HAVE SOLID BLOCKING AT MID-HEIGHT OR AS OTHERWISE NOTED ON BUILDING SECTIONS.

5. PREFABRICATED WOOD STRUCTURAL MEMBERS, INCLUDING TRUSSES SHALL BE DESIGNED SPECIFICALLY FOR THIS PROJECT OR A 140-MPH WIND LOAD HW ASCE 7-22 LATERAL LOAD AND SEALED BY A FLORIDA REGISTERED ENGINEER.

6. REVIEW ALL DRAWINGS INCLUDING MECHANICAL, ELECTRICAL PLUMBING ETC. TO ASCERTAIN LOADS FROM EQUIPMENT OPENINGS FOR DUCTS ETC. AND PROVIDE MODIFICATION TO TRUSSES IF REQUIRED TO SUPPORT SAME.

7. USE SIMPSON SP1 & SP2 (OR EQUAL) TO SECURE STUDS TO BOTTOM AND TOP PLATES, OR AS INDICATED ON PLAN.

8. USE TWO (2) SIMPSON LSTA21 (OR EQUAL) TO SECURE EACH BEAM HEADER BEARING END TO EACH SUPPORT, OR AS INDICATED PER PLAN.

9. USE SIMPSON LSTA21 STRAP TIES (OR EQUAL) OR SIMPSON SP4 (OR EQUAL) AT TOP OF EACH EXTERIOR WINDOW AND DOOR FRAME OPENING, OR AS INDICATED PER PLAN.

10. CUTTING NOTCHING BORED HOLES IN STUD WALLS, RAFTERS, ETC., SHALL BE DONE IN ACCORDANCE WITH THE FLORIDA BUILDING CODE 2023 RESIDENTIAL.

11. RIDGE BOARDS WHERE INDICATED ON FRAMING PLANS SHALL NOT BE LESS THAN 1" IN THICKNESS, AND NOT LESS IN DEPTH THAN CUT END RAFTERS. RAFTERS SHALL BE PLACED DIRECTLY OPPOSITE EACH OTHER AND NAILED TO RIDGE BOARD.

12. ALL WOOD BUILT-UP GIRDERS BEAMS, STUDS TO SOLE PLATES, ETC. TO BE CONNECTED AS PER 2023 FLORIDA BUILDING CODE.

13. OPENING IN EXTERIOR WALLS, A WALL STUD SHALL BE AT EACH SIDE OF THE OPENING WITH THE ENDS OF THE HEADER SUPPORTED AS FOLLOWS (UNLESS OTHERWISE NOTED):

13.1. FOR OPENINGS LESS THAN 3 FEET IN WIDTH, EACH SIDE OF HEADER SHALL REST ON A SINGLE HEADER STUD OR MAY BE SUPPORTED BY FRAMING ANCHORS ATTACHED TO WALL STUD.

13.2. FOR OPENINGS OVER 3 FEET TO LESS THAN 6'-0", EACH END SHALL BEAR ON A SINGLE HEADER STUD.

13.3. FOR OPENINGS MORE THAN 6'-0" AND LESS THAN 12' IN WIDTH, EACH END SHALL BEAR ON A DOUBLE HEADER STUD.

14. ANY HEADER SUPPORTING CONCENTRATED LOADS FROM BEAMS ABOVE, EACH END SHALL BEAR ON DOUBLE HEADER STUDS.

15. WHERE WOOD BEAMS BEAR ON STUD WALLS, PROVIDE MINIMUM DOUBLE OR TRIPLE STUDS, DEPENDING ON BEAM WIDTH AND LOADS, UNDER FOUNDATION.

FRAMING

1. ROOF SHEATHING: 5/8 CDX - NAIL 10d RING SHANK FLAT HEAD - 3" PERIM./4" FIELD.

2. ROOF RAFTERS: 2x8 - 24" O.C. (MAX. UNBRACED HORIZONTAL SPAN - 12'-6" OR PRE-ENGINEERED ROOF TRUSSES.

3. WALL FRAMING: 2x6 OR 2x4 @ 16" O.C. - LODGE POLE MAY BE USED FOR INTERIOR STUD FRAMING. SYP SHALL BE USED FOR TOP, BOTTOM PLATES, AND EXTERIOR WALL STUDS.

4. SECURE ROOF RAFTERS TO TOP PLATE DIRECTLY WITH SIMPSON H10, OR H10-2, OR MSD12/16. CLIPS OR EQUAL OR GREATER UPLIFT CAPACITY MAY BE SUBSTITUTED.

5. WALL SHEATHING: 1/2 CDX - NAIL 8d COMMON - 4" PERIM./4" FIELD.

6. STRAP TIES: SIMPSON SP1 AND SP2 OR SIMPSON LSTA21 - 20 GA. - (16) 10d COMMON. THE SPACING: 32" O.C.

7. TOP PLATE NAILING: 24" O.C. - USE 16d COMMON. USP CONNECTORS MAY BE USED IN LIEU OF SIMPSON.

8. IF USED, RUN 3" OR 3/4" ALL THREAD RODS ON 72" CENTERS, PLACE ALL THREAD RODS EACH SIDE OF BEARING OPENINGS GREATER THAN 3'-0", AND WITHIN 12" OF ALL CORNERS.

9. ALL COLUMN TO BEAM CONNECTIONS SHALL BE SIMPSON CC OR ECC L/R. STRAPPED CONNECTIONS ARE NOT ALLOWED.

FABRICATED WOOD TRUSSES

1. DESIGN OF WOOD TRUSSES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. SUBMIT SHOP DRAWINGS, DESIGN LOAD DATA, AND SUPPORT REACTIONS SEALED BY AN ENGINEER LICENSED IN THE PROJECT STATE. REVIEW OF SHOP DRAWINGS SHALL BE FOR CONFORMANCE WITH THE CONTRACT DOCUMENTS WITH REGARD TO TRUSS CONFIGURATION, AND THE CONTRACTOR'S INTERPRETATION OF DESIGN LOADS AND DETAILS. SUCH REVIEW SHALL NOT RELIEVE THE CONTRACTOR OF THE FULL RESPONSIBILITY FOR THE DESIGN OF THE TRUSSES OR TRUSS CONNECTIONS NOT SPECIFICALLY DETAILED IN THE CONTRACT DOCUMENTS.

2. ERECTION AND TEMPORARY BRACING OF PREFABRICATED WOOD TRUSSES SHALL BE IN CONFORMANCE WITH THE RECOMMENDATIONS OF THE TRUSS MANUFACTURER AND THE TRUSS PLATE INSTITUTE'S "BRACING WOOD TRUSSES: COMMENTARY AND RECOMMENDATIONS".

FABRICATED WOOD TRUSSES CONT

3. SECURE EACH COMMON ROOF TRUSS/RAFTER TO TOP PLATE WITH SIMPSON H-10 OR H-7 HURRICANE CLIP AT ALL BEARING POINTS. USE SIMPSON H-7 AT GIRDER TRUSSES. PROVIDE A MINIMUM OF TWO STUDS UNDER GIRDER TRUSS END BEARING.

4. CONTRACTOR TO REFER TO "STANDARD FOR HURRICANE RESISTANT CONSTRUCTION"SD 10-93 FOR FRAMING REQUIREMENTS OF WOOD FRAMED WALL SYSTEMS, TABLE 305C AND FIGURE 306D.

5. TRUSS LAYOUT AS SHOWN ON PLANS IS SCHEMATIC AND MAY BE MODIFIED WITH APPROVAL OF THE ENGINEER.

6. ALTHOUGH WEB LAYOUT MAY BE SHOWN ON PLANS IT IS THE RESPONSIBILITY OF THE TRUSS DESIGNER TO ACCEPT, APPROVE, OR MODIFY, AS REQUIRED FOR THE DESIGN PURPOSE.

7. WOOD-TO-WOOD FRAMED CONNECTIONS ARE TO BE MADE WITH BOLTS AND/OR JOIST HANGERS AS SHOWN. TOE-NAILING IS NOT PERMITTED.

8. MAXIMUM SPANS OF DIMENSIONAL LUMBER USED FOR JACK RAFTERS AT HIPPED ROOF SECTIONS SHALL BE IN ACCORDANCE WITH SPAN TABLES FOR JOISTS AND RAFTERS AS PUBLISHED BY THE NATIONAL WOOD PRODUCTS ASSOCIATION.

9. HIP RAFTERS SHALL BE 2 INCHES DEEPER THAN JACK RAFTERS.

10. ALL TRUSSES AND RAFTERS SHALL BE STRAPPED OR HURRICANE CLIPPED TO SUPPORTING MEMBERS AT ALL BEARING POINTS.

11. SECURE EACH ROOF TRUSS/RAFTER TO TOP PLATE WITH SIMPSON HURRICANE CLIPS (OR EQUAL) AS INDICATED ON PLANS. CONTRACTOR TO SUBMIT SHOP DRAWINGS OF TRUSSES TO ENGINEER TO VERIFY/MODIFY UPLIFT CONNECTORS.

12. ALL EXTERIOR WALL FRAMING SHALL BE 2"x4" OR 2"x6" AT 16" O.C. UNLESS NOTED OTHERWISE. 7/16" OSB SHEATHING OR 1/2" CDX PLYWOOD PANELS SHOULD EXTEND TO THE TOP PLATE AND BOTTOM OF EXTERIOR GIRDERS OR SILL PLATE. NAIL PLYWOOD AT 4" O.C. AT ALL EDGES AND 6" O.C. AT INTERMEDIATE SUPPORTS OR AS INDICATED PER PLAN.

13. USE SIMPSON ST18 (OR EQUAL) RIDGE/RAFTER CONNECTORS OR SIMPSON RR STRAPS AT ALL RAFTERS RIDGE BEAMS OR AS INDICATED PER PLAN.

FLOOR TRUSS LOADS:

1. FLOOR TRUSSES SHALL BE DESIGNED FOR THE FOLLOWING LOADS UNLESS A SPECIAL LOADING PATTERN IS PROVIDED BY THE STRUCTURAL ENGINEER OF RECORD.

TOP CHORD LIVE LOAD	40 PSF
TOP CHORD DEAD LOAD	25 PSF
BOTTOM CHORD DEAD LOAD	10 PSF
TOTAL	75 PSF

ROOF TRUSS LOADS:

1. ROOF TRUSSES SHALL BE DESIGNED FOR THE FOLLOWING LOADS UNLESS A SPECIAL LOADING PATTERN IS PROVIDED BY THE STRUCTURAL ENGINEER OF RECORD.

TOP CHORD LIVE LOAD	20 PSF
TOP CHORD DEAD LOAD	15 PSF
BOTTOM CHORD DEAD LOAD	10 PSF
TOTAL	45 PSF
	(50 PSF FOR TILE ROOF)

NOTES TO GENERAL CONTRACTOR:

IN CASE OF CONFLICT BETWEEN THE DRAWINGS AND THE SPECIFICATIONS OR NOTES, E.O.R. SHALL BE NOTIFIED PRIOR TO THE EXECUTION OF ANY WORK.

IN CASE OF CONFLICT AS TO THE TYPE OF MATERIALS OR THE QUALITY OF CONSTRUCTION, THE MATERIAL OUTLINE SHALL PREVAIL; IF CLARIFICATION IS NEEDED, NOTIFY ENGINEER PRIOR TO EXECUTION OF ANY WORK.

IN CASE OF CONFLICT BETWEEN THE DOCUMENTS AND THE BUILDING CODE, THE BUILDING CODE PREVAILS.

NOTIFY ENGINEER OF ERRORS OR OMISSIONS IMMEDIATELY UPON DISCOVERY AND STOP WORK UNTIL RESOLVED.

NO CHANGES SHALL BE MADE WITHOUT WRITTEN APPROVAL FROM ENGINEER.

DETAILS ON ONE SHEET GENERALLY APPLY TO ALL SIMILAR SITUATIONS EVEN IF NOT SHOWN OR REFERENCED TO OTHER DRAWINGS. IF A CONFLICT OCCURS, NOTIFY STRUCTURAL ENGINEER PRIOR TO PROCEEDING.

NAIL PATTERNS AND OTHER DETAILS NOT DRAWN ARE TO BE INSTALLED ACCORDING TO CODE AND TO ACCEPTABLE STANDARD PRACTICE FOR QUALITY CUSTOM CONSTRUCTION; STRUCTURAL ENGINEER SHALL BE THE SOLE JUDGE OR ARBITRATOR AS TO WHAT DETERMINES "ACCEPTABLE QUALITY CUSTOM CONSTRUCTION".

MAINTAIN A STAMPED AND SEALED SET OF CURRENT CONSTRUCTION DOCUMENTS, INCLUDING ANY AND ALL ADDENDA, SHOP DRAWING AND SKETCH DESIGN/DETAIL DRAWINGS ON SITE AND ACCESSIBLE TO ALL INVOLVED PARTIES.

DIMENSIONS SHOWN ARE FRAMING OR MASONRY DIMENSIONS UNLESS NOTED AS SURFACE DIMENSIONS.

DO NOT SCALE THE DRAWING. CALL STRUCTURAL ENGINEER FOR CLARIFICATION AS NECESSARY.

COUNTY CERTIFICATION:

I CERTIFY THAT THE DESIGN PLANS AND SPECIFICATIONS FOR THIS CONSTRUCTION ARE IN COMPLIANCE WITH THE CRITERIA ESTABLISHED BY THE 2023 FLORIDA BUILDING CODE.

THIS BUILDING AND/OR STRUCTURE IS DESIGNED TO WITHSTAND WIND VELOCITY OF 140 MPH.

ALSO, UPON COMPLETION OF THIS BUILDING AND/OR STRUCTURE, I WILL CERTIFY AT THAT TIME THE BUILDING AND/OR STRUCTURE HAS COMPLIED WITH THIS SPECIFIC BUILDING DESIGN. THIS MUST BE ON FILE AT THE COUNTY BUILDING DEPARTMENT BEFORE RECEIVING AN INSPECTION FOR POWER.

I UNDERSTAND THAT ANY CHANGE IN DESIGN OR SPECIFICATION MUST BE SUBMITTED IN WRITING BY ME TO THE BUILDING DEPARTMENT.

ALL DRAWINGS AND/OR CORRESPONDENCE SHALL BE SIGNED AND SEALED.

Wind Pressures (Normal to Ridge)

All wind pressures include a Load Factor (LF) of 0.6

Elev ft	GCP	q psf	Kz	Kd	q psf	Windward Press psf	Leeward Press psf	Side Press psf	Total Press psf	Minimum Pressure* psf
9.500	0.18	26.06	0.851	1.000	25.62	10.82	-13.40	-17.17	24.23	9.60
9.500	-0.18	26.06	0.851	1.000	25.62	18.80	-5.43	-9.19	24.23	9.60

Wind Pressures (Parallel to Ridge)

All wind pressures include a Load Factor (LF) of 0.6

Elev ft	GCP	q psf	Kz	Kd	q psf	Windward Press psf	Leeward Press psf	Side Press psf	Total Press psf	Minimum Pressure* psf
23.111	0.18	26.06	0.930	1.000	27.99	12.19	-12.72	-17.17	24.91	9.60
16.306	0.18	26.06	0.866	1.000	26.06	11.08	-12.72	-17.17	23.80	9.60
9.500	0.18	26.06	0.851	1.000	25.62	10.82	-12.72	-17.17	23.54	9.60
23.111	-0.18	26.06	0.930	1.000	27.99	20.16	-4.74	-9.19	24.91	9.60
16.306	-0.18	26.06	0.866	1.000	26.06	19.05	-4.74	-9.19	23.80	9.60
9.500	-0.18	26.06	0.851	1.000	25.62	18.80	-4.74	-9.19	23.54	9.60

Roof Wind Pressures (Normal to Ridge)

All wind pressures include a Load Factor (LF) of 0.6

Component	Description	Location	Start ft	End ft	GCP	C _{pit}	C _{pe}	PCpMin _{ref}	PCpMax _{ref}	P _{ref} psf
OH	Overhang Top	356	All	All	0	0.257	-0.195	4.84	-3.66	4.80
OH	Overhang Leeward	278	All	All	0	-0.600	-0.600	-11.30	-11.30	4.80
OH Bot	Overhang Bottom	3	All	All	0	0.800	0.800	15.07	15.07	4.80
Roof	Roof Windward	1	All	All	0.18	0.257	-0.195	0.85	-7.65	4.80
Roof	Roof Leeward	2	All	All	0.18	-0.600	-0.600	-15.29	-15.29	4.80
OH	Overhang Top	356	All	All	0	0.257	-0.195	4.84	-3.66	4.80
OH	Overhang Leeward	278	All	All	0	-0.600	-0.600	-11.30	-11.30	4.80
OH Bot	Overhang Bottom	3	All	All	0	0.800	0.800	15.07	15.07	4.80
Roof	Roof Windward	1	All	All	-0.18	0.257	-0.195	8.83	0.32	4.80
Roof	Roof Leeward	2	All	All	-0.18	-0.600	-0.600	-7.31	-7.31	4.80

Roof Wind Pressures (Parallel to Ridge)


All wind pressures include a Load Factor (LF) of 0.6

Component	Description	Location	Start ft	End ft	GCP	C _{pit}	C _{pe}	PCpMin _{ref}	PCpMax _{ref}	P _{ref} psf
OH Bot	Overhang Bottom	57	All	All	0	0.800	0.800	15.07	15.07	4.80
OH Top	Overhang Top (0 to h)	3457	0.000	16.306	0	-0.500	-0.180	-16.95	-3.39	4.80
OH Top	Overhang Top (h to 2*h)	34	16.306	32.611	0.18	-0.500	-0.180	-13.40	-7.38	4.80
OH Top	Overhang Top (>= 2*h)	3468	32.611	54.660	0.18	-0.300	-0.180	-9.64	-7.38	4.80
Roof	Roof (0 to h)	12	1.330	16.306	0.18	-0.500	-0.180	-20.94	-7.38	4.80
Roof	Roof (h to 2*h)	12	16.306	32.611	0.18	-0.500	-0.180	-13.40	-7.38	4.80
Roof	Roof (>= 2*h)	12	32.611	53.330	0.18	-0.300	-0.180	-9.64	-7.38	4.80
OH Bot	Overhang Bottom	57	All	All	0	0.800	0.800	15.07	15.07	4.80
OH Top	Overhang Top (0 to h)	3457	0.000	16.306	0	-0.500	-0.180	-16.95	-3.39	4.80
OH Top	Overhang Top (h to 2*h)	34	16.306	32.611	-0.18	-0.500	-0.180	-5.43	0.60	4.80
OH Top	Overhang Top (>= 2*h)	3468	32.611	54.660	-0.18	-0.300	-0.180	-1.66	0.60	4.80
Roof	Roof (0 to h)	12	1.330	16.306	-0.18	-0.500	-0.180	-12.96	0.60	4.80
Roof	Roof (h to 2*h)	12	16.306	32.611	-0.18	-0.500	-0.180	-5.43	0.60	4.80
Roof	Roof (>= 2*h)	12	32.611	53.330	-0.18	-0.300	-0.180	-1.66	0.60	4.80

Wind Pressures for C&C Ch 30 P 1 Roof & Wall

All wind pressures include a Load Factor (LF) of 0.6

Description	Zone	Width ft	Span ft	Area ft²	1/3 Rule	Figure	GCP Max	GCP Min	p psf	p psf
Zone 1	1	1,000	1,000	1,000	No	30.3-20	0.900	-1.800	23.93	-43.87
Zone 2	2	1,000	1,000	1,000	No	30.3-20	0.900	-2.000	23.93	-48.30
Zone 3	3	1,000	1,000	1,000	No	30.3-20	0.900	-2.500	23.93	-59.38
Zone 4	4	1,000	1,000	1,000	No	30.3-1	1.000	-1.100	26.14	-28.36
Zone 5	5	1,000	1,000	1,000	No	30.3-1	1.000	-1.400	26.14	-35.00
305S EXT DOOR	4	3,000	6,670	20,001	No	30.3-1	0.947	-1.047	24.96	-27.18
4040 WINDOW	4	4,000	4,000	16,000	No	30.3-1	0.964	-1.064	25.34	-27.56
3050 WINDOW	4	3,000	5,000	15						



FRAMING SCHEDULE					
NO.	TYPE	SIZE	ANCHOR/STRAPPING		REMARKS
			SIDE 1	SIDE 2	
H1	WINDOW/DOOR HEADER	(3 PLT) 2X8 FLITCHED W/ (2) 2" CDX/OSB PLYWOOD	SIMPSON LSTA 24	SIMPSON LSTA 24	CONNECT USING (2) ROWS 16D RING SHANK NAILS SPACED @ 16" O.C. EACH SIDE
WC8	PT WOOD COLUMN	PT 6X6	SEE DETAILS SHEET S-2.0	SIMPSON ECCLQ/CC	SET PT COLUMN FLUSH WITH EDGE OF SLAB
WC8	PT WOOD COLUMN	PT 6X6	SEE DETAILS SHEET S-2.0	SEE DETAILS SHEET S-2.1	SET PT COLUMN FLUSH WITH EDGE OF SLAB
PHB-1	PORCH HEADER BEAM	(3 PLT) 2X12 FLITCHED W/ (2) 2" CDX/OSB SPACERS	STUD PACK W/ SIMPSON LSTA 24	SIMPSON ECCLQ/CC	CONNECT USING (2) ROWS 16D RING SHANK NAILS SPACED @ 12" O.C. EACH SIDE
PHB-2	PORCH HEADER BEAM	(3 PLT) 2X12 FLITCHED W/ (2) 2" CDX/OSB SPACERS	SIMPSON ECCLQ/CC	SIMPSON ECCLQ/CC	CONNECT USING (2) ROWS 16D RING SHANK NAILS SPACED @ 12" O.C. EACH SIDE
PHB-3	PORCH HEADER BEAM	PRESSURE TREATED 5.5"x14" GULAM BEAM	STUD PACK W/ SIMPSON LSTA 24	SIMPSON ECCLQX	FASTEN TO BEAM TO SIMPSON CONNECTORS USING MFG RECOMMENDED FASTENERS ONLY
PHB-4	PORCH HEADER BEAM	PRESSURE TREATED 5.5"x14" GULAM BEAM	SIMPSON ECCLQX	SIMPSON COTQ6X	FASTEN TO BEAM TO SIMPSON CONNECTORS USING MFG RECOMMENDED FASTENERS ONLY
PHB-5	PORCH HEADER BEAM	PRESSURE TREATED 5.5"x14" GULAM BEAM	STUD PACK W/ SIMPSON LSTA 24	SIMPSON COTQ6X	FASTEN TO BEAM TO SIMPSON CONNECTORS USING MFG RECOMMENDED FASTENERS ONLY
PHB-6	PORCH HEADER BEAM	PRESSURE TREATED 5.5"x14" GULAM BEAM	SIMPSON COTQ6X	SIMPSON COTQ6X	FASTEN TO BEAM TO SIMPSON CONNECTORS USING MFG RECOMMENDED FASTENERS ONLY

INTERIOR NON LOAD BEARING WALL
LOAD BEARING WALL/SHEAR WALL


ROOF PLAN & FRAMING NOTES

- FOR GENERAL NOTES AND DESIGN LIVE LOADS SEE SHEET S-1
- FOR TYPICAL FRAMING DETAILS SEE S-SERIES SHEETS. SEE ARCHITECTURAL DWGS. FOR DIMENSIONS NOT SHOWN. IF A CONFLICT EXISTS, THE ARCH DIMENSIONS SHALL GOVERN. NOTIFY ENGINEER OF RECORD IN WRITING IF CONFLICT EXISTS.
- ALL LUMBER EXPOSED TO WEATHER OR IN CONTACT WITH CONCRETE/MASONRY SHALL BE PRESSURE TREATED.
- ATTACH ALL ROOF TRUSSES TO TOP PLATE USING SIMPSON H10A/H10A-2/MTS18 HURRICANE TIES. SEE SHOP DRAWINGS FOR GIRDER TRUSS HOLD DOWN.
- TRUSS TO TRUSS/BREAM CONNECTORS SHALL BE SPECIFIED BY TRUSS DESIGNER. OVERHANG: 1'-0"
- - INDICATES LOCATIONS OF 3/8" HDG ALLTHREAD HOLD DOWNS OR HD38 HOLD DOWNS FOR SHEAR WALL ENDS.
- TRUSS MFG TO PROVIDE SPACE FOR HVAC DUCT AND UNIT
- ROOF PITCH TO BE 7:12 MAIN. SEE PLAN FOR VARIATIONS

FRAMING NOTES:

- STUD PACKS SHALL BE CONTINUOUS THROUGH ZONE OF GIRDER TRUSSES VIA MATCHING BLOCKING.
- SHEAR WALLS WHERE NOTED TO HAVE 3/4" PLYWOOD EACH SIDE NAILED @ 4" O/C EDGE AND 6" O/C FIELD. PLACE SIMPSON HD38 HOLD DOWN EACH END OF SHEAR WALL TO DOUBLE STUD PACK.
- ALL INTERIOR PLUMBING WALLS TO BE 2X6 TO ACCOMMODATE PIPING.

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM OR BY ANY MEANS WITHOUT PERMISSION FROM JL ENGINEERING & CONSULTING LLC. JL ENGINEERING & CONSULTING LLC DISCLAIMS ANY RESPONSIBILITY FOR ITS UNAUTHORIZED USE. PRINTED COPIES ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



JL ENGINEERING & CONSULTING LLC
490 LAKESIDE DRIVE
DEFUNIAK SPRINGS, FL 32435
CONTACT: (850)-399-1188

No.	Revision/Issue	Date

Project Name and Address
LAMNECK/POOLE RESIDENCE

SHEET TITLE
ROOF AND FRAMING PLAN

Project
25-2024


Date
05-06-2024

Scale
1/4" = 1'-0"


Sheet

S-11


1
S-1.1 **LOAD BEARING & ROOF FRAMING PLAN**
SCALE: 1/4" = 1'-0"




1 TYP. PERIMETER WALL FOOTING DETAIL
N.T.S. ALT. DETAIL FOR CMU FOUNDATION W/ SLAB




2 TYP. PORCH PERIMETER COLUMN DETAIL
N.T.S. ALT. DETAIL FOR CMU FOUNDATION W/ SLAB




3 TYP. PORCH STEP DOWN DETAIL
N.T.S. ALT. DETAIL FOR CMU FOUNDATION W/ SLAB




1B TYP. EXT. WALL FOOTING (MONO)
SCALE: 3/4" = 1'-0"




2B TYP. PORCH COLUMN FOOTING (MONO)
SCALE: 3/4" = 1'-0"




3B RECESS SLAB FOOTING (PORCH) MONO FOOTING
SCALE: 3/4" = 1'-0"



4 TYP. INTERIOR LOAD BEARING FOOTING
SCALE: 3/4" = 1'-0"




1 TYP. EXTERIOR WALL ROOF FRAMING DETAIL
SCALE: N.T.S.



2 TYP. EXTERIOR COLUMN ROOF FRAMING DETAIL
SCALE: N.T.S.

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM OR BY ANY MEANS WITHOUT PERMISSION FROM JL ENGINEERING & CONSULTING LLC. JL ENGINEERING & CONSULTING LLC DISCLAIMS ANY RESPONSIBILITY FOR ITS UNAUTHORIZED USE. PRINTED COPIES ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.




JL ENGINEERING & CONSULTING LLC
490 LAKESIDE DRIVE
DEFUNIAK SPRINGS, FL 32435
CONTACT: (850)-399-1188

No.	Revision/Issue	Date


Project Name and Address
LAMNECK/POOLE RESIDENCE

SHEET TITLE
TYPICAL FOUNDATION & FLOOR FRAMING DETAILS


Project	25-2024	Sheet
Date	05-06-2024	S-2.0
Scale	NTS	




3
S-2.1
TYP. GABLE END ROOF FRAMING DETAIL
SCALE: 3/8" = 1'-0"




4
S-2.1
LAY ON/ GABLE FRAME OVER VALLEY
N.T.S.




5
S-2.1
GABLE END PORCH FRAME
N.T.S.



6
S-2.1
BARGE RAFTER DETAIL @ COLUMN
N.T.S.




7
S-2.1
GABLE END FRONT PORCH FRAME
N.T.S.



8
S-2.1
GABLE END FRONT PORCH FRAME
N.T.S.

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM OR BY ANY MEANS WITHOUT PERMISSION FROM JL ENGINEERING & CONSULTING LLC. JL ENGINEERING & CONSULTING LLC DISCLAIMS ANY RESPONSIBILITY FOR ITS UNAUTHORIZED USE. PRINTED COPIES ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.




JL ENGINEERING & CONSULTING LLC
490 LAKESIDE DRIVE
DEFUNIAK SPRINGS, FL 32435
CONTACT: (850)-399-1188

No.	Revision/Issue	Date

Project Name and Address
LAMNECK/POOLE RESIDENCE

SHEET TITLE
TYPICAL ROOF FRAMING DETAILS


Project 25-2024	Sheet S-2.1
Date 05-06-2024	
Scale NTS	



1
S-3

OPTION 1&2 WALL OPENING W/ HEADER BEARING
SCALE: N.T.S.


WINDOW SILL & LOW HEADER SCHEDULE		
MAX. WIDTH OF OPENING	MIN. MEMBER SIZE	FASTENERS/ CONNECTOR @ EA. END
3'-0"	1 - 2X6	4 - 3"x0.131" TOE NAILS
6'-6"	2 - 2X6	2 - SIMPSON A23 ANGLES (1 TOP, 1 BOTTOM)
9'-6"	2 - 1-3/4" X 5-1/2" LVL	SIMPSON HL35 ANGLEW/(4) 1/2" Ø CARRIAGE BOLTS INTO SILL PL./ LOW HEADER & (4) 3/4"x5" LONG LAG BOLTS INTO KING STUD
12'-0"	3 - 1-3/4" X 5-1/2" LVL	SIMPSON HL35 ANGLEW/(4) 1/2" Ø CARRIAGE BOLTS INTO SILL PL./ LOW HEADER & (4) 3/4"x5" LONG LAG BOLTS INTO KING STUD
> 12'-0"	SEE PLAN OR CONSULT W/ EOR	
NOTE: 1. PROVIDE 2X6 TRIMMER BELOW EA. END OF WINDOW SILL & LOW HEADER. 2. SEE ARCH. DRAWINGS FOR OPENING WIDTH. 3. ALL WINDOW SILL AND LOW HEADER PLIES SHALL BE INSTALLED IN FLAT ORIENTATION.		



2
S-3


TYPICAL ALIGNED OPENING FRAMING
N.T.S.

JACK STUD & CONT. STUD REQUIREMENTS FOR ROUGH OPENINGS (R.O.)						
	UP TO 3'-0" R.O.		3'-1" TO 6'-0" R.O.		6'-0" TO 10'-0" R.O.	
	CONT.	JACK	CONT.	JACK	CONT.	JACK
2X EXTERIOR WALL SINGLE STORY	(2) 2X6	(1) 2X6	(3) 2X6	(2) 2X6	(4) 2X6	(2) 2X6




3
S-3

TYPICAL PORCH BEAM POCKET
N.T.S.




6
S-3

TYPICAL SHEARWALL DETAIL
SCALE: N.T.S.




7
S-3

TYPICAL VERT. & HORIZ. REINFORCING @ CMU WALLS
SCALE: N.T.S.




8
S-3

TYP. CMU FOOTING STEP DETAIL
SCALE: N.T.S.




9
S-3

WALL TOP PLATE SPLICE DETAIL
N.T.S.



10
S-3

THREADED ROD HOLDOWN DETAIL
N.T.S.



11
S-3


ROOF/WALL PANEL SCHEDULE AND NAILING DETAIL
N.T.S.

NAILING SCHEDULE	
JOISTS SITTING ON SILL OR GIRDER	(3) 8d TOENAILS, EACH SIDE
BLOCKING BETWEEN JOISTS/ RAFTERS	(2) 10d TOENAILS, EACH SIDE, EACH END
RIM BLOCKING BETWEEN JOISTS/ RAFTERS	(3) 10d TOENAILS EACH END
TOP PLATE TO STUD	(2) 16d END NAILS
STUD TO SILL PLATE	(2) 16d END NAILS OR (4) 8d TOENAILS
DOUBLE STUDS	(2) 10d @ 12" ON CENTER
DOUBLE TOP PLATES-BETWEEN SPLICE NAILING	16d @ 16" ON CENTER FACE NAILS
DOUBLE TOP PLATES-EA. SIDE OF SPLICED PLATE	(8) 16d
ELEVATED SILL PLATE TO 2X TRUSS RIBBON BOARD OR END WALL TRUSS	10d FACE NAILS @ 6" ON CENTER
BLOCKING TO TOP PLATE	(2) 10d TOENAILS, EACH SIDE
RIM JOIST OR BLOCKING TO TOP PLATE OR SILL PLATE	8d TOENAILS @ 6" ON CENTER
CONT. (2) AND (3) PIECE HEADERS	16d @ 16" ON CENTER ALONG EACH EDGE
BUILT UP CORNER STUDS	16d @ 24" ON CENTER
DECKING BOARDS	(2) #8 2 1/2" ST STEEL SCREWS @ EACH BEARING
CROSS BRIDGING	(2) 10d EACH END
HORIZONTAL BLOCKING BETWEEN WALL STUDS	(2) 10d TOENAILS EACH END

WALL SHEATHING SCHEDULE		
LOCATION	SHEATHING	NAILING
EXTERIOR WALL (TYP.)	1/2" PLYWOOD SHEATHING	10d COMMON NAILS @ 4" ON CENTER (MAX) @ PANEL EDGES & 6" ON CENTER (MAX) FIELD

ROOF DIAPHRAGM SCHEDULE				
LOCATION	SHEATHING	UNSUPPORTED EDGE	FIELD NAILING	EDGE NAILING
ROOF	5/8" APA RATED PLYWOOD	SIMPSON PSC1 19/32 PANEL SHEATHING CLIP OR EQUAL	10d RING SHANK NAILS @ 6" O/C	10d RING SHANK NAILS @ 4" O/C
ROOF OVERHANG	5/8" APA RATED PLYWOOD U.N.O. SEE ELEV FOR FINISHES	N/A	10d RING SHANK NAILS @ 3" O/C	10d RING SHANK NAILS @ 3" O/C

NO PART OF THIS DOCUMENT MAY BE REPRODUCED IN ANY FORM OR BY ANY MEANS WITHOUT PERMISSION FROM JL ENGINEERING & CONSULTING LLC. JL ENGINEERING & CONSULTING LLC DISCLAIMS ANY RESPONSIBILITY FOR ITS UNAUTHORIZED USE. PRINTED COPIES ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



JL ENGINEERING & CONSULTING LLC
490 LAKESIDE DRIVE
DEFUNIAK SPRINGS, FL 32435
CONTACT: (850)-399-1188

No.	Revision/Issue	Date

Project Name and Address
LAMNECK/POOLE RESIDENCE

SHEET TITLE
TYPICAL FOUNDATION & FRAMING DETAILS

Project 25-2024	Sheet S-2.2
Date 05-06-2024	
Scale NTS	