

REVISIONS

SOFTPLAN
ARCHITECTURAL DESIGN SOFTWARE



LEFT ELEVATION
SCALE: 1/4" = 1'-0"



FRONT ELEVATION
SCALE: 1/4" = 1'-0"



RIGHT ELEVATION
SCALE: 1/4" = 1'-0"



REAR ELEVATION
SCALE: 1/4" = 1'-0"

REQUIRED ROOF VENTILATION:
AS PER FLORIDA BUILDING CODE 2309.7

RIDGE VENT
MIN. 50% TOTAL VENT AREA
LOCATED IN THE UPPER PORTION OF ATTIC (MIN. 3' ABOVE EAVE)
2444 S.F. / 300 x 50% = 4.1 S.F. RIDGE VENT AREA REQUIRED
37.3 FEET OF RIDGE VENT REQUIRED

SOFFIT VENT
2444 S.F. / 300 x 50% = 4.1 S.F. SOFFIT VENT AREA REQUIRED
69 FEET OF SOFFIT VENT REQUIRED

BUILDER MUST VERIFY THE FOLLOWING MINIMUM NET FREE VENT AREAS:

1. RIDGE VENTS = 16 IN2/FT (.11 FT2/FT)
2. OFF-RIDGE VENTS = .70 FT2 PER 4' UNIT
3. SOFFIT VENTS = 8.6 IN2/FT (.06 FT2/FT)

WINDLOAD ENGINEER: Mark Disosway,
P.E. No. 53915, P.O. Box 868, Lake City, FL
32056, 386-754-5119

DIMENSIONS:
Stated dimensions/superscale scaled
dimensions. Refrain questions to
Mark Disosway, P.E. for resolution.
Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disosway, P.E. hereby expressly reserves
its common law copyrights and property right in
these instruments of service. This document is
not to be reproduced, altered or copied in any
form or manner without first the express written
permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have
examined this plan, and that the applicable
portions of the plan, relating to wind engineering
comply with section 1608, Florida building code
2001, to the best of my knowledge.

LIMITATION: This design is valid for one
building, at specified location.

MARK DISOSWAY
P.E. 53915

Mark Disosway
1/18/08
SEAL

BUCK WILLIAMS
RESIDENCE

ADDRESS:
353 SW CR240
COLUMBIA COUNTY, FLORIDA

Mark Disosway P.E.
P.O. Box 868
Lake City, Florida 32056
Phone: (386) 754 - 5419
Fax: (386) 269 - 4871
windloadengineer@bellsouth.net

PRINTED DATE:
January 17, 2008

DRAWN BY: CHECKED BY:
Ben Sparks

26767


FINALS DATE
17 / Jan / 08

JOB NUMBER:
#01172

DRAWING NUMBER
A-1


OF 6 SHEETS

| REVISIONS | |
|-----------|--|
| | |
| | |
| | |



TYPICAL DESIGN WALL SECTION
NON - STRUCTURAL DATA

SCALE: 1\"/>



FLOOR PLAN
SCALE: 1/4\"/>

AREA SUMMARY

| | | |
|-------------|------|-------|
| LIVING AREA | 1612 | S. F. |
| PORCH AREA | 832 | S. F. |
| TOTAL AREA | 2444 | S. F. |

WINDLOAD ENGINEER: Mark Discosway,
P.E. No. 53815, P.G. 988, Lake City, FL
32056, 386-754-5119

DIMENSIONS:
Stated dimension supercede scaled
dimensions. Refer all questions to
Mark Discosway, P.E. for resolution.
Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Discosway, P.E. hereby expressly reserves
its common law copyrights and property right in
these instrument(s) of service. This document is
not to be reproduced, altered or copied in any
form or manner without first the express written
permission and consent of Mark Discosway.

CERTIFICATION: I hereby certify that I have
examined this plan, and that the applicable
portions of the plan, relating to wind engineering
comply with section 1606, Florida building code
2001, to the best of my knowledge.

LIMITATION: This design is valid for one
building, at specified location.

MARK DISCOSWAY
P.E. 53815

Mark Discosway
12 JAN 08
SEAL

BUCK WILLIAMS
RESIDENCE

ADDRESS:
353 SW CR240
COLUMBIA COUNTY, FLORIDA

Mark Discosway P.E.
P.O. Box 868
Lake City, Florida 32056
Phone: (386) 754 - 5419
Fax: (386) 269 - 4871
windloadengineer@bellsouth.net

PRINTED DATE:
January 17, 2008

DRAWN BY: Ben Sparks
CHECKED BY:

FINALS DATE:
17 / Jan / 08

JOBNUMBER:
801172


DRAWING NUMBER

A-2

Of 6 SHEETS

REVISIONS

SOFTPLAN
ARCHITECTURAL DESIGN SOFTWARE



ELECTRICAL PLAN NOTES

- E -1 WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS.
- E -2 CONSULT THE OWNER FOR THE NUMBER OF SEPERATE TELEPHONE LINES TO BE INSTALLED.
- E -3 ALL INSTALLATIONS SHALL BE PER NATL. ELECTRIC CODE.
- E -4 ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE, AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS.
- E -5 TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNER'S DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF NEC-LATEST EDITION.
- E -6 ELECTRICAL CONTR SHALL BE RESPONSIBLE FOR THE DESIGN & SIZING OF ELECTRICAL SERVICE AND CIRCUITS.
- E -7 ENTRY OF SERVICE (UNDERGROUND OR OVERHEAD) TO BE DETERMINED BY POWER COMPANY.
- E -8 ALL BEDROOM RECEPTACLES SHALL BE AFCI (ARC FAULT CIRCUIT INTERRUPT)
- E -9 ALL OUTLETS TO BE LOCATED ABOVE BASE FLOOD ELEVATION

ELECTRICAL LEGEND

| | |
|--|--------------------------------------|
| | CEILING FAN (PRE-WIRE FOR LIGHT KIT) |
| | DOUBLE SECURITY LIGHT |
| | 2X4 FLUORESCENT LIGHT FIXTURE |
| | RECESSED CAN LIGHT |
| | BATH EXHAUST FAN WITH LIGHT |
| | BATH EXHAUST FAN |
| | LIGHT FIXTURE |
| | DUPLEX OUTLET |
| | 220v OUTLET |
| | GFI DUPLEX OUTLET |
| | SMOKE DETECTOR |
| | WALL SWITCH |
| | 3 WAY WALL SWITCH |
| | 4 WAY WALL SWITCH |
| | WATER PROOF GFI OUTLET |
| | PHONE JACK |
| | TELEVISION JACK |
| | GARAGE DOOR OPENER |
| | WALL HEATER |

WINDLOAD ENGINEER: Mark Disoway,
PE No. 53915, POB 68, Lake City, FL
32066, 386-754-0471

DIMENSIONS:
Stated dimensions are per code scaled dimensions. Refer a questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with section 609, Florida building code 2001, to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

MARKDISOWAY
P.E. 53915

Mark Disoway
TRANSD
SEAL

BUCK WILLIAMS RESIDENCE

ADDRESS:
35235W CR240
COLUMBIA COUNTY, FLORIDA

Mark Disoway P.E.
P.O. Box 868
Lake City, Florida 32056
Phone: (386) 754 - 5419
Fax: (386) 269 - 4871
windloadengineer@bellsouth.net

PRINTED DATE:
January 17, 2008


DRAWN BY: Ben Sparks
CHECKED BY:

FINALS DATE:
17 / Jan / 08

JOB NUMBER:
801172

DRAWING NUMBER
A-3


OF 3 SHEETS




ONE STORY WALL SECTION
SCALE: 3/4" = 1'-0"

EXTERIOR WALL STUD TABLE FOR SPF #2 STUDS

| | |
|------------------|------------------------|
| (1) 2x4 @ 16" OC | TO 10'-0" WALL HEIGHT |
| (1) 2x4 @ 12" OC | TO 13'-0" WALL HEIGHT |
| (1) 2x6 @ 16" OC | TO 18'-10" WALL HEIGHT |
| (1) 2x6 @ 12" OC | TO 20'-0" WALL HEIGHT |




BEAM MID-WALL CONNECTION DETAIL
SCALE: N.T.S.




BEAM CORNER CONNECTION DETAIL
SCALE: N.T.S.

SUPPORTIVE CENTER POST TO BEAM DETAIL
SCALE: N.T.S.



TYPICAL PORCH POST DETAIL
SCALE: 1/2" = 1'-0"



TYPICAL GABLE END (X-BRACING)

ALL MEMBERS SHALL BE SYP

ANCHOR TABLE

OBTAIN UPLIFT REQUIREMENTS FROM TRUSS MANUFACTURER'S ENGINEERING

| UPLIFT LBS. SYP | UPLIFT LBS. SPF | TRUSS CONNECTOR* | TO PLATES | TO RAFTER/TRUSS | TO STUDS |
|-------------------------------|-----------------|-----------------------|------------------|-----------------|-----------------------------------|
| < 420 | < 245 | H5A | 3-8d | 3-8d | |
| < 455 | < 265 | H5 | 4-8d | 4-8d | |
| < 360 | < 235 | H4 | 4-8d | 4-8d | |
| < 455 | < 320 | H3 | 4-8d | 4-8d | |
| < 415 | < 365 | H2.5 | 5-8d | 5-8d | |
| < 600 | < 535 | H2.5A | 5-8d | 5-8d | |
| < 950 | < 820 | H8 | 8-8d | 8-8d | |
| < 745 | < 565 | H8 | 5-10d, 1 1/2" | 5-10d, 1 1/2" | |
| < 1465 | < 1050 | H14-1 | 13-8d | 12-8d, 1 1/2" | |
| < 1465 | < 1050 | H14-2 | 15-8d | 12-8d, 1 1/2" | |
| < 990 | < 850 | H10-1 | 8-8d, 1 1/2" | 8-8d, 1 1/2" | |
| < 1470 | < 1265 | H10-2 | 6-10d | 6-10d | |
| < 1470 | < 1265 | H16-1 | 10-10d, 1 1/2" | 2-10d, 1 1/2" | |
| < 1470 | < 1265 | H16-2 | 10-10d, 1 1/2" | 2-10d, 1 1/2" | |
| < 1000 | < 860 | MTS24C | 7-10d 1 1/2" | 7-10d 1 1/2" | |
| < 1450 | < 1245 | HTS24 | 12-10d 1 1/2" | 12-10d 1 1/2" | |
| < 2900 | < 2490 | 2 - HTS24 | | | |
| < 2050 | < 1785 | LG12 | 14 - 16d | 14 - 16d | |
| HEAVY GIRDER TIEDOWNS* | | | | | TO FOUNDATION |
| < 3965 | < 3330 | MGT | | 22 - 10d | 1-5/8" THREADED ROD 12" EMBEDMENT |
| < 10890 | < 6485 | HGT-2 | | 16 - 10d | 2-5/8" THREADED ROD 12" EMBEDMENT |
| < 10530 | < 9035 | HGT-3 | | 16 - 10d | 2-5/8" THREADED ROD 12" EMBEDMENT |
| < 9250 | < 9250 | HGT-4 | | 16 - 10d | 2-5/8" THREADED ROD 12" EMBEDMENT |
| STUD STRAP CONNECTOR* | | | | | TO STUDS |
| < 435 | < 435 | SSP DOUBLE TOP PLATE | 3 - 10d | | 4 - 10d |
| < 455 | < 420 | SSP SINGLE SILL PLATE | 1 - 10d | | 4 - 10d |
| < 825 | < 825 | DSP DOUBLE TOP PLATE | 6 - 10d | | 8 - 10d |
| < 825 | < 600 | DSP SINGLE SILL PLATE | 2 - 10d | | 8 - 10d |
| < 885 | < 760 | SP4 | | | 6-10d, 1 1/2" |
| < 1240 | < 1065 | SPH4 | | | 10-10d, 1 1/2" |
| < 885 | < 760 | SP6 | | | 6-10d, 1 1/2" |
| < 1240 | < 1065 | SPH6 | | | 10-10d, 1 1/2" |
| < 1235 | < 1165 | LST18 | 14 - 10d | | |
| < 1235 | < 1235 | LST21 | 16 - 10d | | |
| < 1030 | < 1030 | CS20 | 16 - 8d | | |
| < 1705 | < 1705 | CS16 | 28 - 8d | | |
| STUD ANCHORS* | | | | | TO STUDS |
| < 1350 | < 1305 | LTT19 | 8 - 16d | | 12" AB |
| < 2310 | < 2310 | LTT131 | 16 - 10d, 1 1/2" | | 12" AB |
| < 2775 | < 2570 | HD2A | 2-5/8" BOLTS | | 5/8" AB |
| < 4175 | < 3695 | HTT16 | 18 - 16d | | 5/8" AB |
| < 1400 | < 1400 | PHM242 | 16 - 16d | | |
| < 3335 | < 3335 | HPMH222 | 16 - 16d | | |
| < 2200 | < 2200 | ABU44 | 12 - 16d | | 12" AB |
| < 2300 | < 2300 | ABU66 | 12 - 16d | | 12" AB |
| < 2320 | < 2320 | ABU88 | 18 - 16d | | 2-5/8" AB |
| STUD ANCHORS* | | | | | TO FOUNDATION |


GRADE & SPECIES TABLE

| | | Fb (psi) | E (10 ⁶ psi) |
|------|--------------|----------|-------------------------|
| 2x8 | SYP #2 | 1200 | 1.8 |
| 2x10 | SYP #2 | 1050 | 1.6 |
| 2x12 | SYP #2 | 975 | 1.6 |
| GLB | 24F-V3 SP | 2400 | 1.8 |
| LSL | TIMBERSTRAND | 1700 | 1.7 |
| LVL | MICROLAM | 2900 | 2.0 |
| PSL | PARALAM | 2900 | 2.0 |

2x6 SYP #2 GARAGE DOOR BUCK ATTACHMENT

ATTACH GARAGE DOOR BUCK TO STUD PACK AT EACH SIDE OF DOOR OPENING WITH 3/8" LAG SCREWS w/ 1" WASHER LAG SCREWS MAY BE COUNTERSUNK. HORIZONTAL JAMBS DO NOT TRANSFER LOAD. CENTER LAG SCREWS OR STAGGER 16d NAILS OR (2) ROWS OF .131 x 3 1/4" ON PER TABLE BELOW:

| DOOR WIDTH | 3/8" x 4" LAG | 16d STAGGER | (2) ROWS OF .131 x 3 1/4" GN |
|------------|---------------|-------------|------------------------------|
| 8' - 10' | 24" O.C. | 5" O.C. | 5" O.C. |
| 11' - 15' | 18" O.C. | 4" O.C. | 4" O.C. |
| 16' - 18' | 16" O.C. | 3" O.C. | 3" O.C. |



GARAGE DOOR BUCK INSTALLATION DETAIL
SCALE: N.T.S.

GENERAL NOTES:

TRUSSES: TRUSSES SHALL BE DESIGNED BY A FLORIDA LICENSED ENGINEER IN ACCORDANCE WITH THE FBC 2001. TRUSS ENGINEERING SHALL INCLUDE TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND ALL BEARING LOCATIONS. TRUSS ENGINEERING IS THE RESPONSIBILITY OF THE TRUSS MANUFACTURER AND SHALL BE SIGNED & SEALED BY THE MANUFACTURER'S DESIGN ENGINEER. IT IS THE BUILDER'S RESPONSIBILITY TO VERIFY THE TRUSS DESIGNER HAS SATISFIED ALL THE ABOVE REQUIREMENTS AND TO SELECT UPLIFT CONNECTIONS BASED ON TRUSS ENGINEERING UPLIFT AND PROVIDE FOOTINGS FOR INTERIOR BEARING WALLS. BUILDER IS TO FURNISH TRUSS ENGINEERING TO WIND LOAD ENGINEER FOR REVIEW OF TRUSS REACTIONS ON THE BUILDING STRUCTURE. STRAP 2x6 RAFTERS WITH MIN UPLIFT CONNECTION 415LB EACH END, 2x8 RAFTERS 700 LB EACH END.

SITE PREPARATION: SITE ANALYSIS AND PREPARATION IS NOT PART OF THIS PLAN

FOUNDATION: CONFIRM THAT THE FOUNDATION DESIGN & SITE CONDITIONS MEET GRAVITY LOAD REQUIREMENTS (ASSUME 1000 PSF BEARING CAPACITY UNLESS VISUAL OBSERVATION OR SOILS TEST PROVES OTHERWISE)

CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS, F_c = 3000 PSI

WELDED WIRE REINFORCED SLAB: 6" x 6" W1 x 4 W1.4 FB = 85KSI, WELDED WIRE REINFORCEMENT FABRIC (W1.4) CONFORMING TO ASTM A601, LOCATED IN MIDDLE OF THE SLAB, SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACINGS NOT TO EXCEED 3'.

FIBER CONCRETE SLAB: CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT. FIBER LENGTH 1/2 INCH TO 2 INCHES. DOSAGE AMOUNTS FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD PER THE MANUFACTURER'S RECOMMENDATIONS. FIBERS TO COMPLY WITH ASTM C 1115. SUPPLIER TO PROVIDE ASTM C 1116 CERTIFICATION OF COMPLIANCE WHEN REQUESTED BY BUILDING OFFICIAL.

CONTROL JOINTS: WHERE SPECIFIED, SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 308. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. THE LENGTH / WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1.5 AND TYPICAL SPACING OF CUTS TO BE 12FT. DO NOT CUT W/M OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)

REBAR: ASTM A 615, GRADE 60, DEFORMED BARS, F_y = 60 KSI. ALL LAP SPLICES 48" DB (30" FOR #5 BARS); UNO. ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH ACI 315-96, U.N.O.

GLULAM BEAMS: GLULAM BEAM, GLB, 24F-V3SP, F_b = 2400psi, E = 1800ksi; UNO. SUPPLIER MAY SUPPLY AN ALTERNATE BEAM WITH EQUAL PROPERTIES OR MAY SUBMIT THEIR OWN SIZING CALCULATIONS.

ROOF SHEATHING: ALL ROOFERS HORIZONTAL DIAPHRAGMS, 7/16" OSB SHEATHING, UNLOCKED, APPLIED PERPENDICULAR TO FRAMING, OVER A MINIMUM OF 3 FRAMING MEMBERS, WITH PANEL EDGES STAGGERED, FASTENED WITH 8d COMMON NAILS (131), 6"OC PANEL EDGES, 12"OC INTERMEDIATE MEMBERS, GABLE ENDS AND DIAPHRAGM BOUNDARY, 4"OC, UNO.

STRUCTURAL CONNECTORS: MANUFACTURERS AND PRODUCT NUMBER FOR CONNECTORS, ANCHORS, AND REINFORCEMENT ARE LISTED FOR EXAMPLE NOT ENDORSEMENT, AN EQUIVALENT DEVICE OF THE SAME OR OTHER MANUFACTURER CAN BE SUBSTITUTED FOR ANY DEVICES LISTED IN THE EXAMPLE TABLES AS LONG AS IT MEETS THE REQUIRED LOAD CAPACITIES, MANUFACTURER'S INSTALLATION INSTRUCTIONS MUST BE FOLLOWED TO ACHIEVE RATED LOADS.

ANCHOR BOLTS: A 3/8" ANCHOR BOLTS WITH MINIMUM EMBEDMENT AS SPECIFIED IN DRAWINGS BUT NO LESS THAN 7" IN CONCRETE OR REINFORCED BOND BEAM OR 15" IN GRAVELLED CMU.

WASHERS: WASHERS USED WITH 1/2" BOLTS TO BE 2" x 3/8", WITH 5/8" BOLTS TO BE 3" x 3/8" x 9/64", WITH 3/4" BOLTS TO BE 3" x 3/8" x 9/64", WITH 7/8" BOLTS TO BE 3" x 3/8" x 5/16", UNO.

NAILS: ALL NAILS ARE COMMON NAILS UNLESS OTHERWISE SPECIFIED OR ACCEPTED BY FBC TEST REPORTS AS HAVING EQUAL STRUCTURAL VALUES.

BUILDER'S RESPONSIBILITY

THE BUILDER AND OWNER ARE RESPONSIBLE FOR THE FOLLOWING, WHICH ARE SPECIFICALLY NOT PART OF THE WIND LOAD ENGINEER'S SCOPE OF WORK.

CONFIRM SITE CONDITIONS, FOUNDATION BEARING CAPACITY, GRADE AND BACKFILL HEIGHT, WIND SPEED AND DEBRIS ZONE, AND FLOOD ZONE.

PROVIDE MATERIALS AND CONSTRUCTION TECHNIQUES, WHICH COMPLY WITH FBC 2001 REQUIREMENTS FOR THE STATED WIND VELOCITY AND DESIGN PRESSURES.

PROVIDE A CONTINUOUS LOAD PATH FROM TRUSSES TO FOUNDATION. IF YOU BELIEVE THE PLAN OMMITS A CONTINUOUS LOAD PATH CONNECTION, CALL THE WIND LOAD ENGINEER IMMEDIATELY.

VERIFY THE TRUSS MANUFACTURER'S SEALED ENGINEERING INCLUDES TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS.

ROOF SYSTEM DESIGN


THE SEAL ON THESE PLANS FOR COMPLIANCE WITH FBC 2001, SECTION 1606 IS BASED ON REACTIONS, UPLIFTS, AND BEARING LOCATIONS IN TRUSS ENGINEERING SUBMITTED TO THE WIND LOAD ENGINEER. IT IS THE RESPONSIBILITY OF THE BUILDER TO CHECK ALL DETAILS OF THE COMPLETE ROOF SYSTEM DESIGN SUBMITTED BY THE TRUSS MANUFACTURER AND HAVE IT SIGNED, AND SEALED BY A DESIGN PROFESSIONAL FOR CORRECT APPLICATION OF FBC 2001 REQUIRED LOADS AND ANY SPECIAL LOADS. THE BUILDER IS RESPONSIBLE TO REVIEW EACH INDIVIDUAL TRUSS MEMBER AND THE TRUSS ROOF SYSTEM AS A WHOLE AND TO PROVIDE RESTRAINT FOR ANY LATERAL BRACING. THE BUILDER SHOULD USE CARE CHECKING THE ROOF DESIGN BECAUSE THE WIND LOAD ENGINEER IS SPECIFICALLY NOT RESPONSIBLE FOR THE TRUSS LAYOUT WHICH WAS CREATED BY THE TRUSS MANUFACTURER AND THE TRUSS DESIGNER. ALSO DENIES RESPONSIBILITY FOR THE LAYOUT PER NOTES ON THEIR SEALED TRUSS SHEETS.

DESIGN DATA

| WIND LOADS PER FLORIDA BUILDING CODE 2001, SECTION 1606.2 | |
|--|--|
| (ENCLOSED SIMPLE DIAPHRAGM BUILDINGS WITH FLAT, HIPPED, OR GABLE ROOFS; MEAN ROOF HEIGHT NOT EXCEEDING LEAST HORIZONTAL DIMENSION OR 60 FT; NOT ON UPPER HALF OF HILL OR ESCARPMENT 60FT IN EXP. B, 30FT IN EXP. C AND >10% SLOPE AND UNOBSTRUCTED UPWIND FOR 50x HEIGHT OR 1 MILE WHICHEVER IS LESS.) | |
| BUILDING IS NOT IN THE HIGH VELOCITY HURRICANE ZONE | |
| BUILDING IS NOT IN THE WIND-BORNE DEBRIS REGION | |
| 1.) BASIC WIND SPEED = 110 MPH | |
| 2.) WIND EXPOSURE = B | |
| 3.) WIND IMPORTANCE FACTOR = 1.0 | |
| 4.) BUILDING CATEGORY = II | |
| 5.) ROOF ANGLE = 10-45 DEGREES | |
| 6.) MEAN ROOF HEIGHT = <30 FT | |
| 7.) INTERNAL PRESSURE COEFFICIENT = N/A (ENCLOSED BUILDING, 1606.2) | |
| 8.) COMPONENTS AND CLADDING DESIGN WIND PRESSURES (FBC TABLE 1606.2 B&C) | |

| Zone | Effective Wind Area (ft ²) |
|--------|--|
| 1 | 19.9 - 21.8 |
| 2 | 19.9 - 25.5 |
| 2 0thg | -40.6 |
| 3 | 19.9 - 25.5 |
| 3 0thg | -68.3 |
| 4 | 21.8 - 23.6 |
| 5 | 21.8 - 29.1 |

| | |
|--|-------------|
| Doors & Windows | 21.8 - 29.1 |
| Worst Case (Zone 5, 10 ft ²) | |
| 8x7 Garage Door | 19.5 - 22.9 |
| 16x7 Garage Door | 18.5 - 21.0 |



| DESIGN LOADS | |
|---------------------------------------|--|
| FLOOR | 40 PSF (ALL OTHER DWELLING ROOMS) |
| | 30 PSF (SLEEPING ROOMS) |
| | 30 PSF (ATTICS WITH STORAGE) |
| | 10 PSF (ATTICS WITHOUT STORAGE, <3:12) |
| ROOF | 20 PSF (FLAT OR <4:12) |
| | 16 PSF (4:12 TO <12:12) |
| | 12 PSF (12:12 AND GREATER) |
| STAIRS | 40 PSF (ONE & TWO FAMILY DWELLINGS) |
| | SOIL BEARING CAPACITY 1000PSF |
| NOT IN FLOOD ZONE (BUILDER TO VERIFY) | |

REVISIONS

| NO. | DESCRIPTION |
|-----|-------------|
| | |
| | |
| | |



WINDLOAD ENGINEER: Mark Disoway, P.E. 53915, FDB 868, Lake City, FL 32066, 386-7545419

DIMENSIONS: Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disoway P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disoway P.E. hereby expressly reserves its common law copyright and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with section 1606, Florida building code 2001, to the best of my knowledge.

LIMITATION: The design is valid for one building, at specified location.

MARK DISOWAY
P.E. 53915

SEAL

BUCK WILLIAMS RESIDENCE

ADDRESS:
323 SW CR240
COLUMBIA COUNTY, FLORIDA

MarkDisoway P.E.
P.O. Box 868
Lake City, Florida 32056
Phone: (386) 754 - 5419
Fax: (386) 269 - 4871
windloadengineer@bellsouth.net

PRINTED DATE:
January 17, 2008

DRAWN BY:
Ben Sparks

CHECKED BY:

FINALS DATE:
17 / Jan / 08

JOB NUMBER:
801172


DRAWING NUMBER

S-1


4# 6 SHEETS

| REVISIONS | |
|-----------|--|
| | |
| | |
| | |
| | |


SOFTPLAN
 ARCHITECTURAL DESIGN SOFTWARE




F9 S-2 STEM WALL FOOTING
 SCALE: 1/2" = 1'-0"



F12 S-2 ALT. STEM WALL PORCH FOOTING
 SCALE: 1/2" = 1'-0"



F2 S-2 INTERIOR BEARING FOOTING
 SCALE: 1/4" = 1'-0"



FOUNDATION PLAN
 SCALE: 1/4" = 1'-0"
 DIMENSIONS ON STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS

WINDLOAD ENGINEER: Mark Discoway,
 PE No. 53915, PG 866, Lake City, FL
 32056, 386-754-919

DIMENSIONS:
 Stated dimension supercede scaled
 dimensions. Refer all questions to
 Mark Discoway, P.E. for resolution.
 Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
 Mark Discoway, P.E. hereby expressly reserves
 its common law copyrights and property right in
 these instrumented services. This document is
 not to be reproduced, altered or copied in any
 form or manner without first the express written
 permission and consent of Mark Discoway.

CERTIFICATION hereby certify that I have
 examined this plan, and that the applicable
 portions of the plan, relating to wind engineering
 comply with section 1606, Florida building code
 2001, to the best of my knowledge.

LIMITATION: This design is valid for one
 building, at specified location.

MARK DISCOWAY
 P.E. 53915
Mark Discoway
 F. Jan 08
 SEAL

BUCK WILLIAMS
RESIDENCE

ADDRESS:
 353 SW CR240
 COLUMBIA COUNTY, FLORIDA

Mark Discoway P.E.
 P.O. Box 868
 Lake City, Florida 32056
 Phone: (866) 754 - 5419
 Fax: (366) 269 - 4871
 windloadengineer@bellsouth.net

PRINTED DATE:
 January 17, 2008
 DRAWN BY: Ben Sparks
 CHECKED BY:

FINALS DATE
 17 / Jan / 08


JOB NUMBER:
 01172

DRAWING NUMBER
S-2
 OF 6 SHEETS

REVISIONS

| | |
|--|--|
| | |
| | |
| | |
| | |

SCFPLAN
ARCHITECTURAL DESIGN SOFTWARE



STRUCTURAL PLAN
SCALE: 1/4" = 1'-0"

STRUCTURAL PLAN NOTES

- SN-1 ALL LOAD BEARING FRAME WALL & PORCH HEADERS SHALL BE A MINIMUM OF (2) 2X12 SYP#2 (U.N.O.)
- SN-2 ALL LOAD BEARING FRAME WALL HEADERS SHALL HAVE (1) JACK STUD & (1) KING STUD EACH SIDE (U.N.O.)
- SN-3 DIMENSIONS ON STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS
- SN-4 PERMANENT TRUSS BRACING IS TO BE INSTALLED AT LOCATIONS AS SHOWN ON THE SEALED TRUSS DRAWINGS. LATERAL BRACING IS TO BE RESTRAINED PER BCSI-03. BCSI-B1, BCSI-B2, & BCSI-B3. BCSI-B1, BCSI-B2, & BCSI-B3 ARE FURNISHED BY THE TRUSS SUPPLIER, WITH THE SEALED TRUSS PACKAGE

WALL LEGEND

| | |
|------------|--|
| SWS = 0.0' | 1ST FLOOR EXTERIOR WALL |
| SWS = 0.0' | 2ND FLOOR EXTERIOR |
| IBW | 1ST FLOOR INTERIOR BEARING WALLS SEE DETAILS ON SHEET S-1 |
| IBW | 2ND FLOOR INTERIOR BEARING WALLS SEE DETAILS ON SHEET S-1 |

THREADED ROD LEGEND

- INDICATES LOCATION OF:
1ST FLOOR 1/2" A307 ALL THREADED ROD
- INDICATES LOCATION OF:
2ND FLOOR 1/2" A307 ALL THREADED ROD

TOTAL SHEAR WALL SEGMENTS

| | | |
|--------------|----------|--------|
| | REQUIRED | ACTUAL |
| TRANSVERSE | 38.5' | 44.5' |
| LONGITUDINAL | 32.5' | 71.0' |

HEADER LEGEND

- (2) 2X12X0', 1J 1K — HEADER/BEAM CALL-OUT (U.N.O.)
- NUMBER OF KING STUDS (FULL LENGTH)
- NUMBER OF JACK STUDS (UNDER HEADER)
- SPAN OF HEADER
- SIZE OF HEADER MATERIAL
- NUMBER OF PLIES IN HEADER

CONNECTIONS, WALL & HEADER DESIGN IS BASED ON REACTIONS & UPLIFTS FROM TRUSS ENGINEERING FURNISHED BY BUILDER. BUILDERS FIRST SOURCE (JOB #LL121209)

WINDLOAD ENGINEER: Mark Disosway,
P.E. No. 53915, 378 865, Lake City, FL
32056, 386-754519

DIMENSIONS:
Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disosway P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disosway P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with section 1606, Florida building code 2001, to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

MARK DISOSWAY
P.E. 53915

SEAL

BUCK WILLIAMS
RESIDENCE

ADDRESS:
323 SW CR240
COLUMBIA COUNTY, FLORIDA

Mark Disosway P.E.
P.O. Box 868
Lake City, Florida 32056
Phone: (386) 754 - 5419
Fax: (386) 269 - 4871
windloadengineer@bellsouth.net

PRINTED DATE:
January 17, 2008

DRAWN BY:
Ben Sparks

CHECKED BY:

FINALS DATE:
17 / Jan / 08

JOB NUMBER:
801172

DRAWING NUMBER

S-3

(OF 6 SHEETS)