

BUILDING SYSTEM DESIGN CRITERIA Loads Applied in Accordance with the 2004 FLORIDA BUILDING CODE			
ORDER NO. 226650	DATE 11/07/05		
REVISION 0			
BUILDING(S)	A		
DESIGN LOCALE	COLUMBIA CO., FL		
LIVE LOAD FRAME	12 PSF		
ROOF	20 PSF		
WIND VELOCITY	110 M MPH (3 SECOND GUST)	1.0	
	IMPORTANCE FACTOR	B	
	EXPOSURE	ENCLOSED	
	INTERNAL PRESSURE COEFFICIENT	+/- 0.18	
	COLLATERAL COMPONENT and CLADDING PRESSURE	23.6 PSF	
DEAD LOAD	The weight of the metal building components as it occurs.		
COLLATERAL LOADS UNIFORM LOAD	2.0 PSF		
CONCENTRATED LOAD	See Drawings for Magnitude and		

BUILDING INFORMATION

SYSTEM: 1	AREA: A		
TYPE	GET	ROOF PANEL	"PBR"
SLOPE	2:12	FRONT WALL PANEL	"PBR"
WIDTH	70'-0"	BACK WALL PANEL	"PBR"
HEIGHT	19'-0"	LEFT WALL PANEL	"PBR"
LENGTH	100'-0"	RIGHT WALL PANEL	"PBR"

TABLE OF CONTENTS

TITLE SHEET DRAWINGS .....	T1
ANCHOR BOLT DRAWINGS .....	A1
PROJECT DESIGN DATA .....	PD1
ERECTION DRAWINGS .....	E1 - E6
DETAILS/SECTIONS DRAWINGS .....	D1
REFERENCE DRAWINGS	

GENERAL INFORMATION Version 2000	
Care of Material, Pg.1	RG0101-0
Care of Material, Pg.2	RG0102-0
Fastener Identification	RG0103-0
Bolt & Nut Identification	RG0104-1
Pop Rivet Locations, Pg.1	RG0105-0
Pop Rivet Locations, Pg.2	RG0106-0
Pop Rivet Locations, Pg.3	RG0107-0
Dealer Responsibilities	RG0108-0

PBR ROOF SYSTEM	
Gable Standard Construction	RR0101-1

PBR ROOF EAVE AND RAKE	
Low Eave Trim Installation	RR0301-0
Rake Trim Installation	RR0303-1
Eave Gutter Installation	RR0304-2
Roll Formed Downspouts Pg.1	RR0305-0
Roll Formed Downspouts Pg.2	RR0306-0

WALL SYSTEM PBR,PBA,PBX,PBU Panel	
Sidewall Panel Installation	RW0101-1
Endwall Panel Installation	RW0102-1
Panel Base Installation	RW0103-1
Corner and Side Trim Installation	RW0104-1

WALK DOORS PBR,PBA,PBX Panel	
3070 & 4070 Walk Door Installation	RW0201-0
Walk Door Framing	RW0203-1
Walk Door Trim	RW0204-0

WALL F.O. PBR,PBA,PBX,PBU Panel	
Framed Opening Types	RM0101-0
Connection Details, Pg.1	RM0102-0
Connection Details, Pg.2	RM0103-0
Trim Details	RM0104-1

ROOF ACCESSORIES

EAVE GUTTER

AT FRONT AND BACK WALLS

WALL ACCESSORIES

WALK DOORS PBR,PBA or PBX Panel

6 3070WH Cylinder, Solid, 110 mph Rated

FRAMED OPENNING

4 ZFO type# 2, 6'- 4 x 7'- 2 - A @ Front  
4 ZFO type# 4, 5' x 5' - B @ Front  
2 ZFO type# 1 & 6 5' x 5' - C @ Front  
2 ZFO type# 2, 10' x 10' - D @ Back  
1 ZFO type# 6, 4' x 4' - E @ Left  
1 ZFO type# 2, 16' x 14' - F @ Left  
1 ZFO type# 6, 4' x 4' - G @ Right  
1 ZFO type# 2, 14' x 14' - H @ Right

General Notes

1. THE ERECTION DRAWING PACKAGE MAY CONSIST OF ERECTION DRAWINGS, DETAIL SHEETS, REFERENCE DRAWINGS, REFERENCE MANUALS, THIS TITLE SHEET DRAWING AND A BILL OF MATERIALS.
2. ALL DRAWINGS ARE TO BE USED IN CONJUNCTION WITH EACH OTHER. IF CONFLICTS OCCUR THE ERECTION DRAWINGS SHALL TAKE PRECEDENCE.

Abbreviations

BLDG = BUILDING	BEF = BEARING END FRAME	GA = GAUGE
SW = SIDEWALL	FEF = FULL END FRAME	UN = UNLESS NOTED
EW = ENDWALL	BUE = BUILT-UP END FRAME	psf = POUNDS PER SQUARE FOOT
FW = FRONT WALL	SL = STEEL LINE	mph = MILES PER HOUR
BW = BACK WALL	BL = BASE LINE	kip = 1000 POUNDS
LW = LEFT WALL	RL = RIDGE LINE	

Symbols

RW = RIGHT WALL	○ GRID LINE	◇ REFERENCES TO A DETAIL FOUND ON THE "DETAIL SHEETS"
BES = BOTTOM OF EAVESTRUT (LOW SIDE)	○ PARTITION COLUMN LINE OR FLOOR COLUMN LINE	
BEH = BOTTOM OF EAVESTRUT (HIGH SIDE)		

Design Certification

These drawings and the metal building they represent are the product of MESCO Building Solutions, (P.O. Box 93629, Southlake, Texas 76092, 817-488-8511). The engineer whose seal appears hereon is employed by MESCO Building Solutions and is not the Engineer of Record. The structural design of the building systems meets the specifications including the design criteria, design loads and serviceability requirements incorporated by the buyer into the order documents. MESCO's engineer is not responsible for observation or inspection of the erection of the building system and is not acting as the prime design professional for the construction project utilizing this building system. The information required to integrate the building system into the construction project is given in the Project Design Data.

Customer Service "Notice"

In the event of fabrication or design problems, shortages of material, damaged or wrong material customer services is available to assist you. Should one of these problems occur contact our customer service department at the numbers listed below. When contacting us please refer to the "Job Number" shown in the lower right hand corner of this sheet.

Customer Service: Telephone 1-800-556-3726  
or Fax 817-329-2346

Note: In order to receive reimbursement of costs, customer service must approve cost of materials or field work prior to procurement of materials or to work being performed. See the truck copy of the erection drawing package for further information and for sample forms of authorization to perform field work.

Special Notice for Buildings with GRAY PRIMER:

When Gray Primer is specified the customer is reminded that Gray Primer is intended as a PRIMER and that it should have minimal exposure to atmospheric conditions. The customer should also be reminded of the potential aesthetic issues that are specifically associated with Gray Primers such as: 1) Gray Primer will show rust spots/streaks due to imperfections in the application process and the properties associated with Gray Primers and 2) Abrasions caused by handling, loading, shipping, unloading, and during the erection process are unavoidable. As a result any rusting or abrasions on members with Gray Primer are NOT subject to customer rejection or claim for touch up to Mesco Building Solutions

DRAWING ISSUE HISTORY					
NO.	DATE	DESCRIPTION	DET	CKR	ENG
0	11/07/05	ISSUED FOR CONSTRUCTION	MJP	CBS	JAA



Mesco Building Solutions

P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326



Buyer:  
Simque Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Site Location:  
LAKE CITY FL.

Job Number  
22-6650

Drawing Issue  
0

Sheet Number  
T1 of 1

DRAWING STATUS:

"FOR CONSTRUCTION "

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.

The engineer whose seal appears hereon is employed by the Building Manufacturer and is NOT the Engineer of Record for the overall Project.



**SITE PREPARATION:** SITE ANALYSIS AND PREPARATION ARE NOT PART OF THIS PLAN AND ARE RESPONSIBILITY OF THE OWNER. SITE INSPECTION BY BUILDER OR BUILDING OFFICIAL SHALL DETERMINE IF THERE IS ANY EVIDENCE OF UNSUITABLE BEARING MATERIALS. IF THERE IS ANY QUESTION, CALL A GEOTECHNICAL ENGINEER TO ASSURE THAT EXPANDING CLAYS AND OTHER PROBLEMATIC SOIL CONDITIONS DO NOT EXIST OR TO ALLOW MITIGATION SHOULD THEY EXIST. ALL FILL UNDER STRUCTURAL ELEMENTS SHALL BE CLEAN SAND/SOIL FILL, FREE FROM DEBRIS AND ORGANIC MATERIALS COMPACTED TO 95% OF MAXIMUM DRY BEARING CAPACITY, IN LIFTS OF NOT MORE THAN 6 INCHES. IT IS THE OWNER'S/BUILDERS RESPONSIBILITY TO VERIFY EXISTING SOIL AND CLEAN FILL ARE COMPACTED STABLE SOIL CONDITIONS WITH 1000 PSF BEARING CAPACITY OR TO REQUEST FOUNDATION DESIGN BASED ON ACTUAL SITE CONDITIONS.

**FOUNDATION:** THE OWNER HAS NOT YET PROVIDED A GEOTECHNICAL REPORT TO THE ENGINEER. ASSUMED SAFE BEARING CAPACITY OF 2000 PSF SHALL BE APPROVED BY THE OWNER. FOOTINGS AND SLAB ARE TO BEAR ON FIRM UNDISTURBED EARTH OR CLEAN SAND/SOIL FILL, FREE FROM DEBRIS AND ORGANIC MATERIALS COMPACTED IN LIFTS OF NOT MORE THAN 6 INCHES. WHERE UNACCEPTABLE MATERIAL OCCURS, EXCAVATE AND REPLACE WITH ENGINEERED FILL. FOUNDATION WORK MUST BE COORDINATED WITH UNDERGROUND UTILITIES. FOOTINGS SHALL BE LOWERED WHERE REQUIRED TO AVOID UTILITIES. TO MINIMIZE WEATHERING, THE LAST 6 INCHES OF EXCAVATION FOR ALL FOOTINGS SHALL BE MADE IMMEDIATELY PRIOR TO PLACEMENT OF FOOTINGS.

**CONCRETE:** MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS SHALL BE  $F_c = 3000$  PSI. WHERE EXCESS WATER IS ADDED TO THE CONCRETE SO THAT ITS SERVICEABILITY IS DEGRADED, THE ATTAINMENT OF REQUIRED STRENGTH SHALL NOT RELEASE THE CONTRACTOR FROM PROVIDING SUCH MODIFICATIONS AS MAY BE REQUIRED BY THE ENGINEER TO PROVIDE A SERVICEABLE MEMBER OR SURFACE. ALL CONCRETE SHALL BE VIBRATED. NO REPAIR OR RUBBING OF CONCRETE SURFACES SHALL BE MADE PRIOR TO INSPECTION BY AND APPROVAL OF THE ENGINEER, OWNER, OR HIS REPRESENTATIVE.

**FIBER CONCRETE SLAB:** CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT. FIBER LENGTHS SHALL BE 1/2 INCH TO 2 INCHES IN LENGTH. DOSAGE AMOUNTS SHALL BE FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. SYNTHETIC FIBERS SHALL COMPLY WITH ASTM C 1116. THE MANUFACTURER OR SUPPLIER SHALL PROVIDE CERTIFICATION OF COMPLIANCE WITH ASTM C 1116 WHEN REQUESTED BY THE BUILDING OFFICIAL.

**WELDED WIRE REINFORCED SLAB:** 6"x6" W1.4xW1.4, FB = 85KSI, WELDED WIRE REINFORCEMENT FABRIC (W.W.M.) CONFORMING TO ASTM A185; LOCATED IN THE MIDDLE OF THE SLAB; SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACING NOT TO EXCEED 3'.

**REBAR:** ASTM A 615, GRADE 60, REINFORCED BARS,  $F_y = 60$  KSI. ALL LAP SPLICES 40" DB (30" FOR #5 BARS); UNO. ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH ACI 315-95 UNLESS NOTED OTHERWISE. ALL TENSION DEVELOPMENT LENGTHS SHALL BE 30 INCHES.

**CONCRETE CONTROL JOINTS:** WHERE SPECIFIED, SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 302. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. LENGTH/WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1.5 AND TYPICAL SPACING OF CUTS TO BE 12FT. DO NOT CUT W.W.M. OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)

BASED ON COLUMN REACTIONS BY MCSGO  
SEALED ENGINEERING FOR PROJECT 22-6650, DATED 11/8/05

NOTE: THIS FOUNDATION DESIGN MEETS ALL REQUIREMENTS FOR WIND LOADS PER FBC2004, SECTION 1609, 110 MPH BASIC WIND SPEED, EXPOSURE B, 1.0 USE FACTOR; COLUMN PAD LOCATIONS ARE TYPICAL. EXACT ANCHOR BOLT LOCATIONS AND SIZES ARE PER METAL BUILDING SEALED ENGINEERING ANCHOR BOLT PLAN.


- ANCHOR BOLTS AND REINFORCEMENT - 16" A-307 ANCHOR BOLTS, BOLT DIAMETER, AND LOCATION PER METAL BUILDING SEALED ENGINEERING DESIGN DRAWINGS. TIE ANCHOR BOLTS TO BOTTOM REINFORCING STEEL. REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185. DETAILING OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI DETAILING MANUAL, SP-66, AND ACI318. REINFORCING SHALL NOT BE HEATED OR WELDED. REINFORCING SHALL BE APPROVED BY ENGINEER OR HIS REPRESENTATIVE BEFORE CONCRETE IS PLACED. PROVIDE 3" COVER FOR EXPOSED FOOTING SURFACES, 2" COVER FOR FORMED EXPOSED SURFACES, 3/4" COVER FOR NOT EXPOSED SURFACES. LAP SPLICES SHALL BE 48 BAR DIAMETERS. TOP STEEL LAPS SHALL OCCUR AT MID SPAN; BOTTOM LAPS AT COLUMNS.

- CONCRETE - MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS SHALL BE  $F_c = 3000$  PSI. WHERE EXCESS WATER IS ADDED TO THE CONCRETE SO THAT ITS SERVICEABILITY IS DEGRADED, THE ATTAINMENT OF REQUIRED STRENGTH SHALL NOT RELEASE THE CONTRACTOR FROM PROVIDING SUCH MODIFICATIONS AS MAY BE REQUIRED BY THE ENGINEER TO PROVIDE A SERVICEABLE MEMBER OR SURFACE. ALL CONCRETE SHALL BE VIBRATED. NO REPAIR OR RUBBING OF CONCRETE SURFACES SHALL BE MADE PRIOR TO INSPECTION BY AND APPROVAL OF THE ENGINEER, OWNER OR HIS REPRESENTATIVE.


- CONTROL JOINTS - SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 302. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. THE LENGTH/WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1.5. DO NOT CUT W.W.M. OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)

- FOUNDATION - THE OWNER HAS NOT YET PROVIDED A GEOTECHNICAL REPORT TO THE ENGINEER. ASSUMED SAFE BEARING CAPACITY OF 2000 PSF SHALL BE CONFIRMED IN THE FIELD BY A REGISTERED GEOTECHNICAL ENGINEER OR SHALL BE APPROVED BY THE OWNER. FOOTINGS AND SLABS ARE TO BEAR ON FIRM UNDISTURBED EARTH OR APPROVED CONTROLLED FILL. WHERE UNACCEPTABLE MATERIAL OCCURS, EXCAVATE AND REPLACE WITH ENGINEERED FILL.


- UNLESS OTHERWISE SPECIFIED ALL MATERIALS AND CONSTRUCTION ARE TO MEET LOCAL BUILDING CODES.



FOUNDATION PLAN  
SCALE: 3/16" = 1'-0"



SECTION B-B  
SCALE: 1" = 1'-0"



SECTION A-A  
SCALE: 1" = 1'-0"

WINDLOAD ENGINEER: Mark Disosway, P.E. No. 53915, P.O. Box 868, Lake City, FL 32056, 386-754-5419

**DIMENSIONS:** Stated dimensions supercede all other dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

**COPYRIGHTS AND PROPER:** Mark Disosway, P.E. hereby certifies that these instruments of service, not to be reproduced, altered, or used in any form or manner without first obtaining the permission and consent of Mark Disosway, P.E.

**CERTIFICATION:** I hereby certify that I have examined this plan, and that the portions of the plan, relating to the foundation, comply with section 1609, Florida Building Code, 2004, to the best of my knowledge.

**LIMITATION:** This design is for building, at specified location.



Simque  
Metal Building  
Foundation

Wayne Hud

ADDRESS:

Mark Disosway  
P.O. Box 868  
Lake City, Florida  
Phone: (386) 754-5419  
Fax: (386) 754-5419  
Email: mdpe@bell.net


PRINTED DATE:  
November 24, 2005  
DRAWN BY: CH

FINALS DATE:  
01/ May / 05

JOB NUMBER:  
511174

DRAWING NUMBER:  
F1

OF 1 SHEET




Base Edge Parts	Roof Panel Fasteners
14 BE1	2020 S210CZ
	1056 S17CZ
	59 SL-R3

		<h1>Mesco Building Solutions</h1> <p>P.O.Box 93629, Southlake, Texas 76092 Voice 817-488-8511 Fax 817-329-2326</p>			
Buyer: Simque Construction		Job Number  22-6650		Drawing Issue 0	
Owner: WAYNE HUDSON					
Project Name: HUDSON III		Job Site Location: LAKE CITY FL		Sheet Number F1 of 6	


**DRAWING STATUS:**

**"FOR CONSTRUCTION"**

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.




The engineer whose seal appears on this drawing is not the Building Manufacturer and is NOT the Engineer of Record for the overall Project.



FRONT SIDEWALL ASSEMBLY

GHOLES=39.75,85.75,129.75,189.75

- C** 2 ZFO type# 1 & 6, 5' x 5'
- 4 HZ60006
  - 4 CYS
  - 16 BN410FA
  - 2 TH10LS-6275
  - 2 TB20LS-6275
  - 4 JZ83446
  - 4 CYS
  - 4 CYS-2
  - 32 BN410FA
  - 4 TS10LS-6100
  - 72 PR13LS
  - 24 ISL-TWH
  - 8 CG14
  - 32 BN410FA
- B** 4 ZFO type# 4, 5' x 5'
- 4 HZ60006
  - 8 CYS
  - 32 BN410FA
  - 4 TH10LS-6275
  - 4 TB20LS-6275
  - 8 JZ83756
  - 16 CYS
  - 64 BN410FA
  - 8 TS10LS-6100
  - 145 PR13LS
  - 48 ISL-TWH
  - 8 CG14
  - 32 BN410FA
  - 4 CCH6700K6
  - 40 S27CR-N
- A** 4 ZFO type# 2, 6'-4" x 7'-2" 6 3070WH Cylinder, Solid
- 4 HZ76006
  - 8 CYS
  - 32 BN410FA
  - 4 TH10LS-7875
  - 8 JZ128006
  - 8 CYS
  - 8 CG14
  - 64 BN410FA
  - 8 TS10LS-8750
  - 140 PR13LS
  - 48 ISL-TWH
  - 16 CG14
  - 64 BN410FA



DRAWING ISSUE HISTORY

NO.	DATE	DESCRIPTION	DET	CKR	ENG
0	11/07/05	ISSUED FOR CONSTRUCTION	MJP	CBS	



Mesco Building Solutions

P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326



Buyer:  
Simque Construction  
Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Site Location:  
LAKE CITY FL.

Job Number  
22-6650


Drawing Issue  
0



Sheet Number  
E2 of 6

DRAWING STATUS:  
"FOR CONSTRUCTION"


These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.

The engineer whose seal appears hereon is employed by the Building Manufacturer and is NOT the Engineer of Record for this overall Project.





DRAWING ISSUE HISTORY					
NO.	DATE	DESCRIPTION	DET	CKR	ENG
0	11/07/05	ISSUED FOR CONSTRUCTION	MJP	CBS	



**Mesco Building Solutions**  
P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326

Buyer:  
Simque Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Number  
**22-6650**


Drawn Issue  
0


Sheet Number  
**E3 of 6**

DRAWING STATUS:  
"FOR CONSTRUCTION"

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.


The engineer whose seal appears hereon is not the Engineer of Record for the overall Project.






- RAKE TRIM ASSEMBLY  
1 TR10LFN  
2 TR10FN  
1 TR10RFN  
21 PR13FN  
144 S17FN  
864 ISL-R3  
24 CLO-RO  
1 TA102MSFN
- LEFT SIDE TRIM ASSEMBLY  
1 TC10LS-22900  
39 PR13LS
- RIGHT SIDE TRIM ASSEMBLY  
1 TC10RS-22900  
39 PR13LS
- ENDWALL PANEL FASTENERS  
450 S210LS  
345 S17LS

LEFT ENDWALL PANEL LAYOUT  
*Width = 70'-0", Height = 19'-0"*  
*Type = "PBR", Finish = LS*  
*Panel = PBR-6LSE*



- |  |   |  |
|--|---|--|
| <p><b>[F]</b> 1 ZFO W08# 2, 16" x 14"</p> <p>2 H21920QJ2</p> <p>2 CV5</p> <p>8 BN410FA</p> <p>1 TH10LS-19475</p> <p>2 J21880QJ4</p> <p>2 CV5</p> <p>2 CG14</p> <p>8 BN410FA</p> <p>2 TS10LS-16950</p> <p>62 PR13LS</p> <p>12 ISL-TWH</p> <p>6 CG14</p> <p>24 BN410FA</p> | <p><b>[E]</b> 1 ZFO W08# 6, 4" x 4"</p> <p>2 H24800Q2</p> <p>4 CV5</p> <p>16 BN410FA</p> <p>1 TH10LS-5075</p> <p>1 TB20LS-5075</p> <p>2 J2100S06</p> <p>2 CG14</p> <p>8 BN410FA</p> <p>2 TS10LS-4900</p> <p>30 PR13LS</p> <p>12 ISL-TWH</p> | <p>* 8 FLANGE BRACE ASSY</p> <p>8 FA-2008</p> <p><b>[T]</b> 16 BN410AA</p> |
|--|---|--|

LEFT ENDWALL ASSEMBLY  
GHOLES=39.75,85.75,129.75,189.75

[illegible]

Buyer:	Simque Construction
Owner:	WAYNE HUDSON

Project Name:	HUDSON III
---------------	------------

Mesco Building Solutions

P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326




Job Number  
22-6650


Drawing Issue	0
---------------	---

Sheet Number  
F4 of 6

**DRAWING STATUS:**  
**"FOR CONSTRUCTION"**  
 These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.




The engineer whose seal appears here on is employed by the Building Manufacturer and is **NOT** the Engineer of Record for the overall Project.

**RIGHT ENDWALL PANEL LAYOUT**


Width = 70'-0", Height = 19'-0"  
Type = "PBR", Finish = LS  
Panel = PBR-6LSE

- RAKE TRIM ASSEMBLY**  
1 TR10LFN  
2 TR10FN  
1 TR10RFN  
21 PR13FN  
144 S17FN  
864 ISL-R3  
24 CLO-R0  
1 TA102M5FN
- LEFT SIDE TRIM ASSEMBLY**  
1 TC10LS-22900  
39 PR13LS
- RIGHT SIDE TRIM ASSEMBLY**  
1 TC10LS-22900  
39 PR13LS
- ENDWALL PANEL FASTENERS**  
450 S210LS  
345 S17LS

**RIGHT ENDWALL ASSEMBLY**

GH0LES=39.75, 85.75, 129.75, 189.75

- H** 1 ZFO Type# 2, 14' x 14'  
1 HZ18500J2  
2 CV5  
8 BN410FA  
1 TH10LS-17075  
2 JZ18500J4  
2 CV5  
2 CG14  
16 BN410FA  
2 TS10LS-16950  
62 PR13LS  
12 ISL-TWH  
6 CG14  
24 BN410FA
- G** 1 ZFO Type# 6, 4' x 4'  
1 HZ48006  
4 CV5  
16 BN410FA  
1 TH10LS-5075  
1 TS20LS-5075  
2 JZ100506  
4 CG14  
16 BN410FA  
2 TS10LS-4900  
30 PR13LS  
12 ISL-TWH
- T** 8 FLANGE BRACE ASSY  
8 FA-2008  
16 BN410AA



DRAWING ISSUE HISTORY					
NO.	DATE	DESCRIPTION	DET	CKR	ENG
0	11/07/05	ISSUED FOR CONSTRUCTION	MJP	CBS	



**Mesco Building Solutions**

P.O.Box 93629, Southlake, Texas 76092

Voice 817-488-8511 Fax 817-329-2326

Buyer:  
Simque Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Site Location:  
LAKE CITY FL.



Job Number

22-6650

Drawing Issue

0


Sheet Number

E5 of 6

DRAWING STATUS:  
"FOR CONSTRUCTION"

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.


The engineer whose seal appears here is not the Engineer of Record for this Building Manufacturer and is NOT the Engineer of Record for this overall Project.



NOTE:  
AT LOCATIONS SHOWN, INSTALL FLANGE BRACES  
THAT ARE LEFT OF RL AT NEAR SIDE ONLY AND  
FLANGE BRACES THAT ARE RIGHT OF RL AT FAR  
SIDE ONLY. (UNLESS NOTED)


MEMBER DATA			
Column data is listed from Base to Eave - Rafter data is listed from Eave to Ridge (High Side)			
Mark	Outside Flange	Web	Inside Flange
Col (RC-1)	1/4 x 6	8 GA x 12 to 28	5/16 x 6
Raf (RR-3)	1/4 x 6	8 GA x 33 to 15	1/4 x 6
	1/4 x 6 x 17-10 1/16	1/8 x 15 x 17-10 1/16	1/4 x 6 x 17-10 1/16

GIRT & PURLIN DATA	
Front Girts Depth : 8	Back Girts Depth : 8
Front Purlins Depth: 8	Back Purlins Depth: 8



Frame Section: 2-4

AssyQty = 3



DRAWING ISSUE HISTORY					
NO.	DATE	DESCRIPTION	DET	CKR	ENG
0	11/07/05	ISSUED FOR CONSTRUCTION	MJP	CBS	



**Mesco Building Solutions**  
P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326

Buyer:  
Simque Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III


Job Number  
**22-6650**


Sheet Number  
**E6 of 6**

DRAWING STATUS:  
**"FOR CONSTRUCTION"**

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.

The engineer whose seal appears hereon is not the Engineer of Record for the overall Project.





DRAWING ISSUE HISTORY				
NO.	DATE	DESCRIPTION	DET	CKR
0	11/07/05	ISSUED FOR CONSTRUCTION	MJP	CBS

**Mesco Building Solutions**  
P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326

Buyer:  
Stimco Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Number  
**22-6650**

Drawing Issue  
0

Sheet Number  
D1 of 1


**DRAWING STATUS:**  
"FOR CONSTRUCTION"

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.


The engineer whose seal appears hereon is not the Engineer of Record for the overall Project.




POP RIVETS AT TRIM SPLICES




PART NO : TR \_\_\_\_  
BASE TRIM (4) POP RIVETS




PART NO : TE1  
HIGH SIDE TRIM (6) POP RIVETS




PART NO : TF \_\_\_\_  
CLOSURE TRIM (10) POP RIVETS




PART NO : THS  
SLIDE DOOR HEAD TRIM (6)  
POP RIVETS




PART NO : TH4  
SOFFIT CAP TRIM (6) POP RIVETS




PART NO : TC1  
CORNER TRIM (6) POP RIVETS




PART NO : TE3 \_\_\_\_  
EAVE TRIM (3) POP RIVETS




PART NO : TFB  
BACKING TRIM (3) POP RIVETS




PART NO : TH1  
ANGLE TRIM (3) POP RIVETS




PART NO : TH \_\_\_\_  
FACIA CAP TRIM (5) POP RIVETS




PART NO : TC1  
CORNER TRIM (3) POP RIVETS



PART NO : TFI  
PARTITION TRIM (4) POP RIVETS



PART NO : TH \_\_\_\_  
HEAD TRIM (4) POP RIVETS




PART NO : TH \_\_\_\_  
CAP TRIM (4) POP RIVETS


NOTES:  
WHERE TUBE SEALANT IS REQ'D. FOR TRIM LAPS, BRONZE SEALANT IS PROVIDED FOR BRONZE TRIM & WHITE TUBE SEALANT IS PROVIDED FOR ALL OTHER FINISHES.

RG0105-0


POP RIVETS AT TRIM SPLICES




PART NO : TR \_\_\_\_  
RAKE TRIM (6) POP RIVETS




PART NO : TU \_\_\_\_  
SPACER TRIM (3) POP RIVETS




PART NO : APK \_\_\_\_  
PEAK CAP (6) POP RIVETS  
(PLASTIC)



PART NO : TS \_\_\_\_  
JAMB/SIDE TRIM (6) POP RIVETS



PART NO : TT \_\_\_\_  
TRANSITION TRIM (5) POP RIVETS




PART NO : TX \_\_\_\_  
PEAK CAP (6) POP RIVETS  
(STEEL)

NOTES:  
WHERE TUBE SEALANT IS REQ'D. FOR TRIM LAPS, BRONZE SEALANT IS PROVIDED FOR BRONZE TRIM & WHITE TUBE SEALANT IS PROVIDED FOR ALL OTHER FINISH CODED TRIMS.


NOTES:  
USE COLOR MATCH POP RIVETS FOR THE FOLLOWING COLORS: AG, BS, CW, DG, DS, FN, LS, PW, RR, AND ST. ALL OTHER COLORS USE STAINLESS STEEL POP RIVETS.

RG0106-0


POP RIVETS AT RAINWARE SPLICES




PART NO : RB \_\_\_\_  
ELBOWS (6) POP RIVETS




PART NO : RG \_\_\_\_  
GUTTER (10) POP RIVETS




PART NO : RT \_\_\_\_  
DOWNSPOUT STRAP (4) POP RIVETS




PART NO : RE \_\_\_\_  
GUTTER ENDCAPS (10) POP RIVETS




PART NO : RD \_\_\_\_  
DOWNSPOUTS (6) POP RIVETS



PART NO : RK \_\_\_\_  
KICKOUTS (6) POP RIVETS



PART NO : RR \_\_\_\_  
RETURNS (6) POP RIVETS



3" MAX SPACING, EACH LEG OF VALLEY  
GUTTER, USE SELF-SEALING POP RIVET.

NOTES:  
WHERE TUBE SEALANT IS REQ'D. FOR TRIM LAPS, BRONZE SEALANT IS PROVIDED FOR BRONZE TRIM/RAINWARE & WHITE TUBE SEALANT IS PROVIDED FOR ALL OTHER FINISH CODED TRIMS/RAINWARE.

NOTES:  
USE COLOR MATCH POP RIVETS FOR THE FOLLOWING COLORS: AG, BS, CW, DG, DS, FN, LS, PW, RR, AND ST. ALL OTHER COLORS USE STAINLESS STEEL POP RIVETS.

RG0107-0

DEALER / CONTRACTOR RESPONSIBILITIES

IT IS THE RESPONSIBILITY OF THE DEALER/CONTRACTOR TO INSURE THAT ALL PROJECT PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE REQUIREMENTS OF ANY GOVERNING BUILDING AUTHORITIES. THE SUPPLYING OF SEALED ENGINEERING DATA AND DRAWINGS FOR THE METAL BUILDING SYSTEM DOES NOT IMPLY OR CONSTITUTE AN AGREEMENT THAT MESCO METAL BUILDINGS OR ITS DESIGN ENGINEER IS ACTING AS THE ENGINEER OF RECORD OR DESIGN PROFESSIONAL FOR A CONSTRUCTION PROJECT.

THE DEALER/CONTRACTOR MUST SECURE ALL REQUIRED APPROVALS AND PERMITS FROM THE APPROPRIATE AGENCY AS REQUIRED.

APPROVAL OF MESCO'S DRAWINGS AND CALCULATIONS INDICATE THAT MESCO METAL BUILDINGS CORRECTLY INTERPRETED AND APPLIED THE REQUIREMENTS OF THE CONTRACT DRAWINGS AND SPECIFICATIONS. (SECT. 4.2.1 AISC CODE OF STANDARD PRACTICES, 9TH ED.)

WHERE DISCREPANCIES EXIST BETWEEN MESCO'S STRUCTURAL STEEL PLANS AND THE PLANS FOR OTHER TRADES, THE STRUCTURAL STEEL PLANS SHALL GOVERN. (SECT. 3.3 AISC CODE OF STANDARD PRACTICE 9TH ED.)

DESIGN CONSIDERATIONS OF ANY MATERIALS IN THE STRUCTURE WHICH ARE NOT FURNISHED BY MESCO METAL BUILDINGS ARE THE RESPONSIBILITY OF THE CONTRACTORS AND ENGINEERS OTHER THAN MESCO METAL BUILDING'S ENGINEERS UNLESS SPECIALLY INDICATED.

THE DEALER/CONTRACTOR IS RESPONSIBLE FOR ALL ERECTION OF STEEL AND ASSOCIATED WORK IN COMPLIANCE WITH MESCO METAL BUILDING'S "FOR CONSTRUCTION" DRAWINGS.

ALL BRACING AS SHOWN AND PROVIDED BY MESCO FOR THIS BUILDING IS REQUIRED AND SHALL BE INSTALLED BY THE ERECTOR AS A PERMANENT PART OF THE STRUCTURE.

TEMPORARY SUPPORTS, SUCH AS TEMPORARY GUYS, BRACES, FALSEWORK, CRIBBING OR OTHER ELEMENTS REQUIRED FOR THE ERECTION OPERATION WILL BE DETERMINED AND FURNISHED AND INSTALLED BY THE ERECTOR. THESE TEMPORARY SUPPORTS WILL SECURE THE STEEL FRAMING, OR ANY PARTLY ASSEMBLED STEEL FRAMING, AGAINST LOADS COMPARABLE IN INTENSITY TO THOSE FOR WHICH THE STRUCTURE WAS DESIGNED, RESULTING FROM WIND, SEISMIC FORCES AND ERECTION OPERATIONS, BUT NOT THE LOADS RESULTING FROM THE PERFORMANCE OF WORK, BY OR THE ACTS OF OTHERS, NOR SUCH UNPREDICTABLE LOADS AS THOSE DUE TO TORNADO, EXPLOSION OR COLLISION. (SECT. 7.9.1 AISC CODE OF STANDARD PRACTICE, 9TH ED.)

GENERAL NOTES

- THE STRUCTURE UNDER THIS PURCHASE ORDER HAS BEEN DESIGNED AND DETAILED FOR THE LOADS AND CONDITIONS STIPULATED IN THE PURCHASE ORDER AND SHOWN ON THESE DRAWINGS. ANY ALTERATIONS TO THE STRUCTURAL SYSTEM OR REMOVAL OF ANY COMPONENT PARTS, OR THE ADDITION OF OTHER CONSTRUCTION MATERIALS OR LOADS MUST BE DONE UNDER THE ADVICE AND DIRECTION OF A REGISTERED ARCHITECT, CIVIL OR STRUCTURAL ENGINEER. MESCO METAL BUILDINGS WILL ASSUME NO RESPONSIBILITY FOR ANY LOADS NOT INDICATED. THIS METAL BUILDING IS DESIGNED WITH MESCO METAL BUILDING'S STANDARD PRACTICES WHICH ARE BASED ON PERTINENT PROCEDURES AND RECOMMENDATIONS OF THE FOLLOWING ORGANIZATIONS AND CODES.
1. AMERICAN INSTITUTE OF STEEL CONSTRUCTION: "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS"
  2. AMERICAN IRON AND STEEL INSTITUTE: "SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS"
  3. AMERICAN WELDING SOCIETY: "STRUCTURAL WELDING CODE" AWS D1.1.
  4. METAL BUILDING MANUFACTURER'S ASSOCIATION: "LOW RISE BUILDING SYSTEMS MANUAL"
  5. INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS: "UNIFORM BUILDING CODE"
  6. SOUTHERN BUILDING CODE CONGRESS INTERNATIONAL: "STANDARD BUILDING CODE"
  7. BUILDING OFFICIAL AND CODE ADMINISTRATORS INTERNATIONAL: "BOCA NATIONAL BUILDING CODE"
- SHOP AND FIELD INSPECTIONS AND ASSOCIATED FEES ARE THE RESPONSIBILITY OF THE DEALER/CONTRACTOR, UNLESS STIPULATED OTHERWISE IN THE CONTRACT.

SAFETY COMMITMENT

MESCO METAL BUILDINGS HAS A COMMITMENT TO MANUFACTURE QUALITY BUILDING COMPONENTS THAT CAN BE SAFELY ERECTED. HOWEVER, THE SAFETY COMMITMENT AND JOB SITE PRACTICES OF THE ERECTOR ARE BEYOND THE CONTROL OF MESCO METAL BUILDINGS.

IT IS STRONGLY RECOMMENDED THAT SAFE WORKING CONDITIONS AND ACCIDENT PREVENTION PRACTICES BE THE TOP PRIORITY OF ANY JOB SITE.

LOCAL, STATE AND FEDERAL SAFETY AND HEALTH STANDARDS SHOULD ALWAYS BE FOLLOWED TO HELP INSURE WORKER SAFETY.

MAKE CERTAIN ALL EMPLOYEES KNOW THE SAFEST AND MOST PRODUCTIVE WAY OF ERECTING A BUILDING. EMERGENCY PROCEDURES SHOULD BE KNOWN TO ALL EMPLOYEES.

DAILY MEETINGS HIGHLIGHTING SAFETY PROCEDURES ARE ALSO RECOMMENDED. THE USE OF HARD HATS, RUBBER SOLE SHOES FOR ROOF WORK, PROPER EQUIPMENT FOR HANDLING MATERIAL, AND SAFETY NETS WHERE APPLICABLE, ARE RECOMMENDED.

RG0108-0

DRAWING ISSUE HISTORY					
NO.	DATE	DESCRIPTION	DET	CKR	ENG
0					



Mesco Building Solutions

P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326



Buyer:  
Simque Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Site Location:  
LAKE CITY FL.

Job Number  
22-6650

Drawing Issue  
0


Sheet Number  
RG0108-0


DRAWING STATUS:

"FOR CONSTRUCTION"







These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.

The engineer whose seal appears here is not the Building Manufacturer and is NOT the Engineer of Record for the overall Project.
















1. START FIRST SIDEWALL PANEL AT CORNER WITH THE CENTER LINE OF THE MAJOR RIB ALIGNED WITH THE ENDWALL STEEL LINE.
2. INSTALL ONE FASTENER AT CORNER OF EACH FRAMING MEMBER TO HOLD PANEL IN PLACE UNTIL REMAINING FASTENERS CAN BE INSTALLED.
3. ATTACH PANEL TO FRAMING MEMBERS AT PANEL TO FRAMING FASTENER SPACING. REFER TO ERECTION DRAWING FOR FASTENER TYPE AND COLOR.
4. INSTALL MAJOR FRAMING RIBS. ATTACH PANEL TO PANEL USING FASTENERS AT STITCH FASTENER SPACING. REFER TO ERECTION DRAWINGS FOR FASTENER TYPE AND COLOR.
5. CONTINUE SHEETING SIDEWALL CHECKING VERTICAL ALIGNMENT AND COVERAGE. PANEL MAY END AT MAJOR RIB OR REQUIRE FIELD CUTTING. REFER TO ERECTION DRAWINGS FOR PANEL LAYOUT.



- SIDEWALL PANEL GENERAL NOTES

1. SQUARE AND PLUMB BUILDING PRIOR TO INSTALLATION OF WALL PANELS.
2. MARK FOUNDATION AT BASE LINE AT 3 FT. INCREMENTS FOR THE LENGTH OF THE SIDEWALL TO USE WHILE INSTALLING PANEL TO ASSURE PANEL COVERAGE. REFER TO DETAIL AT FOUNDATION.
3. BLOCK GIRTS TO LEVEL. IF REQUIRED, PRIOR TO INSTALLATION OF PANEL LEAVE BLOCK BURNING UNTIL PANEL INSTALLATION IS COMPLETE. REFER TO DETAIL AT BLOCK.
4. REFER TO SIDEWALL PANEL INSTALLATION NOTES FOR PANEL INSTALLATION.
5. PRE DRILLING OF PANEL SIDEAP IS RECOMMENDED. REFER TO STANDARD DRAWING FOR RECOMMENDED FASTENER INSTALLATION.
6. THIS DRAWING IS TO BE USED IN CONJUNCTION WITH THE ERECTION DRAWINGS AND OTHER DRAWINGS OF THIS SERIES.







- ENDWALL PANEL GENERAL NOTES:

1. SQUARE AND PLUMB BUILDING PRIOR TO INSTALLATION OF WALL PANELS.
2. MARK FOUNDATION AT BASE LINE AT 3 FT. INCREMENTS FOR THE WIDTH OF THE ENDWALL WHILE INSTALLING PANEL TO INSURE ALIGNMENT AND PANEL COVERAGE. REFER TO "DETAIL AT FOUNDATION" FOR MARKING AND INSTALLATION.
3. BLOCK GIRTS TO LEVEL, IF REQUIRED, PRIOR TO INSTALLATION OF PANEL. LEAVE BLOCKING IN PLACE UNTIL PANEL INSTALLATION IS COMPLETE. REFER TO "DETAIL AT BLOCKING" FOR DETAIL TO ENDWALL. PANEL INSTALLATION MUST BE DONE IN PANEL SEQUENTIAL ORDER.
4. THE DRILLING OF PANEL SIDE LAP IS RECOMMENDED. REFER TO STANDARD DRAWINGS FOR RECOMMENDED FASTENER INSTALLATION.
5. THIS DRAWING IS TO BE USED IN CONJUNCTION WITH THE ERECTION DRAWINGS AND OTHER DRAWINGS OF THIS SERIES.

- ENDWALL PANEL INSTALLATION NOTES:

1. ENDWALL START PANEL LOCATION FOR GABLE BLDG. CASE 1 IS LOCATED BY ALIGNING CENTER LINE OF ENDWALL WITH THE RIDGELINE OF THE BLDG. AS SHOWN IN ENDWALL START PANEL LOCATION. ENDWALL START PANEL LOCATION FOR GABLE BLDG. CASE 2 IS LOCATED BY ALIGNING CENTER LINE OF THE MAJOR RIB WITH THE RIDGELINE OF THE BLDG. AS SHOWN IN ENDWALL START PANEL LOCATION.
2. ENDWALL START PANEL LOCATION FOR SINGLE SLOPE ENDWALL IS LOCATED BY ALIGNING CENTER LINE OF THE MAJOR RIB WITH THE RIDGELINE OF THE BLDG. AS SHOWN IN ENDWALL START PANEL LOCATION.
3. ENDWALL START PANEL LOCATION FOR SINGLE SLOPE ENDWALL IS LOCATED BY ALIGNING CENTER LINE OF THE MAJOR RIB WITH THE RIDGELINE OF THE BLDG. AS SHOWN IN ENDWALL START PANEL LOCATION.
4. REFERENCE ERECTION DOWNS, SINGLE SLOPE ENDWALL.
5. REFERENCE ERECTION DOWNS, SINGLE SLOPE TYPE AND CASE CONDITION OF YOUR DOWNS.
6. INSTALL (2) FASTENERS PER EACH ENDWALL PANEL. FASTENERS ARE TO BE INSTALLED HOLD PANEL IN PLACE UNTIL REMAINING FASTENERS CAN BE INSTALLED. REFER TO ERECTION DOWNS FOR FASTENER TYPE AND COLOR.
7. ATTACH PANEL TO FRAMING AT PANEL TO FRAMING FASTENER SPACING. REFER TO ERECTION DOWNS FOR FASTENER TYPE AND COLOR.
8. INSTALL PANEL LAPSPRINGS. LAPSPRINGS ARE PREVIOUSLY INSTALLED PANEL. SECURE PANEL AT LAPSPRINGS WITH FASTENERS AT STITCH FASTENER SPACING. REFER TO ERECTION DOWNS FOR FASTENER TYPE AND COLOR.
9. CONTINUE ERECTION ENDWALL PANELS. MAINTAIN VERTICAL ALIGNMENT AND PANEL COVERAGE. PANEL MAY END AT MAJOR RIBS OR REQUIRE FIELD CUTTING. REFER TO ERECTION DOWNS, FOR PANEL LAYOUT

[illegible]

## Mesco Building Solutions

P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326



Job Number

22-6650

Project Name

Job Site Location:  
LAKE CITY FL


Drawing Issue

0	RW0102-1
---	----------


DRAWING STATUS:

"FOR CONSTRUCTION "

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.




The engineer whose seal appears hereon is employed by the Building Manufacturer and is NOT the Engineer of Record for the overall Project.



- 
- Diagram A: CORNER SECTION. CORNER TRIM INSTALLATION WITH MAJOR RIBS AT THE STEEL LINE. Labels: Pop Rivets, Corner Trim, Wall Panel, Steel Line, Corner Angle, Wall Framing Member.
- Diagram B: CORNER SECTION. CORNER TRIM DETAIL WITH MINOR RIB AT THE STEEL LINE AND MAJOR RIB WITH MAXIMUM OFFSET AT THE OPPOSITE STEEL LINE. Labels: Pop Rivets, Corner Trim, Wall Panel, Steel Line, Corner Angle, Wall Framing Member.
- Diagram C: SIDE TRIM SECTION. CORNER TRIM DETAIL WITH MINOR RIB AT THE STEEL LINE AND MAJOR RIB WITH MAXIMUM OFFSET AT THE OPPOSITE STEEL LINE. Labels: Pop Rivets, Wall Panel, Steel Line, Wall Framing Member, Side Trim (at minor rib), Side Trim (at major rib).
- Diagram D: CORNER SECTION. CORNER TRIM DETAIL WITH MAJOR RIB AT THE STEEL LINE AND A MINOR RIB AT THE OPPOSITE STEEL LINE. Labels: Pop Rivets, Corner Trim, Wall Panel, Steel Line, Corner Angle, Wall Framing Member.
- Diagram E: CORNER SECTION. CORNER TRIM DETAIL WITH MINOR RIB AT EACH STEEL LINE. Labels: Pop Rivets, Corner Trim, Wall Panel, Steel Line, Corner Angle, Wall Framing Member.
- PBA Wall Panel Shown. PBX Wall Panel Similar.

INSTALLATION STEP 1: PANEL PREPARATION	INSTALLATION STEP 2: BASE MEMBER CUT OUT
--	--


RW0203-1



- 


		<h1>Mesco Building Solutions</h1> <p>P.O.Box 93629, Southlake, Texas 76092</p> <p>Voice 817-488-8511      Fax 817-329-2326</p>			
Buyer: Simque Construction		Job Number <h2>22-6650</h2>		Drawing Issue 0	
Owner: WAYNE HUDSON					
Project Name: HUDSON III		Job Site Location: LAKE CITY FL.		Sheet Number RW0203-1	

**DRAWING STATUS:**  
**"FOR CONSTRUCTION"**  
 These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.



The engineer whose seal appears hereon is Engineer in Charge, Building Manufacturer and is **NOT** the Engineer of Record for the above Project.

INSTALLATION STEP 4: TRIM ASSEMBLY



INSTALLATION STEP 5: LOCKSETS

REFER TO INSTRUCTION PACKAGE PROVIDED WITH LOCKSETS FOR INSTALLATION.


NOTE: CYLINDRICAL PREP DOOR LEAF FOR USE WITH CYLINDRICAL LOCKSETS AND/OR PANIC DEVICE.

MORTISE PREP. DOOR LEAF FOR USE WITH MORTISE LOCKSETS ONLY.

INSTALLATION STEP 6: 6070 HARDWARE

6070 DOORS REQUIRE (1) ONE ACTIVE LEAF AND (1) INACTIVE LEAF. INACTIVE LEAF IS ALWAYS A CYLINDRICAL PREP. DOOR LEAF.

INSTALL CYLINDRICAL FILLER PLATE, ASTRAGAL, TOP AND BOTTOM SURFACE BOLTS TO INACTIVE LEAF.



DRAWING ISSUE HISTORY					
NO.	DATE	DESCRIPTION	DET	CKR	ENG
0					



Mesco Building Solutions

P.O.Box 93629, Southlake, Texas 76092  
Voice 817-488-8511 Fax 817-329-2326



Buyer:  
Simque Construction

Owner:  
WAYNE HUDSON

Project Name:  
HUDSON III

Job Site Location:  
LAKE CITY FL.

Job Number  
22-6650

Drawing Issue  
0


Sheet Number

DRAWING STATUS:  
"FOR CONSTRUCTION "

These drawings are to be considered as Final Construction Drawings and are to be used for the construction and installation of the project.

The engineer whose seal appears hereon is employed by the Building Manufacturer and is NOT the Engineer of Record for the Overall Project.





SCALE: 3/16" = 1'-0"

### - ELECTRICAL PLAN -


- ALL OVERHEAD LIGHTS ARE COMMERCIAL HALAGON
- ALL EXIT DOORS ARE EQUIPPED WITH LIGHTED SIGNS AND EMERGENCY LIGHTING.
- EACH BATHROOM AND WAREHOUSE TO HAVE SMOKE DETECTOR ALARMS.
- EACH WAREHOUSE TO HAVE SMOKE DETECTORS, ALARMS, AND FIRE EXTINGUISHERS IN EACH CORNER.
- ALL ELECTRIC OUTLETS IN BATHROOMS AND WAREHOUSE TO BE GFI

### - FLOOR PLAN -

- BATHROOM CEILINGS 8' HIGH 5/8 FIRE RATED SHEETROCK
- ALL DOORS EXIT OUT, COMMERCIAL METAL, SEE CONTRACTOR DOOR SCHEDULE HANDICAP ACCESSIBLE & HARDWARE
- ALL WINDOWS BY CODE SEE CONTRACTOR WINDOW SCHEDULE

### - PLUMBING PLAN -

- ALL PIPING AND FIXTURES BY CODE



TYPICAL  
TOILET ROOM ELEVATION  
SCALE: 3/4" = 1'-0"