

BEARING HEIGHT SCHEDULE

8'0"

6/12
PITCH
24"
0H

NOTES:

- 1) REFER TO HB 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY BRACING) MUST BE CORRECTLY DECKED OR REFER TO DETAIL NOTES FOR ALTERNATE BRACING REQUIREMENTS
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER
- 4) ALL TRUSSES ARE DESIGNED FOR 2' 0" MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6) SY42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP
- 7) ALL ROOF TRUSS HANGERS TO BE SIMPSON HUS26 UNLESS OTHERWISE NOTED. ALL ROOF TRUSS HANGERS TO BE SIMPSON TH4422 UNLESS OTHERWISE NOTED
- 8) BEAM/RAFTER/INTEL (BRI) TO BE FURNISHED BY BUILDER

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VALS. ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Engineered Drawing No.:

Approved By:

Date:



PHONE 904-437-3349 FAX 904-437-3994
Bunnell

PHONE 904-772-6100 FAX 904-772-1973
Jacksonville

PHONE 386-755-6894 FAX 386-755-7973
Lake City

PHONE 407-322-0059 FAX 407-322-5553
Sanford

SUBJECT: HOMES BY HOUSECRAFT

REAL AGENTS: GAY RESIDENCE

MODEL: CUSTOM HOME NT5

DATE: 10/27/06 JOE L 125196

