

DATE 05/05/2006

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000024466

APPLICANT CHARESE NORTON PHONE 752-3331
ADDRESS 3367 S US HIGHWAY 441 LAKE CITY FL 32025
OWNER ELMER & RITA NICHOLS PHONE 752-1221
ADDRESS 1381 SW BEDENBAUGH LANE LAKE CITY FL 32025
CONTRACTOR JAMES NORTON PHONE 752-3331
LOCATION OF PROPERTY 441S, TR ON CR 131, TR ON BEDENBAUGH LANE, SITE ON LEFT
JUST BEFORE PAVEMENT ENDS

TYPE DEVELOPMENT SFD,UTILITY ESTIMATED COST OF CONSTRUCTION 76650.00
HEATED FLOOR AREA 1533.00 TOTAL AREA 1921.00 HEIGHT STORIES 1
FOUNDATION CONC WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB
LAND USE & ZONING A-3 MAX. HEIGHT 19
Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 30-4S-17-08914-002 SUBDIVISION
LOT BLOCK PHASE UNIT TOTAL ACRES

RB0031780
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
EXISTING 06-0415-N BK JH Y
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: ONE FOOT ABOVE THE ROAD
SPECIAL FAMILY LOT PERMIT, DAUGHTER TO MOTHER

Check # or Cash 21608

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power Foundation Monolithic
date/app. by date/app. by date/app. by
Under slab rough-in plumbing Slab Sheathing/Nailing
date/app. by date/app. by date/app. by
Framing Rough-in plumbing above slab and below wood floor
date/app. by date/app. by
Electrical rough-in Heat & Air Duct Peri. beam (Lintel)
date/app. by date/app. by date/app. by
Permanent power C.O. Final Culvert
date/app. by date/app. by date/app. by
M/H tie downs, blocking, electricity and plumbing Pool
date/app. by date/app. by
Reconnection Pump pole Utility Pole
date/app. by date/app. by date/app. by
M/H Pole Travel Trailer Re-roof
date/app. by date/app. by date/app. by

BUILDING PERMIT FEE \$ 385.00 CERTIFICATION FEE \$ 9.61 SURCHARGE FEE \$ 9.61
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ TOTAL FEE 479.22
INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permit Application

Revised 9-23-04

For Office Use Only Application # 0604-85 Date Received 4/26/06 By LT Permit # 24466
 Application Approved by - Zoning Official BLK Date 04.05.06 Plans Examiner DKJH Date 5-1-06
 Flood Zone X Development Permit N/A Zoning A-3 Land Use Plan Map Category A-3
 Comments Section 14.9 Special Family Lot Permit Daughter to mother
NOC, EH CR# 21608 06-0415-N

Applicants Name Charese Norton, @ Norton Home Improvement Phone 386-752-3331
 Address 3367 S US HWY 441, Ste 101, Lake City, FL 32025
 Owners Name Elmer & Rita Nichols Phone 386-752-1221
 911 Address 1381 SW Bedenbrough Lane, Lake City, FL 32025
 Contractors Name James H. Norton Phone 386-752-3331
 Address 3367 S US HWY 441, Ste 101, Lake City, FL 32025
 Fee Simple Owner Name & Address NA
 Bonding Co. Name & Address NA
 Architect/Engineer Name & Address Mark Disoway P.O. Box 868, Lake City, FL 32056
Tim Deibene, 142 SW Sagewood Gln, Lake City, FL 32024
 Mortgage Lenders Name & Address 1st Fed., 4705 W. US Hwy 90, Lake City, FL 32056
 Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
 Property ID Number 30-45-17-08914-002 Estimated Cost of Construction \$100,000.00
 Subdivision Name — Lot — Block — Unit — Phase —
 Driving Directions 441 South to 131, turn Right go down to Bedenbrough Lane, turn Right and site is on left just before pavement ends.
 Type of Construction SFD, new home Construct. Number of Existing Dwellings on Property 0
 Total Acreage .50 Lot Size — Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
 Actual Distance of Structure from Property Lines - Front 97.3' Side 37.7' Side 37.7' Rear 36'
 Total Building Height 19' Number of Stories 1 Heated Floor Area 1533 Roof Pitch 6/12
Porch 388 TOTAL 1921

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

James H. Norton
 Owner Builder or Agent (Including Contractor)
 Patricia T. Peeler
 My Commission DD129866
 Expires September 05, 2008

STATE OF FLORIDA
 COUNTY OF COLUMBIA

Sworn to (or affirmed) and subscribed before me
 this 26th day of April 2006.
 Personally known ✓ or Produced Identification —

James H. Norton
 Contractor Signature
 Contractors License Number RB0031780
 Competency Card Number 5553
 NOTARY STAMP/SEAL

Patricia T. Peeler
 Notary Signature

Tw called Charese 5.5.06 -



APPROXIMATE SCALE IN FEET




NATIONAL FLOOD INSURANCE PROGRAM

FIRM FLOOD INSURANCE RATE MAP

COLUMBIA
COUNTY,
FLORIDA
(UNINCORPORATED AREAS)

PANEL 175 OF 290

PANEL LOCATION



COMMUNITY-PANEL NUMBER

120070 0175 B


EFFECTIVE DATE:

JANUARY 6, 1988



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT Version 1.0. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. Further information about National Flood Insurance Program flood hazard maps is available at www.fema.gov/nifm/fscd.



Columbia County Property Appraiser

J. Doyle Crews, CFA - Lake City, Florida - 386-758-1083

PARCEL: 30-4S-17-08914-002 - NO AG ACRE (009900)

THE W1/2 OF E1/2 OF THE FOLLOWING DESC: A PARCEL 449.4 FT E & W BY 194.7 FT N & S IN

Name: NICHOLS RITA & ELMER

Site:

439 SE LILLIAN LOOP

Mail: APT 104

LAKE CITY, FL 32025

Sales 2/9/2006 \$100.00 V / U

Info 12/28/2000 \$100.00 V / U

LandVal \$12,000.00

BldgVal \$0.00

ApprVal \$12,000.00

JustVal \$12,000.00

Assd \$12,000.00


Exmpt \$0.00

Taxable \$12,000.00

0 150 300 450 ft



This information, GIS Map Updated: 4/6/2006, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, its use, or its interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.



http://www.columbia.floridana.com/GIS/Print_Man.asp?niboiibchhibnligcafceelbiemnolkik... 5/1/2006

Columbia County Property Appraiser

DB Last Updated: 3/7/2006

2006 Proposed Values

Parcel: 30-4S-17-08914-002

Tax Record

Property Card

Interactive GIS Map

Print

Owner & Property Info

Search Result: 1 of 1

Owner's Name	NICHOLS RITA & ELMER
Site Address	
Mailing Address	439 SE LILLIAN LOOP APT 104 LAKE CITY, FL 32025
Brief Legal	THE W1/2 OF E1/2 OF THE FOLLOWNG DESC:A PARCEL 449.4 FT E & W BY 194.7 FT N & S IN

Use Desc. (code)	NO AG ACRE (009900)
Neighborhood	30417.00
Tax District	2
UD Codes	MKTA01
Market Area	01
Total Land Area	0.500 ACRES

Property & Assessment Values

Mkt Land Value	cnt: (1)	\$12,000.00
Ag Land Value	cnt: (0)	\$0.00
Building Value	cnt: (0)	\$0.00
XFOB Value	cnt: (0)	\$0.00
Total Appraised Value		\$12,000.00

Just Value	\$12,000.00
Class Value	\$0.00
Assessed Value	\$12,000.00
Exempt Value	\$0.00
Total Taxable Value	\$12,000.00

Sales History

Sale Date	Book/Page	Inst. Type	Sale Vlmp	Sale Qual	Sale RCode	Sale Price
2/9/2006	1073/2066	QC	V	U	01	\$100.00
12/28/2000	918/1522	WD	V	U	03	\$100.00

Building Characteristics

Bldg Item	Bldg Desc	Year Blt	Ext. Walls	Heated S.F.	Actual S.F.	Bldg Value
NONE						

Extra Features & Out Buildings

Code	Desc	Year Blt	Value	Units	Dims	Condition (% Good)
NONE						

Land Breakdown

Lnd Code	Desc	Units	Adjustments	Eff Rate	Lnd Value
009900	AC NON-AG (MKT)	.500 AC	1.00/1.00/1.50/1.00	\$24,000.00	\$12,000.00

Columbia County Property Appraiser

DB Last Updated: 3/7/2006

1 of 1

Inst: 2006003329 Date: 02/10/2006 Time: 15:15

Doc Stamp-Deed : 0.70

YMK DC, P. DeWitt Cason, Columbia County B: 1073 P: 2066

Above Space Reserved for Recording

[If required by your jurisdiction, list above the name & address of: 1) where to return this form; 2) preparer; 3) party requesting recording.]

Quitclaim Deed

Date of this Document: 2/9/2006

Reference Number of Any Related Documents: _____

Grantor:

Name KATHY HOWK
Street Address 1401 SW BEDENBAUGH LN
City/State/Zip LAKE CITY, FL 32025

Grantee:

Name RITA + ELMER NICHOLS
Street Address 439 SE LILLIAN LOOP APT. #104
City/State/Zip LAKE CITY, FL 32025

Abbreviated Legal Description (i.e., lot, block, plat or section, township, range, quarter/quarter or unit, building and condo name): SEE Attachment A

Assessor's Property Tax Parcel/Account Number(s): 30-4S-17-08914-002

THIS QUITCLAIM DEED, executed this NINTH day of FEBRUARY, 2006, by first party, Grantor, KATHY HOWK, whose mailing address is 1401 SW BEDENBAUGH LN, to second party, Grantee, RITA + ELMER NICHOLS, whose mailing address is 439 SE LILLIAN LOOP APT. #104, LAKE CITY FL.

WITNESSETH that the said first party, for good consideration and for the sum of ONE HUNDRED Dollars (\$ 100.00) paid by the said second party, the receipt whereof is hereby acknowledged, does hereby remise, release and quitclaim unto the said second party forever, all the right, title, interest and claim,

which the said first party has in and to the following described parcel of land, and improvements and appurtenances thereto in the County of Columbia, State of FLORIDA
to wit: _____

IN WITNESS WHEREOF, the said first party has signed and sealed these presents the day and year first written above. Signed, sealed and delivered in the presence of:

Inst:2006003329 Date:02/10/2006 Time:15:15
Doc Stamp-Deed : 0.70

Signature of Witness _____ DC, P. Dewitt Cason, Columbia County B:1073 P:2067
Print Name of Witness _____

Signature of Witness Kenneth Green
Print Name of Witness Kenneth Green

Signature of Grantor Kathy R. Houk
Print Name of Grantor KATHY R. HOUK

State of Florida)
County of Columbia)

On February 9, 2006 before me, Kathy R. Houk,
appeared _____, personally known to me (or proved
to me on the basis of satisfactory evidence) to be the person(s) whose name(s) is/are subscribed to the within
instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies),
and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the
person(s) acted, executed the instrument.

WITNESS my hand and official seal.

W. Dale Menninger
Signature of Notary

Affiant ☒ Known _____ Produced ID _____
Type of ID _____
(Seal)



W. Dale Menninger
Commission # DD289041
Expires May 13, 2008
Deeded Way Pals - Immature, Inc. 800-366-7000

Columbia County Tax Collector

generated on 2/9/2006 4:41:19 PM EST

Tax Record

DATA VIEW AS OF: 2/9/2006 4:41:19 PM ET

Attachment A**Ad Valorem Taxes and Non-Ad Valorem Assessments**

The information contained herein does not constitute a title search and should not be relied on as such.

Account Number	Tax Type	Tax Year	
R08914-002	Real Estate	2005	
Mailing Address HOUK KATHY R LAKE CITY FL 32025			
Folio 125515.0000			
Assessed Value	Exempt Amount	Taxable Value	
\$7,200.00	\$0.00	\$7,200.00	
Exemption Detail		Millage Rate	
NO EXEMPTIONS		002 19.06040	
Legal Description			
THE W1/2 OF E1/2 OF THE FOLLOWING DESC: A PARCEL 449.4 FT E & W BY 194.7 FT N & S IN SE COR OF SE1/4 OF SE1/4. ORB 523-323 THRU 325, 678-614, 918-1519, 918-1522,			
Tax Districts Detail			
Code	Description	Exemption	Amount
C001	BOARD OF COUNTY COMMISSIONERS	\$0.00	\$62.83
S002	COLUMBIA COUNTY SCHOOL BOARD	\$0.00	\$57.27
W SR	SUWANNEE RIVER WATER MGT DIST	\$0.00	\$3.54
HLSH	LAKE SHORE HOSPITAL AUTH	\$0.00	\$12.60
IIDA	INDUSTRIAL DEVELOPEMENT AUTH	\$0.00	\$0.99
FFIR	FIRE ASSESSMENTS	\$0.00	\$28.09
		Total Gross	\$165.32
		Discount	(\$1.65)
		Total	\$163.67
If Paid By		Amount Due	
02/28/2006		\$163.67	
03/31/2006		\$165.32	

Inst: 2006003329 Date: 02/10/2006 Time: 15:15
 Doc Stamp-Deed : 0.70
 DC, P. Dewitt Cason, Columbia County B: 1073 P: 2068

Prior Year Taxes Due

NO DELINQUENT TAXES

COLUMBIA COUNTY TAX COLLECTOR

Rec 15.00
due .70

FILED AND RECORDED IN PUBLIC
RECORDS OF COLUMBIA COUNTY, FL.

SK 0918 PG1522

01-01230

01 JAN 22 PM 4:02

OFFICIAL RECORDS

WARRANTY DEED



THIS INDENTURE, made this 23 day of December, 2000, between
TOMMY D. HOUK, a single person, and **RITA NICHOLS f/k/a RITA HOUK**, a married
woman not residing on the property, parties of the first part, Grantor, and **KATHY R.**
HOUK, (Social Security No. 590-40-1327), whose mailing address is Route 12, Box
10-S, Lake City, Florida 32025, party of the second part, Grantee,

WITNESSETH:

That said grantor, for and in consideration of the sum of **TEN AND NO/100**
(\$10.00) **DOLLARS**, and other good and valuable considerations to said grantor in
hand paid by said grantee, the receipt whereof is hereby acknowledged, has granted,
bargained and sold to the said grantee, and grantee's heirs, successors and assigns
forever, the following described land, situate, lying and being in Columbia County,
Florida, to-wit:

TOWNSHIP 4 SOUTH, RANGE 17 EAST

Section 30: The W 1/2 of the E 1/2 of the following described real
property:

449.4 feet East and West by 194.7 feet North and South in the Southeast
corner of SE 1/4 of SE 1/4, Page 672 of 1976 tax roll; more particularly
described as follows: Commence at the SE Corner of Section 30,
Township 4 South, Range 17 East, Columbia County, Florida, and run N
2°54'37" W along the East line of said Section 30, a distance of 219.49
feet; thence S 87°58'49" W 53.4 feet to the **POINT OF BEGINNING**;
thence S 1°20'05" E 194.70 feet; thence S 87°58'49" W 449.40 feet;
thence N 1°20'05" W 194.70 feet; thence N 87°58'49" E 449.40 feet to
the **POINT OF BEGINNING**.

Prepared by Marlin M. Feagles
Attorney at Law
Post Office Box 1853
Lake City, Florida 32055
(as to form only)

Documentary Stamp 70
Intangible Tax 70
P. Clerk's Office
Clerk of Court
By ML D.S.

BK 0918 PG 1523

SUBJECT TO reservations, restrictions and easement of record, if any, together with ad valorem taxes and non-ad valorem assessments **OFFICIAL RECORDS** subsequent to December 31, 2000.

Tax Parcel No.: 30-4S-17-08914-000

and said grantor does hereby fully warrant the title to said land, and will defend the same against the lawful claim of all persons whatsoever.

IN WITNESS WHEREOF, Grantor has hereunto set grantor's hand and seal the day and year first above written.

Signed, sealed and delivered
in the presence of:

Becky Westberry
Witness

Becky Westberry
(Print or type name)

Belki Hors
Witness

Robbi Goss
(Print or type name)

Tommy D. Houk (SEAL)
TOMMY D. HOUK

Signed, sealed and delivered
in the presence of:

Becky Westberry
Witness

Becky Westberry
(Print or type name)

Belki Hors
Witness

Robbi Goss
(Print or type name)

Rita Nichols (SEAL)
RITA NICHOLS
f/k/a Rita Houk

BK 0918 PG 1524

OFFICIAL RECORDS

STATE OF FLORIDA
COUNTY OF COLUMBIA

I HEREBY CERTIFY that on this day before me, an officer duly qualified to take acknowledgments, personally appeared TOMMY D. HOUK who is personally known to me or who has produced personally known as identification.

WITNESS my hand and official seal in the County and State last aforesaid this 29 day of December, 2000.

Donna S. Higge
NOTARY PUBLIC
MY COMMISSION EXPIRES:

(NOTARIAL SEAL)



Donna S. Higge
MY COMMISSION & CREDENTIALS EXPIRE
March 31, 2003
SCHEIDT & BOYD FORT MYERS, FL

STATE OF FLORIDA
COUNTY OF COLUMBIA

I HEREBY CERTIFY that on this day before me, an officer duly qualified to take acknowledgments, personally appeared RITA NICHOLS f/k/a RITA HOUK who is personally known to me or who has produced personally known as identification.

WITNESS my hand and official seal in the County and State last aforesaid this 29 day of December, 2000.

Donna S. Higge
NOTARY PUBLIC
MY COMMISSION EXPIRES:

(NOTARIAL SEAL)



Donna S. Higge
MY COMMISSION & CREDENTIALS EXPIRE
March 31, 2003
SCHEIDT & BOYD FORT MYERS, FL

COLUMBIA COUNTY 9-1-1 ADDRESSING

P. O. Box 1787, Lake City, FL 32056-1787

PHONE: (386) 758-1125 • FAX: (386) 758-1365 • Email: ron_croft@columbiacountyfla.com

Addressing Maintenance

To maintain the Countywide Addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for assigning and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Service Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County.

DATE REQUESTED: 1/27/2006 DATE ISSUED: 2/7/2006


ENHANCED 9-1-1 ADDRESS:

1381 SW BEDENBAUGH LN

LAKE CITY FL 32025

PROPERTY APPRAISER PARCEL NUMBER:

30-4S-17-08914-002

Remarks:Address Issued By: 

Columbia County 9-1-1 Addressing / GIS Department

NOTICE: THIS ADDRESS WAS ISSUED BASED ON LOCATION INFORMATION RECEIVED FROM THE REQUESTER. SHOULD, AT A LATER DATE, THE LOCATION INFORMATION BE FOUND TO BE IN ERROR, THIS ADDRESS IS SUBJECT TO CHANGE.

56

COLUMBIA COUNTY
9-1-1 ADDRESSING
APPROVED

LYNCH WELL DRILLING, INC.

173 SW Tustenuggee Ave

Lake City, FL 32025

Phone 386-752-6677

Fax 386-752-1477

Building Permit # _____ Owner's Name Nichols

Well Depth _____ Ft. Casing Depth _____ Ft. Water Level _____ Ft.

Casing Size 4 inch Steel Pump Installation: Deep Well SubmersiblePump Make Aermotor Pump Model S20-100 HP 1System Pressure (PSI) _____ On 30 Off 50 Average Pressure 40Pumping System GPM at average pressure and pumping level 20 (GPM)Tank Installation: Bladder ~~Galvanized~~ Make Challenger
Model PC 244 Size 81Tank Draw-down per cycle at system pressure 25.1 gallons**I HEREBY VERIFY THAT THIS WATER WELL SYSTEM HAS BEEN
INSTALLED AS PER THE ABOVE INFORMATION.**Linda Newcomb
Signature2609
License NumberLinda Newcomb
Print Name4-20-06
Date

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs Residential Whole Building Performance Method A

Project Name: **Nichols Residence**
Address: **SW Bedebaugh Lane**
City, State: **Lake City, FL 32055-**
Owner: **Nichols**
Climate Zone: **North**

Builder: **Jim Norton**
Permitting Office: **Columbia Co.**
Permit Number: **24466**
Jurisdiction Number: **421000**

1. New construction or existing New ☐
2. Single family or multi-family Single family ☐
3. Number of units, if multi-family 1 ☐
4. Number of Bedrooms 3 ☐
5. Is this a worst case? No ☐
6. Conditioned floor area (ft²) 1533 ft² ☐
7. Glass area & type Single Pane Double Pane ☐
 - a. Clear glass, default U-factor 0.0 ft² 141.0 ft² ☐
 - b. Default tint 0.0 ft² 0.0 ft² ☐
 - c. Labeled U or SHGC 0.0 ft² 0.0 ft² ☐
8. Floor types ☐
 - a. Slab-On-Grade Edge Insulation R=0.0, 170.0(p) ft ☐
 - b. N/A ☐
 - c. N/A ☐
9. Wall types ☐
 - a. Frame, Wood, Exterior R=13.0, 1177.0 ft² ☐
 - b. N/A ☐
 - c. N/A ☐
 - d. N/A ☐
 - e. N/A ☐
10. Ceiling types ☐
 - a. Under Attic R=30.0, 1533.0 ft² ☐
 - b. N/A ☐
 - c. N/A ☐
11. Ducts ☐
 - a. Sup: Unc. Ret: Unc. AH: Interior Sup. R=6.0, 20.0 ft ☐
 - b. N/A ☐

12. Cooling systems ☐
 - a. Central Unit Cap: 35.0 kBtu/hr SEER: 14.00 ☐
 - b. N/A ☐
 - c. N/A ☐
13. Heating systems ☐
 - a. Electric Heat Pump Cap: 35.0 kBtu/hr HSPF: 7.90 ☐
 - b. N/A ☐
 - c. N/A ☐
14. Hot water systems ☐
 - a. Electric Resistance Cap: 30.0 gallons EF: 0.90 ☐
 - b. N/A ☐
 - c. Conservation credits ☐

(HR-Heat recovery, Solar
DHP-Dedicated heat pump)
15. HVAC credits PT, CF, ☐

(CF-Ceiling fan, CV-Cross ventilation,
HF-Whole house fan,
PT-Programmable Thermostat,
MZ-C-Multizone cooling,
MZ-H-Multizone heating)

Glass/Floor Area: 0.09

Total as-built points: 18656

Total base points: 24301

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Tim Delbene

DATE: 3/11/02

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____

DATE: _____



SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: **SW Bedebaugh Lane, Lake City, FL, 32055-**

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BSPM = Points Floor Area				Type/SC Overhang Ornt Len Hgt Area X SPM X SOF = Points							
.18	1533.0	20.04	5529.8	Double, Clear	N	2.0	5.0	9.0	19.20	0.87	150.5
				Double, Clear	E	2.0	5.0	9.0	42.06	0.80	301.7
				Double, Clear	E	2.0	7.0	30.0	42.06	0.89	1117.9
				Double, Clear	S	8.0	7.0	30.0	35.87	0.50	538.2
				Double, Clear	S	2.0	7.0	30.0	35.87	0.82	882.5
				Double, Clear	W	2.0	3.0	3.0	38.52	0.64	73.8
				Double, Clear	W	2.0	7.0	30.0	38.52	0.89	1024.8
				As-Built Total:		141.0				4089.4	
WALL TYPES Area X BSPM = Points				Type R-Value Area X SPM = Points							
Adjacent	0.0	0.00	0.0	Frame, Wood, Exterior			13.0	1177.0		1.50	1765.5
Exterior	1177.0	1.70	2000.9								
Base Total:		1177.0	2000.9	As-Built Total:		1177.0				1765.5	
DOOR TYPES Area X BSPM = Points				Type Area X SPM = Points							
Adjacent	0.0	0.00	0.0	Exterior Insulated				21.0		4.10	86.1
Exterior	42.0	6.10	256.2	Exterior Insulated				21.0		4.10	86.1
Base Total:		42.0	256.2	As-Built Total:		42.0				172.2	
CEILING TYPES Area X BSPM = Points				Type R-Value Area X SPM X SCM = Points							
Under Attic	1533.0	1.73	2652.1	Under Attic			30.0	1533.0	1.73 X 1.00		2652.1
Base Total:		1533.0	2652.1	As-Built Total:		1533.0				2652.1	
FLOOR TYPES Area X BSPM = Points				Type R-Value Area X SPM = Points							
Slab	170.0(p)	-37.0	-6290.0	Slab-On-Grade Edge Insulation			0.0	170.0(p)		-41.20	-7004.0
Raised	0.0	0.00	0.0								
Base Total:			-6290.0	As-Built Total:		170.0				-7004.0	
INFILTRATION Area X BSPM = Points				Area X SPM = Points							
	1533.0	10.21	15651.9					1533.0	10.21		15651.9

SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**ADDRESS: **SW Bedebaugh Lane, Lake City, FL, 32055-**

PERMIT #:

BASE				AS-BUILT							
Summer Base Points: 19801.0				Summer As-Built Points: 17327.1							
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component	X	Cap Ratio	X Duct Multiplier	X System Multiplier	X Credit Multiplier	= Cooling Points	
							(DM x DSM x AHU)				
19801.0		0.4266	8447.1	17327.1	1.000	(1.090 x 1.147 x 0.91)	0.244	0.902		4337.2	
				17327.1	1.00	1.138	0.244	0.902		4337.2	

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: **SW Bedebaugh Lane, Lake City, FL, 32055-**

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points				
.18	1533.0	12.74	3515.5	Double, Clear	N	2.0	5.0	9.0	24.58	1.01	222.7
				Double, Clear	E	2.0	5.0	9.0	18.79	1.08	183.2
				Double, Clear	E	2.0	7.0	30.0	18.79	1.05	589.4
				Double, Clear	S	8.0	7.0	30.0	13.30	2.96	1182.5
				Double, Clear	S	2.0	7.0	30.0	13.30	1.17	467.1
				Double, Clear	W	2.0	3.0	3.0	20.73	1.12	69.6
				Double, Clear	W	2.0	7.0	30.0	20.73	1.03	641.3
				As-Built Total:				141.0	3355.9		
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	0.0	0.00	0.0	Frame, Wood, Exterior	13.0		1177.0	3.40		4001.8	
Exterior	1177.0	3.70	4354.9								
Base Total:				1177.0		4354.9					
				As-Built Total:		1177.0		4001.8			
DOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	0.0	0.00	0.0	Exterior Insulated			21.0	8.40		176.4	
Exterior	42.0	12.30	516.6	Exterior Insulated			21.0	8.40		176.4	
Base Total:				42.0		516.6					
				As-Built Total:		42.0		352.8			
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	1533.0	2.05	3142.6	Under Attic	30.0		1533.0	2.05 X 1.00		3142.6	
Base Total:				1533.0		3142.6					
				As-Built Total:		1533.0		3142.6			
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	170.0(p)	8.9	1513.0	Slab-On-Grade Edge Insulation	0.0		170.0(p)	18.80		3196.0	
Raised	0.0	0.00	0.0								
Base Total:				1513.0		3196.0					
				As-Built Total:		170.0		3196.0			
INFILTRATION Area X BWPM = Points						Area X WPM = Points					
						1533.0		-0.59		-904.5	

WINTER CALCULATIONS**Residential Whole Building Performance Method A - Details**ADDRESS: **SW Bedebaugh Lane, Lake City, FL, 32055-**

PERMIT #:

BASE				AS-BUILT									
Winter Base Points: 12138.2				Winter As-Built Points: 13144.6									
Total Winter Points	X	System Multiplier	= Heating Points	Total Component	X	Cap Ratio	X	Duct Multiplier	X	System Multiplier	X	Credit Multiplier	= Heating Points
							(DM x DSM x AHU)						
12138.2		0.6274	7615.5	13144.6	1.000	1.00	(1.069 x 1.169 x 0.93)	0.432	0.950	0.432	0.950	6264.3	6264.3

WATER HEATING & CODE COMPLIANCE STATUS**Residential Whole Building Performance Method A - Details**ADDRESS: **SW Bedebaugh Lane, Lake City, FL, 32055-**

PERMIT #:

BASE				AS-BUILT					
WATER HEATING				Tank	EF	Number of	X	Tank X	Multiplier X Credit = Total
Number of	X	Multiplier	=	Volume		Bedrooms		Ratio	Multiplier
Bedrooms									
3		2746.00		30.0	0.90	3		1.00	2684.98 1.00 8054.9
				As-Built Total:					8054.9

CODE COMPLIANCE STATUS

BASE						AS-BUILT					
Cooling Points	+	Heating Points	+	Hot Water Points	= Total Points	Cooling Points	+	Heating Points	+	Hot Water Points	= Total Points
8447		7615		8238	24301	4337		6264		8055	18656

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: **SW Bedebaugh Lane, Lake City, FL, 32055-**

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	✓
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	✓
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	✓
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	✓
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	✓
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	N/A
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	✓

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)


COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	✓
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	N/A
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	✓
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	✓
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	✓
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	✓

Application for Onsite Sewage Disposal System Construction Permit. Part II Site Plan

Permit Application Number: 06-045N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

NICHOLS/CR 05-3488



1 inch = 40 feet

Site Plan Submitted By Paul L. Lyle Date 4/21/06
Plan Approved ☒ Not Approved ☐ Date 5/1/06

By Ma A. M. Columbia CPHU

Notes: _____

COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001 ONE (1) AND TWO (2) FAMILY DWELLINGS ALL REQUIREMENTS ARE SUBJECT TO CHANGE EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE----- 110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

Applicant	Plans Examiner
<input checked="" type="checkbox"/>	<input type="checkbox"/> All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.
<input checked="" type="checkbox"/>	<input type="checkbox"/> Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.
<input checked="" type="checkbox"/>	<input type="checkbox"/> <u>Site Plan including:</u> <ol style="list-style-type: none">a) Dimensions of lotb) Dimensions of building set backsc) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements.d) Provide a full legal description of property.
<input checked="" type="checkbox"/>	<input type="checkbox"/> <u>Wind-load Engineering Summary, calculations and any details required</u> <ol style="list-style-type: none">a) Plans or specifications must state compliance with FBC Section 1606b) The following information must be shown as per section 1606.1.7 FBC<ol style="list-style-type: none">a. Basic wind speed (MPH)b. Wind importance factor (I) and building categoryc. Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicatedd. The applicable internal pressure coefficiente. Components and Cladding. The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional
<input checked="" type="checkbox"/>	<input type="checkbox"/> <u>Elevations including:</u> <ol style="list-style-type: none">a) All sidesb) Roof pitchc) Overhang dimensions and detail with attic ventilationd) Location, size and height above roof of chimneyse) Location and size of skylightsf) Building heighte) Number of stories

Floor Plan including:

- a) Rooms labeled and dimensioned
- b) Shear walls
- c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown)
- d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth
- e) Stairs with dimensions (width, tread and riser) and details of guardrails and handrails
- f) Must show and identify accessibility requirements (accessible bathroom)

Foundation Plan including:

- a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling
- d) Location of any vertical steel

Roof System:

- a) Truss package including:
 - 1. Truss layout and truss details signed and sealed by Fl. Pro. Eng.
 - 2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- b) Conventional Framing Layout including:
 - 1. Rafter size, species and spacing
 - 2. Attachment to wall and uplift
 - 3. Ridge beam sized and valley framing and support details
 - 4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections including:

- a) Masonry wall
 - 1. All materials making up wall
 - 2. Block size and mortar type with size and spacing of reinforcement
 - 3. Lintel, tie-beam sizes and reinforcement
 - 4. Gable ends with rake beams showing reinforcement or gable truss and wall bracing details
 - 5. All required connectors with uplift rating and required number and size of fasteners for continuous tie from roof to foundation
 - 6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with resistance rating)
 - 7. Fire resistant construction (if required)
 - 8. Fireproofing requirements
 - 9. Shoe type of termite treatment (termicide or alternative method)
 - 10. Slab on grade
 - a. Vapor retardant (6mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
 - 11. Indicate where pressure treated wood will be placed
 - 12. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
 - a. Vapor retardant (6Mil. Polyethylene with joints lapped 6 inches and sealed
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

- c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment
- g) Arc Fault Circuits (AFCI) in bedrooms

HVAC information

- a) Manual J sizing equipment or equivalent computation
- b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)

Gas System Type (LP or Natural) Location and BTU demand of equipment

Disclosure Statement for Owner Builders

*****Notice Of Commencement Required Before Any Inspections Will Be Done**

Private Potable Water

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

need: recorded
ENV. HEALTH
Manual J
NOC FORM



MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING

PRODUCT CONTROL NOTICE OF ACCEPTANCE

Premdor Entry Systems
911 E. Jefferson, P.O. Box 76
Pittsburgh, KS 66762

BUILDING CODE COMPLIANCE OFFICE
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1565
(305) 375-2901 FAX (305) 375-2908

CONTRACTOR LICENSING SECTION
(305) 375-2527 FAX (305) 375-2558

CONTRACTOR ENFORCEMENT DIVISION
(305) 375-2966 FAX (305) 375-2908

PRODUCT CONTROL DIVISION
(305) 375-2902 FAX (305) 372-6339

Your application for Notice of Acceptance (NOA) of:
Series Entry 6-8 S-W/E Inswing Opaque Residential Insulated Steel Door w/II. M. Frame
under Chapter 8 of the Code of Miami-Dade County governing the use of Alternate Materials and Types of
Construction, and completely described herein, has been recommended for acceptance by the Miami-Dade
County Building Code Compliance Office (BCCO) under the conditions specified herein.

This NOA shall not be valid after the expiration date stated below. BCCO reserves the right to secure this
product or material at any time from a jobsite or manufacturer's plant for quality control testing. If this
product or material fails to perform in the approved manner, BCCO may revoke, modify, or suspend the
use of such product or material immediately. BCCO reserves the right to revoke this approval, if it is
determined by BCCO that this product or material fails to meet the requirements of the South Florida
Building Code.


The expense of such testing will be incurred by the manufacturer.

ACCEPTANCE NO.: 01-0313.06
EXPIRES: 02/19/2006

Raul Rodriguez
Chief Product Control Division

THIS IS THE COVERSHEET, SEE ADDITIONAL PAGES FOR SPECIFIC AND GENERAL
CONDITIONS
BUILDING CODE & PRODUCT REVIEW COMMITTEE

This application for Product Approval has been reviewed by the BCCO and approved by the Building
Code and Product Review Committee to be used in Miami-Dade County, Florida under the conditions set
forth above.



APPROVED: 04/19/2001

Francisco J. Quintana, R.A.
Director
Miami-Dade County
Building Code Compliance Office

ACCEPTANCE NO.: 01-0313.06
APPROVED : APR 19 2001
EXPIRES : February 19, 2006

NOTICE OF ACCEPTANCE: SPECIFIC CONDITIONS

1. DESCRIPTION OF UNIT

- 1.1 This renews the Notice of Acceptance No. 97-0910.11 which was issued on February 19, 1998. It approves a residential insulated steel door, as described in Section 2 of this Notice of Acceptance, designed to comply with the South Florida Building Code (SFBC), 1994 Edition for Miami-Dade County, for the locations where the pressure requirements, as determined by SFBC Chapter 23, do not exceed the Design Pressure Rating values indicated in the approved drawings.

2. PRODUCT DESCRIPTION

- 2.1 The Series Entergy 6' 8" S-W/E Inswing Opaque Residential Insulated Steel Door in a Hollow Metal Frame-Impact and its components shall be constructed in strict compliance with the following documents: Drawing No 31-1032-EW-I, Sheets 1 through 5 of 5; titled "Premdor (Entergy Brand Wood Edge) 3'0" x 6'8" Steel door in a Hollow Metal Frame (Inswing)" dated 6/25/97 with revision C. dated 3/20/01, bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division. These documents shall hereinafter be referred to as the approved drawings.

3. LIMITATIONS

- 3.1 This approval applies to single unit applications of single door only, as shown in approved drawings.
- 3.2 Unit shall be installed only at locations protected by a canopy or overhang such that the angle between the edge of canopy or overhang to sill is less than 45 degrees. Unless unit is installed in non-habitable areas where the unit and the area are designed to accept water infiltration.

4. INSTALLATION

- 4.1 The residential insulated steel door and its components shall be installed in strict compliance with the approved drawings.
- 4.2 Hurricane protection system (shutters): the installation of this unit will not require a hurricane protection system.

5. LABELING

- 5.1 Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved".

6. BUILDING PERMIT REQUIREMENTS

- 6.1 Application for building permit shall be accompanied by copies of the following:
- 6.1.1 This Notice of Acceptance
- 6.1.2 Duplicate copies of the approved drawings, as identified in Section 2 of this Notice of Acceptance, clearly marked to show the components selected for the proposed installation.
- 6.1.3 Any other documents required by the Building Official or the South Florida Building Code (SFBC) in order to properly evaluate the installation of this system.


Manuel Perez, P.E. Product Control Examiner
Product Control Division



AMTROL INC.

WEL-FLO® Pre-pressurized Water System Tanks

- Proven Diaphragm Design
- Tough Gloss Finish
- Sizes from 14 to 119 Gallons
- Outstanding Value





NEW HOME CONST ONLY

Pump and Tank Code
Section 613
Well Pumps and Tanks used for private potable water
systems

~~July 1, 2001~~ March 1, 2002

613.1 Pumps. Well pumps used for potable water shall comply with sections 613.1.1 and 613.1.2
613.1.1 Pump Installation. Pumps shall be installed for operation without re-priming or breaking suction. Pumps shall be connected to the well head by means of a union, companion flange or compression coupling in such a manner that it is accessible for maintenance, repair and removal.
613.1.2 Pump Sizing. Minimum pump size shall be determined by table 613.1.

Table 613.1

Minimum Private Potable Water System Pump Size

	Bathrooms in Home				
Minimum Pump Size	1	1 1/2	2-2 1/2	3-4	5-6
	7gpm	10gpm	14gpm	17gpm	21gpm

Notes:

1. Values given are average and do not include high and low extremes
 2. Installations over 6 bathrooms shall be approved by the code official
- 613.2 Pressure Tanks. Tanks relying on expansion of a flexible membrane within a restricting container, or tanks with direct water-to-air interface to provide pressure in the water system shall be used. All pressure tanks for storing potable water under pressure, including those having an airspace for pressure for expansion shall be identified by seal, label, or plate indicating the manufacturer's name and model number and shall meet the following specifications:

Pressure tank drawdown shall be a minimum of 1 gallon for every gallon produced by the pump (Example: 20 gallon per minute pump will require a draw of 20 gallons usable). Exceptions: Pump start applications, constant pressure devices and variable speed pumps.

2. Pressure tanks must be constructed of steel, fiberglass, or comparable materials. Tanks to be buried shall have a minimum wall thickness of 1/4 inch and be built by the manufacturer specifically for underground use. Fiberglass or other non-metallic tanks to be buried shall have the structural strength to prevent collapse.

613.3 Piping. Piping associated with well pumps and tanks shall comply with Sections 613.3.1 through 613.3.5.

613.3.1 Drop Pipe. The Drop pipe from the submersible pump to the first fitting past the well seal shall be either galvanized steel, stainless steel, or PVC Schedule 80 threaded/coupled or lock joint pipe. The drop pipe for a single (pipe) jet pump shall be either galvanized steel, or stainless steel. The drop pipe for a double (pipe) jet shall be galvanized steel, stainless steel on the suction side and/or minimum PVC Schedule 40 on the pressure side.

613.3.2 Pump Discharge Pipe Sizing. For submersible pumps, pipe size shall be equal to the pump discharge. Piping for all other types of pumps shall be sized in accordance to the manufacturers specifications.

613.3.3 Pressure Tank Pipe Sizing. Piping size for the offset of the pressure tank shall use the piping friction loss charts for the piping material used.

613.4 Electrical wiring. All wiring shall be installed in accordance with chapter 27 of the Florida Building code and NFPA 70.

613.5 Disinfection. The pump installer shall disinfect any potable well and water system in accordance with Section 610.

613.6 Valves. A pressure relief valve shall be installed on any pumping system that can produce pressures of 75 psi or greater. A check valve shall be installed at the well head of submersible pumps.

* Cycle Stop valves ARE CONSTANT PRESS Device

* Counties may Add Higher Demands

HOL INC.

WELL-X-TROL 5

essurized Diaphragm Well Tanks

CHAMPION (WEL-FLO, PRO-LINE See Nat Sheet:

A

Model / Part No.	List Price (\$)	Diameter (ins)	Dimensions Height (ins)	Total Volume (gals)	Max. Accept. Factor	System Drawdown			Shipping Wt. (Vol.) lbs (cu ft)
						20/40 (gals)	30/60 (gals)	40/80 (gals)	
CH 4202/WF60/CA4202	213.00	15 1/4	31 1/2	20.0	0.57	8.0	6.8	5.9	33 (4.9)
CH 6000/WF80/CA6000	225.00	15 3/4	38 1/2	26.0	0.44	10.5	8.8	7.6	36.0
CH 8003/WF100/CA8003	364.00	15 3/4	46 1/2	32.0	0.35	-	10.9	9.4	43 (7.0)
CH 8205/WF110/CA8205	399.00	22	29 1/2	34.0	1.00	13.7	11.6	10.0	61 (9.5)
CH 10050/WF140/CA10050	461.00	22	36	44.0	0.77	17.7	15.0	13.0	69 (11.0)
CH 12051/WF200/CA12051	545.00	22	46 1/2	62.0	0.55	24.9	21.1	18.3	92 (13.5)
CH 17255/WF255/CA17255	585.00	22	56 1/2	81.0	0.41	32.6	27.5	23.9	103
CH 17252/WF252/CA17252	663.00	22	52 1/2	86.0	0.39	34.6	29.2	25.4	114 (18.1)
CH 17002/WF260/CA17002	647.00	26	47 1/2	86.0	0.54	34.6	29.2	25.4	123 (18.9)
CH 22050/WF360/CA22050	922.00	26	51 1/2	119.0	0.39	47.8	40.5	35.1	165 (24.5)

CH4202, CH8000, CH8003, WF60, WF80, WF100, CA 4202, CA6000, & CA8003 have a 1" NPTF system connection and a 28 psig pre-charge.

CH10050, CH12051, CH17255, CH17252, CH17002, CH22050 have a 1 1/2" NPTF system connection and a 38 psig pre-charge.

CH10050, CH12051, CH17255, CH17252, CH17002, CH22050 have a 1 1/2" NPTF system connection and a 38 psig pre-charge.



January 31, 2002

TO: OUR FLORIDA CUSTOMERS:

Effective February 1, 2002, the following TAMKO shingles, as manufactured at TAMKO's Tuscaloosa, Alabama, facility, comply with ASTM D-3161, Type I modified to 110 mph. Testing was conducted using four nails per shingle. These shingles also comply with Florida Building Code TAS 100 for wind driven rain.

- Glass-Seal AR
- Elite Glass-Seal AR
- ASTM Heritage 30 AR (formerly ASTM Heritage 25 AR)
- Heritage 40 AR (formerly Heritage 30 AR)
- Heritage 50 AR (formerly Heritage 40 AR)

All testing was performed by Florida State certified independent labs.


Please direct all questions to TAMKO's Technical Services Department at 1-800-641-4691.

TAMKO Roofing Products, Inc.

XX

Glazed Inswing Unit

COP-WL-JH4142-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:**

Note:
Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

Double Door
Maximum unit size = 6'0" x 6'8"

Design Pressure
+40.5/-40.5
Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0002-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0002-02.

APPROVED DOOR STYLES:**1/4 GLASS:**

100 Series



133, 135 Series



136 Series



880 Series



822 Series

1/2 GLASS:

105 Series*



106, 160 Series*



129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 6-panel; 6-panel with scroll; Eyebrow 6-panel; Eyebrow 6-panel with scroll.

Johnson
EntrySystems

March 29, 2002
Our continuing program of product improvement means specifications, design and product data are subject to change without notice.

PRENDOR
Premium Quality Doors

Continuously from
Masonite
Masonite International Corporation

XX

Glazed Inswing Unit

COP-WI-JH4142-02

WOOD-EDGE STEEL DOORS**APPROVED DOOR STYLES:****3/4 GLASS:**

404 Series



410 Series



490 Series

FULL GLASS:

100 Series

114, 120, 122
Series

152 Series



140 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested In Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2784-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

Kurt L. Bath

State of Florida, Professional Engineer
Kurt Bathazor, P.E. - License Number 56533

Johnson
EntrySystems


March 20, 2002
Our continuing program of product improvement makes specifications, design and product
detail subject to change without notice.

PREMIER Collection
Premium Quality Doors

Exclusively from
Masonite
Masonite International Corporation

XX
Unit

MID-WL-MA0002-02

DOUBLE DOOR

Minimum Fastener Count

- 6 per vertical framing member
- 8 per horizontal framing member

Hinge and strike plates require two 2-1/2" long screws per location.

Latching Hardware:

- Compliance requires that GRADE 2 or better (ANSI/BHMA A156.2) cylindrical and deadlock hardware be installed.

Notes:

1. Anchor calculations have been carried out with the lowest (least) fastener rating from the different fasteners being considered for use. Fasteners analyzed for this unit include #8 and #10 wood screws or 3/16" Tapcons.
2. The wood screw single shear design values come from Table 11.3A of ANSVAF & PA NDS for southern pine lumber with a side member thickness of 1-1/4" and penetration of minimum embedment. The 3/16" Tapcon single shear design values come from the ITW and ELCO Dade County approvals respectively, each with minimum 1-1/4" embedment.
3. Wood bucks by others, must be anchored properly to transfer loads to the structure.

March 29, 2002
Our continuing program of product improvement means specifications, design and product detail subject to change without notice.

PREMIER Collection
Premium Quality Doors



Exclusively from
Masonite

Masonite International Corporation



**AAMA/NWWDA 101/I.S.2-97
TEST REPORT**

Rendered to:

MI HOME PRODUCTS, INC.


SERIES/MODEL: 650

TYPE: Aluminum Triple Single Hung Window

Title of Test	Summary of Results
AAMA Rating	H-R35 112 x 72
Uniform Load Deflection Test Pressure	+35.3 psf -47.2 psf
Operating Force	25 lb max.
Air Infiltration	0.16 cfm/ft ²
Water Resistance Test Pressure	5.25 psf
Uniform Load Structural Test Pressure	+53.0 psf -52.5 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to ATI Report No. 01-41641.01 for complete description and data.

Allen H. Reeves
7 JUNE 2002





Architectural Testing

AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
P.O. Box 370
650 West Market Street
Gratz, Pennsylvania 17030-0370

Report No: 01-41641.01
Test Date: 05/13/02
And: 05/16/02
Report Date: 06/05/02
Expiration Date: 05/16/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to witness testing on a Series/Model 650, aluminum triple single hung window at their facility located in Elizabethville, Pennsylvania. The sample tested successfully met the performance requirements for a H-R35 112 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650

Type: Aluminum Triple Single Hung Window

Overall Size: 9' 3-1/2" wide by 5' 11-11/16" high


Active Sash Size (3): 3' 0-1/4" wide by 2' 10-3/4" high

Fixed Daylight Opening Size (3): 2' 8-1/4" wide by 2' 9-1/8" high

Screen Size (3): 2' 9-1/8" wide by 2' 11" high

Finish: All aluminum was painted white.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com





Test Specimen Description: (Continued)

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.


Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" by 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. The meeting rail was secured to the frame utilizing two 1-1/4" screws. The mullions were secured utilizing four #8 x 1-1/4" screws through the head and sill into the mullion screw boss.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each stiles' screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.



Test Specimen Description: (Continued)

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper	1	Midspan of each active meeting rail with adjacent keepers
Plastic tilt latch	2	Each active sash meeting rail ends
Metal tilt pin	2	Each active sash bottom rail ends
Balance assembly	2	Each active sash contained one in each jamb
Screen plunger	2	Each screen contained two 4" from rail ends on top rail

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	25 lbs	30 lbs max.
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.16 cfm/ft ²	0.3 cfm/ft ² max


Note #1: The tested specimen meets the performance levels specified in AAMA/NWWDA 101/I.S. 2-97 for air infiltration.

Water Resistance (ASTM E 547-00)
(with and without screen)
WTP = 2.86 psf

No leakage

No leakage

Allen N. Reeves
7 JUNE 2002






Test Results: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 52 seconds) @ 15.0 psf (positive) @ 15.0 psf (negative)	0.15" 0.29"	0.41" max. 0.41" max.
2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 10 seconds) @ 22.5 psf (positive) @ 22.5 psf (negative)	0.01" 0.01"	0.29" max. 0.29" max.
2.2 .6.2	Deglazing Test (ASTM E 987-88) In operating direction at 70 lbs Right sash, meeting rail Right sash, bottom rail Middle sash, meeting rail Middle sash, bottom rail Left sash, meeting rail Left sash, bottom rail In remaining direction at 50 lbs Right sash, right stile Right sash, left stile Middle sash, right stile Middle sash, left stile Left sash, right stile Left sash, left stile	 0.12"/25% 0.12"/25% 0.12"/25% 0.12"/25% 0.12"/25% 0.12"/25% 0.06"/12% 0.06"/12% 0.06"/12% 0.06"/12% 0.06"/12% 0.06"/12%	 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100%
2 .8	Forced Entry Resistance (ASTM F 588-97) Type: A Grade: 10 Lock Manipulation Test Test A1 through A5 Test A7 Lock Manipulation Test	 No entry No entry No entry No entry	 No entry No entry No entry No entry

Allen N. Reeves
7 JUNE 2002





Test Results: (Continued)


<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
<u>Optional Performance</u>			
4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 5.25 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 52 seconds)		
	@ 35.3 psf (positive)	0.46"*	0.41" max
	@ 47.2 psf (negative)	0.67"*	0.41" max

**Exceeds L/175 for deflection, but meets all other test requirements.*


Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 10 seconds)		
@ 53.0 psf (positive)	0.03"	0.29" max
@ 52.5 psf (negative)	0.02"	0.29" max

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.


For ARCHITECTURAL TESTING, INC:


Mark A. Hess
Technician

MAH:nlb
01-41641.01


Allen N. Reeves, P.E.
Director - Engineering Services
7 JUNE 2002





**AAMA/NWDA 101/I.S.2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.


SERIES/MODEL: 650 Fin

TYPE: Aluminum Single Hung Window

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10


Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.


For ARCHITECTURAL TESTING, INC.



Mark A. Hess, Technician

MAH:nlb


1 APRIL 2002





Architectural Testing

AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high


Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen M. Rasmussen
1 APRIL 2002





Test Specimen Description: (Continued)

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.


Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:


The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max
	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.02" 0.02"	0.18" max. 0.18" max.
---------	---	----------------	--------------------------

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)


<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 588-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.47"*	0.26" max.
	@ 47.2 psf (negative)	0.46"*	0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds)	
@ 67.5 psf (positive)	0.05"
@ 70.8 psf (negative)	0.05"



Allen N. Reeves
1 APRIL 2002



Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess
Technician

MAH:nlb
01-41134.01

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002




X

Glazed Inswing Unit

COP-WL-JH4141-02

WOOD-EDGE STEEL DOORS

APPROVED ARRANGEMENT:

**Note:**

Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itsamko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Single Door
Maximum unit size = 3'0" x 6'8"

Design Pressure

+40.5/-40.5

Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0001-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0001-02.

APPROVED DOOR STYLES:

1/4 GLASS:

160 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:

105 Series*



105, 160 Series*



129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

* This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems™

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite®
Masonite International Corporation

X

Glazed Inswing Unit

COP-WL-JH4141-02

WOOD-EDGE STEEL DOORS**APPROVED DOOR STYLES:**
3/4 GLASS:

404 Series



410 Series



450 Series

FULL GLASS:

109 Series

114, 120, 122
Series

152 Series



149 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533Test Data Review Certificate #3028447A
and COP/Test Report Validation Matrix
#3028447A-001 provides additional
information - available from the ITSAWH
website (www.itasemko.com), the
Masonite website (www.masonite.com)
or the Masonite technical center.**Johnson™**
EntrySystemsJune 17, 2002
Our continuing program of product improvement makes specifications, design and product
detail subject to change without notice.

Exclusively from

Masonite International Corporation

THIS INSTRUMENT PREPARED BY
AND RETURN TO:
TITLE OFFICES, LLC
1089 SW MAIN BLVD.
LAKE CITY, FLORIDA 32025

Parcel I.D. #: 08914-002

061-02124

24466

SPACE ABOVE THIS LINE FOR PROCESSING DATA

SPACE ABOVE THIS LINE FOR RECORDING DATA

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF COLUMBIA

THE UNDERSIGNED hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713.13, Florida Statutes, the following information is provided in this Notice of Commencement. This Notice shall be void and of no force and effect if construction is not commenced within ninety (90) days after recordation.

1. Description of property: (Legal description of property, and street address if available)

1381 SW BEDENBAUGH LANE, LAKE CITY, FLORIDA 32025
TOWNSHIP 4 SOUTH, RANGE 17 EAST

SECTION 30: THE W 1/4 OF THE E 1/4 OF THE FOLLOWING DESCRIBED REAL PROPERTY: 449.40 FEET EAST AND WEST BY 194.70 FEET NORTH AND SOUTH IN THE SOUTHEAST CORNER OF SE 1/4 OF SE 1/4, PAGE 672 OF 1976 TAX ROLL; MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCE AT THE SE CORNER OF SECTION 30, TOWNSHIP 4 SOUTH, RANGE 17 EAST, COLUMBIA COUNTY, FLORIDA AND RUN N 2°54'37" W ALONG THE EAST LINE OF SAID SECTION 30, A DISTANCE OF 219.49 FEET; THENCE S 87°58'49" W 53.40 FEET TO THE POINT OF BEGINNING; THENCE S 1°20'05" E 194.70 FEET; THENCE S 87°58'49" W 449.40 FEET; THENCE N 1°20'05" W 194.70 FEET; THENCE N 87°58'49" E 449.40 FEET TO THE POINT OF BEGINNING.

2. General description of improvement: construction of single family dwelling

3. Owner information:

- a. Name and address:
ELMER M. NICHOLS, JR. and RITA J. NICHOLS
439 SE LILLIAN LOOP, APT. 104, LAKE CITY,
FLORIDA 32025
- b. Interest in property: Fee Simple
- c. Name and Address of Fee Simple Titleholder (if other than owner):

4. Contractor: (Name and Address)

NORTON HOME IMPROVEMENT CO., INC.
3367 S. US HWY. 441, SUITE 101, LAKE CITY, FLORIDA 32025
Telephone Number: (386) 752-3331

5. Surety (if any):

Inst: 2006009992 Date: 04/25/2006 Time: 15:04

- a. Name and Address:
Telephone Number: _____
- b. Amount of Bond \$ _____

J. P. DeWitt Cason, Columbia County B: 1081 P: 1593

6. Lender: (Name and Address)

FIRST FEDERAL SAVINGS BANK OF FLORIDA
4705 WEST U.S. HWY 90, P.O. BOX 2029, LAKE CITY, FL 32056
Telephone Number: 755-0600

7. Persons within the State of Florida designated by Owner upon whom notice or other documents may be served as provided by Section 713.13(1)(a)7., Florida Statutes: (Name and Address)
N/A

8. In addition to himself, Owner designates the following person(s) to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes: (Name and Address) **PAULA HACKER**
FIRST FEDERAL SAVINGS BANK OF FLORIDA
4705 WEST U.S. HWY 90, P.O. BOX 2029, LAKE CITY, FL 32056
Telephone Number: 755-0600

9. Expiration date of Notice of Commencement (the expiration date is 1 year from the date of recording unless a different date is specified)

Elmer M. Nichols Jr. (SEAL)
ELMER M. NICHOLS, JR.

Rita J. Nichols (SEAL)
RITA J. NICHOLS

Sworn to and subscribed before me this 21st day of April, 2006, by ELMER M. NICHOLS, JR. and RITA J. NICHOLS, who are personally known to me or who have produced

as identification.

Martha Bryan
Notary Public

My Commission Expires:



Martha Bryan
MY COMMISSION # DD232534 EXPIRES
August 10, 2007
FARMERS GROUP FARM INSURANCE, INC.

Inst:2006009992 Date:04/25/2006 Time:15:04
_____, P. Dewitt Cason, Columbia County B:1081 P:1594

COLUMBIA COUNTY FLORIDA DEPARTMENT OF BUILDING AND ZONING

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 30-4S-17-08914-002

Building permit No. 000024466

Use Classification SFD, UTILITY

Fire: 18.17

Permit Holder JAMES NORTON

Waste: 0.00

Owner of Building ELMER & RITA NICHOLS

Total: 18.17

Location: 1381 SW BEDENBAUGH LANE



Date: 09/12/2006



[Signature]

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)

[Log On](#)[DBPR Home](#) | [Online Services Home](#) | [Help](#) | [Site Map](#)**Public Services**

[Search for a Licensee](#)
[Apply for a License](#)
[View Application Status](#)
[Apply to Retake Exam](#)
[Find Exam Information](#)
[Find a CE Course](#)
[File a Complaint](#)
[AB&T Delinquent Invoice & Activity List Search](#)

User Services

[Renew a License](#)
[Change License Status](#)
[Maintain Account](#)
[Change My Address](#)
[View Messages](#)
[Change My PIN](#)
[View Continuing Ed](#)

[Term Glossary](#)[Online Help](#)**Licensee Details****Licensee Information**

Name: **NORTON, JAMES H (Primary Name)**
NORTON HOME IMPROVEMENT COMPANY
INC (DBA Name)
Main Address: **RT 28 BOX 388A**
LAKE CITY, Florida 32025
Lic. Location: **RT 28 BOX 388A**
LAKE CITY, FL 32025
Columbia

License Information

License Type: **Registered Building Contractor**
Rank: **Reg Building**
License Number: **RB0031780**
Status: **Current, Active**
Licensure Date: **02/16/1978**
Expires: **08/31/2005**

Special Qualifications Effective Date

Bldg Code Core Course Credit

Qualified Business License Required 02/20/2004

[View Related License Information](#)

[View License Complaint](#)

[New Search](#)[Back](#)[Terms of Use](#) | [Privacy Statement](#)

Job L156415	Truss T01G	Truss Type SPECIAL	Qty 1	Ply 1	Job Reference (optional)
----------------	---------------	-----------------------	----------	----------	--------------------------

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Thu Apr 06 14:29:06 2006 Page 1




Plate Offsets (X,Y): [2:0-3-8,Edge], [3:0-1-11,0-1-8], [4:0-3-0,0-3-0], [18:0-3-0,0-1-9], [21:0-5-0,Edge], [21:0-1-12,0-2-8], [27:0-3-0,0-0-4], [34:0-3-0,0-0-4]

LOADING (psf)	SPACING	CS	DEFL	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.90	In (loc) 22	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.50	Vert(LL) 0.13		
BCLL 10.0	Rep Stress Incr NO	WB 0.27	Vert(TL) 0.22		
BCDL 5.0	Code FBC2004/TP12002	(Matrix)	Horz(TL) 0.01		
				Weight: 257 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2 "Except"
 T5 2 X 4 SYP No.1D
 BOT CHORD 2 X 4 SYP No.2
 OTHERS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 11-32

REACTIONS (lb/size) 21=722/41-8-0, 2=550/41-8-0, 32=265/41-8-0, 33=287/41-8-0, 35=288/41-8-0, 36=288/41-8-0, 37=285/41-8-0, 38=299/41-8-0, 39=244/41-8-0, 40=421/41-8-0, 31=287/41-8-0, 30=289/41-8-0, 29=286/41-8-0, 28=296/41-8-0, 26=255/41-8-0, 25=429/41-8-0, 24=293/41-8-0, 23=1257/41-8-0
 Max Horz 2=147(load case 5)
 Max Uplift 21=-353(load case 4), 2=-215(load case 5), 33=-118(load case 5), 35=-137(load case 5), 36=-131(load case 5), 37=-131(load case 5), 38=-135(load case 5), 39=-120(load case 5), 40=-178(load case 5), 31=-113(load case 6), 30=-139(load case 6), 29=-130(load case 6), 28=-134(load case 6), 26=-122(load case 6), 25=-177(load case 6), 24=-294(load case 10), 23=-463(load case 4)
 Max Grav 21=722(load case 1), 2=550(load case 1), 32=265(load case 1), 33=291(load case 9), 35=288(load case 1), 36=289(load case 9), 37=285(load case 1), 38=299(load case 9), 39=244(load case 1), 40=422(load case 9), 31=291(load case 10), 30=289(load case 1), 29=286(load case 10), 28=296(load case 1), 26=255(load case 10), 25=429(load case 1), 24=102(load case 4), 23=1257(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-8/54, 2-3=-167/76, 3-4=-153/72, 4-5=-91/102, 5-6=-75/131, 6-7=-78/168, 7-8=-78/204, 8-9=-78/242, 9-10=-78/303, 10-11=-78/349, 11-12=-78/349, 12-13=-78/303, 13-14=-78/242, 14-15=-78/186, 15-16=-76/128, 16-17=-85/94, 17-18=-33/62, 18-19=-32/59, 19-20=-132/87, 20-21=-112/82, 21-22=-8/53
BOT CHORD 2-40=0/158, 39-40=0/165, 38-39=0/165, 37-38=0/165, 36-37=0/165, 35-36=0/165, 34-35=0/165, 33-34=0/165, 32-33=0/165, 31-32=0/165, 30-31=0/165, 29-30=0/165, 28-29=0/165, 27-28=0/165, 26-27=0/165, 25-26=0/165, 24-25=0/165, 23-24=0/165, 22-23=0/165
WEBS 11-32=-205/0, 10-33=-231/139, 9-35=-228/171, 8-36=-228/161, 7-37=-227/162, 6-38=-234/166, 5-39=-201/151, 4-40=-320/210, 12-31=-231/139, 13-30=-229/171, 14-29=-227/161, 15-28=-232/165, 16-26=-208/152, 17-25=-320/212, 19-24=-83/172, 20-23=-922/526

JOINT STRESS INDEX

2 = 0.71, 3 = 0.00, 3 = 0.34, 4 = 0.32, 5 = 0.34, 6 = 0.34, 7 = 0.34, 8 = 0.34, 9 = 0.34, 10 = 0.34, 11 = 0.18, 12 = 0.34, 13 = 0.34, 14 = 0.34, 15 = 0.34, 16 = 0.34, 17 = 0.34, 18 = 0.36, 19 = 0.00, 20 = 0.34, 21 = 0.92, 21 = 0.13, 23 = 0.34, 24 = 0.34, 25 = 0.34, 26 = 0.00, 27 = 0.30, 28 = 0.34, 29 = 0.34, 30 = 0.34, 31 = 0.34, 32 = 0.34, 33 = 0.34, 34 = 0.30, 35 = 0.00, 36 = 0.34, 37 = 0.34, 38 = 0.34, 39 = 0.34 and 40 = 0.34


NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) The following joint(s) require plate inspection per the Tooth Count Method when this truss is chosen for quality assurance inspection: 21 and 21.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 2-0-0 oc.
- 8) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 353 lb uplift at joint 21, 215 lb uplift at joint 2, 118 lb uplift at joint 33, 137 lb uplift at joint 35, 131 lb uplift at joint 36, 131 lb uplift at joint 37, 135 lb uplift at joint 38, 120 lb uplift at joint 39, 178 lb uplift at joint 40, 113 lb uplift at joint 31, 139 lb uplift at joint 29, 130 lb uplift at joint 30, 130 lb uplift at joint 28, 122 lb uplift at joint 26, 177 lb uplift at joint 25, 294 lb uplift at joint 24 and 463 lb uplift at joint 23.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

Continued on page 2

APRIL 06, 2006 TRUSS DESIGN ENGINEER:
 THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
 STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
 16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



Job L156415	Truss T03	Truss Type SPECIAL	Qty 3	Ply 1	Job Reference (optional)
----------------	--------------	-----------------------	----------	----------	--------------------------

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Thu Apr 06 14:29:07 2006 Page 1




Plate Offsets (X,Y): [1:0-5-15,Edge], [4:0-3-8,0-3-0], [12:0-3-8,0-2-8]

LOADING (psf)	SPACING	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.59	Vert(LL)	-0.27	1-17	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.81	Vert(TL)	-0.47	1-17	>914	180		
BCLL 10.0	Rep Stress Incr YES	WB 0.82	Horz(TL)	0.09	11	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002	(Matrix)							
								Weight: 227 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3
 SLIDER Left 2 X 6 SYP No.1D 2-2-10

BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-2-8 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 4-15, 6-15

REACTIONS (lb/size) 1=1441/0-4-0, 11=2067/0-4-0, 9=95/0-4-0
 Max Horz 1=163(load case 6)
 Max Uplift 1=470(load case 5), 11=655(load case 6), 9=212(load case 4)
 Max Grav 1=1441(load case 1), 11=2067(load case 1), 9=144(load case 10)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-2355/1102, 2-3=-2311/1111, 3-4=-2173/988, 4-5=-1588/846, 5-6=-1584/847, 6-7=-2005/931, 7-8=-1479/702, 8-9=-417/1015, 9-10=0/25
 BOT CHORD 1-17=-834/2001, 16-17=-632/1888, 15-16=-632/1888, 14-15=-572/1726, 13-14=-566/1459, 12-13=-566/1459, 11-12=-940/480, 9-11=-940/480
 WEBS 3-17=-171/213, 4-17=-7/326, 4-15=-739/413, 5-15=-454/971, 6-15=-567/341, 6-14=0/173, 7-14=-48/284, 7-12=-873/476, 8-12=-1107/2553, 8-11=-188/1887

JOINT STRESS INDEX
 1 = 0.75, 1 = 0.85, 2 = 0.00, 3 = 0.34, 4 = 0.69, 5 = 0.63, 6 = 0.41, 7 = 0.72, 8 = 0.77, 9 = 0.28, 11 = 0.69, 12 = 0.57, 13 = 0.65, 14 = 0.35, 15 = 0.57, 16 = 0.67 and 17 = 0.35

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 470 lb uplift at joint 1, 655 lb uplift at joint 11 and 212 lb uplift at joint 9.

LOAD CASE(S) Standard

Job L156415	Truss T04	Truss Type SPECIAL	Qty 2	Ply 1	Job Reference (optional)
Builders FirstSource, Lake City, FL 32055			6.200 s Jul 13 2005 MiTek Industries, Inc. Thu Apr 06 14:29:08 2006 Page 1		




Plate Offsets (X,Y): [1:0-5-15,Edge], [4:0-3-8,0-3-0], [10:0-3-8,0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.63	in (loc) l/def L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.83	Vert(LL) -0.28 1-15 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.77	Vert(TL) -0.47 1-15 >899 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.11 9 n/a n/a		
	Code FBC2004/TP12002			Weight: 206 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3
 SLIDER Left 2 X 6 SYP No.1D 2-2-10

BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-0-7 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-4-5 oc bracing.
 WEBS 1 Row at midpt 4-13, 6-13

REACTIONS (lb/size) 1=1492/0-4-0, 9=1492/Mechanical
 Max Horz 1=182(load case 5)
 Max Uplift 1=483(load case 5), 9=485(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-2448/1137, 2-3=-2403/1145, 3-4=-2276/1027, 4-5=-1695/886, 5-6=-1691/887, 6-7=-2240/1020, 7-8=-2148/950, 8-9=-1438/646
 BOT CHORD 1-15=-980/2079, 14-15=-785/1980, 13-14=-785/1980, 12-13=-769/1935, 11-12=-769/1935, 10-11=-926/2106, 9-10=-32/68
 WEBS 3-15=-161/207, 4-15=-6/322, 4-13=-736/411, 5-13=-489/1066, 6-13=-691/397, 6-11=-15/305, 7-11=-230/170, 7-10=-691/419, 8-10=-951/2168

JOINT STRESS INDEX
 1 = 0.76, 1 = 0.89, 2 = 0.00, 3 = 0.34, 4 = 0.70, 5 = 0.63, 6 = 0.41, 7 = 0.77, 8 = 0.82, 9 = 0.69, 10 = 0.86, 11 = 0.35, 12 = 0.70, 13 = 0.57, 14 = 0.84 and 15 = 0.35

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 483 lb uplift at joint 1 and 485 lb uplift at joint 9.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
L156415	T05G	COMMON	1	1	

Builders FirstSource, Lake City, Fl 32055

6.200 s Jul 13 2005 Mitek Industries, Inc. Thu Apr 06 14:29:09 2006 Page 1




Plate Offsets (X, Y): [2:0-3-8,Edge], [3:0-1-11,0-1-8], [7:0-3-0,0-3-0], [15:0-3-0,0-3-0], [19:0-1-11,0-1-8], [20:0-3-8,Edge], [27:0-3-0,0-0-4], [33:0-3-0,0-0-4]

LOADING (psf)	SPACING	CSI	DEFL	In (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.49	Vert(LL)	-0.03	21	n/r	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.08	Vert(TL)	-0.05	21	n/r		
BCLL 10.0	Lumber Increase 1.25	WB 0.27	Horz(TL)	0.01	20	n/a		
BCDL 5.0	Rep Stress Incr NO	(Matrix)						
	Code FBC2004/TPI2002						Weight: 239 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 OTHERS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 11-30

REACTIONS (lb/size) 2=557/35-8-0, 30=246/35-8-0, 31=286/35-8-0, 32=289/35-8-0, 34=287/35-8-0, 35=285/35-8-0, 36=302/35-8-0, 37=235/35-8-0, 38=431/35-8-0, 29=286/35-8-0, 28=289/35-8-0, 26=287/35-8-0, 25=285/35-8-0, 24=302/35-8-0, 23=235/35-8-0, 22=431/35-8-0, 20=557/35-8-0
 Max Horz 2=147(load case 6)
 Max Uplift 2=214(load case 5), 31=118(load case 5), 32=138(load case 5), 34=130(load case 5), 35=131(load case 5), 36=137(load case 5), 37=113(load case 5), 38=185(load case 5), 29=114(load case 6), 28=139(load case 6), 26=130(load case 6), 25=131(load case 6), 24=136(load case 6), 23=115(load case 6), 22=180(load case 6), 20=245(load case 6)
 Max Grav 2=557(load case 1), 30=246(load case 1), 31=290(load case 9), 32=289(load case 1), 34=287(load case 9), 35=285(load case 1), 36=302(load case 9), 37=235(load case 1), 38=432(load case 9), 29=290(load case 10), 28=289(load case 1), 26=287(load case 10), 25=285(load case 1), 24=302(load case 10), 23=235(load case 1), 22=432(load case 10), 20=557(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-8/54, 2-3=-181/66, 3-4=-157/64, 4-5=-113/96, 5-6=-97/124, 6-7=-101/162, 7-8=-101/198, 8-9=-101/237, 9-10=-102/297, 10-11=-100/344, 11-12=-100/344, 12-13=-102/297, 13-14=-101/237, 14-15=-101/180, 15-16=-102/123, 16-17=-97/64, 17-18=-113/35, 18-19=-94/9, 19-20=-181/12, 20-21=-8/54
 BOT CHORD 2-38=0/171, 37-38=0/171, 36-37=0/171, 35-36=0/171, 34-35=0/171, 33-34=0/171, 32-33=0/171, 31-32=0/171, 30-31=0/171, 29-30=0/171, 28-29=0/171, 27-28=0/171, 26-27=0/171, 25-26=0/171, 24-25=0/171, 23-24=0/171, 22-23=0/171, 20-22=0/171
 WEBS 11-30=-186/0, 10-31=-230/139, 9-32=-229/171, 8-34=-227/160, 7-35=-227/162, 6-36=-238/168, 5-37=-192/144, 4-38=-329/217, 12-29=-230/139, 13-28=-229/171, 14-26=-227/161, 15-25=-227/162, 16-24=-237/168, 17-23=-192/144, 18-22=-329/217


JOINT STRESS INDEX
 2 = 0.71, 3 = 0.00, 3 = 0.35, 3 = 0.35, 4 = 0.34, 5 = 0.34, 6 = 0.34, 7 = 0.21, 8 = 0.34, 9 = 0.34, 10 = 0.34, 11 = 0.18, 12 = 0.34, 13 = 0.34, 14 = 0.34, 15 = 0.21, 16 = 0.34, 17 = 0.34, 18 = 0.34, 19 = 0.00, 19 = 0.35, 19 = 0.35, 20 = 0.71, 22 = 0.34, 23 = 0.34, 24 = 0.34, 25 = 0.34, 26 = 0.00, 27 = 0.30, 28 = 0.34, 29 = 0.34, 30 = 0.34, 31 = 0.34, 32 = 0.34, 33 = 0.30, 34 = 0.00, 35 = 0.34, 36 = 0.34, 37 = 0.34 and 38 = 0.34

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02: 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Mitek "Standard Gable End Detail"
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 214 lb uplift at joint 2, 118 lb uplift at joint 31, 138 lb uplift at joint 32, 130 lb uplift at joint 34, 131 lb uplift at joint 35, 137 lb uplift at joint 36, 113 lb uplift at joint 37, 185 lb uplift at joint 38, 114 lb uplift at joint 29, 139 lb uplift at joint 28, 130 lb uplift at joint 26, 131 lb uplift at joint 25, 136 lb uplift at joint 24, 115 lb uplift at joint 23, 180 lb uplift at joint 22 and 245 lb uplift at joint 20.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert 1-11=-114(F=-60), 11-21=-114(F=-60), 2-20=-30



Job L156415	Truss T07G	Truss Type COMMON	Qty 1	Ply 1	Job Reference (optional)
----------------	---------------	----------------------	----------	----------	--------------------------

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Thu Apr 06 14:29:11 2006 Page 1




Plate Offsets (X,Y): [2-0-2-12,0-1-12], [14-0-2-12,0-1-4]

LOADING (psf)	SPACING	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2'-0-0	TC 0.49	Vert(LL)	-0.04	15	n/r	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.07	Vert(TL)	-0.06	15	n/r		
BCLL 10.0	Lumber Increase 1.25	WB 0.11	Horz(TL)	0.00	14	n/a		
BCDL 5.0	Rep Stress Incr NO	(Matrix)						
	Code FBC2004/TP12002							
							Weight: 118 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 OTHERS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS (lb/size) 2=501/21-0-0, 14=501/21-0-0, 21=265/21-0-0, 22=289/21-0-0, 23=285/21-0-0, 24=303/21-0-0, 25=231/21-0-0, 19=289/21-0-0, 18=285/21-0-0, 17=303/21-0-0, 16=231/21-0-0
 Max Horz 2=95(load case 5)
 Max Uplift 2=242(load case 5), 14=264(load case 6), 22=-129(load case 5), 23=-130(load case 5), 24=-145(load case 5), 25=-81(load case 5), 19=-127(load case 6), 18=-131(load case 6), 17=-146(load case 6), 16=-78(load case 5)
 Max Grav 2=501(load case 1), 14=501(load case 1), 21=265(load case 1), 22=293(load case 9), 23=285(load case 1), 24=303(load case 9), 25=231(load case 9), 19=293(load case 10), 18=285(load case 1), 17=303(load case 10), 16=231(load case 10)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-8/54, 2-3=-133/49, 3-4=-77/47, 4-5=-73/71, 5-6=-76/147, 6-7=-76/200, 7-8=-76/200, 8-9=-76/200, 9-10=-76/147, 10-11=-77/90,
 11-12=-73/34, 12-13=-36/14, 13-14=-133/16, 14-15=-8/54
 BOT CHORD 2-25=0/116, 24-25=0/116, 23-24=0/116, 22-23=0/116, 21-22=0/116, 20-21=0/116, 19-20=0/116, 18-19=0/116, 17-18=0/116, 16-17=0/116,
 14-16=0/116
 WEBS 8-21=-205/0, 7-22=-233/154, 6-23=-226/164, 5-24=-238/173, 4-25=-184/114, 9-19=-233/154, 10-18=-226/164, 11-17=-238/173,
 12-16=-184/114

JOINT STRESS INDEX


2 = 0.70, 3 = 0.00, 3 = 0.00, 3 = 0.29, 4 = 0.34, 5 = 0.34, 6 = 0.34, 7 = 0.34, 8 = 0.25, 9 = 0.34, 10 = 0.34, 11 = 0.34, 12 = 0.34, 13 = 0.00, 13 = 0.29, 13 = 0.00, 14 = 0.70, 16 = 0.34, 17 = 0.34, 18 = 0.34, 19 = 0.34, 20 = 0.15, 21 = 0.34, 22 = 0.34, 23 = 0.34, 24 = 0.34 and 25 = 0.34


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2'-0-0 oc.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 242 lb uplift at joint 2, 264 lb uplift at joint 14, 129 lb uplift at joint 22, 130 lb uplift at joint 23, 145 lb uplift at joint 24, 81 lb uplift at joint 25, 127 lb uplift at joint 19, 131 lb uplift at joint 18, 146 lb uplift at joint 17 and 78 lb uplift at joint 16.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert 1-8=-114(F=60), 8-15=-114(F=60), 2-14=-30





Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
L156415	T11	COMMON	2	1	

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mittek Industries, Inc. Thu Apr 06 14:29:14 2006 Page 1




Plate Offsets (X,Y): [2-0-5-15,Edge], [6-0-5-15,Edge]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.44	Vert(LL)	-0.10	6-7	>999	240	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.36	Vert(TL)	-0.14	6-7	>999	180		
BCLL 10.0	Lumber Increase 1.25	WB 0.08	Horz(TL)	0.02	6	n/a	n/a		
BCDL 5.0	Rep Stress Incr YES	(Matrix)							
	Code FBC2004/TP12002								
								Weight: 79 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3
 SLIDER Left 2 X 6 SYP No.1D 4-4-2, Right 2 X 6 SYP No.1D 4-4-2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 6=644/0-4-0, 2=766/0-4-0

Max Horz 2=93(load case 5)

Max Uplift 6=-208(load case 6), 2=-330(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/26, 2-3=-831/360, 3-4=-736/377, 4-5=-736/370, 5-6=-825/350

BOT CHORD 2-7=-192/659, 6-7=-192/659

WEBS 4-7=0/258


JOINT STRESS INDEX

2 = 0.47, 2 = 0.16, 2 = 0.16, 3 = 0.00, 4 = 0.75, 5 = 0.00, 6 = 0.47, 6 = 0.16, 6 = 0.16 and 7 = 0.19

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 208 lb uplift at joint 6 and 330 lb uplift at joint 2.

LOAD CASE(S) Standard



Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
L156415	T01G	SPECIAL	1	1	

Builders FirstSource, Lake City, Fl 32055

6.200 s Jul 13 2005 Mitek Industries, Inc. Thu Apr 06 14:29:06 2006 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)


Vert: 1-11=-114(F=60), 11-18=-114(F=60), 18-22=-114(F=60), 2-21=30

Symbols

PLATE LOCATION AND ORIENTATION



* Center plate on joint unless dimensions indicate otherwise. Dimensions are in inches. Apply plates to both sides of luss and webs and secure.



* For 1 x 2 orientation, locate plates 1/8" from outside edge of luss and vertical web.



* This symbol indicates the required direction of slits in connector plates.

PLATE SIZE




The first dimension is the width perpendicular to slits. Second dimension is the length parallel to slits.

LATERAL BRACING




Indicates location of required continuous lateral bracing.

BEARINGS



Indicates location of joints at which bearings (supports) occur.

Numbering System



JOINTS AND CHORDS ARE NUMBERED CLOCKWISE AROUND THE TRUSS STARTING AT THE LOWEST JOINT FARTHEST TO THE LEFT.

WEBS ARE NUMBERED FROM LEFT TO RIGHT

CONNECTOR PLATE CODE APPROVALS

BOCA	96-31, 96-67
ICBO	3907, 4922
SBCCI	9667, 9432A
WISC/DIHR	960022 W, 970036 II
IER	561



MITEL Engineering Reference Sheet: MIT-7473

General Safety Notes

Failure to Follow Could Cause Properly Damage or Personal Injury

1. Provide copies of this luss design to the building designer, erection supervisor, properly owner and all other interested parties.
2. Cut members to bear tightly against each other.
3. Place plates on each face of luss at each joint and embed fully. Avoid knots and weave at joint locations.
4. Unless otherwise noted, locate chord splices at 1/4 panel length (12' from adjacent joint).
5. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
6. Unless expressly noted, this design is not applicable for use with the redundant or preservative treated lumber.
7. Camber is a non-structural consideration and is the responsibility of luss fabricator. General practice is to camber for dead load deflection.
8. Plate type, size and location dimensions shown indicate minimum plating requirements.
9. Lumber shall be of the species and size, and in all respects, equal to or better than the grade specified.
10. Top chords must be sheathed or purlins provided at spacing shown on design.
11. Bottom chords require lateral bracing at 10 ft spacing, or less, if no ceiling is installed, unless otherwise noted.
12. Anchorage and / or load transferring connections to lusses are the responsibility of others unless shown.
13. Do not overload roof or floor lusses with stacks of construction materials.
14. Do not cut or alter luss member or plate without prior approval of a professional engineer.
15. Care should be exercised in handling, erection and installation of lusses.

© 1993 MITEL Holdings, Inc.

BEARING HEIGHT SCHEDULE

8'-0"

6/12 PITCH
(3/12 PITCH -- FRONT PORCH)
2' OVERHANGS

NOTES:

- 1) REFER TO BID SPECIFICATIONS FOR BRACKING INSTALLATION AND TRUSS/RAFT BRACKING. REFER TO ENGINEERED DRAWINGS FOR ROUGHEN BRACKING REQUIRED.
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECIDED OR REFER TO DETAIL VIDS FOR ALTERNATE BRACING REQUIREMENTS.
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
- 4) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6) S142 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
- 7) ALL ROOF TRUSS HANGERS TO BE SHIPSON HTD5 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSS HANGERS TO BE SHIPSON TR4422 UNLESS OTHERWISE NOTED.
- 8) BEAM/HEADER/INTEL (NOR) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VIDS. ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU!

Requested Drawing Date: _____

Approved By: _____ Date: _____





Builders FirstSource
Bunnell
PHONE: 904-437-3349 FAX: 904-437-3994
Jacksonville
PHONE: 904-772-6100 FAX: 904-772-1973
Lake City
PHONE: 386-755-6894 FAX: 386-755-7973
Sanford
PHONE: 407-322-0059 FAX: 407-322-5553

BUILDER:
NORTON HOME IMP. CO. INC.

TRAIL ADDRESS:
NICHOLS RESIDENCE

MODEL:
CUSTOM SCALE: NTS REGION:

DWG:
03-20-06 FROM DT: RAL DWG I: L156415



*** HAGNER SCHEDULE ***

8 - HTU26