

BOARD OF COUNTY COMMISSIONERS
OFFICE OF
BUILDING & ZONING
COLUMBIA COUNTY, FLORIDA

BUILDING PERMIT RECEIPT

RECEIPT NUMBER / PERMIT NUMBER 000029234 DATE 03/07/2011
APPLICANT PATRICIA JOHNSON
OWNER PATRICIA JOHNSON
CONTRACTOR PATRICIA JOHNSON
PARCEL ID NUMBER 10-4S-16-02853-415 NUMBER OF EXISTING DWELLINGS 0
TYPE OF DEVELOPMENT RE-NEW 28279, SFD
COMMENTS: RE-NEWAL PERMIT # 28279-EXPIRED, 75% COMPLETED
EXISTING PLANS MOVED TO THIS FILE
NEW NOC RECORDED

FEES:

BUILDING PERMIT	<u>0.00</u>	CERTIFICATION FEE	<u>0.00</u>
ZONING FEE	<u></u>	SURCHARGE FEE	<u>0.00</u>
FLOOD ZONE FEE	<u></u>	FLOOD DEVELOPMENT PERMIT	<u></u>
MOBILE HOME PERMIT	<u></u>	RELOCATION PERMIT	<u></u>
TRAVEL TRAILER PERMIT	<u></u>	RE-NEW PERMIT	<u>288.75</u>
UTILITY POLE PERMIT	<u></u>	WASTE ASSESSMENT FEE	<u></u>
FIRE FEE (5 ACRES OR LESS)	<u></u>	CULVERT PERMIT	<u></u>
FIRE FEE (MORE THAN 5 ACRES)	<u></u>	RENEW PERMIT	<u></u>

CHECK NUMBER 2213

TOTAL FEES CHARGES 288.75

MAKE CHECKS PAYABLE TO: BCC (Board of County Commissioners)

NOTE: A SEPARATE CHECK IS REQUIRED FOR THE CULVERT WAIVER PERMITS

135 NE HERNANDO AVE.
SUITE B-21
LAKE CITY, FL 32055
Phone: 386-758-1008
Fax: 386-758-2160



Columbia County Building Permit Application

For Office Use Only Application # 0912-16 Date Received 12/1/09 By GT Permit # 1776/28229
Zoning Official BLK Date 09-12-09 Flood Zone X Land Use RES. L-Dev Zoning RSF-2
FEMA Map # N/A Elevation N/A MFE 18 ft above RL River N/A Plans Examiner WR Date 12/15/09
Comments _____
☒ NOC ☒ EH ☒ Deed or PA ☒ Site Plan ☐ State Road Info ☐ Parent Parcel # _____
☐ Dev Permit # _____ ☐ In Floodway ☐ Letter of Auth. from Contractor ☐ F W Comp. letter
IMPACT FEES: EMS _____ Fire _____ Corr _____ Road/Code _____
School _____ = TOTAL N/A Suspended

Septic Permit No. _____ Fax _____
Name Authorized Person Signing Permit Patricia M Johnson Phone 386-755-4038
Address 204 SW Dusty Glen Lake City, FL 32024
Owners Name John S and Patricia M Johnson Phone 386-755-4038
911 Address 234 SW Scott Place Lake City, FL 32024
Contractors Name Patricia M Johnson Phone 386-755-4038
Address 204 SW Dusty Glen Lake City FL 32024
Fee Simple Owner Name & Address _____
Bonding Co. Name & Address _____
Architect/Engineer Name & Address Mark Disoway PO Box 868 Lake City, FL 32056
Mortgage Lenders Name & Address _____

Circle the correct power company - FL Power & Light - Clay Elec - Suwannee Valley Elec. - Progress Energy

Property ID Number 10-45-16-02853-415 Estimated Cost of Construction \$198,000.

Subdivision Name Russwood Estates Lot 15 Block _____ Unit 4 Phase _____

Driving Directions Branford Hwy (247) Right on Troy ST one mile. Right into Russwood Estates. Russwood Terrace To left on Bethany Place. Right on Dorothy. Right on Scott Place to end on right
Number of Existing Dwellings on Property 0

Construction of Wood Frame SFD Total Acreage 3/4 Lot Size 33.133 sq ft

Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive Total Building Height 24'

Actual Distance of Structure from Property Lines - Front 46 Side 39 Side 34 Rear 85

Number of Stories 1 Heated Floor Area 3124 Total Floor Area 4612 Roof Pitch 7/12

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

Spoke to John
12/16/09

Columbia County Building Permit Application

TIME LIMITATIONS OF APPLICATION : An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment


According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUILDING PERMITEE:

YOU ARE HEREBY NOTIFIED as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.


WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

OWNERS CERTIFICATION: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning. I further understand the above written responsibilities in Columbia County for obtaining this Building Permit.



Owners Signature

CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit.



Contractor's Signature (Permitee)

Contractor's License Number RR 28²⁸ 211528
Columbia County
Competency Card Number 337

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 10 day of Nov 2009.
Personally known _____ or Produced Identification DL



State of Florida Notary Signature (For the Contractor)

SEAL:



VERA LISA HICKS
Notary Public, State of Florida
My Comm. Expires Aug. 23, 2010
Comm. No. DD 568090

SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER _____ CONTRACTOR Patricia M. Johnson PHONE 386-755-4038

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is REQUIRED that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL ER13012377	Print Name <u>Holly Electric INC</u> License #: <u>ER13012377</u>	Signature <u>[Signature]</u> Phone #: <u>386-755-5944</u>
MECHANICAL/ A/C	Print Name <u>Booster Htg & H/C</u> License #: <u>RA0035027</u>	Signature <u>[Signature]</u> Phone #: <u>386-754-6700</u>
PLUMBING/ GAS	Print Name <u>Caly Davis Buss Plumbing</u> License #: <u>CFC1427145 (115)</u>	Signature <u>[Signature]</u> Phone #: <u>386-623-0509</u>
ROOFING	Print Name <u>Darrell Turner</u> License #: <u>CCC1328465</u>	Signature <u>[Signature]</u> Phone #: <u>755-0086</u>
SHEET METAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
FIRE SYSTEM/ SPRINKLER	Print Name _____ License #: _____	Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____	Signature _____ Phone #: _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER	<u>000218</u>	<u>TONY E. JORDAN SR</u>	<u>[Signature]</u>
FRAMING	<u>RG0066597</u>	<u>John D. Norris</u>	<u>[Signature]</u>
INSULATION	<u>RR282811528</u>	<u>Patricia M Johnson</u>	<u>[Signature]</u>
STUCCO			
DRYWALL	<u>000345</u>	<u>Kim Heitzman</u>	<u>[Signature]</u>
PLASTER			
CABINET INSTALLER	<u>RR282811528</u>	<u>Patricia M Johnson</u>	<u>[Signature]</u>
PAINTING	<u>RR282811528</u>	<u>Patricia M Johnson</u>	<u>[Signature]</u>
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE	<u>RR282811528</u>	<u>Patricia M Johnson</u>	<u>[Signature]</u>
FLOOR COVERING	<u>RR282811528</u>	<u>Patricia M Johnson</u>	<u>[Signature]</u>
ALUM/VINYL SIDING			
GARAGE DOOR	<u>RR282811528</u>	<u>Patricia M Johnson</u>	<u>[Signature]</u>
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER 0912-10

CONTRACTOR Patricia M. Johnson PHONE 386-755-403

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL ER13012377	Print Name <u>Holly Electric INC</u> License #: <u>ER13012377</u> Phone #: <u>386-755-5944</u>	Signature <u>[Signature]</u>
MECHANICAL/A/C	Print Name <u>BARTER HTg & H/C</u> License #: <u>RA0035027</u> Phone #: <u>386-754-6700</u>	Signature <u>[Signature]</u>
PLUMBING/GAS	Print Name <u>Cody Davis Buss Plumbing</u> License #: <u>CFC1427145</u> Phone #: <u>386-823-0509</u>	Signature <u>[Signature]</u>
ROOFING	Print Name <u>Darrell Turner</u> License #: <u>CCC1328465</u> Phone #: <u>755-0086</u>	Signature <u>[Signature]</u>
SHEET METAL	Print Name _____ License #: _____ Phone #: _____	Signature _____
FIRE SYSTEM/SPRINKLER	Print Name _____ License #: _____ Phone #: _____	Signature _____
SOLAR	Print Name _____ License #: _____ Phone #: _____	Signature _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON	RR282811528	Patricia M Johnson	Patricia M Johnson
CONCRETE FINISHER	000218	TONY E. JORDAN SR	Tony E. Jordan
FRAMING	RG0066597	John D. Norris	John D. Norris
INSULATION	RR282811528	Patricia m Johnson	Patricia m Johnson
STUCCO			
DRYWALL	000345	Kim Heitzman	Kim Heitzman
PLASTER			
CABINET INSTALLER	RR282811528	Patricia m Johnson	Patricia m Johnson
PAINTING	RR282811528	Patricia m Johnson	Patricia m Johnson
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE	RR282811528	Patricia m Johnson	Patricia m Johnson
FLOOR COVERING	RR282811528	Patricia m Johnson	Patricia m Johnson
ALUM/VINYL SIDING			
GARAGE DOOR	RR282811528	Patricia m Johnson	Patricia m Johnson
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.



**COLUMBIA COUNTY BUILDING DEPARTMENT
RESIDENTIAL CHECK LIST REQUIRMENTS**

**MINIMUM PLAN REQUIREMENTS FOR THE
FLORIDA BUILDING CODE RESIDENTIAL 2007
ONE (1) AND TWO (2) FAMILY DWELLINGS**

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

ALL BUILDING PLANS MUST INDICATE COMPLIANCE with the Current 2007 FLORIDA BUILDING CODES RESIDENTIAL. ALL PLANS OR DRAWINGS SHALL PROVIDE CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FIGURE R301.2(4) of the FLORIDA BUILDING CODES RESIDENTIAL (Florida Wind speed map) SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE ----- 110 MPH
NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

**GENERAL REQUIREMENTS:
APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL**

Items to Include-
Each Box shall be
Circled as
Applicable

		Yes	No	N/A
1	Two (2) complete sets of plans containing the following:	✓		
2	All drawings must be clear, concise, drawn to scale, details that are not used shall be marked void	✓		
3	Condition space (Sq. Ft.) <u>3124</u>	 ✓		
	Total (Sq. Ft.) under roof <u>4612</u>			

Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal shall be affixed to the plans and documents as per the FLORIDA BUILDING CODES RESIDENTIAL R101.2.1

Site Plan information including:

4	Dimensions of lot or parcel of land	✓		
5	Dimensions of all building set backs	✓		
6	Location of all other structures (include square footage of structures) on parcel, existing or proposed well and septic tank and all utility easements.	✓		
7	Provide a full legal description of property.	✓		

Wind-load Engineering Summary, calculations and any details required

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
8	Plans or specifications must show compliance with FBCR Chapter 3	IIIII	IIII	IIIII
		YES	NO	N/A
9	Basic wind speed (3-second gust), miles per hour	✓		
10	(Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated)	✓		
11	Wind importance factor and nature of occupancy	✓		
12	The applicable internal pressure coefficient, Components and Cladding	✓		
13	The design wind pressure in terms of psf (kN/m ²), to be used for the design of exterior component, cladding materials not specifiably designed by the registered design professional.	✓		

Elevations Drawing including:

14	All side views of the structure	✓		
15	Roof pitch	✓		
16	Overhang dimensions and detail with attic ventilation	✓		
17	Location, size and height above roof of chimneys			✓
18	Location and size of skylights with Florida Product Approval			✓
18	Number of stories			
20A	Building height from the established grade to the roofs highest peak	✓		

Floor Plan including:

20	Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches, deck, balconies	✓		
21	Raised floor surfaces located more than 30 inches above the floor or grade			✓
22	All exterior and interior shear walls indicated	✓		
23	Shear wall opening shown (Windows, Doors and Garage doors)	✓		
24	Emergency escape and rescue opening shown in each bedroom (net clear opening shown)	✓		
25	Safety glazing of glass where needed	✓		
26	Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 of FBCR)	✓		
27	Stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails (see FBCR SECTION 311)			✓
28	Identify accessibility of bathroom (see FBCR SECTION 322)	✓		

All materials placed within opening or onto/into exterior walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the plan (see Florida product approval form)

GENERAL REQUIREMENTS:
APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

Items to Include-
Each Box shall be
Circled as
Applicable

FBCR 403: Foundation Plans

		YES	NO	N/A
29	Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.	✓		
30	All posts and/or column footing including size and reinforcing	✓		
31	Any special support required by soil analysis such as piling.			✓
32	Assumed load-bearing value of soil <u>1000</u> Pound Per Square Foot	✓		
33	Location of horizontal and vertical steel, for foundation or walls (include # size and type)	✓		

FBCR 506: CONCRETE SLAB ON GRADE

34	Show Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)	✓		
35	Show control joints, synthetic fiber reinforcement or welded fire fabric reinforcement and Supports	✓		

FBCR 320: PROTECTION AGAINST TERMITES

36	Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or submit other approved termite protection methods. Protection shall be provided by registered termiticides	✓		
----	---	---	--	--

FBCR 606: Masonry Walls and Stem walls (load bearing & shear Walls)

37	Show all materials making up walls, wall height, and Block size, mortar type	✓		
38	Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement	✓		

Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer or Architect

Floor Framing System: First and/or second story

39	Floor truss package shall including layout and details, signed and sealed by Florida Registered Professional Engineer			✓
40	Show conventional floor joist type, size, span, spacing and attachment to load bearing walls, stem walls and/or piers			✓
41	Girder type, size and spacing to load bearing walls, stem wall and/or piers			✓
42	Attachment of joist to girder			✓
43	Wind load requirements where applicable			✓
44	Show required under-floor crawl space			✓
45	Show required amount of ventilation opening for under-floor spaces			✓
46	Show required covering of ventilation opening			✓
47	Show the required access opening to access to under-floor spaces			✓
	Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges &			✓

48	intermediate of the areas structural panel sheathing			✓
49	Show Draftstopping, Fire caulking and Fire blocking			✓
50	Show fireproofing requirements for garages attached to living spaces, per FBCR section 309			✓
51	Provide live and dead load rating of floor framing systems (psf).			✓

FBCR CHAPTER 6 WOOD WALL FRAMING CONSTRUCTION

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
		YES	NO	N/A
52	Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls	✓		
53	Fastener schedule for structural members per table FBCR 602.3 are to be shown	✓		
54	Show Wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural members, showing fastener schedule attachment on the edges & intermediate of the areas structural panel sheathing	✓		
55	Show all required connectors with a max uplift rating and required number of connectors and oc spacing for continuous connection of structural walls to foundation and roof trusses or rafter systems	✓		
56	Show sizes, type, span lengths and required number of support jack studs, king studs for shear wall opening and girder or header per FBCR Table 502.5 (1)	✓		
57	Indicate where pressure treated wood will be placed	✓		
58	Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing edges & intermediate areas	✓		
59	A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail	✓		

FBCR :ROOF SYSTEMS:

60	Truss design drawing shall meet section FBCR 802.10 Wood trusses	✓		
61	Include a layout and truss details, signed and sealed by Florida Professional Engineer	✓		
62	Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters	✓		
63	Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details			✓
64	Provide dead load rating of trusses	✓		

FBCR 802:Conventional Roof Framing Layout

65	Rafter and ridge beams sizes, span, species and spacing			✓
66	Connectors to wall assemblies' include assemblies' resistance to uplift rating			✓
67	Valley framing and support details			✓
68	Provide dead load rating of rafter system			✓

FBCR Table 602,3(2) & FBCR 803 ROOF SHEATHING

69	Include all materials which will make up the roof decking, identification of structural panel sheathing, grade, thickness	✓		
70	Show fastener Size and schedule for structural panel sheathing on the edges & intermediate areas	✓		

FBCR ROOF ASSEMBLIES FRC Chapter 9

71	Include all materials which will make up the roof assembles covering			
72	Submit Florida Product Approval numbers for each component of the roof assembles covering			

FBCR Chapter 11 Energy Efficiency Code for residential building

Residential construction shall comply with this code by using the following compliance methods in the FBCR chapter 11 Residential buildings compliance methods. *Two of the required forms are to be submitted, showing dimensions condition area equal to the total condition living space area*

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
		YES	NO	N/A
73	Show the insulation R value for the following areas of the structure	✓		
74	Attic space	✓		
75	Exterior wall cavity	✓		
76	Crawl space			✓

HVAC information

77	Submit two copies of a Manual J sizing equipment or equivalent computation study			
78	Exhaust fans locations in bathrooms			
79	Show clothes dryer route and total run of exhaust duct			

Plumbing Fixture layout shown

80	All fixtures waste water lines shall be shown on the foundation plan	✓		✓
81	Show the location of water heater	✓		

Private Potable Water

82	Pump motor horse power			
83	Reservoir pressure tank gallon capacity			
84	Rating of cycle stop valve if used			

Electrical layout shown including

85	Switches, outlets/receptacles, lighting and all required GFCI outlets identified	✓		
86	Ceiling fans	✓		
87	Smoke detectors & Carbon dioxide detectors	✓		
88	Service panel, sub-panel, location(s) and total ampere ratings	✓		
89	On the electrical plans identify the electrical service overcurrent protection device for the main electrical service. This device shall be installed on the exterior of structures to serve as a disconnecting means for the utility company electrical service. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground. Indicate if the utility company service entrance cable will be of the overhead or underground type.			

90	Appliances and HVAC equipment and disconnects	✓		
91	Arc Fault Circuits (AFCI) in bedrooms	✓		

Disclosure Statement for Owner Builders *If you as the applicant will be acting as an owner builder under section 489.103(7) of the Florida Statutes, submit the required owner builder disclosure statement form.*

Notice Of Commencement

A notice of commencement form **recorded** in the Columbia County Clerk Office is required to be filed with the building department Before Any Inspections can be preformed.

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable
---	--	--

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

		YES	NO	N/A
✓ 92	Building Permit Application A current Building Permit Application form is to be completed and submitted for all residential projects			
✓ 93	Parcel Number The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested			
X 94	Environmental Health Permit or Sewer Tap Approval A copy of a approved Columbia County Environmental Health (386) 758-1058			
95	City of Lake City A permit showing an approved waste water sewer tap			
96	Toilet facilities shall be provided for all construction sites			
97	Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White an approval land use development letter issued by the Town of Fort is required to be submitted with the application for a building permit.			
98	Flood Information: All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting a application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.5.2 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.5.3 of the Columbia County Land Development Regulations			
99	CERTIFIED FINISHED FLOOR ELEVATIONS will be required on any project where the base flood elevation (100 year flood) has been established			
? 100	A development permit will also be required. Development permit cost is \$50.00			
101	Driveway Connection: If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.			
✓ 102	911 Address: If the project is located in an area where a 911 address has not been issued, then application for a 911 address must be applied for and received through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125			

Section R101.2.1 of the Florida Building Code Residential:

The provisions of Chapter 1, Florida Building Code, Building shall govern the administration and enforcement of the Florida Building Code, Residential.

Section 105 of the Florida Building Code defines the:

Time limitation of application.

An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

Single-family residential dwelling.

Section 105.3.4 A building permit for a single-family residential dwelling must be issued within 30 working days of application therefor unless unusual circumstances require a longer time for processing the application or unless the permit application fails to satisfy the Florida Building Code or the enforcing agency's laws or ordinances.

Permit intent.

Section 105.4.1: A permit issued shall be constructed to be a license to proceed with the work and not as authority to violate, cancel, alter or set aside any of the provisions of the technical codes, nor shall issuance of a permit prevent the building official from thereafter requiring a correction of errors in plans, construction or violations of this code. Every permit issued shall become invalid unless the work authorized by such permit is commenced within six months after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of six months after the time the work is commenced.

If work has commenced.

Section 105.4.1.1: If work has commenced and the permit is revoked, becomes null and void, or expires because of lack of progress or abandonment, a new permit covering the proposed construction shall be obtained before proceeding with the work.

New Permit.

Section 105.4.1.2: If a new permit is not obtained within 180 days from the date the initial permit became null and void, the building official is authorized to require that any work which has been commenced or completed be removed from the building site. Alternately, a new permit may be issued on application, providing the work in place and required to complete the structure meets all applicable regulations in effect at the time the initial permit became null and void and any regulations which may have become effective between the date of expiration and the date of issuance of the new permit.

Work Shall Be:

Section 105.4.1.3: Work shall be considered to be in active progress when the permit has received an approved inspection within 180 days. This provision shall not be applicable in case of civil commotion or strike or when the building work is halted due directly to judicial injunction, order or similar process.

The Fee:

Section 105.4.1.4: The fee for renewal reissuance and extension of a permit shall be set forth by the administrative authority.

When the submitted application is approved for permitting the applicant will be notified by phone as to the date and time a building permit will be prepared and issued by the Columbia County Building & Zoning Department

STATE OF FLORIDA
DEPARTMENT OF HEALTH AND REHABILITATIVE SERVICES
ONSITE SEWAGE DISPOSAL SYSTEM
APPLICATION FOR CONSTRUCTION PERMIT
Authority: Chapter 381, FS & Chapter 10D-6, FAC

SPV
09-0581-N
PERMIT # Ap 943095
DATE PAID 11/19/2009
FEE PAID \$ 310.00
RECEIPT # 12-PFD-1205616
CR # 09-4742

APPLICATION FOR:

☐ New System ☐ Existing System ☐ Holding Tank ☐ Temporary/Experimental System
☐ Repair ☐ Abandonment ☐ Other (Specify) _____

APPLICANT: JOHN & PATRICA JOHNSON

TELEPHONE: 755-4038

AGENT: JOHN JOHNSON CONSTRUCTION

MAILING ADDRESS: 204 SW DUSTY GLENN CITY: LAKE CITY STATE: FL ZIP: 32024

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. ATTACH BUILDING PLAN AND TO-SCALE SITE PLAN SHOWING PERTINENT FEATURES REQUIRED BY CHAPTER 10D-6, FLORIDA ADMINISTRATIVE CODE.

PROPERTY INFORMATION [IF LOT IS NOT IN A RECORDED SUBDIVISION, ATTACH LEGAL DESCRIPTION OR DEED]

LOT: 15 BLOCK: _____ SUBDIVISION: RUSSWOOS EST. UNIT 4 DATESUBD: 1/2007

PROPERTY ID #: 10-4S-16-02853-415 [Section/Township/Range/Parcel] ZONING: RES

PROPERTY SIZE: 0.76 ACRES [Sqft/43560] PROPERTY WATER SUPPLY: ☒ PRIVATE ☐ PUBLIC

PROPERTY STREET ADDRESS: 234 SW SCOTT PLACE

DIRECTIONS TO PROPERTY: 90 WEST TURN LEFT ON CR 252, TURN RIGHT ON TROY RD. TURN RIGHT ON RUSSWOOD TERR. TURN LEFT ON EMILY GLENN, TURN RIGHT ON DOROTHY TERR. TURN RIGHT ON SCOTT PLACE TO END ON RIGHT.

BUILDING INFORMATION

☒ RESIDENTIAL

☐ COMMERCIAL

Unit No	Type of Establishment	No. of Bedrooms	Building Area Sqft	# Persons Served	Business Activity For Commercial Only
1	<u>HOUSE</u>	<u>4</u>	<u>3236</u>	<u>4</u>	
2					
3					
4					

☐ Garbage Grinders/Disposals
☐ Ultra-low Volume Flush Toilets

☐ Spas/Hot Tubs
☐ Other (Specify) _____

☐ Floor/Equipment Drains

APPLICANT'S SIGNATURE: John S Johnson

DATE: 11-18-09


RECEIVED
11/18/09

ENTERED
KSF

Application for Onsite Sewage Disposal System Construction Permit. Part II Site Plan

Permit Application Number: 09-0581-N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT



APPROVED

Site Plan Submitted By Pam R. Reed Date 11/18/09
 Plan Approved X Not Approved _____ Date 11/25/09
 By [Signature] Celestina CPHU
 Notes: _____

[Handwritten signature]

THIS INSTRUMENT WAS PREPARED BY:

TERRY McDAVID
POST OFFICE BOX 1328
LAKE CITY, FL 32056-1328

Recording Fee \$ 18.50
Documentary Stamp \$ 1,274.00

RETURN TO:

TERRY McDAVID
POST OFFICE BOX 1328
LAKE CITY, FL 32056-1328
07-84

Inst:2007004456 Date:02/23/2007 Time:11:04

Doc Stamp-Deed : 1274.00

D. F. DC, P. Dewitt Cason, Columbia County B:1111 P:2014

Property Appraiser's
Parcel Identification No.
02853-415; 416; 417;
423; 424; 426; 427

WARRANTY DEED

THIS INDENTURE, made this 22nd day of February, 2007, BETWEEN
LOID RUSSELL BAILEY and his wife, DOROTHY H. BAILEY, whose post
office address is 2016 SW Sisters Welcome Road, Lake City, Florida
32025, of the County of Columbia, State of Florida, grantor*, and
JOHN S. JOHNSON and his wife, PATRICIA M. JOHNSON, whose post
office address is 204 SW Dusty Glen, Lake City, FL 32024, of the
County of Columbia, State of Florida, grantee*.

WITNESSETH: that said grantor, for and in consideration of
the sum of Ten Dollars (\$10.00), and other good and valuable
considerations to said grantor in hand paid by said grantee, the
receipt whereof is hereby acknowledged, has granted, bargained and
sold to the said grantee, and grantee's heirs and assigns forever,
the following described land, situate, lying and being in Columbia
County, Florida, to-wit:

Lots 15, 16, 17, 23, 24, 26 and 27, RUSSWOOD ESTATES UNIT
4, a subdivision according to the plat thereof recorded
in Plat Book 9, Pages 2 & 3, of the public records of
Columbia County, Florida.

SUBJECT TO: Restrictions, easements and outstanding
mineral rights of record, if any, and taxes for the
current year.

and said grantor does hereby fully warrant the title to said land,

and will defend the same against the lawful claims of all persons

4, a subdivision according to the plat thereof recorded in Plat Book 9, Pages 2 & 3, of the public records of Columbia County, Florida.

SUBJECT TO: Restrictions, easements and outstanding mineral rights of record, if any, and taxes for the current year.

and said grantor does hereby fully warrant the title to said land, and will defend the same against the lawful claims of all persons whomsoever.

*"Grantor" and "grantee" are used for singular or plural, as context requires.

IN WITNESS WHEREOF, grantor has hereunto set grantor's hand and seal the day and year first above written.

Signed, sealed and delivered
in our presence:

DeEtte F. Brown
(First Witness)

DeEtte F. Brown

Printed Name

Crystal L. Brunner
(Second Witness)

Crystal L. Brunner

Printed Name

Loid Russell Bailey (SEAL)
LOID RUSSELL BAILEY


Dorothy H. Bailey (SEAL)
DOROTHY H. BAILEY

STATE OF FLORIDA
COUNTY OF COLUMBIA

The foregoing instrument was acknowledged before me this 22nd
day of February, 2007, by LOID RUSSELL BAILEY and his wife, DOROTHY
H. BAILEY, who are personally known to me and who did not take an
oath.

My Commission Expires:

DeEtte F. Brown
Notary Public



PLAY BOOK 9 PAGE 3
SHEET 2 OF 2.

SEE SHEET 1 OF 2 FOR DESCRIPTION.

UNPLANTED LANDS
NOT A PART

CURVE TABLE

NO.	ANALYST	DELTA	ANG	THICKNESS	CHORD
1	30.00	90.0000	47.12	30.00	52.43
2	30.00	90.0000	47.12	30.00	52.43
3	30.00	90.0000	47.12	30.00	52.43
4	30.00	90.0000	47.12	30.00	52.43
5	30.00	90.0000	47.12	30.00	52.43
6	30.00	90.0000	47.12	30.00	52.43
7	30.00	90.0000	47.12	30.00	52.43
8	30.00	90.0000	47.12	30.00	52.43
9	30.00	90.0000	47.12	30.00	52.43
10	30.00	90.0000	47.12	30.00	52.43
11	30.00	90.0000	47.12	30.00	52.43
12	30.00	90.0000	47.12	30.00	52.43
13	30.00	90.0000	47.12	30.00	52.43
14	30.00	90.0000	47.12	30.00	52.43
15	30.00	90.0000	47.12	30.00	52.43
16	30.00	90.0000	47.12	30.00	52.43
17	30.00	90.0000	47.12	30.00	52.43
18	30.00	90.0000	47.12	30.00	52.43
19	30.00	90.0000	47.12	30.00	52.43
20	30.00	90.0000	47.12	30.00	52.43
21	30.00	90.0000	47.12	30.00	52.43
22	30.00	90.0000	47.12	30.00	52.43
23	30.00	90.0000	47.12	30.00	52.43
24	30.00	90.0000	47.12	30.00	52.43
25	30.00	90.0000	47.12	30.00	52.43
26	30.00	90.0000	47.12	30.00	52.43
27	30.00	90.0000	47.12	30.00	52.43
28	30.00	90.0000	47.12	30.00	52.43
29	30.00	90.0000	47.12	30.00	52.43
30	30.00	90.0000	47.12	30.00	52.43


NOT A PART

BUILDING SETBACKS / MINIMUM YARD REQUIREMENTS.
FRONT - 25'
SIDE - 10' FOR EACH SIDE YARD.
REAR - 15'

STREET LIGHTING, IF REQUIRED BY COLUMBIA COUNTY BOARD OF COUNTY COMMISSIONERS, WILL BE INSTALLED AND CONSTRUCTED BY THE SUBGRANTEE ACCORDING TO THE STANDARDS OF SAID BOARD PURSUANT TO SECTION 5.26.3.6 COLUMBIA COUNTY LAND DEVELOPMENT REGULATIONS.

SYMBOL LEGEND

- 11 CONCRETE MONUMENT FOUND
- 12 4"x4" CONCRETE MONUMENT SET, LS 4708
- 13 IRON PIV ON PIPE FOUND
- 14 8"x8" IRON ROD SET, LS 4708
- 15 WIRE FENCE
- 16 ELECTRIC UTILITY LINE (WOODHEAD)
- 17 LANDSCAPING ELECTRIC SERVICE



Russwood Estates
Unit 4 Lot 15



LYNCH WELL DRILLING, INC.

173 SW YOUNG PLACE

LAKE CITY, FL 32025

Invoice

Date	Invoice #
11/18/2009	10829

Bill To

John Johnson
204 SW Dusty Glen
Lake City, FL 32024

Due Date

11/25/2009

Quantity	Description	Rate	Amount
1	4" steel casing well to 100' with 1 1/2 HP pump, 1 1/4 galv. drop pipe, 81 gallon bladder tank		
30	4" well over 100'(Rustwood Est. lot 15)(well 130 water 73 pump set 94)		
Every 30 days 1.5% finance charges will be added to balance Well 130Water depth 73, pump set 94		Total	



Phone #	Fax #	E-Mail	Web Site
(386) 752-6677	(386) 752-1477	lynchwell@bizsea.rr.com	lynchwelldrilling.com

Location:

Project Name:

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit on or after April 1, 2004. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS			<i>FL 4242-R1</i>
1. Swinging			
2. Sliding			
3. Sectional			
4. Roll up			
5. Automatic			
6. Other			
B. WINDOWS			
1. Single hung			<i>FL 5108</i>
2. Horizontal Slider			<i>FL 5451</i>
3. Casement			
4. Double Hung			
5. Fixed			<i>FL 5418</i>
6. Awning			
7. Pass-through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11 Dual Action			
12. Other			
C. PANEL WALL			
1. Siding			<i>FL 889-R2</i>
2. Soffits			<i>FL 4899</i>
3. EIFS			
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			<i>FL 3820-R1</i>
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS			
1. Asphalt Shingles			<i>FL 586-R2</i>
2. Underlayments			<i>FL 1814-R1</i>
3. Roofing Fasteners			
4. Non-structural Metal Rf			
5. Built-Up Roofing			
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

Category/Subcategory (cont.)	Manufacturer	Product Description	Approval Number(s)
13. Liquid Applied Roof Sys			
14. Cements-Adhesives - Coatings			FL. 1960-R1
15. Roof Tile Adhesive			
16. Spray Applied Polyurethane Roof			
17. Other			
E. SHUTTERS			
1. Accordion			
2. Bahama			
3. Storm Panels			
4. Colonial			
5. Roll-up			
6. Equipment			
7. Others			
F. SKYLIGHTS			
1. Skylight			FL 451-R1
2. Other			
G. STRUCTURAL COMPONENTS			
1. Wood connector/anchor			FL. 474-R1
2. Truss plates			
3. Engineered lumber			FL 1008-R1
4. Railing			
5. Coolers-freezers			
6. Concrete Admixtures			
7. Material			
8. Insulation Forms			
9. Plastics			
10. Deck-Roof			
11. Wall			
12. Sheds			
13. Other			
H. NEW EXTERIOR ENVELOPE PRODUCTS			
1.			
2.			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) the performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

I understand these products may have to be removed if approval cannot be demonstrated during inspection

Patricia M. Johnson
 Contractor or Contractor's Authorized Agent Signature

Patricia M. Johnson
 Print Name

Date

Location

Permit # (FOR STAFF USE ONLY)

MI HOME PRODUCTS
- PRIME ALUMINUM WINDOWS -
INSTALLATION INSTRUCTIONS FOR
"NAIL FIN" PRODUCTS

MI Home Products appreciates your recent purchase of a maintenance free prime window, which will not rust, rot, mildew, or warp. This is a quality product that left our factory in good condition - proper handling and installation are just as important as good design and workmanship. Please follow these recommendations to allow this product to complete its function.

1. Handle units one at a time in the closed and locked position and take care not to scratch frame or glass or to bend the nailing fin.
2. Set unit plumb and square into opening and make sure that there is $3/16" \pm 1/16"$ clearance around the frame. Fasten unit into opening in the closed and locked position, making sure that fasteners are screwed in straight in order to avoid twisting or bowing of the frame. Make sure that sill is straight and level. Check operation of unit before any and all fasteners are set.
3. Use # 8 sheet metal or wood screws with a minimum of 1" penetration into the framing (stud). Place first screws (two at each corner) 3" from end of fin. For positive and negative DPs (design pressures) up to 35, do not exceed 24" spacing of additional screws. For DPs from 35.1 to 50, do not exceed 18". Install load bearing shim adjacent to each anchor. Use shim where space exceeds 1/16".
4. Flash over head and caulk outside perimeter in accordance with code requirements and good installation practices.
5. Fill voids between frame and construction with loose batten type insulation or non-expanding aerosol foam specifically formulated for windows and doors to eliminate drafts. The use of expanding aerosol type insulating foam, which can bow the frame, waives all stated warranties.
6. Remove plaster, mortar, paint and any other debris that may have collected on the unit and make sure that sash/vent tracks and interlocks are also clear. Do not use abrasives, solvents, ammonia, vinegar, alkaline, or acid solutions for clean-up, especially with insulated glass units as their use could cause chemical breakdown of the glass seal. Take care not to scratch glass; scratches severely weaken glass and it could eventually break from thermal expansion and contraction. Clean units with water and mild detergent as you would your automobile.

CAUTION -


MI Home Products or its representatives are unable to control and cannot assume responsibility for the selection and placement of their products in a building or structure in a manner required by laws, statutes, and/or building codes. The purchaser is solely responsible for knowledge of and adherence to the same. MI Home Products window products are not provided with safety glazing unless specifically ordered with such. Many laws and codes require safety glazing near doors, bathtubs, and shower enclosures. Also be aware of emergency egress code requirements.

Corporate Headquarters:
650 West Market St.
Gratz, PA 17030-0370
(717) 365-3300




- 20 GA. WIRE, END STUDS ATTACHED TO DOOR
- SHOWN WITH PATENTED TOS-1-LOC SYSTEM
(TOP, BOTTOM & CENTER).

ADDED: J448 ATTACHMENT INFORMATION
ADDED: USE TRACK OPTION NOTE: DEL M/N 82/50
QTY(1) WAS (2) FOR TRACK BOLTS



INTERPLAYATIONS

REPORT#96060

[illegible]

CLASP BUILDING PRODUCTS COMPANY
312 WALNUT STREET
SUITE 1000
CINCINNATI, OH 45202
(615) 381-4800

Clasp Corporation. All Rights Reserved.

The trademarks depicted herein are the sole property of Clasp Corporation and may not be reproduced in any form without its written permission.

PLUMB	MAX. DOOR SIZE: 16'0" x 8'0"
DESCRIPTIONS	
M/N 73/75/84A/94 16"W +24/-24.5 PSF DES.	
B	DRAWING NUMBER: 101711
	REV. NO. 0

PLUMB	MAX. DOOR SIZE: 16'0" x 8'0"
DESCRIPTIONS	
M/N 73/75/84A/94 16"W +24/-24.5 PSF DES.	
B	DRAWING NUMBER: 101711
	REV. NO. 0

TimberSaver PT is a borate based wood preservative applied to lumber and plywood using a pressure-treatment process, to provide permanent protection against wood destroying insects and decay fungi in interior applications. TimberSaver PT borate treated lumber and plywood is not suitable for applications exposed to the weather or in ground contact and must be protected from exposure to liquid water.


The active ingredient in TimberSaver PT, Disodium Octaborate Tetrahydrate or DOT, is the most widely accepted form of borates used for treatment of forest products. DOT is manufactured from naturally occurring boron, which is widely used in a variety of applications in agriculture, cleaning products and detergents, and in wood preservation.

Product Attributes

TimberSaver® PT

- Offers the most effective level of borate protection
- Provides permanent protection for dry interior applications
- Protects against fungal decay
- Protects against Formosan Termites and other wood destroying insects
- Non-corrosive to metal fasteners
- Non-toxic to humans and animals
- Does not adversely affect the strength properties of the treated lumber or plywood
- Is a colorless treatment and is also available with a dye to make job site product identification easier
- Is applied through a pressure-treatment process to optimize penetration of borate preservative
- Penetrates difficult-to-treat refractory species such as Spruce-Pine-Fir and Douglas-Fir*

* Incising is required for Coastal Douglas-Fir and Western Spruce-Pine-Fir as per AWWA Standard C31



Uses for **TimberSaver® PT**

Applications for **TimberSaver PT** treated products include:

- Framing Lumber
- Studs
- Sill Plates
- Floor Joists
- Roof Rafters
- Trusses
- Plywood
- Interior Sheathing
- Furring Strips
- Flooring
- Moldings
- Interior Wood Trim

TimberSaver PT Protects Against These Wood Destroying Insects and Decay Causing Fungi.




- Formosan Termites*
- Subterranean Termites (*Coptotermes*, *Reticulitermes*, *Heterotermes*)
- Dampwood Termites (*Zootermopsis*)
- Drywood Termites (*Kaloterms*, *Incisitermes*)
- Carpenter Ants (*Componotus*)
- Powderpost Beetles (*Lyctidae*)
- Furniture Beetles (*Anobiidae*)
- Longhorn Beetles (*Cerambycidae*)
- Brown Rot Fungi
- White Rot Fungi
- Wet Rot Fungi

* Borate preservatives have been and continue to be a key weapon used in controlling Formosan Termites in Hawaii and other high hazard areas throughout the world. **TimberSaver PT** borate-treated lumber and plywood is protected against this aggressive termite species when the higher 0.42 pcf (DOT) retention is specified.

Handling and Use **TimberSaver® PT**

TimberSaver PT borate treated wood can be sawn, nailed, drilled, stained and assembled using standard fastener systems typically used in general wood construction practices.



Lumber and plywood treated with **TimberSaver PT** must be protected from exposure to the weather while in transit and while being stored at retail yards and job sites. **TimberSaver PT** products should be stored out of ground contact, either indoors or wrapped in plastic to protect against exposure to liquid water.

With the exception of Southern Pine, all end cut surfaces and field cuts of any type must receive an application of **TimberSaver** solution by brushing, spraying, dipping, or flooding.

Residential System Sizing Calculation

Summary

Spec

Lake City, FL

Project Title:
911124JohnsonBuildersLot15Russwood

Class 3 Rating
Registration No. 0
Climate: North


12/4/2009

Location for weather data: Gainesville - Defaults: Latitude(29) Altitude(152 ft.) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(54gr.)			
Winter design temperature	33 F	Summer design temperature	92 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	37 F	Summer temperature difference	17 F
Total heating load calculation	47504 Btuh	Total cooling load calculation	43368 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	117.9 56000	Sensible (SHR = 0.75)	113.4 42000
Heat Pump + Auxiliary(0.0kW)	117.9 56000	Latent	220.9 14000
		Total (Electric Heat Pump)	129.1 56000

WINTER CALCULATIONS

Winter Heating Load (for 3124 sqft)


Load component		Load	
Window total	375 sqft	12055	Btuh
Wall total	2176 sqft	7144	Btuh
Door total	70 sqft	907	Btuh
Ceiling total	3237 sqft	3814	Btuh
Floor total	288 sqft	12574	Btuh
Infiltration	272 cfm	11009	Btuh
Duct loss		0	Btuh
Subtotal		47504	Btuh
Ventilation	0 cfm	0	Btuh
TOTAL HEAT LOSS		47504	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 3124 sqft)

Load component		Load	
Window total	375 sqft	21825	Btuh
Wall total	2176 sqft	2763	Btuh
Door total	70 sqft	686	Btuh
Ceiling total	3237 sqft	5361	Btuh
Floor total		0	Btuh
Infiltration	141 cfm	2616	Btuh
Internal gain		3780	Btuh
Duct gain		0	Btuh
Sens. Ventilation	0 cfm	0	Btuh
Total sensible gain		37031	Btuh
Latent gain(ducts)		0	Btuh
Latent gain(infiltration)		5138	Btuh
Latent gain(ventilation)		0	Btuh
Latent gain(internal/occupants/other)		1200	Btuh
Total latent gain		6338	Btuh
TOTAL HEAT GAIN		43368	Btuh



For Florida residences only

EnergyGauge® System Sizing

PREPARED BY:

DATE: 12/4/09 EVAN BARNES

System Sizing Calculations - Winter

Residential Load - Whole House Component Details

Spec

Project Title:

Class 3 Rating

911124JohnsonBuildersLot15Russwood

Registration No. 0

Lake City, FL

Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

12/4/2009

This calculation is for Worst Case. The house has been rotated 315 degrees.

Component Loads for Whole House

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft) X	HTM=	Load
1	2, Clear, Metal, 0.87	NW	15.0	32.2	483 Btuh
2	2, Clear, Metal, 0.87	NW	8.0	32.2	258 Btuh
3	2, Clear, Metal, 0.87	NW	36.0	32.2	1159 Btuh
4	2, Clear, Metal, 0.87	NE	36.0	32.2	1159 Btuh
5	2, Clear, Metal, 0.87	N	20.0	32.2	644 Btuh
6	2, Clear, Metal, 0.87	NW	54.0	32.2	1738 Btuh
7	2, Clear, Metal, 0.87	SW	10.0	32.2	322 Btuh
8	2, Clear, Metal, 0.87	NW	36.0	32.2	1159 Btuh
9	2, Clear, Metal, 0.87	NE	8.0	32.2	258 Btuh
10	2, Clear, Metal, 0.87	NE	16.0	32.2	515 Btuh
11	2, Clear, Metal, 0.87	SE	72.0	32.2	2318 Btuh
12	2, Clear, Metal, 0.87	SE	13.5	32.2	435 Btuh
13	2, Clear, Metal, 0.87	SW	20.0	32.2	644 Btuh
14	2, Clear, Metal, 0.87	SW	30.0	32.2	966 Btuh
Window Total			375(sqft)		12055 Btuh
Walls	Type	R-Value	Area X	HTM=	Load
1	Face Brick - Wood - Ext(0.09)	13.0	1953	3.3	6412 Btuh
2	Frame - Wood - Adj(0.09)	13.0	223	3.3	732 Btuh
Wall Total			2176		7144 Btuh
Doors	Type		Area X	HTM=	Load
1	Insulated - Adjacent		20	12.9	259 Btuh
2	Insulated - Exterior		20	12.9	259 Btuh
3	Insulated - Exterior		10	12.9	130 Btuh
4	Insulated - Exterior		20	12.9	259 Btuh
Door Total			70		907Btuh
Ceilings	Type/Color/Surface	R-Value	Area X	HTM=	Load
1	Vented Attic/D/Shin)	30.0	113	1.2	133 Btuh
2	Vented Attic/D/Shin)	30.0	3124	1.2	3681 Btuh
Ceiling Total			3237		3814Btuh
Floors	Type	R-Value	Size X	HTM=	Load
1	Slab On Grade	0	288.0 ft(p)	43.7	12574 Btuh
Floor Total			288		12574 Btuh
Zone Envelope Subtotal:					36494 Btuh
Infiltration	Type	ACH X	Zone Volume	CFM=	
	Natural	0.58	28116	271.8	11009 Btuh
Ductload	Partially sealed, R6.0, Supply(Attic), Return(Attic) (DLM of 0.00)				0 Btuh
Zone #1	Sensible Zone Subtotal				47504 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Spec

Project Title:

Class 3 Rating

Lake City, FL

911124JohnsonBuildersLot15Russwood

Registration No. 0

Climate: North

12/4/2009

WHOLE HOUSE TOTALS

	Subtotal Sensible	47504 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	47504 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(Frame types - metal, wood or insulated metal)

(U - Window U-Factor or 'DEF' for default)

(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



For Florida residences only

System Sizing Calculations - Winter

Residential Load - Room by Room Component Details

Spec

Lake City, FL

Project Title:

911124JohnsonBuildersLot15Russwood

Class 3 Rating

Registration No. 0

Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

12/4/2009

This calculation is for Worst Case. The house has been rotated 315 degrees.

Component Loads for Zone #1: Main

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft)	X	HTM=	Load
1	2, Clear, Metal, 0.87	NW	15.0		32.2	483 Btuh
2	2, Clear, Metal, 0.87	NW	8.0		32.2	258 Btuh
3	2, Clear, Metal, 0.87	NW	36.0		32.2	1159 Btuh
4	2, Clear, Metal, 0.87	NE	36.0		32.2	1159 Btuh
5	2, Clear, Metal, 0.87	N	20.0		32.2	644 Btuh
6	2, Clear, Metal, 0.87	NW	54.0		32.2	1738 Btuh
7	2, Clear, Metal, 0.87	SW	10.0		32.2	322 Btuh
8	2, Clear, Metal, 0.87	NW	36.0		32.2	1159 Btuh
9	2, Clear, Metal, 0.87	NE	8.0		32.2	258 Btuh
10	2, Clear, Metal, 0.87	NE	16.0		32.2	515 Btuh
11	2, Clear, Metal, 0.87	SE	72.0		32.2	2318 Btuh
12	2, Clear, Metal, 0.87	SE	13.5		32.2	435 Btuh
13	2, Clear, Metal, 0.87	SW	20.0		32.2	644 Btuh
14	2, Clear, Metal, 0.87	SW	30.0		32.2	966 Btuh
Window Total			375(sqft)			12055 Btuh
Walls	Type	R-Value	Area	X	HTM=	Load
1	Face Brick - Wood - Ext(0.09)	13.0	1953		3.3	6412 Btuh
2	Frame - Wood - Adj(0.09)	13.0	223		3.3	732 Btuh
Wall Total			2176			7144 Btuh
Doors	Type		Area	X	HTM=	Load
1	Insulated - Adjacent		20		12.9	259 Btuh
2	Insulated - Exterior		20		12.9	259 Btuh
3	Insulated - Exterior		10		12.9	130 Btuh
4	Insulated - Exterior		20		12.9	259 Btuh
Door Total			70			907Btuh
Ceilings	Type/Color/Surface	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shin)	30.0	113		1.2	133 Btuh
2	Vented Attic/D/Shin)	30.0	3124		1.2	3681 Btuh
Ceiling Total			3237			3814Btuh
Floors	Type	R-Value	Size	X	HTM=	Load
1	Slab On Grade	0	288.0	ft(p)	43.7	12574 Btuh
Floor Total			288			12574 Btuh
Zone Envelope Subtotal:						36494 Btuh
Infiltration	Type	ACH X	Zone Volume	CFM=		
	Natural	0.58	28116	271.8		11009 Btuh
Ductload	Partially sealed, R6.0, Supply(Attic), Return(Attic) (DLM of 0.00)					0 Btuh
Zone #1	Sensible Zone Subtotal					47504 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Spec

Project Title:

Class 3 Rating

Lake City, FL

911124JohnsonBuildersLot15Russwood

Registration No. 0

Climate: North

12/4/2009

WHOLE HOUSE TOTALS

	Subtotal Sensible	47504 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	47504 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(Frame types - metal, wood or insulated metal)

(U - Window U-Factor or 'DEF' for default)

(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



For Florida residences only

System Sizing Calculations - Summer

Residential Load - Whole House Component Details

Spec

Project Title:

Class 3 Rating

Lake City, FL

911124JohnsonBuildersLot15Russwood

Registration No. 0

Climate: North

Reference City: Gainesville (Defaults) Summer Temperature Difference: 17.0 F

12/4/2009

This calculation is for Worst Case. The house has been rotated 315 degrees.

Component Loads for Whole House

Window	Type*		Overhang		Window Area(sqft)			HTM		Load	
	Pn/SHGC/U/InSh/ExSh/IS	Ornt	Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded		
1	2, Clear, 0.87, None,N,N	NW	1.5ft	7ft.	15.0	0.0	15.0	29	60	901	Btuh
2	2, Clear, 0.87, None,N,N	NW	1.5ft	6ft.	8.0	0.0	8.0	29	60	480	Btuh
3	2, Clear, 0.87, None,N,N	NW	1.5ft	8ft.	36.0	0.0	36.0	29	60	2161	Btuh
4	2, Clear, 0.87, None,N,N	NE	1.5ft	8ft.	36.0	0.0	36.0	29	60	2161	Btuh
5	2, Clear, 0.87, None,N,N	N	16ft.	8ft.	20.0	0.0	20.0	29	29	579	Btuh
6	2, Clear, 0.87, None,N,N	NW	13ft.	8ft.	54.0	0.0	54.0	29	60	3242	Btuh
7	2, Clear, 0.87, None,N,N	SW	99ft.	8ft.	10.0	10.0	0.0	29	63	290	Btuh
8	2, Clear, 0.87, None,N,N	NW	1.5ft	8ft.	36.0	0.0	36.0	29	60	2161	Btuh
9	2, Clear, 0.87, None,N,N	NE	1.5ft	6ft.	8.0	0.0	8.0	29	60	480	Btuh
10	2, Clear, 0.87, None,N,N	NE	1.5ft	6ft.	16.0	0.0	16.0	29	60	961	Btuh
11	2, Clear, 0.87, None,N,N	SE	10.5f	8ft.	72.0	72.0	0.0	29	63	2085	Btuh
12	2, Clear, 0.87, None,N,N	SE	14ft.	9ft.	13.5	13.5	0.0	29	63	391	Btuh
13	2, Clear, 0.87, None,N,N	SW	1.5ft	7ft.	20.0	2.1	17.9	29	63	1180	Btuh
14	2, Clear, 0.87, None,N,N	SW	1.5ft	7ft.	30.0	3.1	26.9	29	63	1771	Btuh
	Excursion									2981	Btuh
	Window Total				375 (sqft)					21825 Btuh	
Walls	Type		R-Value/U-Value		Area(sqft)			HTM		Load	
1	Face Brick - Wood - Ext		13.0/0.09		1952.5			1.2		2426 Btuh	
2	Frame - Wood - Adj		13.0/0.09		223.0			1.5		336 Btuh	
	Wall Total				2176 (sqft)					2763 Btuh	
Doors	Type				Area (sqft)			HTM		Load	
1	Insulated - Adjacent				20.0			9.8		196 Btuh	
2	Insulated - Exterior				20.0			9.8		196 Btuh	
3	Insulated - Exterior				10.0			9.8		98 Btuh	
4	Insulated - Exterior				20.0			9.8		196 Btuh	
	Door Total				70 (sqft)					686 Btuh	
Ceilings	Type/Color/Surface		R-Value		Area(sqft)			HTM		Load	
1	Vented Attic/DarkShingle		30.0		113.0			1.7		187 Btuh	
2	Vented Attic/DarkShingle		30.0		3124.0			1.7		5174 Btuh	
	Ceiling Total				3237 (sqft)					5361 Btuh	
Floors	Type		R-Value		Size			HTM		Load	
1	Slab On Grade		0.0		288 (ft(p))			0.0		0 Btuh	
	Floor Total				288.0 (sqft)					0 Btuh	
	Zone Envelope Subtotal:									30635 Btuh	
Infiltration	Type		ACH		Volume(cuft)			CFM=		Load	
	SensibleNatural		0.30		28116			140.6		2616 Btuh	
Internal gain			Occupants		Btuh/occupant			Appliance		Load	
			6		X 230 +			2400		3780 Btuh	
Duct load	Partially sealed, R6.0, Supply(Attic), Return(Attic)							DGM = 0.00		0.0 Btuh	
	Sensible Zone Load									37031 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

Spec

Project Title:

Class 3 Rating

Lake City, FL

911124JohnsonBuildersLot15Russwood

Registration No. 0

Climate: North

12/4/2009

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	37031 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	37031 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	37031 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	5138 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	6338 Btuh
	TOTAL GAIN	43368 Btuh

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Ornt - compass orientation)



For Florida residences only

System Sizing Calculations - Summer

Residential Load - Room by Room Component Details

Spec

Project Title:

Class 3 Rating

911124JohnsonBuildersLot15Russwood

Registration No. 0

Lake City, FL

Climate: North

Reference City: Gainesville (Defaults) Summer Temperature Difference: 17.0 F

12/4/2009

This calculation is for Worst Case. The house has been rotated 315 degrees.

Component Loads for Zone #1: Main

Window	Type*		Overhang		Window Area(sqft)			HTM		Load
	Pn/SHGC/U/InSh/ExSh/IS	Ornt	Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded	
1	2, Clear, 0.87, None,N,N	NW	1.5ft	7ft.	15.0	0.0	15.0	29	60	901 Btuh
2	2, Clear, 0.87, None,N,N	NW	1.5ft	6ft.	8.0	0.0	8.0	29	60	480 Btuh
3	2, Clear, 0.87, None,N,N	NW	1.5ft	8ft.	36.0	0.0	36.0	29	60	2161 Btuh
4	2, Clear, 0.87, None,N,N	NE	1.5ft	8ft.	36.0	0.0	36.0	29	60	2161 Btuh
5	2, Clear, 0.87, None,N,N	N	16ft.	8ft.	20.0	0.0	20.0	29	29	579 Btuh
6	2, Clear, 0.87, None,N,N	NW	13ft.	8ft.	54.0	0.0	54.0	29	60	3242 Btuh
7	2, Clear, 0.87, None,N,N	SW	99ft.	8ft.	10.0	10.0	0.0	29	63	290 Btuh
8	2, Clear, 0.87, None,N,N	NW	1.5ft	8ft.	36.0	0.0	36.0	29	60	2161 Btuh
9	2, Clear, 0.87, None,N,N	NE	1.5ft	6ft.	8.0	0.0	8.0	29	60	480 Btuh
10	2, Clear, 0.87, None,N,N	NE	1.5ft	6ft.	16.0	0.0	16.0	29	60	961 Btuh
11	2, Clear, 0.87, None,N,N	SE	10.5f	8ft.	72.0	72.0	0.0	29	63	2085 Btuh
12	2, Clear, 0.87, None,N,N	SE	14ft.	9ft.	13.5	13.5	0.0	29	63	391 Btuh
13	2, Clear, 0.87, None,N,N	SW	1.5ft	7ft.	20.0	2.1	17.9	29	63	1180 Btuh
14	2, Clear, 0.87, None,N,N	SW	1.5ft	7ft.	30.0	3.1	26.9	29	63	1771 Btuh
	Excursion									2981 Btuh
	Window Total				375 (sqft)					21825 Btuh
Walls	Type	R-Value/U-Value		Area(sqft)			HTM		Load	
1	Face Brick - Wood - Ext	13.0/0.09		1952.5			1.2		2426 Btuh	
2	Frame - Wood - Adj	13.0/0.09		223.0			1.5		336 Btuh	
	Wall Total			2176 (sqft)					2763 Btuh	
Doors	Type				Area (sqft)		HTM		Load	
1	Insulated - Adjacent				20.0		9.8		196 Btuh	
2	Insulated - Exterior				20.0		9.8		196 Btuh	
3	Insulated - Exterior				10.0		9.8		98 Btuh	
4	Insulated - Exterior				20.0		9.8		196 Btuh	
	Door Total			70 (sqft)					686 Btuh	
Ceilings	Type/Color/Surface	R-Value		Area(sqft)			HTM		Load	
1	Vented Attic/DarkShingle	30.0		113.0			1.7		187 Btuh	
2	Vented Attic/DarkShingle	30.0		3124.0			1.7		5174 Btuh	
	Ceiling Total			3237 (sqft)					5361 Btuh	
Floors	Type	R-Value		Size			HTM		Load	
1	Slab On Grade	0.0		288 (ft(p))			0.0		0 Btuh	
	Floor Total			288.0 (sqft)					0 Btuh	
	Zone Envelope Subtotal:									30635 Btuh
Infiltration	Type	ACH		Volume(cuft)			CFM=		Load	
	SensibleNatural	0.30		28116			140.6		2616 Btuh	
Internal gain	Occupants		Btuh/occupant			Appliance		Load		
	6		X 230 +			2400		3780 Btuh		
Duct load	Partially sealed, R6.0, Supply(Attic), Return(Attic)							DGM = 0.00		0.0 Btuh
	Sensible Zone Load									37031 Btuh

Manual J Summer Calculations

Residential Load - Component Details (continued)

Spec
Lake City, FL

Project Title:
911124JohnsonBuildersLot15Russwood

Class 3 Rating
Registration No. 0
Climate: North

12/4/2009

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	37031 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	37031 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	37031 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	5138 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	6338 Btuh
	TOTAL GAIN	43368 Btuh

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Ornt - compass orientation)



For Florida residences only

Residential Window Diversity

MidSummer

Spec

Lake City, FL

Project Title:

911124JohnsonBuildersLot15Russwood

Class 3 Rating

Registration No. 0


Climate: North

12/4/2009

Weather data for: Gainesville - Defaults

Summer design temperature	92 F	Average window load for July	15718 Btu
Summer setpoint	75 F	Peak window load for July	23414 Btu
Summer temperature difference	17 F	Excursion limit(130% of Ave.)	20433 Btu
Latitude	29 North	Window excursion (July)	2981 Btu

WINDOW Average and Peak Loads



Warning: This application has glass areas that produce relatively large heat gains for part of the day. Variable air volume devices may be required to overcome spikes in solar gain for one or more rooms. A zoned system may be required or some rooms may require zone control.

EnergyGauge® System Sizing for Florida residences only

PREPARED BY:

DATE:

12/4/09

EnergyGauge® FLR2PB v4.1



**Columbia County Building Department
Culvert Waiver**

**Culvert Waiver No.
000001776**

DATE: 12/16/2009 BUILDING PERMIT NO. 28279

APPLICANT PATRICIA JOHNSON PHONE 755-4038

ADDRESS 204 SW DUSTY GLEN LAKE CITY FL 32024

OWNER PATRICIA JOHNSON PHONE 755-4038

ADDRESS 234 SW SCOTT PLACE LAKE CITY FL 32024

CONTRACTOR PATRICIA JOHNSON PHONE 755-4038

LOCATION OF PROPERTY 90W, TL ON 247S, TR ON TROY ROAD, TR RUSSWOOD TERR., TL

BETHANY PL, TR DOROTHY, TR SCOTT PLACE, TO THE END ON

RIGHT _____

SUBDIVISION/LOT/BLOCK/PHASE/UNIT RUSSWOOD ESTATES 15

PARCEL ID # 10-4S-16-02853-415

I HEREBY CERTIFY THAT I UNDERSTAND AND WILL FULLY COMPLY WITH THE DECISION OF THE COLUMBIA COUNTY PUBLIC WORKS DEPARTMENT IN CONNECTION WITH THE HEREIN PROPOSED APPLICATION.

SIGNATURE: 

A SEPARATE CHECK IS REQUIRED
MAKE CHECKS PAYABLE TO BCC


Amount Paid 50.00

PUBLIC WORKS DEPARTMENT USE ONLY

I HEREBY CERTIFY THAT I HAVE EXAMINED THIS APPLICATION AND DETERMINED THAT THE
CULVERT WAIVER IS:

_____APPROVED_____ NOT APPROVED - NEEDS A CULVERT PERMIT

COMMENTS: _____

SIGNED:  DATE: 12-29-09

ANY QUESTIONS PLEASE CONTACT THE PUBLIC WORKS DEPARTMENT AT 386-752-5955.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160



FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs Residential Performance Method A

Project Name: 911124JohnsonBuildersLot15Russwood
 Street:
 City, State, Zip: Lake City, FL,
 Owner: Spec
 Design Location: FL, Gainesville

Builder Name: John Johnson
 Permit Office: *COLUMBIA*
 Permit Number: *28279*
 Jurisdiction: *221000*

1. New construction or existing	New (From Plans)	
2. Single family or multiple family	Single-family	
3. Number of units, if multiple family	1	
4. Number of Bedrooms	4	
5. Is this a worst case?	Yes	
6. Conditioned floor area (ft ²)	3124	
7. Windows	Description	Area
a. U-Factor:	Dbl, default	374.50 ft ²
SHGC:	Clear, default	
b. U-Factor:	N/A	ft ²
SHGC:		
c. U-Factor:	N/A	ft ²
SHGC:		
d. U-Factor:	N/A	ft ²
SHGC:		
e. U-Factor:	N/A	ft ²
SHGC:		
8. Floor Types	Insulation	Area
a. Slab-On-Grade Edge Insulation	R=0.0	3124.00 ft ²
b. N/A	R=	ft ²
c. N/A	R=	ft ²

9. Wall Types	Insulation	Area
a. Face Brick - Wood, Exterior	R=13.0	2397.00 ft ²
b. Frame - Wood, Adjacent	R=13.0	243.00 ft ²
c. N/A	R=	ft ²
d. N/A	R=	ft ²
10. Ceiling Types	Insulation	Area
a. Under Attic (Vented)	R=30.0	3124.00 ft ²
b. Knee Wall (Vented)	R=30.0	113.00 ft ²
c. N/A	R=	ft ²
11. Ducts		
a. Sup: Attic Ret: Attic AH: Garage Sup. R= 6,	380 ft ²	
12. Cooling systems		
a. Central Unit	Cap: 56.0 kBtu/hr	SEER: 13
13. Heating systems		
a. Electric Heat Pump	Cap: 56.0 kBtu/hr	HSPF: 7.7
14. Hot water systems		
a. Electric	Cap: 50 gallons	EF: 0.93
b. Conservation features		
None		
15. Credits	None	

Glass/Floor Area: 0.120

Total As-Built Modified Loads: 49.08

Total Baseline Loads: 58.73

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY:

DATE: *12/4/09 EVAN BOANSLEY*

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT:

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.



BUILDING OFFICIAL: _____

DATE: _____



PROJECT

Title: 911124JohnsonBuildersLot15	Bedrooms: 4	Address Type: Lot Information
Building Type: FLAsBuilt	Bathrooms: 0	Lot #: 15
Owner: Spec	Conditioned Area: 3124	SubDivision: russwood
# of Units: 1	Total Stories: 1	PlatBook:
Builder Name: John Johnson	Worst Case: Yes	Street:
Permit Office:	Rotate Angle: 315	County: Columbia
Jurisdiction:	Cross Ventilation: No	City, State, Zip: Lake City ,
Family Type: Single-family	Whole House Fan: No	FI ,
New/Existing: New (From Plans)		
Comment:		

CLIMATE

	Design Location	TMY Site	IECC Zone	Design Temp 97.5 % 2.5 %	Int Design Temp Winter Summer	Heating Degree Days	Design Moisture	Daily Temp Range
✓	FL, Gainesville	FL_GAINESVILLE_REGI	2	32 92	75 70	1305.5	51	Medium

FLOORS

	#	Floor Type	Perimeter	R-Value	Area	Tile	Wood	Carpet
✓	1	Slab-On-Grade Edge Insulatio	288 ft	0	3124 ft²	0.3	0.3	0.4

ROOF

	#	Type	Materials	Roof Area	Gable Area	Roof Color	Solar Absor.	Tested	Deck Insul.	Pitch
✓	1	Hip	Composition shingles	3618 ft²	0 ft²	Dark	0.96	No	0	30.3 deg

ATTIC

	#	Type	Ventilation	Vent Ratio (1 in)	Area	RBS	IRCC
✓	1	Full attic	Vented	303	3124 ft²	N	N

CEILING

	#	Ceiling Type	R-Value	Area	Framing Frac	Truss Type
✓	1	Under Attic (Vented)	30	3124 ft²	0.11	Wood
	2	Knee Wall (Vented)	30	113 ft²	0.11	Wood

WALLS

	#	Ornt	Adjacent To	Wall Type	Cavity R-Value	Area	Sheathing R-Value	Framing Fraction	Solar Absor.
✓	1	N	Exterior	Face Brick - Wood	13	688.5 ft²	0	0.23	0.75
	2	S	Exterior	Face Brick - Wood	13	472.5 ft²	0	0.23	0.75
	3	E	Exterior	Face Brick - Wood	13	538.5 ft²	0	0.23	0.75
	4	W	Exterior	Face Brick - Wood	13	595.5 ft²	0	0.23	0.75
	5	NE	Exterior	Face Brick - Wood	13	102 ft²	0	0.23	0.75
	6	??	Garage	Frame - Wood	13	243 ft²		0.23	0.01

DOORS

✓	#	Ornt	Door Type	Storms	U-Value	Area
_____	1	NE	Insulated	None	0.4	10 ft²
_____	2	W	Insulated	None	0.4	10 ft²
_____	3	S	Insulated	None	0.4	20 ft²
_____	4	??	Insulated	None	0.4	20 ft²
_____	5	NE	Insulated	None	0.4	10 ft²

WINDOWS

Window orientation below is as entered. Actual orientation is modified by rotate angle shown in "Project" section above.

✓	#	Ornt	Frame	Panes	NFRC	U-Factor	SHGC	Storms	Area	Overhang		Int Shade	Screening
										Depth	Separation		
_____	1	N	Metal	Double (Clear)	No	0.87	0.66	N	15 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	2	N	Metal	Double (Clear)	No	0.87	0.66	N	8 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	3	N	Metal	Double (Clear)	No	0.87	0.66	N	36 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	4	E	Metal	Double (Clear)	No	0.87	0.66	N	36 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	5	NE	Metal	Double (Clear)	No	0.87	0.66	N	20 ft²	0 ft 192 in	0 ft 42 in	HERS 2006	None
_____	6	N	Metal	Double (Clear)	No	0.87	0.66	N	54 ft²	0 ft 156 in	0 ft 30 in	HERS 2006	None
_____	7	W	Metal	Double (Clear)	No	0.87	0.66	N	10 ft²	0 ft 1188 in	0 ft 42 in	HERS 2006	None
_____	8	N	Metal	Double (Clear)	No	0.87	0.66	N	36 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	9	E	Metal	Double (Clear)	No	0.87	0.66	N	8 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	10	E	Metal	Double (Clear)	No	0.87	0.66	N	16 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	11	S	Metal	Double (Clear)	No	0.87	0.66	N	72 ft²	0 ft 126 in	0 ft 30 in	HERS 2006	None
_____	12	S	Metal	Double (Clear)	No	0.87	0.66	N	13.5 ft²	0 ft 168 in	0 ft 33 in	HERS 2006	None
_____	13	W	Metal	Double (Clear)	No	0.87	0.66	N	20 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None
_____	14	W	Metal	Double (Clear)	No	0.87	0.66	N	30 ft²	0 ft 18 in	0 ft 30 in	HERS 2006	None

INFILTRATION & VENTING

✓	Method	SLA	CFM 50	ACH 50	ELA	EqLA	--- Forced Ventilation ---		Run Time	Fan
							Supply CFM	Exhaust CFM	Fraction	Watts
_____	Default	0.00036	2950	6.30	161.9	304.6	0 cfm	0 cfm	0	0

GARAGE

✓	#	Floor Area	Ceiling Area	Exposed Wall Perimeter	Avg. Wall Height	Exposed Wall Insulation
_____	1	925.2 ft²	925.2 ft²	96 ft	9 ft	(invalid)

COOLING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Air Flow	SHR	Ductless
_____	1	Central Unit	None	SEER: 13	56 kBtu/hr	1680 cfm	0.75	

HEATING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Ductless
_____	1	Electric Heat Pump	None	HSPF: 7.7	56 kBtu/hr	

HOT WATER SYSTEM

✓	#	System Type	EF	Cap	Use	SetPnt	Conservation
_____	1	Electric	0.93	50 gal	70 gal	120 deg	None

SOLAR HOT WATER SYSTEM

✓	FSEC Cert #	Company Name	System Model #	Collector Model #	Collector Area	Storage Volume	FEF
_____	None	None			ft²		

DUCTS

✓	#	Location	Supply R-Value	Area	Location	Return Area	Leakage Type	Air Handler	CFM 25	Percent Leakage	QN	RLF
_____	1	Attic	6	380 ft²	Attic	60 ft²	Default Leakage	Garage				

TEMPERATURES

Programable Thermostat: N

Ceiling Fans:

Cooling	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec
Heating	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec
Venting	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec

Thermostat Schedule: HERS 2006 Reference

Schedule Type		1	2	3	4	5	6	7	8	9	10	11	12
Cooling (WD)	AM	78	78	78	78	78	78	78	78	78	78	78	78
	PM	78	78	78	78	78	78	78	78	78	78	78	78
Cooling (WEH)	AM	78	78	78	78	78	78	78	78	78	78	78	78
	PM	78	78	78	78	78	78	78	78	78	78	78	78
Heating (WD)	AM	68	68	68	68	68	68	68	68	68	68	68	68
	PM	68	68	68	68	68	68	68	68	68	68	68	68
Heating (WEH)	AM	68	68	68	68	68	68	68	68	68	68	68	68
	PM	68	68	68	68	68	68	68	68	68	68	68	68

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS:

Lake City, FL,

PERMIT #:

INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	N1106.AB.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	N1106.AB.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	N1106.AB.1.2.2	Penetrations/openings > 1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	N1106.AB.1.2.3	Between walls & ceilings; penetrations of ceiling plane to top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	N1106.AB.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	N1106.AB.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	N1106.AB.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	N1112.AB.3	Comply with efficiency requirements in Table N112.ABC.3. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	N1112.AB.2.3	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%. Heat pump pool heaters shall have a minimum COP of 4.0.	
Shower heads	N1112.AB.2.4	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	N1110.AB	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated and installed in accordance with the criteria of Section N1110.AB. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	N1107.AB.2	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	N1104.AB.1 N1102.B.1.1	Ceilings-Min. R-19. Common walls-frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE INDEX* = 84

The lower the EnergyPerformance Index, the more efficient the home.

, Lake City, FL,

1. New construction or existing	New (From Plans)	9. Wall Types	Insulation	Area
2. Single family or multiple family	Single-family	a. Face Brick - Wood, Exterior	R=13.0	2397.00 ft ²
3. Number of units, if multiple family	1	b. Frame - Wood, Adjacent	R=13.0	243.00 ft ²
4. Number of Bedrooms	4	c. N/A	R=	ft ²
5. Is this a worst case?	Yes	d. N/A	R=	ft ²
6. Conditioned floor area (ft ²)	3124	10. Ceiling Types	Insulation	Area
7. Windows**	Description	a. Under Attic (Vented)	R=30.0	3124.00 ft ²
a. U-Factor:	Dbl, default	b. Knee Wall (Vented)	R=30.0	113.00 ft ²
SHGC:	Clear, default	c. N/A	R=	ft ²
b. U-Factor:	N/A	11. Ducts		
SHGC:		a. Sup: Attic Ret: Attic AH: Garage Sup. R= 6, 380 ft ²		
c. U-Factor:	N/A	12. Cooling systems	Cap: 56.0 kBtu/hr	
SHGC:		a. Central Unit	SEER: 13	
d. U-Factor:	N/A	13. Heating systems	Cap: 56.0 kBtu/hr	
SHGC:		a. Electric Heat Pump	HSPF: 7.7	
e. U-Factor:	N/A	14. Hot water systems	Cap: 50 gallons	
SHGC:		a. Electric	EF: 0.93	
8. Floor Types	Insulation	b. Conservation features		
a. Slab-On-Grade Edge Insulation	R=0.0	None		
b. N/A	R=	15. Credits		None
c. N/A	R=			

I certify that this home has complied with the Florida Energy Efficiency Code for Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



*Note: The home's estimated Energy Performance Index is only available through the EnergyGauge USA - FlaRes2008 computer program. This is not a Building Energy Rating. If your Index is below 100, your home may qualify for incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at (321) 638-1492 or see the Energy Gauge web site at energygauge.com for information and a list of certified Raters. For information about Florida's Energy Efficiency Code for Building Construction, contact the Department of Community Affairs at (850) 487-1824.

**Label required by Section 13-104.4.5 of the Florida Building Code, Building, or Section B2.1.1 of Appendix G of the Florida Building Code, Residential, if not DEFAULT.

2348W Scott Pl

28279

SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER This is a
corrected copy
In Columbia County one changing the
records of the subcontri name of the
Ordinance 89-6, a contri mason
exemption, general liabi

ACTOR Patricia M. Johnson PHONE 386-755-4038
ED PRIOR TO THE ISSUANCE OF A PERMIT

ing work at the permitted site. It is **REQUIRED** that we have
specific work under the permit. Per Florida Statute 440 and
ctors to provide evidence of workers' compensation or
ate of Competency license in Columbia County.

Any changes, the permi or the corrected form being submitted to this office prior to the
start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL ER13012377	Print Name <u>Holly Electric Inc</u> License #: <u>ER13012377</u> Phone #: <u>386-755-5944</u>	Signature <u>[Signature]</u>
MECHANICAL/ A/C	Print Name <u>BROTHER HT & H/C</u> License #: <u>RA0035027</u> Phone #: <u>386-754-6700</u>	Signature <u>[Signature]</u>
PLUMBING/ GAS	Print Name <u>Cady Davis Davis Plumbing</u> License #: <u>CFC1427145</u> Phone #: <u>386-623-0509</u>	Signature <u>[Signature]</u>
ROOFING	Print Name <u>Durrell Turner</u> License #: <u>CCC1328465</u> Phone #: <u>755-0086</u>	Signature <u>[Signature]</u>
SHEET METAL	Print Name <u> </u> License #: <u> </u> Phone #: <u> </u>	Signature <u> </u>
FIRE SYSTEM/ SPRINKLER	Print Name <u> </u> License #: <u> </u> Phone #: <u> </u>	Signature <u> </u>
SOLAR	Print Name <u> </u> License #: <u> </u> Phone #: <u> </u>	Signature <u> </u>

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON	000810	Roger Romina	Roger Romina
CONCRETE FINISHER	000218	TONY E. JORDAN SR	Tony E. Jordan
FRAMING	RG0066597	John D. Norris	John D. Norris
INSULATION	RR282811528	Patricia M Johnson	Patricia M Johnson
STUCCO			
DRYWALL	000345	Kim Heitzman	Kim Heitzman
PLASTER			
CABINET INSTALLER	RR282811528	Patricia M Johnson	Patricia M Johnson
PAINTING	RR282811528	Patricia M Johnson	Patricia M Johnson
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE	RR282811528	Patricia M Johnson	Patricia M Johnson
FLOOR COVERING	RR282811528	Patricia M Johnson	Patricia M Johnson
ALUM/VINYL SIDING			
GARAGE DOOR	RR282811528	Patricia M Johnson	Patricia M Johnson
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.—Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.



RE: JOHNSON-SPEC - ROOF DESIGN INFO

Site Information:

Customer Info: JOHNSON BUILDERS Model: SPEC LOT15 ROSEWOOD ESTATES
 Lot/Block: . Subdivision: .
 Address: .
 City: LAKE CITY State: FLORIDA

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name: License #:
 Address:
 City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2007 Design Program: Robbins OnLine Plus 25.0.012
 Wind Code: ASCE 7-05 Wind Speed: 120 mph Floor Load: N/A psf
 Roof Load: 40.0 psf

This package includes 79 individual, dated Truss Design Drawings and 0 Additional Drawings.
 With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	T3555288	A1	11/25/09	18	T3555305	A18	11/25/09
2	T3555289	A2	11/25/09	19	T3555306	A19	11/25/09
3	T3555290	A3	11/25/09	20	T3555307	A20	11/25/09
4	T3555291	A4	11/25/09	21	T3555308	A21	11/25/09
5	T3555292	A5	11/25/09	22	T3555309	A22	11/25/09
6	T3555293	A6	11/25/09	23	T3555310	VJ3	11/25/09
7	T3555294	A7	11/25/09	24	T3555311	VJ2	11/25/09
8	T3555295	A8	11/25/09	25	T3555312	VCJ1	11/25/09
9	T3555296	A9	11/25/09	26	T3555313	VJ1	11/25/09
10	T3555297	A10	11/25/09	27	T3555314	J2	11/25/09
11	T3555298	A11	11/25/09	28	T3555315	J8	11/25/09
12	T3555299	A12	11/25/09	29	T3555316	J13	11/25/09
13	T3555300	A13	11/25/09	30	T3555317	J12	11/25/09
14	T3555301	A14	11/25/09	31	T3555318	J11	11/25/09
15	T3555302	A15	11/25/09	32	T3555319	CJ2	11/25/09
16	T3555303	A16	11/25/09	33	T3555320	J10	11/25/09
17	T3555304	A17	11/25/09	34	T3555321	J9	11/25/09



The truss drawing(s) referenced above have been prepared by Robbins Engineering, Inc. under my direct supervision based on the parameters provided by Mayo Truss Company, Inc..

Truss Design Engineer's Name: Velez, Joaquin

My license renewal date for the state of Florida is February 28, 2011.

NOTE: The seal on these drawings indicate acceptance of professional engineering responsibility solely for the truss components shown. The suitability and use of this component for any particular building is the responsibility of the building designer, per ANSI/TPI-1 Sec. 2.

Office Copies - in draft

6904 Parke East Boulevard
 Tampa, FL 33610-4115
 Phone: 813-972-1135 • Fax: 813-971-6117
 www.robbsengineering.com

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert. #5555

DALLAS

TAMPA

FT. WORTH
 Velez, Joaquin

November 25, 2009

1 of 2

RE: JOHNSON-SPEC - ROOF DESIGN INFO

Site Information:

Project Customer: JOHNSON BUILDERS Project Name: SPEC LOT15 ROSEWOOD ESTATES

Lot/Block: Subdivision:

Address:

City: LAKE CITY


State: FLORIDA


No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
35	T3555322	A23GIR	11/25/09	78	T3555365	P5	11/25/09
36	T3555323	A24	11/25/09	79	T3555366	P6	11/25/09
37	T3555324	A25	11/25/09				
38	T3555325	A26	11/25/09				
39	T3555326	A27	11/25/09				
40	T3555327	J6	11/25/09				
41	T3555328	J5	11/25/09				
42	T3555329	J4	11/25/09				
43	T3555330	CJ1	11/25/09				
44	T3555331	E2	11/25/09				
45	T3555332	E1	11/25/09				
46	T3555333	M1GIR	11/25/09				
47	T3555334	A28GIR	11/25/09				
48	T3555335	B1	11/25/09				
49	T3555336	B2	11/25/09				
50	T3555337	B3	11/25/09				
51	T3555338	B4GIR	11/25/09				
52	T3555339	B5	11/25/09				
53	T3555340	B6	11/25/09				
54	T3555341	B7	11/25/09				
55	T3555342	B8	11/25/09				
56	T3555343	B9	11/25/09				
57	T3555344	B10	11/25/09				
58	T3555345	B11	11/25/09				
59	T3555346	B12	11/25/09				
60	T3555347	C1GIR	11/25/09				
61	T3555348	C2	11/25/09				
62	T3555349	J14	11/25/09				
63	T3555350	CJ3	11/25/09				
64	T3555351	CJ4	11/25/09				
65	T3555352	D1GIR	11/25/09				
66	T3555353	J1	11/25/09				
67	T3555354	D2GIR	11/25/09				
68	T3555355	J7	11/25/09				
69	T3555356	E3GIR	11/25/09				
70	T3555357	J15	11/25/09				
71	T3555358	J16	11/25/09				
72	T3555359	J17	11/25/09				
73	T3555360	J19	11/25/09				
74	T3555361	P1	11/25/09				
75	T3555362	P2	11/25/09				
76	T3555363	P3	11/25/09				
77	T3555364	P4	11/25/09				

SPEC LOT15 ROSEWOOD ESTATES



November 25, 2009





Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
TC 0.44 2x 4 SP-#2
BC 0.42 2x 4 SP-#2
CW 0.26 2x 4 SP-#2
WB 0.57 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 25- 4- 0
TC 24.0" 25- 4- 0 35- 3-15
TC Cont. 35- 3-15 51- 8- 0
BC Cont. 0- 0- 0 51- 8- 0
One Continuous Lateral Brace
T -N M -U L -D
Attach CLB with (2)-10d nails
at each web.

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz
A 313 194 U 232 R
I 2039 530 U
F 2180 490 U
E 67 216 U 271 R

Jt Brg Size Required
A 3.5" 1.5"
I 3.5" 2.2"
F 4.2" 2.4"
E 3.5" 1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-Csi-Bnd
-----Top Chords-----
A -R 0.23 529 T 0.06 0.17
R -S 0.44 1141 T 0.19 0.25
S -B 0.27 1810 C 0.02 0.25
B -T 0.42 1902 C 0.06 0.36
T -C 0.39 1528 C 0.09 0.30
C -U 0.24 1310 C 0.01 0.23
U -D 0.24 1302 C 0.01 0.23

Robbins Engineering, Inc./Online Plus™
D -V 0.27 1175 C 0.08 0.19
V -W 0.24 732 C 0.05 0.19
W -X 0.38 654 T 0.10 0.28
X -Y 0.36 399 T 0.08 0.28
-----Bottom Chords-----
A -Q 0.15 518 C 0.00 0.15
Q -I 0.13 111 C 0.00 0.13
H -P 0.22 1100 C 0.00 0.22
P -O 0.42 1786 T 0.30 0.12
O -N 0.39 1656 T 0.27 0.12
N -M 0.38 1302 T 0.21 0.17
M -L 0.34 1013 T 0.17 0.17
L -K 0.23 640 T 0.10 0.13
K -G 0.12 593 C 0.00 0.12
F -J 0.15 62 C 0.00 0.15
J -E 0.15 259 T 0.00 0.15
-----Chord Webs-----
I -H 0.26 2008 C 0.03 0.23
H -S 0.16 1835 C 0.16 0.00
F -G 0.20 2194 C 0.20 0.00
G -W 0.19 1847 C 0.19 0.00

-----Webs-----
Q -R 0.02 174 T
Q -H 0.16 576 C
R -H 0.32 1173 T
S -P 0.54 2976 T
P -B 0.09 771 C
B -O 0.13 199 C
O -T 0.04 300 T
T -N 0.14 527 C 1 Br
N -C 0.23 480 T
M -U 0.12 131 T
M -U 0.11 334 C 1 Br
M -D 0.38 619 T
L -D 0.08 250 C 1 Br
L -V 0.10 567 T
K -V 0.57 956 C
K -W 0.29 1611 T
G -X 0.08 542 C
G -J 0.03 328 C
J -X 0.06 370 T
J -Y 0.13 337 C
E -Y 0.02 200 T WindLd

TL Defl -0.24" in P -O L/999
LL Defl -0.10" in P -O L/999
Shear // Grain in B -T 0.23

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 4.0x 6.0 Ctr 0.1 0.44
R MT20 3.0x 7.0 1.0 Ctr 0.60
S MT20 6.0x 6.0 Ctr Ctr 0.87
B MT20 6.0x 6.0 Ctr Ctr 0.40
T MT20 3.0x 7.0 Ctr Ctr 0.33

APPROX. TRUSS WEIGHT: 442.3 LBS

C MT20 6.0x 6.0 1.0-3.7 0.33
U MT20 3.0x 7.0 Ctr Ctr 0.32
D MT20 7.0x 6.0-1.1-4.2 0.53
V MT20 3.0x 7.0 Ctr Ctr 0.41
W MT20 6.0x 8.0 Ctr 0.1 0.48
X MT20 3.0x 7.0 Ctr Ctr 0.38
Y MT20 6.0x 6.0 Ctr Ctr 0.14
Q MT20 4.0x 6.0 1.2 0.1 0.27
I MT20 3.0x 4.0 Ctr Ctr 0.69
H MT20 6.0x 8.0 Ctr 1.9 0.52
P MT20 6.0x 6.0-1.7 0.1 0.91
O MT20 3.0x 7.0 Ctr Ctr 0.23
N MT20 5.0x 9.0 1.5-0.5 0.43
M MT20 3.0x 7.0 Ctr Ctr 0.43
L MT20 5.0x 7.0 Ctr-0.5 0.39
K MT20 3.0x 7.0 Ctr Ctr 0.73
G MT20 6.0x10.0 Ctr 1.3 0.43
F MT20 3.0x 4.0 Ctr Ctr 0.75
J MT20 4.0x 8.0 Ctr Ctr 0.23
E MT20 2.0x 4.0 Ctr Ctr 0.31

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf


BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- --To--
0- 0- 0 9- 3- 8
44- 8- 9 51- 8- 0
Max comp. force 2194 Lbs
Max tens. force 2976 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555



Scale: 0.105" = 1'

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert. #5555



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 362.6 LBS

Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
 TC 0.58 2x 4 SP-#2
 BC 0.85 2x 4 SP-#2
 WB 0.63 2x 4 SP-#2
 -- 0.11 2x 6 SP-#2
 G -D
 SCAB (1) 2x 4 SP-#2

Brace truss as follows:
 O.C. From To

TC Cont. 0- 0- 0 13- 9- 8
 TC 24.0" 13- 9- 8 23- 9- 8
 TC Cont. 23- 9- 8 40- 1- 8
 BC Cont. 0- 0- 0 40- 1- 8

One Continuous Lateral Brace
 A -T L -W W -V V -P
 Attach CLB with (2)-10d nails
 at each web.

psf-Ld Dead Live
 TC 10.0 20.0
 BC 10.0 0.0
 TC+BC 20.0 20.0
 Total 40.0 Spacing 24.0"
 Lumber Duration Factor 1.25
 Plate Duration Factor 1.25
 TC Fb=1.15 Fc=1.10 Fts=1.10
 BC Fb=1.10 Fc=1.10 Fts=1.10

Total Load Reactions (Lbs)
 Jt Down Uplift Horiz
 A 1813 331 U 252 R
 F 1781 331 U 236 R

Jt Brg Size Required
 A 3.5" 2.1"
 F 3.5" 2.1"

Plus 9 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 BC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd
 -----Top Chords-----
 R -T 0.23 95 T 0.01 0.22
 T -U 0.31 2329 C 0.12 0.19
 U -B 0.25 2132 C 0.12 0.13
 B -W 0.26 1845 C 0.02 0.24
 W -C 0.26 2014 C 0.12 0.14
 C -P 0.29 2091 C 0.12 0.17
 P -Q 0.39 2747 C 0.05 0.34
 Q -D 0.58 3295 C 0.12 0.46
 D -E 0.20 3055 C 0.14 0.06
 -----Bottom Chords-----
 A -S 0.55 1926 T 0.32 0.23
 S -L 0.70 1983 T 0.33 0.37
 L -V 0.70 2016 T 0.33 0.37
 V -I 0.76 2365 T 0.39 0.37

I -H 0.56 2879 T 0.48 0.08
 H -G 0.85 3724 T 0.62 0.23
 G -F 0.23 228 T 0.00 0.23

-----Webs-----
 A -R 0.01 146 C WindLd
 A -T 0.41 2528 C 1 Br
 T -S 0.03 190 T
 S -U 0.02 152 T
 U -L 0.33 341 C
 L -B 0.38 800 T
 L -W 0.15 361 C 1 Br
 W -V 0.03 131 T 1 Br
 V -C 0.40 797 T
 V -P 0.27 738 C 1 Br
 I -P 0.09 528 T
 I -Q 0.35 608 C
 H -Q 0.04 300 T
 H -D 0.31 847 C
 G -D 0.11 1910 C
 G -E 0.63 3429 T
 F -E 0.14 1538 C WindLd

TL Defl -0.46" in V -I L/999
 LL Defl -0.21" in V -I L/999
 Shear // Grain in Q -D 0.24

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area
 Jt Type Plt Size X Y JSI
 R MT20 2.0x 4.0 Ctr Ctr 0.28
 T MT20 5.0x 5.0-0.6-0.3 0.93
 U MT20 5.0x 7.0-0.3 0.5 0.45
 B MT20 5.0x 5.0 0.8-3.1 0.47
 W MT20 3.0x 7.0 Ctr Ctr 0.30
 C MT20 5.0x 5.0-0.8-3.1 0.46
 P MT20 5.0x 7.0 0.3 0.5 0.38
 Q MT20 3.0x 7.0 Ctr Ctr 0.27
 D MT20 5.0x 5.0 Ctr Ctr 0.83
 E MT20 4.0x10.0-1.5 0.8 0.96
 A MT20 5.0x 5.0 Ctr Ctr 0.78
 S MT20 3.0x 7.0-1.0 Ctr 0.35
 L MT20 5.0x 9.0 0.5-0.5 0.51
 V MT20 4.0x 8.0 Ctr Ctr 0.36
 I MT20 5.0x 7.0 Ctr-0.5 0.56
 H MT20 4.0x 6.0 1.2 Ctr 0.33
 G MT20 3.0x 9.0 1.5-0.2 0.96
 F# MT20 2.0x 4.0 Ctr-0.2 0.45

= Plate Monitor used
 REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.

Analysis Conforms To:
 FBC2007
 TPI 2002

Fasten each scab (shaded) with
 2 rows of 10d nails at 6 in
 o.c. each row, staggered
 along entire length.

This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.


Design checked for 10 psf non-
 concurrent LL on BC.

NOTE: USER MODIFIED PLATES
 This design may have plates
 selected through a plate
 monitor.

Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0
 Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 3295 Lbs
 Max tens. force 3724 Lbs
 Fabrication Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which is
 used to calculate total load
 deflection.

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 348.0 LBS

Online Plus -- Version 25.0.012

RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---

TC 0.60 2x 4 SP-#2

BC 0.72 2x 4 SP-#2

WB 0.65 2x 4 SP-#2

Brace truss as follows:

O.C. From To

TC Cont. 0- 0- 0 40- 1- 8

BC Cont. 0- 0- 0 40- 1- 8

One Continuous Lateral Brace

O -S S -P

Attach CLB with (2)-10d nails

at each web.

psf-Ld Dead Live

TC 10.0 20.0

BC 10.0 0.0

TC+BC 20.0 20.0

Total 40.0 Spacing 24.0"

Lumber Duration Factor 1.25

Plate Duration Factor 1.25

TC Fb=1.15 Fc=1.10 Ft=1.10

BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)

Jt Down Uplift Horiz

A 1753 331 U 309 R

F 1736 331 U 311 R

Jt Brg Size Required

A 3.5" 2.1"

F 3.5" 2.0"

Plus 9 Wind Load Case(s)

Plus 1 UBC LL Load Case(s)

Plus 1 BC LL Load Case(s)

Plus 1 DL Load Case(s)

Membr CSI P Lbs Ax1-CSI-Bnd

-----Top Chords-----

R -N 0.44 2229 C 0.07 0.37

N -O 0.38 2191 C 0.11 0.27

O -B 0.37 1758 C 0.11 0.26

B -C 0.20 1561 C 0.11 0.09

C -P 0.37 1757 C 0.11 0.26

P -Q 0.40 2424 C 0.04 0.36

Q -D 0.60 2930 C 0.12 0.48

D -E 0.33 3115 C 0.06 0.27

-----Bottom Chords-----

A -M 0.18 289 T 0.00 0.18

M -L 0.55 1939 T 0.32 0.23

L -S 0.65 1892 T 0.31 0.34

S -I 0.69 2091 T 0.35 0.34

I -H 0.64 2552 T 0.42 0.22

H -G 0.72 3248 T 0.54 0.18

G -F 0.10 290 T 0.00 0.10

-----Webs-----

A -R 0.16 1698 C WindLd

R -M 0.36 1983 T

M -N 0.10 311 C

N -L 0.15 192 C

L -O 0.05 302 T

O -S 0.25 565 C 1 Br

B -S 0.56 649 T

S -C 0.56 645 T

S -P 0.38 860 C 1 Br

I -P 0.16 620 T

I -Q 0.47 602 C

H -Q 0.05 350 T

H -D 0.38 710 C

G -D 0.15 1621 C

G -E 0.65 3529 T

F -E 0.16 1684 C WindLd

TL Defl -0.43" in S -I L/999

LL Defl -0.20" in S -I L/999

Shear // Grain in Q -D 0.24

Plates for each ply each face.

Plate - MT20 20 Ga, Gross Area

Plate - MT2H 20 Ga, Gross Area

Jt Type Plt Size X Y JSI

R MT20 5.0x 5.0 Ctr Ctr 0.81

N MT20 3.0x 7.0 Ctr Ctr 0.30

O MT20 5.0x 7.0-0.3 0.5 0.38

B MT20 5.0x 5.0 0.8-3.1 0.39

C MT20 5.0x 5.0-0.8-3.1 0.39

P MT20 5.0x 7.0 0.3 0.5 0.38

Q MT20 3.0x 7.0 Ctr Ctr 0.30

D MT20 5.0x 5.0 Ctr Ctr 0.74

E MT20 5.0x 7.0 Ctr Ctr 0.92

A MT20 2.0x 4.0 Ctr Ctr 0.55

M MT20 4.0x 6.0-1.7 0.2 0.83

L MT20 5.0x 7.0 Ctr-0.5 0.41

S MT20 4.0x10.0 Ctr Ctr 0.53

I MT20 5.0x 7.0 Ctr-0.5 0.50

H MT20 4.0x 6.0 1.2 0.2 0.27

G MT20 4.0x 6.0 1.5 Ctr 0.94

F MT20 2.0x 4.0 Ctr Ctr 0.53

REVIEWED BY:

Robbins Engineering, Inc.

6904 Parke East Blvd.

Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL

NOTES AND SYMBOLS SHEET FOR

ADDITIONAL SPECIFICATIONS.

NOTES:

Trusses Manufactured by:

Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

This truss has been designed

for 20.0 psf LL on the B.C.

in areas where a rectangle

3- 6- 0 tall by

2- 0- 0 wide

will fit between the B.C.

and any other member.

Design checked for 10 psf non-

concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*

for Exterior zone location.

Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B

Occupancy Factor : 1.00

Building Type: Enclosed

TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf

Max comp. force 3115 Lbs

Max tens. force 3529 Lbs

Connector Plate Fabrication

Tolerance = 20%

This truss is designed for a

creep factor of 1.5 which

is used to calculate total

load deflection.

Joaquin Velez, FL Lic. #68182

Robbins Engineering


6904 Parke East Blvd

Tampa, FL, 33610

FL Cert.#5555

November 25,2009

Job JOHNSON-SPEC	Mark A12	Quan 1	Type SP	Span 400108	Pl-H1 7	Left OH 0	Right OH 0	Engineering T3555299
SPEC LOT15 ROSEWOOD ESTATES								



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
TC 0.54 2x 4 SP-#2
BC 0.62 2x 4 SP-#2
CW 0.10 2x 4 SP-#2
WB 0.59 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0-0-0 12-0-9
TC 24.0\" 12-0-9 25-6-6
TC Cont. 25-6-6 40-1-8
BC Cont. 0-0-0 40-1-8
One Continuous Lateral Brace
L-O
Attach CLB with (2)-10d nails
at each web.

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0\"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 1747 329 U 244 R
F 1730 332 U 247 R

Jt Brg Size Required
A 3.5\" 2.1\"
F 3.5\" 2.0\"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-Csi-Bnd
-----Top Chords-----
Q -N 0.43 2204 C 0.12 0.31
N -B 0.43 2163 C 0.12 0.31
B -O 0.54 2221 C 0.03 0.51
O -C 0.54 2221 C 0.03 0.51
C -P 0.34 2357 C 0.03 0.31
P -D 0.41 2783 C 0.09 0.32
D -E 0.32 2834 C 0.05 0.27

-----Bottom Chords-----
A -H 0.25 54 C 0.00 0.25
G -M 0.55 1925 T 0.32 0.23
M -L 0.59 1862 T 0.31 0.28
L -K 0.62 2033 T 0.34 0.28
K -J 0.60 2420 T 0.40 0.20
J -I 0.57 2892 T 0.48 0.09
I -F 0.12 208 T 0.00 0.12
-----Chord-Webs-----

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 340.6 LBS

H -G 0.10 113 T 0.01 0.09
G -N 0.07 320 C 0.00 0.07

-----Webs-----
A -Q 0.19 1685 C WindLd
A -G 0.03 214 T

Q -G 0.36 1965 T
N -M 0.25 276 C

M -B 0.05 312 T
B -L 0.38 571 T

L -O 0.12 461 C
L -C 0.21 299 T

K -C 0.20 626 T
K -P 0.44 553 C

J -P 0.05 364 T
J -D 0.24 523 C

I -D 0.18 1479 C
I -E 0.59 3240 T

F -E 0.21 1681 C WindLd

TL Defl -0.42\" in L -K L/999
LL Defl -0.19\" in L -K L/999
Shear // Grain in O -C 0.30

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area

Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI

Q MT20 5.0x 5.0 Ctr Ctr 0.80
N MT20 3.0x 7.0 Ctr Ctr 0.28

B MT20 5.0x 7.0 1.4-3.3 0.49
O MT20 2.0x 4.0 Ctr Ctr 0.31

C MT20 5.0x 7.0-1.4-3.3 0.48
P MT20 3.0x 7.0 Ctr Ctr 0.33

D MT20 5.0x 5.0 Ctr Ctr 0.70
E MT20 5.0x 5.0-0.4-0.2 0.99

A MT20 5.0x 5.0 Ctr Ctr 0.35
H MT20 2.0x 4.0 Ctr Ctr 0.58

G MT20 6.0x 8.0 Ctr 1.0 0.84
M MT20 3.0x 7.0 Ctr Ctr 0.23

L MT20 5.0x 7.0 Ctr-0.5 0.48
K MT20 3.0x 7.0 Ctr Ctr 0.31

J MT20 5.0x 7.0 Ctr-0.5 0.57
I MT20 4.0x 6.0 1.0 Ctr 0.89

F MT20 2.0x 4.0 Ctr Ctr 0.58

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002

This truss has been designed
for 20.0 psf LL on the B.C.

in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05
Truss is designed as

Components and Claddings*
for Exterior zone location.

Wind Speed: 120 mph
Mean Roof Height: 15-0

Exposure Category: B
Occupancy Factor: 1.00

Building Type: Enclosed
TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf
Max comp. force 2834 Lbs

Max tens. force 3240 Lbs
Connector Plate Fabrication
Tolerance = 20%

This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert. #5555

Scale: 0.155" = 1'

November 25, 2009

SPEC LOT15 ROSEWOOD ESTATES

HQ 2-2-12



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 382.9 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	---Lumber---
TC	0.65	2x 4	SP-#2
BC	0.73	2x 4	SP-#2
CW	0.18	2x 4	SP-#2
WB	0.41	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	14- 7- 8
TC	24.0"	14- 7- 8	24- 7- 8
TC	Cont.	24- 7- 8	40- 1- 8
BC	Cont.	0- 0- 0	40- 1- 8

One Continuous Lateral Brace
P - C N - S M - F
Attach CLB with (2)-10d nails
at each web.

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0

Total	40.0	Spacing	24.0"
Lumber Duration Factor	1.25		
Plate Duration Factor	1.25		
TC Fb=1.15	Fc=1.10	Ft=1.10	
BC Fb=1.10	Fc=1.10	Ft=1.10	

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	1831	330 U	261 R
H	1750	332 U	253 R

Jt	Brg Size	Required
A	3.5"	2.2"
H	3.5"	2.1"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl-CSI-Bnd
1	1	1	1	1
2	2	2	2	2
3	3	3	3	3
4	4	4	4	4
5	5	5	5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
10	10	10	10	10
11	11	11	11	11
12	12	12	12	12
13	13	13	13	13
14	14	14	14	14
15	15	15	15	15
16	16	16	16	16
17	17	17	17	17
18	18	18	18	18
19	19	19	19	19
20	20	20	20	20
21	21	21	21	21
22	22	22	22	22
23	23	23	23	23
24	24	24	24	24
25	25	25	25	25
26	26	26	26	26
27	27	27	27	27
28	28	28	28	28
29	29	29	29	29
30	30	30	30	30
31	31	31	31	31
32	32	32	32	32
33	33	33	33	33
34	34	34	34	34
35	35	35	35	35
36	36	36	36	36
37	37	37	37	37
38	38	38	38	38
39	39	39	39	39
40	40	40	40	40
41	41	41	41	41
42	42	42	42	42
43	43	43	43	43
44	44	44	44	44
45	45	45	45	45
46	46	46	46	46
47	47	47	47	47
48	48	48	48	48
49	49	49	49	49
50	50	50	50	50
51	51	51	51	51
52	52	52	52	52
53	53	53	53	53
54	54	54	54	54
55	55	55	55	55
56	56	56	56	56
57	57	57	57	57
58	58	58	58	58
59	59	59	59	59
60	60	60	60	60
61	61	61	61	61
62	62	62	62	62
63	63	63	63	63
64	64	64	64	64
65	65	65	65	65
66	66	66	66	66
67	67	67	67	67
68	68	68	68	68
69	69	69	69	69
70	70	70	70	70
71	71	71	71	71
72	72	72	72	72
73	73	73	73	73
74	74	74	74	74
75	75	75	75	75
76	76	76	76	76
77	77	77	77	77
78	78	78	78	78
79	79	79	79	79
80	80	80	80	80
81	81	81	81	81
82	82	82	82	82
83	83	83	83	83
84	84	84	84	84
85	85	85	85	85
86	86	86	86	86
87	87	87	87	

Top Chords						
T	-R	0.42	2352	C	0.11	0.31
R	-B	0.45	2397	C	0.14	0.31
B	-C	0.21	2095	C	0.12	0.09
C	-D	0.28	2342	C	0.03	0.25
D	-S	0.26	2135	C	0.02	0.24
S	-E	0.25	2135	C	0.13	0.12
E	-F	0.65	2310	C	0.10	0.55
F	-G	0.39	2504	C	0.04	0.35
G	-U	0.31	1839	C	0.03	0.28

Bottom Chords					
A	-J	0.25	95	C	0.00 0.25
I	-P	0.72	1944	T	0.32 0.40
P	-N	0.73	2002	T	0.33 0.40
N	-M	0.51	2004	T	0.33 0.18
M	-L	0.60	2526	T	0.42 0.18
L	-K	0.33	1605	T	0.26 0.07
K	-H	0.14	222	T	0.00 0.14

Chord-Webs						
J	I	0.18	113	T	0.01	0.17
I	-R	0.14	462	C	0.01	0.13
Webs						
A	-T	0.20	1786	C	WindLd	
A	-I	0.03	241	T		
T	-I	0.38	2096	T		
I	-B	0.36	363	T		
B	-P	0.20	813	T		
P	-C	0.29	1098	C		1 Br
P	-D	0.27	642	T		
D	-N	0.18	263	T		
N	-S	0.09	292	C		1 Br
N	-E	0.13	267	T		
M	-E	0.18	554	T		
M	-F	0.18	625	C		1 Br
L	-F	0.41	1131	C		
L	-G	0.30	1517	T		
K	-G	0.19	538	C		
K	-U	0.31	1716	T		
H	-U	0.18	1705	C	WindLd	

TL Defl	-0.36"	in M	-L	L/999
LL Defl	-0.16"	in N	-M	L/999
Shear //	Grain	in E	-F	0.25

Plates for each ply each face.						
Plate -		MT20	20	Ga,	Gross Area	
Plate -		MT2H	20	Ga,	Gross Area	
Jt	Type	Plt	Size	X	Y	JSI
R	MT20	5.0x	5.0	Ctr	Ctr	0.85
R	MT20	2.0x	4.0	Ctr	Ctr	0.28
B	MT20	5.0x	5.0	-1.1	-3.6	0.51
C	MT20	5.0x	5.0	Ctr	Ctr	0.59
D	MT20	5.0x	5.0	-1.1	-3.6	0.57
S	MT20	2.0x	4.0	Ctr	Ctr	0.31
E	MT20	5.0x	7.0	-1.4	-3.3	0.51
F	MT20	5.0x	5.0	Ctr	Ctr	0.58
G	MT20	5.0x	9.0	-1.0	-3.6	0.98
U	MT20	5.0x	5.0	Ctr	Ctr	0.67
A	MT20	5.0x	5.0	Ctr	Ctr	0.38
J	MT20	2.0x	4.0	Ctr	Ctr	0.58
I	MT20	5.0x	9.0	Ctr	Ctr	0.86
P	MT20	4.0x	8.0	Ctr	Ctr	0.49
N	MT20	5.0x	7.0	-0.5	-0.5	0.47
M	MT20	5.0x	7.0	Ctr	Ctr	0.55
L	MT20	3.0x	7.0	1.0	Ctr	0.92
K	MT20	3.0x	7.0	Ctr	Ctr	0.71
H	MT20	2.0x	4.0	Ctr	Ctr	0.58

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:

FBC2007
TPI 200

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 2504 Lbs
Max tens. force 2526 Lbs
Connector Plate Fabrication


Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert. #5555

Job JOHNSON-SPEC	Mark A15	Quan 1	Type SP	Span 400108	Pl-H1 7	Left OH 0	Right OH 0	Engineering T3555302
SPEC LOT15 ROSEWOOD ESTATES								

HO 2-5-11

HO 2-2-12



ALL PLATES ARE MT2020

Scale: 0.149" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 387.8 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size-	Lumber----
TC 0.33	2x 4 SP-#2
BC 0.75	2x 4 SP-#2
CW 0.22	2x 4 SP-#2
WB 0.87	2x 4 SP-#2

Brace truss as follows:

O.C.	From	To
TC Cont.	0-0-0	14-7-8
TC 24.0"	14-7-8	24-7-8
TC Cont.	24-7-8	40-1-8
BC Cont.	0-0-0	40-1-8

One Continuous Lateral Brace
O - T
Attach CLB with (2)-10d nails
at each web.

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	1738	330	U 261 R
H	1785	332	U 251 R

Jt	Brg Size	Required
A	3.5"	2.1"
H	3.5"	2.1"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Ax1-CSI-Bnd
-----Top Chords-----				
V -S	0.30	1752	C	0.03 0.27
S -B	0.33	2191	C	0.12 0.21
B -C	0.15	1895	C	0.11 0.04
C -D	0.28	2194	C	0.03 0.25
D -T	0.30	2095	C	0.02 0.28
T -E	0.30	2095	C	0.02 0.28
E -F	0.30	2317	C	0.03 0.27
F -G	0.16	1770	C	0.10 0.06
G -U	0.19	2040	C	0.02 0.17
U -W	0.12	96	T	0.00 0.12
-----Bottom Chords-----				
A -R	0.17	225	T	0.00 0.17
R -J	0.17	46	T	0.00 0.17
I -P	0.49	2088	T	0.35 0.14
P -O	0.46	1919	T	0.32 0.14
O -N	0.68	2006	T	0.33 0.35
N -L	0.75	2379	T	0.39 0.36
L -H	0.58	1392	T	0.23 0.35

-----Chord-Webs-----			
I -B	0.22	936	T 0.17 0.05
J -I	0.09	69	T 0.00 0.09

-----Webs-----			
A -V	0.19	1693	C WindLd
V -R	0.30	1665	T
R -S	0.37	866	C
S -I	0.27	1512	T
S -I	0.09	488	T
I -C	0.68	903	C
C -P	0.33	379	C
P -D	0.23	517	T
D -O	0.20	360	T
O -T	0.11	351	C
O -E	0.16	181	T
N -E	0.25	724	T
N -F	0.51	571	C
F -L	0.86	1135	C
L -G	0.15	789	T
L -U	0.10	559	T
U -H	0.87	2150	C
H -W	0.01	122	C WindLd

TL Defl	-0.36"	in N -L	L/999
LL Defl	-0.14" <th>in N -L</th> <th>L/999</th>	in N -L	L/999
Shear // Grain	in T -E	0.23	

Plates for each ply each face.

Plate	MT20	20 Ga.	Gross Area
Plate	MT2H	20 Ga. <td>Gross Area</td>	Gross Area
Jt Type	Plt Size	X	Y JSI
V	MT20	5.0x 5.0	Ctr Ctr 0.64
S	MT20	3.0x 7.0	Ctr Ctr 0.31
B	MT20	5.0x 7.0	0.9-3.3 0.34
C	MT20	5.0x 5.0	Ctr Ctr 0.56
D	MT20	5.0x 7.0	1.4-3.3 0.51
T	MT20	2.0x 4.0	Ctr Ctr 0.31
E	MT20	5.0x 7.0	1.4-3.3 0.51
F	MT20	5.0x 5.0	Ctr Ctr 0.62
G	MT20	5.0x 5.0	0.8-3.1 0.45
U	MT20	3.0x 7.0	1.2-0.7 0.67
W	MT20	2.0x 4.0	Ctr Ctr 0.28
A	MT20	2.0x 4.0	Ctr Ctr 0.57
R	MT20	5.0x 7.0	Ctr Ctr 0.92
J	MT20	2.0x 4.0	Ctr Ctr 0.58
I	MT20	6.0x12.0	Ctr 0.4 0.50
P	MT20	3.0x 7.0	Ctr Ctr 0.33
O	MT20	4.0x 8.0	Ctr Ctr 0.26
N	MT20	5.0x 7.0	Ctr-0.5 0.47
L	MT20	4.0x 8.0	Ctr Ctr 0.41
H	MT20	5.0x 5.0	Ctr Ctr 0.61

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.

Analysis Conforms To:
FBC2007
TPI 2002

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3-6-0 tall by
2-0-0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor: 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 2317 Lbs
Max tens. force 2379 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555



Scale: 0.150" = 1'

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	----Lumber----
TC	0.35	2x 4	SP-#2
BC	0.62	2x 4	SP-#2
CW	0.13	2x 4	SP-#2
WB	0.92	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	14- 7- 8	7- 8
TC 24.0"	14- 7- 8	24- 7- 9	7- 9
TC Cont.	24- 7- 9	40- 1- 8	1- 8
BC Cont.	0- 0- 0	40- 1- 8	1- 8

One Continuous Lateral Brace
M - R

Attach CLB with (2)-10d nails
at each web.

psf-Ld	Dead	Live	
TC	10.0	20.0	
BC	10.0	0.0	
TC+BC	20.0	20.0	
Total	40.0	Spacing	24.0"
Lumber	Duration Factor		1.25
Plate	Duration Factor		1.25
TC Fb=1.15	Fc=1.10	Ft=1.10	
BC Fb=1.10	Fc=1.10	Ft=1.10	

Total Load Reactions (Lbs)				
Jt	Down	Uplift	Horiz-	
A	1742	330 U	246	R
F	1778	332 U	260	R

Jt	Brg Size	Required
A	3.5"	2.1"
F	3.5"	2.1"

```

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

```

Membr	CSI	P	Lbs	Axl-CSI-Bnd
-------	-----	---	-----	-------------

-----Top Chords-----					
T	-P	0.33	2162	C	0.11 0.22
P	-Q	0.35	2531	C	0.13 0.22
Q	-B	0.27	2228	C	0.03 0.24
B	-R	0.31	2105	C	0.02 0.29
R	-C	0.31	2105	C	0.02 0.29
C	-D	0.30	2303	C	0.03 0.27
D	-E	0.19	1779	C	0.02 0.17
E	-S	0.29	2061	C	0.11 0.18
S	-U	0.30	1852	C	0.04 0.26

-----Bottom Chords-----						
A	-O	0.17	226	T	0.00	0.17
O	-H	0.17	65	T	0.00	0.17
G	-N	0.50	2184	T	0.36	0.14
N	-M	0.46	1925	T	0.32	0.14
M	-L	0.58	2009	T	0.33	0.25
L	-J	0.62	2211	T	0.37	0.25
J	-I	0.46	1609	T	0.27	0.19
I	-F	0.13	229	T	0.00	0.13

-----Chord-Webs-----					
H	-G	0.13	74	T	0.00 0.13
G	-Q	0.10	297	T	0.04 0.06

		Webbs	
A	-T	0.16	1696 C WindLd
T	-O	0.35	1938 T
O	-P	0.20	720 C
O	-G	0.34	1852 T
P	-G	0.06	358 T
Q	-N	0.40	463 C
N	-B	0.22	527 T
B	-M	0.21	369 T
M	-R	0.11	357 C
M	-C	0.16	197 T
L	-C	0.30	741 T
L	-D	0.46	517 C
D	-J	0.92	922 C
J	-E	0.23	788 T
J	-S	0.04	261 T
I	-S	0.21	584 C
I	-U	0.32	1738 T
F	-U	0.18	1729 C WindLd

TL Defl	-0.31"	in L	-J	L/999
LL Defl	-0.14"	in N	-M	L/999
Shear //	Grain	in B	-R	0.23

Plates for each ply each face.							
Plate		M20		20 Ga.		Gross Area	
Jt		M20N		20 Ga.		Gross Area	
Plt	Type	Plt Size	X	Y	JSI		
T	M20	5.0x 5.0	Ctr	Ctr	0.7		
P	M20	3.0x 7.0	Ctr	Ctr	0.27		
Q	B M20	6.0x 6.0	Ctr	0.1	0.45		
B	M20	5.0x 7.0	1.4-3.3	0.3	0.51		
R	M20	2.0x 4.0	Ctr	Ctr	0.31		
C	M20	5.0x 7.0	1.4-3.3	0.2	0.52		
D	M20	5.0x 5.0	Ctr	Ctr	0.61		
E	M20	5.0x 5.0	0.4-3.3	0.39			
S	M20	3.0x 7.0	Ctr	Ctr	0.34		
U	M20	5.0x 5.0	Ctr	Ctr	0.67		
A	M20	2.0x 4.0	Ctr	Ctr	0.56		
O	M20	5.0x 9.0	Ctr	Ctr	0.66		
H	M20	2.0x 4.0	Ctr	Ctr	0.58		
G	M20	6.0x 8.0	Ctr	1.0	0.57		
N	M20	3.0x 7.0	Ctr	Ctr	0.27		
M	M20	4.0x 8.0	Ctr	Ctr	0.26		
L	M20	5.0x 7.0	Ctr	0.5	0.47		
J	M20	4.0x 8.0	Ctr	Ctr	0.32		
I	M20	3.0x 7.0	Ctr	Ctr	0.72		
F	M20	2.0x 4.0	Ctr	Ctr	0.57		

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.

Analysis Conforms To:
FBC2007
TPI 2002

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.

Design checked for 10 psf non-concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as

Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 2531 Lbs
Max tens. force 2211 Lbs
Connector Plate Fabrication

This truss is designed for a creep factor of 1.5 which is used to calculate total load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert #5555



Scale: 0.154" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 385.4 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	----Lumber----
TC	0.38	2x 4	SP-#2
--	0.19	2x 6	SP-#2
	B -D		
BC	0.50	2x 4	SP-#2
CW	0.13	2x 4	SP-#2
WB	0.40	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0 - 0 - 0	14 - 7 - 8	
TC 24.0"	14 - 7 - 8	25 - 3 - 6	
TC Cont.	25 - 3 - 6	40 - 1 - 8	
BC Cont.	0 - 0 - 0	40 - 1 - 8	

One Continuous Lateral Brace
M - R V - D
Attach CLB with (2)-10d nails
at each web.

psf-Ld	Dead	Live	
TC	10.0	20.0	
BC	10.0	0.0	
TC+BC	20.0	20.0	
Total	40.0		Spacing 24.0"
Lumber	Duration Factor		1.25
Plate	Duration Factor		1.25
TC Fb=1.15	Fc=1.10	Ft=1.10	
BC Fb=1.10	Fc=1.10	Ft=1.10	

Total Load Reactions (Lbs)				
Jt	Down	Uplift	Horiz-	
A	1712	330 U	241	R
F	1711	332 U	256	R

Jt	Brg Size	Required
A	3.5"	2.0"
F	3.5"	2.0"

```

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

```

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
T -P	0.33	2121	C	0.11	0.22
P -Q	0.35	2475	C	0.13	0.22
Q -B	0.31	2170	C	0.02	0.29
B -R	0.19	2064	C	0.02	0.17
R -D	0.18	2064	C	0.09	0.09
D -E	0.19	1946	C	0.12	0.07
E -S	0.38	1939	C	0.11	0.27
S -U	0.37	1791	C	0.10	0.27
-----Bottom Chords-----					
A -O	0.17	221	T	0.00	0.17
O -H	0.17	64	T	0.00	0.17
G -N	0.49	2134	T	0.35	0.14
N -M	0.49	1878	T	0.31	0.18
M -V	0.50	1938	T	0.32	0.18
V -Y	0.39	1670	T	0.28	0.11

J		I		F		T		C		W		Ld	
J	-I	0.36	1563	T	0.26	0.6	0.10						
I	-F	0.19	225	T	0.00	0.19							
Chord-Webs													
H	-G	0.13	74	T	0.00	0.13							
G	-Q	0.10	298	T	0.04	0.06							
Webs													
A	-T	0.16	1666	C	WindLd								
T	-O	0.35	1901	T									
O	-P	0.20	704	C									
O	-G	0.33	1818	T									
P	-G	0.06	341	T									
Q	-N	0.40	458	C									
N	-B	0.21	524	T									
B	-M	0.23	357	T									
M	-R	0.10	332	C							1 Br		
M	-D	0.13	237	T									
V	-D	0.13	434	C							1 Br		
V	-E	0.29	659	T									
J	-E	0.02	153	T									
I	-S	0.10	136	T									
J	-S	0.18	514	C									
I	-U	0.31	1688	T									
F	-U	0.18	1670	C	WindLd								

TL Defl	-0.28"	in N	-M	L/999
LL Defl	-0.12"	in N	-M	L/999
Shear //	Grain	in T	-P	0.20

Plates for each ply each face.					
Plate	MT20	20 Ga,	Gross Area		
Plate	MT20	20 Ga,	Gross Area		
Jt	Type	Pit	Size	X	Y
D	MT20	5.0x	5.0	Ctr	Ctr 0.77
P	MT20	3.0x	7.0	Ctr	Ctr 0.27
Q	MT20	6.0x	6.0	Ctr	0.1 0.45
B	MT20	6.0x	8.0-0.5	Ctr	0.61
R	MT20	2.0x	4.0	Ctr	0.31
D					2.07
E	MT20	5.0x	7.0-1.4-3.3		0.60
S	MT20	3.0x	7.0	Ctr	Ctr 0.29
U	MT20	5.0x	5.0	Ctr	Ctr 0.65
A	MT20	2.0x	4.0	Ctr	Ctr 0.56
O	MT20	5.0x	9.0	Ctr	Ctr 0.65
H	MT20	2.0x	4.0	Ctr	Ctr 0.58
G	MT20	6.0x	8.0	Ctr	1.0 0.56
N	MT20	3.0x	7.0	Ctr	Ctr 0.27
M	MT20	5.0x	7.0	Ctr-0.5	0.46
V	MT20	3.0x	7.0	Ctr	Ctr 0.48
J	MT20	5.0x	7.0	Ctr-0.5	0.39
I	MT20	3.0x	7.0	Ctr	Ctr 0.70
F	MT20	2.0x	4.0	Ctr	Ctr 0.57

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:

Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3 - 6 - 0 tall by
2 - 0 - 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.

Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed

TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf

Max comp. force 2475 Lbs
Max tens. force 2134 Lbs

Connector Plate Fabrication
Tolerance = 20%

This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert #5555

Robbins Engineering, Inc./Online Plus™ © 1996-2009 Version 25.0.012 Engineering - Portrait 11/25/2009 1:12:18 PM Page 1



Scale: 0.120" = 1'


```

Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- --To--
0- 0- 0 9- 1-12
Max comp. force 3842 Lbs
Max tens. force 3433 Lbs

```

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25, 2009



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
TC 0.62 2x 4 SP-#2
BC 0.71 2x 4 SP-#2
CW 0.32 2x 4 SP-#2
WB 0.69 2x 4 SP-#2
-- 0.10 2x 6 SP-#2
F -Y

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 51- 8- 0
BC Cont. 0- 0- 0 51- 8- 0
One Continuous Lateral Brace
M -T
Attach CLB with (2)-10d nails
at each web.

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 77 149 U 128 R
P 2692 668 U
F 1800 358 U 162 R

Jt Brg Size Required
A 3.5" 1.5"
P 3.5" 2.9"
F 3.5" 2.1"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P Lbs	Ax1-CSI-Bnd
A -R	0.48	815 T	0.14 0.34
R -B	0.62	1732 T	0.28 0.34
B -C	0.44	178 C	0.00 0.44
C -D	0.40	1888 C	0.06 0.34
D -S	0.44	2613 C	0.04 0.40
S -T	0.49	2613 C	0.04 0.45
T -U	0.53	2969 C	0.13 0.40
U -E	0.36	2982 C	0.06 0.30
E -X	0.27	2828 C	0.16 0.11
X -V	0.27	2967 C	0.07 0.20
V -Y	0.25	3493 C	0.09 0.16

Robbins Engineering, Inc./Online Plus™

-----Bottom Chords-----

A	Q	0.14	776 C	0.00	0.14
Q -P	0.15	776 C	0.00	0.15	
P -O	0.25	1835 C	0.13	0.12	
O -N	0.25	258 T	0.00	0.25	
N -M	0.48	1635 T	0.27	0.21	
M -L	0.71	2929 T	0.49	0.22	
L -J	0.30	125 T	0.00	0.30	
J -W	0.56	2305 T	0.38	0.18	
W -H	0.69	3090 T	0.51	0.18	
H -G	0.03	155 T	0.02	0.01	

-----Chord-Webs-----

J	I	0.26	109 T	0.00	0.26
I -U	0.15	301 C	0.01	0.14	
U -H	0.32	37 T	0.00	0.32	
H -V	0.22	300 T	0.04	0.18	

-----Webs-----

Q	R	0.03	206 C
R -P	0.30	1070 T	
P -B	0.27	2335 C	
B -O	0.45	2439 T	
O -C	0.18	1599 C	
C -N	0.52	1670 T	
N -D	0.15	292 C	
D -M	0.69	1294 T	
M -S	0.22	407 C	
S -T	0.13	421 C	1 Br
T -L	0.09	214 T	
L -I	0.69	2834 T	
I -E	0.02	103 T	
E -W	0.08	484 T	
W -X	0.06	281 C	
X -V	0.23	508 C	
V -Y	0.55	3012 T	
Y -H	0.01	175 C	
H -F	0.10	1695 C	WindLd

TL Defl -0.57" in L -J L/881
LL Defl -0.25" in M -L L/999
Shear // Grain in T -U 0.29

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 4.0x 6.0 Ctr 0.1 0.44
R MT20 3.0x 7.0 Ctr Ctr 0.35
B MT20 6.0x10.0 Ctr-0.3 0.57
C MT20 6.0x 6.0 Ctr Ctr 0.52
D MT20 6.0x 8.0 1.1-3.9 0.63
S MT20 2.0x 4.0 Ctr Ctr 0.31
T MT20 5.0x 7.0 Ctr 0.5 0.44
U MT20 2.0x 4.0 Ctr Ctr 0.31
E MT20 6.0x 6.0-0.1-4.2 0.52
X MT20 2.0x 4.0 Ctr Ctr 0.30
V MT20 3.0x 7.0 Ctr Ctr 0.25
Y MT20 6.0x 8.0 Ctr Ctr 0.78
Q MT20 2.0x 4.0 Ctr Ctr 0.31

APPROX. TRUSS WEIGHT: 396.0 LBS

P	MT20	3.0x	7.0-2.0	0.4	0.57
O	MT20	5.0x	7.0 Ctr-0.5	0.85	
N	MT20	3.0x	7.0 Ctr Ctr	0.68	
M	MT20	5.0x	9.0-0.5-0.5	0.69	
L	MT20	5.0x	5.0 2.2	0.2 0.98	
J	MT20	2.0x	4.0 Ctr Ctr	0.58	
I	MT20	6.0x10.0	Ctr	1.2 0.54	
W	MT20	4.0x	8.0 0.5 Ctr	0.35	
H	MT20	6.0x10.0	0.7 1.2	0.89	
G	MT20	2.0x	4.0 Ctr Ctr	0.58	
F	MT20	6.0x	6.0 Ctr Ctr	0.25	

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:

Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05
Truss is designed as

Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf


User-defined wind-exposed BC
regions --From-- ---To---
0- 0- 0 9- 3- 8

Max comp. force 3493 Lbs
Max tens. force 3090 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total

load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

Job	Mark	Quan	Type	Span	Pl-H1	Left OH	Right OH	Engineering
JOHNSON-SPEC	VJ3	2	SP	20308	7	2- 0- 0	0	T3555310
SPEC LOT15 ROSEWOOD ESTATES								



Scale: 0.413" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 24.4 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI	-Size-	----	Lumber----
TC	0.05	2x 4	SP-#2
BC	0.09	2x 4	SP-#2
CW	0.06	2x 4	SP-#2
SL	0.00	2x 6	SP-#2

Brace truss as follows:	O.C.	From	To
TC Cont.	0- 0- 0	2- 3- 8	
BC Cont.	0- 0- 0	2- 3- 8	

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)	Jt	Down	Uplift	Horiz-
A	252	85 U	106 R	
D	79	49 U		
B	21	48 U	43 R	

Jt	Brg Size	Required
A	3.5"	1.5"
D	1.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
A -G	0.04	37 C	0.00	0.04	
G -F	0.05	34 T	0.00	0.05	
F -B	0.01	37 T	0.00	0.01	
-----Bottom Chords-----					
A -E	0.05	33 C	0.00	0.05	
H -D	0.09	0 T	0.00	0.09	
-----Chord-Webs-----					

E -H	0.05	35 T	0.00	0.05
H -F	0.06	73 T	0.01	0.05
-----Sliders-----				
A -G	0.00	65 C		
TL Defl	0.00"	in A -E	L/999	
LL Defl	0.00"	in A -E	L/999	
Shear //	Grain	in H -D	0.08	

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 3.0x 9.0 1.5 0.3 0.58
G MT20 3.0x 4.0 Ctr Ctr 0.09
F MT20 2.0x 4.0 Ctr Ctr 0.12
E MT20 2.0x 4.0 Ctr Ctr 0.58
H MT20 2.0x 4.0 Ctr Ctr 0.58

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction


NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002

OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 65 Lbs
Max tens. force 73 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

CSI	Size	Lumber
TC	0.17 2x 4	SP-#2
BC	0.29 2x 4	SP-#2
CW	0.17 2x 4	SP-#2
SL	0.01 2x 6	SP-#2

Brace truss as follows:

O.C.	From	To
TC Cont.	0- 0- 0	5- 0- 0
BC Cont.	0- 0- 0	5- 0- 0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	334	93 U	177 R
C	92	21 U	
B	139	67 U	72 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	1.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
A -G	0.06	49 C	0.00	0.06	
G -F	0.12	110 C	0.00	0.12	
F -B	0.17	70 C	0.00	0.17	
-----Bottom Chords-----					
A -E	0.07	104 T	0.00	0.07	
D -C	0.29	0 T	0.00	0.29	
-----Chord-Webs-----					

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 32.5 LBS

E -D	0.17	38 T	0.00	0.17
D -F	0.15	61 T	0.00	0.15
-----Sliders-----				
A -G	0.01	154 C		

TL Defl	-0.06"	in D -C	L/969
LL Defl	-0.02"	in D -C	L/999
Shear //	Grain	in F -B	0.12

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area
 Jt Type Plt Size X Y JSI
 A MT20 3.0x 9.0 1.5 0.3 0.58
 G MT20 3.0x 4.0 Ctr Ctr 0.09
 F MT20 2.0x 4.0 Ctr Ctr 0.12
 E MT20 2.0x 4.0 Ctr Ctr 0.58
 D MT20 2.0x 4.0 Ctr Ctr 0.58

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

For proper installation of
 toe-nails, refer to the 2001
 National Design Specification
 (NDS) for Wood Construction

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.
 Analysis Conforms To:
 FBC2007
 TPI 2002

OH Loading
 Soffit psf 2.0
 This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.

Design checked for 10 psf non-
 concurrent LL on BC.
 Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0
 Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 154 Lbs
 Max tens. force 104 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

	HO 11-9			HO 4-0-9
TC	2-9-15	3-3-10	6-4-14	9-10-13



Scale: 0.365" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 78.4 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	----Lumber----
TC	0.30	2x 4	SP-#2
BC	0.28	2x 4	SP-#2
CW	0.59	2x 6	SP-#2
WB	0.14	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	9-10-13
BC	Cont.	0- 0- 0	9-10-13

psf-Ld	Dead	Live		
TC	10.0	20.0		
BC	10.0	0.0		
TC+BC	20.0	20.0		
Total	40.0	Spacing	24.0"	
Lumber	Duration	Factor	1.25	
Plate	Duration	Factor	1.25	
TC Fb=1.00	Fc=1.00	Ft=1.00		
BC Fb=1.00	Fc=1.00	Ft=1.00		

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	461	116 U	168 R
C	550	94 U	179 R

Jt	Brg Size	Required
A	4.9"	1.5"
C	3.5"	1.5"

LC#	1	Standard Loading			
Dur	Fctrs	-	Lbr	1.25	Plt
plf	-	Dead	Live*	From	To
TC V	20	40	0.0'	9.9'	
EC V	20	0	0.0'	9.9'	
TC V	-20	-40	0.0'		
	22	45		9.9'	
EC V	-20	0	0.0'		
	22	0		9.9'	

Plus 7 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl-CSI-Bnd
1	1	1	1	1
2	1	1	1	1
3	1	1	1	1
4	1	1	1	1
5	1	1	1	1
6	1	1	1	1
7	1	1	1	1
8	1	1	1	1
9	1	1	1	1
10	1	1	1	1
11	1	1	1	1
12	1	1	1	1
13	1	1	1	1
14	1	1	1	1
15	1	1	1	1
16	1	1	1	1
17	1	1	1	1
18	1	1	1	1
19	1	1	1	1
20	1	1	1	1
21	1	1	1	1
22	1	1	1	1
23	1	1	1	1
24	1	1	1	1
25	1	1	1	1
26	1	1	1	1
27	1	1	1	1
28	1	1	1	1
29	1	1	1	1
30	1	1	1	1
31	1	1	1	1
32	1	1	1	1
33	1	1	1	1
34	1	1	1	1
35	1	1	1	1
36	1	1	1	1
37	1	1	1	1
38	1	1	1	1
39	1	1	1	1
40	1	1	1	1
41	1	1	1	1
42	1	1	1	1
43	1	1	1	1
44	1	1	1	1
45	1	1	1	1
46	1	1	1	1
47	1	1	1	1
48	1	1	1	1
49	1	1	1	1
50	1	1	1	1
51	1	1	1	1
52	1	1	1	1
53	1	1	1	1
54	1	1	1	1
55	1	1	1	1
56	1	1	1	1
57	1	1	1	1
58	1	1	1	1
59	1	1	1	1
60	1	1	1	1
61	1	1	1	1
62	1	1	1	1
63	1	1	1	1
64	1	1	1	1
65	1	1	1	1
66	1	1	1	1
67	1	1	1	1
68	1	1	1	1
69	1	1	1	1
70	1	1	1	1
71	1	1	1	1
72	1	1	1	1
73	1	1	1	1
74	1	1	1	1
75	1	1	1	1
76	1	1	1	1
77	1	1	1	1
78	1	1	1	1
79	1	1	1	1
80	1	1	1	1
81	1	1	1	1
82	1	1	1	1
83	1	1	1	1
84	1	1	1	1
85	1	1	1	1
86	1	1	1	1
87	1	1	1	1
88	1	1	1	1
89	1	1	1	1
90	1	1	1	1
91	1	1	1	1
92	1	1	1	1
93	1	1	1	1
94	1	1	1	1

-----Top Chords-----				
I -F	0.18	37 T	0.00	0.18
F -H	0.30	492 C	0.03	0.27
H -B	0.27	64 C	0.00	0.27

A - E	0.11	590 T		
D - G	0.28	542 T	0.10	0.18
G - C	0.17	481 T	0.08	0.09
-----Chord-Webs-----				
E - D	0.59	42 T	0.00	0.59
D - F	0.51	201 C	0.00	0.51
-----Webs-----				
A - I	0.05	414 T	WindId	
A - D	0.09	624 C		
F - G	0.01	136 T		
G - H	0.03	234 T		
H - C	0.14	580 C		
C - B	0.07	247 T	WindId	

TL Defl	-0.12"	in D	-G	L/896
LL Defl	-0.05"	in D	-G	L/999
Shear //	Grain	in E	-D	0.49

Jt	Type	Plt	Size	X	Y	JSI
I	MT20	2.0x	4.0	Ctr	Ctr	0.29
F	MT20	3.0x	4.0	Ctr	Ctr	0.20
H	MT20	3.0x	4.0	Ctr	Ctr	0.29
B	MT20	2.0x	4.0	Ctr	Ctr	0.18
A	MT20	2.0x	4.0	Ctr	Ctr	0.50
E	MT20	2.0x	4.0	Ctr	Ctr	0.91
D	MT20	4.0x10.0		Ctr		0.2
G	MT20	3.0x	4.0-1.5	0.3	0.19	
C	MT20	2.0x	4.0	Ctr	Ctr	0.57

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:

Trusses Manufactured by:

Mayo Truss Co. Inc.
Analysis Conforms To:

FBC2007

TPI 2002

OH Loading
Soffit psf 2.0


This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by

2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 624 Lbs
Max tens. force 590 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert. #5555

Job	Mark	Quan	Type	Span	Pl-H1	Left OH	Right OH	Engineering
JOHNSON-SPEC	J2	31	JCA2	70000	7	2- 0- 0	0	T3555314

SPEC LOT15 ROSEWOOD ESTATES



Scale: 0.383" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 34.2 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

LL Defl -0.08" in A -C L/953
Shear // Grain in E -B 0.24

CSI -Size- ----Lumber----

TC	0.51	2x 4	SP-#2
BC	0.43	2x 4	SP-#2
WB	0.51	2x 4	SP-#2

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
E MT20 2.0x 4.0 Ctr Ctr 0.17
A MT20 4.0x 4.0 0.2 Ctr 0.11

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	7- 0- 0	
BC Cont.	0- 0- 0	7- 0- 0	

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 356 Lbs
Max tens. force 263 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

psf-Ld Dead Live

TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	24.0"

Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	411	114 U	279 R
C	134		
B	237	125 U	114 R

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0


Membr CSI P Lbs Ax1-CS1-Bnd

-----Top Chords-----				
E -B	0.51	129 C	0.01	0.50
-----Bottom Chords-----				
A -C	0.43	0 T	0.00	0.43
-----Webs-----				
A -E	0.51	356 C	0.03	0.48

TL Defl -0.19" in A -C L/406

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 57.5 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

D -C 0.08 73 C WindLd

CSI -Size- ----Lumber-----
TC 0.42 2x 4 SP-#2
BC 0.44 2x 4 SP-#2
WB 0.08 2x 4 SP-#2

TL Defl -0.24" in A -E L/316
LL Defl -0.09" in A -E L/830
Shear // Grain in E -D 0.27

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 7- 0- 0
BC Cont. 0- 0- 0 7- 0- 0

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
F MT20 2.0x 4.0 Ctr Ctr 0.31
B MT20 4.0x 4.0 Ctr Ctr 0.58
C MT20 2.0x 4.0 Ctr Ctr 0.12
A MT20 2.0x 4.0 Ctr Ctr 0.23
E MT20 3.0x 4.0-1.0 0.1 0.33
D MT20 2.0x 4.0 Ctr Ctr 0.12

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 411 79 U 93 R
D 277 93 U 164 R

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

Jt Brg Size Required
A 3.5" 1.5"
D 3.5" 1.5"

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.


Membr CSI P Lbs Ax1-CSI-Bnd
-----Top Chords-----
F -B 0.42 86 C 0.00 0.42
B -C 0.09 120 T 0.00 0.09
-----Bottom Chords-----
A -E 0.44 81 T 0.00 0.44
E -D 0.43 129 T 0.00 0.43
-----Webs-----
A -F 0.04 311 C WindLd
F -E 0.03 122 T
E -B 0.04 224 T

Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 311 Lbs
Max tens. force 284 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

Job	Mark	Quan	Type	Span	Pl-H1	Left OH	Right OH	Engineering
JOHNSON-SPEC	J13	2	JCA2	10000	3	2- 0- 0	0	T3555316

SPEC LOT15 ROSEWOOD ESTATES



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----
TC 0.00 2x 4 SP-#2
BC 0.00 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 1- 0- 0
BC Cont. 0- 0- 0 1- 0- 0

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 49 115 U 33 R
B 26 11 U
C 18 6 U 5 R

Jt Brg Size Required
A 3.5" 1.5"
B 1.5" 1.5"
C 1.5" 1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-Csi-Bnd
-----Top Chords-----
A -B 0.00 11 C
-----Bottom Chords-----
A -C 0.00 5 T

TL Defl 0.00" in A -C L/999
LL Defl 0.00" in A -C L/999
Shear // Grain in A -B 0.03

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 8.0 LBS

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 2.0x 4.0 Ctr Ctr 0.79

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:

Trusses Manufactured by:
Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0


This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- ---To---
0- 1- 1 1- 1- 1
Max comp. force 11 Lbs
Max tens. force 5 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 15.5 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----
TC 0.14 2x 4 SP-#2
BC 0.15 2x 4 SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	3- 0- 0	
BC Cont.	0- 0- 0	3- 0- 0	

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	
Spacing 24.0"		
Lumber Duration Factor 1.25		
Plate Duration Factor 1.25		
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	255	151 U	101 R
C	53	26 U	
B	74	40 U	18 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P Lbs	Axl	CSI-Bnd
-----Top Chords-----				
A - B	0.14	47 C	0.00	0.14
-----Bottom Chords-----				
A - C	0.15	0 T	0.00	0.15

TL Defl	-0.01"	in A - C	L/999
LL Defl	0.00"	in A - C	L/999
Shear // Grain		in A - B	0.16

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 2.0x 4.0 Ctr Ctr 0.79

REVIEWED BY:

Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:

Trusses Manufactured by:

Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*

for Exterior zone location.

Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B

Occupancy Factor : 1.00


Building Type: Enclosed

TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- ---To---
0- 0- 0 3- 0- 0
Max comp. force 47 Lbs
Max tens. force 12 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 23.2 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	----Lumber----
TC	0.45	2x 4	SP-#2
BC	0.46	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	5- 0- 0	0
BC Cont.	0- 0- 0	5- 0- 0	0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	333	190 U	143 R
C	91	43 U	
B	130	70 U	31 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P Lbs	Ax1-CSI-Bnd
-----Top Chords-----			
A -B	0.45	79 C	0.00 0.45
-----Bottom Chords-----			
A -C	0.46	0 T	0.00 0.46

TL Defl	-0.05"	in A -C	L/999
LL Defl	-0.02"	in A -C	L/999
Shear // Grain		in A -B	0.28

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 2.0x 4.0 Ctr Ctr 0.79

REVIEWED BY:

Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:

Trusses Manufactured by:
Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*
for Exterior zone location.

Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B

Occupancy Factor : 1.00


Building Type: Enclosed

TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- ---To---
0- 0- 0 5- 0- 0
Max comp. force 79 Lbs
Max tens. force 19 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

TC	BC	WB	Size	Lumber
0.49	0.32	0.29	2x 4	SP-#2

Brace truss as follows:

O.C.	From	To
TC Cont.	0- 0- 0	9-10-13
BC Cont.	0- 0- 0	9-10-13

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.00	Fc=1.00	Ft=1.00
BC Fb=1.00	Fc=1.00	Ft=1.00

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	461	343 U	62 R
C	349	178 U	
B	230	139 U	80 R

Jt	Brg Size	Required
A	4.9"	1.5"
C	1.5"	1.5"
B	1.5"	1.5"

LC#	1	Girder Loading
Dur Fctrs	- Lbr 1.25	Plt 1.25
plf - Dead	Live*	From To
TC V	20	40 0.0' 9.9'
BC V	20	0 0.0' 9.9'
TC V	-20	-40 0.0' 9.9'
BC V	-20	45 0.0' 9.9'
BC V	-20	0 0.0' 9.9'
BC V	22	0 0.0' 9.9'

Plus 8 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr	CSI	P Lbs	Axl	CSI-Bnd
A -E	0.49	1757 T	0.25	0.24

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 54.6 LBS

E -B	0.34	48 T	0.00	0.34
-----Bottom Chords-----				
A -D	0.26	1781 C	0.19	0.07
D -C	0.32	1781 C	0.19	0.13
-----Webs-----				
D -E	0.03	337 C		
E -C	0.29	1886 T		
C -B	0.01	0 T	WindLd	

TL Defl	-0.08"	in A -D	L/999
LL Defl	-0.03"	in A -D	L/999
Shear //	Grain	in E -B	0.27

Plates for each ply each face.

Plate	- MT20	20 Ga,	Gross Area
Plate <td>- MT2H</td> <td>20 Ga, <td>Gross Area</td> </td>	- MT2H	20 Ga, <td>Gross Area</td>	Gross Area
Jt Type	Plt Size	X Y	JSI
A	MT20	3.0x 7.0	3.5 1.3 0.81
E	MT20	3.0x 4.0	0.5 0.1 0.82
B	MT20	2.0x 4.0	Ctr Ctr 0.12
D	MT20	2.0x 4.0	Ctr Ctr 0.19
C	MT20	3.0x 4.0	1.0 Ctr 0.83

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

For proper installation of
 toe-nails, refer to the 2001
 National Design Specification
 (NDS) for Wood Construction

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.
 Analysis Conforms To:
 FBC2007
 TPI 2002


Girder King Jack
 Loading TC and BC
 Setback 7- 0- 0
 OH Loading
 Soffit psf 2.0
 Design checked for 10 psf non-
 concurrent LL on BC.
 Use properly rated hangers for

loads framing into girder
 truss.
 Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0
 Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 User-defined wind-exposed BC
 regions --From-- --To--
 0- 0- 0 9-10-13
 Max comp. force 1781 Lbs
 Max tens. force 1886 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.


Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

November 25,2009

SPEC LOT15 ROSEWOOD ESTATES



November 25, 2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 50.9 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	Size	----Lumber----
TC	0.39	2x 4	SP-#2
BC	0.27	2x 4	SP-#2
WB	0.23	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	7- 0- 0
BC	Cont.	0- 0- 0	7- 0- 0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	411	173 U	49 R
D	277	168 U	76 R

Jt	Brg Size	Required
A	3.5"	1.5"
D	3.5"	1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P Lbs	Ax1-CSI-Bnd
-----Top Chords-----			
F -B	0.20	674 T	0.08 0.12
B -C	0.39	637 T	0.08 0.31
-----Bottom Chords-----			
A -E	0.26	37 T	0.00 0.26
E -D	0.27	61 T	0.00 0.27
-----Webs-----			
A -F	0.10	711 T	WindLd
F -E	0.05	584 C	
E -B	0.02	257 C	

E -C	0.23	629 C
D -C	0.06	451 T WindLd
TL Defl	-0.03" in E -D L/999	
LL Defl	-0.02" in E -D L/999	
Shear // Grain	in E -D 0.26	

Plates for each ply each face.

Plate	MT20	20 Ga,	Gross Area
Plate -	MT2H	20 Ga,	Gross Area
Jt	Type	Plt Size	X Y JSI
F	MT20	2.0x 4.0	Ctr Ctr 0.78
B	MT20	4.0x 4.0	Ctr Ctr 0.58
C	MT20	2.0x 4.0	Ctr Ctr 0.51
A	MT20	2.0x 4.0	Ctr Ctr 0.59
E	MT20	3.0x 7.0	Ctr Ctr 0.39
D	MT20	2.0x 4.0	Ctr Ctr 0.37

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0


This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*

for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- --To--
0- 0- 0 7- 0- 0
Max comp. force 629 Lbs
Max tens. force 711 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555



Robbins Engineering, Inc./Online Plus™ © 1996-2009 Version 25.0.012 Engineering - Portrait 11/25/2009 1:12:24 PM Page 1



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
TC 0.68 2x 4 SP-#2
BC 0.78 2x 4 SP-#2
WB 0.60 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 43-11- 8
BC Cont. 0- 0- 0 43-11- 8
One Continuous Lateral Brace
R -T U -F I -N E -X
Y -D

Attach CLB with (2)-10d nails
at each web.

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz
R 2053 362 U 261 R
D 2170 394 U 248 R

Jt Brg Size Required
R 3.5" 2.4"
D 3.5" 2.6"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Ax1-CSI-Bnd
-----Top Chords-----
Q -T 0.29 95 T 0.01 0.28
T -U 0.37 2682 C 0.14 0.23
U -B 0.38 2517 C 0.04 0.34
B -N 0.68 2507 C 0.04 0.64
N -C 0.68 2507 C 0.04 0.64
C -X 0.40 2588 C 0.04 0.36
X -Y 0.42 2936 C 0.15 0.27
Y -V 0.34 97 T 0.01 0.33
-----Bottom Chords-----
R -S 0.62 2212 T 0.37 0.25
S -F 0.77 2292 T 0.38 0.39
F -I 0.75 2184 T 0.36 0.39
I -E 0.75 2245 T 0.37 0.38
E -W 0.78 2417 T 0.40 0.38
W -D 0.69 2542 T 0.42 0.27
-----Webs-----

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 376.1 LBS

R -Q 0.01 144 C WindLd
R -T 0.48 2901 C 1 Br
T -S 0.03 210 T
S -U 0.03 150 T
U -F 0.09 344 C 1 Br
F -B 0.19 523 T
B -I 0.47 528 T
I -N 0.18 518 C 1 Br
I -C 0.39 427 T
E -C 0.25 636 T
E -X 0.11 419 C 1 Br
X -W 0.10 301 T
W -Y 0.06 225 T
Y -D 0.60 3134 C 1 Br
D -V 0.04 280 C WindLd

TL Defl -0.42" in I -E L/999
LL Defl -0.20" in I -E L/999
Shear // Grain in B -N 0.33

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
Q MT20 2.0x 4.0 Ctr Ctr 0.28
T MT20 6.0x 6.0-1.0-0.6 0.74
U MT20 5.0x 7.0-0.3 0.5 0.43
B MT20 7.0x 6.0 1.1-4.2 0.53
N MT20 2.0x 4.0 Ctr Ctr 0.32
C MT20 7.0x 6.0-1.1-4.2 0.53
X MT20 5.0x 7.0 0.3 0.5 0.43
Y MT20 6.0x 6.0 0.9-0.5 0.81
V MT20 2.0x 4.0 Ctr Ctr 0.28
R MT20 5.0x 5.0 Ctr Ctr 0.90
S MT20 3.0x 7.0-0.9 Ctr 0.34
F MT20 5.0x 7.0 Ctr-0.5 0.47
I MT20 4.0x 8.0 Ctr Ctr 0.28
E MT20 5.0x 7.0 Ctr-0.5 0.49
W MT20 3.0x 7.0 0.9 Ctr 0.34
D MT20 5.0x 5.0-0.5 Ctr 0.89

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.

in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor: 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 3134 Lbs
Max tens. force 2542 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555


November 25,2009

Job JOHNSON-SPEC	Mark A25	Quan 1	Type HIPP	Span 431108	Pl-Hl 7	Left OH 0	Right OH 2- 0- 0	Engineering T3555324
----------------------------	--------------------	------------------	---------------------	-----------------------	-------------------	---------------------	----------------------------	--------------------------------

SPEC LOT15 ROSEWOOD ESTATES

HO 1-6-0

HO 11-14



ALL PLATES ARE MT2020

Scale: 0.139" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 370.6 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
TC 0.45 2x 4 SP-#2
BC 0.69 2x 4 SP-#2
WB 0.49 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 43-11- 8
BC Cont. 0- 0- 0 43-11- 8
One Continuous Lateral Brace
I -L H -M U -D
Attach CLB with (2)-10d nails
at each web.

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
P 1953 362 U 231 R
D 2067 394 U 217 R

Jt Brg Size Required
P 3.5" 2.3"
D 3.5" 2.4"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Ax1-CSI-Bnd
-----Top Chords-----
O -K 0.45 2491 C 0.13 0.32
K -B 0.45 2499 C 0.13 0.32
B -L 0.41 2646 C 0.09 0.32
L -M 0.42 2656 C 0.04 0.38
M -C 0.44 2656 C 0.09 0.35
C -T 0.34 2566 C 0.04 0.30
T -U 0.26 2758 C 0.15 0.11
U -Q 0.17 84 T 0.00 0.17
-----Bottom Chords-----
P -J 0.21 211 T 0.00 0.21
J -S1 0.56 2168 T 0.36 0.20
S1 -I 0.61 2153 T 0.36 0.25
I -H 0.69 2646 T 0.44 0.25
H -R 0.59 2223 T 0.37 0.22
R -S 0.58 2369 T 0.39 0.19
S -D 0.52 2314 T 0.38 0.14
-----Webs-----

P -O 0.18 1904 C WindLd
O -J 0.41 2225 T
J -K 0.12 381 C
K -S1 0.24 254 C
S1 -B 0.04 287 T
B -I 0.49 820 T
I -L 0.11 399 C
L -H 0.11 94 T
H -M 0.11 396 C
M -C 0.45 720 T
C -R 0.11 384 T
R -T 0.27 335 C
T -S 0.02 170 T
S -U 0.02 154 T
U -D 0.40 2903 C
D -Q 0.03 257 T WindLd

TL Defl -0.41" in H -R L/999
LL Defl -0.19" in H -R L/999
Shear // Grain in M -C 0.27

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
O MT20 5.0x 5.0 Ctr Ctr 0.90
K MT20 3.0x 7.0 Ctr Ctr 0.28
B MT20 7.0x 6.0 1.1-4.2 0.60
L MT20 5.0x 7.0 Ctr 0.5 0.39
M MT20 2.0x 4.0 Ctr Ctr 0.31
C MT20 7.0x 6.0-1.1-4.2 0.53
T MT20 5.0x 7.0 0.3 0.5 0.47
U MT20 6.0x 6.0 0.8-0.5 0.75
Q MT20 2.0x 4.0 Ctr Ctr 0.28
P MT20 2.0x 4.0 Ctr Ctr 0.63
J MT20 4.0x 6.0-2.2 0.3 0.84
S1 MT20 5.0x 7.0 Ctr-0.5 0.47
I MT20 3.0x 7.0 Ctr Ctr 0.47
H MT20 5.0x 9.0 1.0-0.5 0.57
R MT20 5.0x 7.0 Ctr-0.5 0.48
S MT20 3.0x 7.0 1.2 Ctr 0.37
D MT20 5.0x 5.0 Ctr Ctr 0.93

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610


REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 2903 Lbs
Max tens. force 2646 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

Job JOHNSON-SPEC	Mark A26	Quan 1	Type HIPP	Span 431108	Pl-H1 7	Left OH 0	Right OH 2- 0- 0	Engineering T3555325
SPEC LOT15 ROSEWOOD ESTATES								



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 344.3 LBS

Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----

TC	0.75	2x 4	SP-#2
BC	0.85	2x 4	SP-#2
WB	0.71	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	43-11- 8	
BC Cont.	0- 0- 0	43-11- 8	

psf-Ld Dead Live

TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"

Lumber Duration Factor 1.25
 Plate Duration Factor 1.25
 TC Fb=1.15 Fc=1.10 Ft=1.10
 BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
P	1966	362 U	200 R
D	2075	394 U	188 R

Jt Brg Size Required

P	3.5"	2.3"
D	3.5"	2.4"

Plus 9 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 BC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr CSI P Lbs Ax1-CSI-Bnd

-----Top Chords-----

O -K	0.32	2395 C	0.12	0.20
K -B	0.35	2582 C	0.04	0.31
B -L	0.73	3057 C	0.17	0.56
L -M	0.61	3065 C	0.06	0.55
M -C	0.75	3065 C	0.17	0.58
C -N	0.38	2705 C	0.04	0.34
N -Q	0.42	2776 C	0.10	0.32

-----Bottom Chords-----

P -J	0.12	180 T	0.00	0.12
J -F	0.59	2080 T	0.34	0.25
F -I	0.71	2233 T	0.37	0.34
I -H	0.85	3057 T	0.51	0.34
H -E	0.68	2337 T	0.39	0.29
E -G	0.65	2407 T	0.40	0.25
G -D	0.15	176 T	0.00	0.15

-----Webs-----

P -O	0.18	1921 C	WindLd
O -J	0.39	2162 T	

J -K 0.12 507 C
 K -F 0.08 188 T
 F -B 0.03 220 T
 B -I 0.71 1129 T
 I -L 0.37 479 C
 L -H 0.08 82 T
 H -M 0.37 476 C
 M -C 0.64 997 T
 E -C 0.05 319 T
 E -N 0.19 277 C
 G -N 0.06 249 C
 G -Q 0.44 2431 T
 D -Q 0.18 2022 C WindLd

TL Defl -0.51" in I -H L/999
 LL Defl -0.24" in H -E L/999
 Shear // Grain in B -L 0.32

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area

Jt Type	Plt Size	X	Y	JSI
O MT20	5.0x 5.0	Ctr	Ctr	0.86
K MT20	3.0x 7.0	Ctr	Ctr	0.28
B MT20	5.0x 9.0	1.0-3.6	0.70	
L MT20	5.0x 7.0	Ctr	0.5	0.39
M MT20	2.0x 4.0	Ctr	Ctr	0.31
C MT20	5.0x 9.0-1.0-3.6	0.62		
N MT20	3.0x 7.0	Ctr	Ctr	0.28
Q MT20	5.0x 7.0	Ctr	Ctr	0.73
P MT20	2.0x 4.0	Ctr	Ctr	0.63
J MT20	4.0x 6.0-1.7	0.3	0.90	
F MT20	5.0x 7.0	Ctr-0.5	0.48	
I MT20	3.0x 7.0	Ctr	Ctr	0.54
H MT20	5.0x 9.0	1.0-0.5	0.66	
E MT20	5.0x 7.0	Ctr-0.5	0.51	
G MT20	5.0x 5.0	2.2	0.1	0.84
D MT20	2.0x 4.0	Ctr	Ctr	0.74

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610


REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.
 Analysis Conforms To:
 FBC2007
 TPI 2002
 OH Loading
 Soffit psf 2.0
 This truss has been designed

for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.
 Design checked for 10 psf non-
 concurrent LL on BC.
 Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0
 Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 3065 Lbs
 Max tens. force 3057 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

Job JOHNSON-SPEC	Mark A27	Quan 1	Type HIPP	Span 441000	Pl-H1 7	Left OH 2- 0- 0	Right OH 2- 0- 0	Engineering T3555326
SPEC LOT15 ROSEWOOD ESTATES								



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----

TC	0.57	2x 4	SP-#2
BC	0.80	2x 4	SP-#2
WB	0.66	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	44-10- 0	0
BC Cont.	0- 0- 0	44-10- 0	0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	2097	402 U	161 R
D	2097	402 U	161 R

Jt	Brg Size	Required
A	3.5"	2.5"
D	3.5"	2.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 BC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd

-----Top Chords-----

Q -L	0.28	2736 C	0.14	0.14
L -B	0.31	2809 C	0.05	0.26
B -M	0.57	3478 C	0.17	0.40
M -N	0.52	3780 C	0.09	0.43
N -O	0.52	3780 C	0.09	0.43
O -C	0.57	3478 C	0.17	0.40
C -P	0.31	2810 C	0.05	0.26
P -R	0.28	2737 C	0.14	0.14

-----Bottom Chords-----

A -K	0.10	149 T	0.00	0.10
K -F	0.55	2369 T	0.39	0.16
F -J	0.62	2432 T	0.40	0.22
J -I	0.80	3478 T	0.58	0.22
I -H	0.80	3478 T	0.58	0.22
H -E	0.62	2432 T	0.40	0.22
E -G	0.55	2369 T	0.39	0.16
G -D	0.10	149 T	0.00	0.10

-----Webs-----

A -Q	0.19	2051 C	WindLd
Q -K	0.44	2404 T	

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 351.0 LBS

K -L	0.06	340 C
L -F	0.07	153 C
F -B	0.03	214 T
B -J	0.66	1395 T
J -M	0.37	694 C
M -I	0.20	405 T
I -N	0.20	385 C
I -O	0.20	405 T
H -O	0.37	694 C
H -C	0.66	1395 T
E -C	0.03	214 T
E -P	0.07	153 C
G -P	0.06	340 C
G -R	0.44	2405 T
D -R	0.19	2051 C

TL Defl -0.65" in I -H L/821
LL Defl -0.30" in I -H L/999
Shear // Grain in B -M 0.28

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
Q MT20 5.0x 7.0 Ctr Ctr 0.71
L MT20 3.0x 7.0 Ctr Ctr 0.28
B MT20 5.0x 9.0 1.0-3.6 0.86
M MT20 3.0x 7.0 Ctr Ctr 0.23
N MT20 5.0x 7.0 Ctr 0.5 0.39
O MT20 3.0x 7.0 Ctr Ctr 0.23
C MT20 5.0x 9.0-1.0-3.6 0.86
P MT20 3.0x 7.0 Ctr Ctr 0.28
R MT20 5.0x 7.0 Ctr Ctr 0.71
A MT20 2.0x 4.0 Ctr Ctr 0.76
K MT20 5.0x 5.0-2.2 0.1 0.83
F MT20 5.0x 7.0 Ctr-0.5 0.53
J MT20 3.0x 7.0 Ctr Ctr 0.65
I MT20 5.0x 7.0 Ctr-0.5 0.82
H MT20 3.0x 7.0 Ctr Ctr 0.65
E MT20 5.0x 7.0 Ctr-0.5 0.53
G MT20 5.0x 5.0 2.2 0.1 0.83
D MT20 2.0x 4.0 Ctr Ctr 0.76

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.


NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading

Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 3780 Lbs
Max tens. force 3478 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

Job	Mark	Quan	Type	Span	P1-H1	Left OH	Right OH	Engineering
JOHNSON-SPEC	J6	12	JCA2	10000	7	2- 0- 0	0	T3555327

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 9.8 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	-----Lumber-----
TC	0.02	2x 4	SP-#2
BC	0.02	2x 4	SP-#2
WB	0.05	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	1- 0- 0	
BC Cont.	0- 0- 0	1- 0- 0	

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	195	92 U	76 R
C	21	9 U	
B	37	27 U	27 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
D -B	0.02	29 T	0.00	0.02	
-----Bottom Chords-----					
A -C	0.02	0 T	0.00	0.02	
-----Webs-----					
A -D	0.05	176 C	0.02	0.03	

TL Defl 0.00" in A -C L/999

LL Defl 0.00" in A -C L/999
Shear // Grain in D -B 0.04

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
D MT20 2.0x 4.0 Ctr Ctr 0.13
A MT20 2.0x 4.0 Ctr Ctr 0.13

REVIEWED BY:

Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:

Trusses Manufactured by:
Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007
TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05
Truss is designed as


Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0

Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 176 Lbs
Max tens. force 160 Lbs
Connector Plate Fabrication
Tolerance = 20%

This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 17.9 LBS
 Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

	CSI	-Size-	----Lumber----
TC	0.09	2x 4	SP-#2
BC	0.10	2x 4	SP-#2
WB	0.13	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	3- 0- 0
BC	Cont.	0- 0- 0	3- 0- 0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor 1.25		
Plate Duration Factor 1.25		
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	256	91 U	147 R
C	57	1 U	
B	110	60 U	56 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Ax1	CSI-Bnd
-----Top Chords-----					
E -B	0.09	61 C	0.00	0.09	
-----Bottom Chords-----					
A -C	0.10	0 T	0.00	0.10	
-----Webs-----					
A -E	0.13	228 C	0.02	0.11	

TL Defl 0.00" in A -C L/999

LL Defl 0.00" in A -C L/999
 Shear // Grain in E -B 0.10

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area
 Jt Type Plt Size X Y JSI
 E MT20 2.0x 4.0 Ctr Ctr 0.12
 A MT20 2.0x 4.0 Ctr Ctr 0.16

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

For proper installation of
 toe-nails, refer to the 2001
 National Design Specification
 (NDS) for Wood Construction

NOTES:

Trusses Manufactured by:
 Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007
 TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.

Design checked for 10 psf non-
 concurrent LL on BC.


Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0

Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 228 Lbs
 Max tens. force 192 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 26.1 LBS
 Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

CSI	-Size-	-----Lumber-----
TC	0.27	2x 4 SP-#2
BC	0.24	2x 4 SP-#2
WB	0.29	2x 4 SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	5- 0- 0
BC	Cont.	0- 0- 0	5- 0- 0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	333	102 U	218 R
C	96		
B	176	93 U	85 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Ax1	CSI-Bnd
-----Top Chords-----					
E -B	0.27	97 C	0.01	0.26	
-----Bottom Chords-----					
A -C	0.24	0 T	0.00	0.24	
-----Webs-----					
A -E	0.29	291 C	0.03	0.26	

TL Defl -0.05" in A -C L/999

LL Defl -0.02" in A -C L/999
 Shear // Grain in E -B 0.17

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area
 Jt Type Plt Size X Y JSI
 E MT20 2.0x 4.0 Ctr Ctr 0.15
 A MT20 2.0x 4.0 Ctr Ctr 0.19

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

For proper installation of
 toe-nails, refer to the 2001
 National Design Specification
 (NDS) for Wood Construction

NOTES:

Trusses Manufactured by:
 Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.

Design checked for 10 psf non-
 concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*

for Exterior zone location.


Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 291 Lbs
 Max tens. force 231 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 76.8 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size-	---	Lumber----
TC	0.52	2x 4 SP-#2
BC	0.24	2x 4 SP-#2
WB	0.20	2x 4 SP-#2

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	9-10-13	
BC Cont.	0- 0- 0	9-10-13	

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.00	Fc=1.00	Ft=1.00
BC Fb=1.00	Fc=1.00	Ft=1.00

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz
A	461	139 U	122 R
C	346	37 U	
B	245	108 U	201 R

Jt	Brg Size	Required
A	4.9"	1.5"
C	1.5"	1.5"
B	1.5"	1.5"

LC#	1	Girder Loading
Dur Fctrs	- Lbr 1.25	Plt 1.25
plf	- Dead	Live* From To
TC V	20	40 0.0' 9.9'
BC V	20	0 0.0' 9.9'
TC V	-20	-40 0.0' 9.9'
	22	45 0.0' 9.9'
BC V	-20	0 0.0' 9.9'
	22	0 0.0' 9.9'

Plus 7 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
F -E	0.39	430	C	0.02	0.37
E -B	0.52	129	T	0.00	0.52

-----Bottom Chords-----

A -D	0.18	101	C	0.00	0.18
D -C	0.24	416	T	0.04	0.20

-----Webs-----

A -F	0.06	471	T	WindLd
F -D	0.07	420	T	
D -E	0.03	196	T	
E -C	0.20	481	C	
C -B	0.12	0	T	WindLd

TL Defl	-0.05"	in D -C	L/999
LL Defl	-0.02"	in D -C	L/999
Shear // Grain	in E -B	0.34	

Plates for each ply each face.

Plate -	MT20	20 Ga,	Gross Area
Plate -	MT2H	20 Ga,	Gross Area
Jt Type	Plt Size	X Y	JSI
F	MT20	2.0x 4.0	Ctr Ctr 0.50
E	MT20	3.0x 4.0	Ctr Ctr 0.25
B	MT20	3.0x 7.0	Ctr-0.3 0.05
A	MT20	2.0x 4.0	Ctr Ctr 0.39
D	MT20	3.0x 4.0-1.5	0.1 0.43
C	MT20	2.0x 4.0	Ctr Ctr 0.48

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:

FBC2007
TPI 2002
Girder King Jack
Loading TC and BC
Setback 7- 0- 0

OH Loading
Soffit psf 2.0
Design checked for 10 psf non-
concurrent LL on BC.

Use properly rated hangers for
loads framing into girder
truss.

Max gap between edge of brg
and end vertical or
diagonal web is 1/2".

Wind Loads - ANSI / ASCE 7-05

Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph

Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00

Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf

Max comp. force 481 Lbs
Max tens. force 471 Lbs
Connector Plate Fabrication

Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert. #5555

November 25, 2009

HO 11-14
TC

4-9-0

8-1-0

12-10-0

HO 11-14
2-0-0

4-3-5

3-9-2

4x6=

4x4=

3x4=

2x4||

3x4||

3x7=

3x4||

2x4||

7

A

B

C

E

F

G

H

D

HGR

R: 511

U: 105

W: 308

R: 642

U: 138

BC

4-10-12

7-11-4


12-10-0

12-10-0


ALL PLATES ARE MT2020

Scale: 0.412" = 1'

November 25, 2009



November 25, 2009



Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

 * 2-Ply Truss *

CSI -Size- ----Lumber----

TC	0.36	2x 6	SP-#2
--	0.28	2x 4	SP-#2
W -B	C -X		
BC	0.75	2x 6	SP-#2
WB	0.44	2x 4	SP-#2
--	0.20	2x 6	SP-#2
A -W	D -X		

Brace truss as follows:

O.C.	From	To
TC Cont.	0- 0- 0	44-10- 0
BC Cont.	0- 0- 0	44-10- 0

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.00	Fc=1.00	Ft=1.00
BC Fb=1.00	Fc=1.00	Ft=1.00

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	4124	855	129 R
D	3792	787	129 R

Jt	Brg Size	Required
A	3.5"	2.4"
D	3.5"	2.2"

LC# 1 Standard Loading

Dur Fctrs	Lbr	1.25	Plt	1.25
plf - Dead	Live*	From	To	
TC V	20	40	0.0'	44.8'
BC V	20	0	0.0'	44.8'
TC V	25	50	7.0'	31.5'
BC V	25	0	7.0'	31.5'
TC V	122	122	7.0'	CL-LB
BC V	173	173	7.0'	CL-LB
BC V	519	519	31.8'	CL-LB

Plus 9 Wind Load Case(s)
 Plus 1 USC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd

W-L	0.21	5437	C	0.17	0.04
L-B	0.28	6257 <td>C</td> <td>0.20</td> <td>0.08</td>	C	0.20	0.08

Robbins Engineering, Inc./Online Plus™

B -T	0.33	8636	C	0.20	0.13
T -U	0.36	10155	C	0.23	0.13
U -V	0.35	10261	C	0.24	0.11
V -O	0.35	10261	C	0.24	0.11
O -C	0.27	8839	C	0.20	0.07
C -P	0.22	5703	C	0.18	0.04
P -X	0.19	4986	C	0.15	0.04

-----Bottom Chords-----

A -K	0.08	117	T	0.00	0.08
K -F	0.39	4687	T	0.31	0.08
F -S	0.43	5435	T	0.36	0.07
S -R	0.64	8636	T	0.57	0.07
R -Q	0.75	10155	T	0.67	0.08
Q -H	0.68	8839	T	0.59	0.09
H -E	0.36	4947	T	0.33	0.03
E -G	0.35	4307	T	0.28	0.07
G -D	0.07	117	T	0.00	0.07

-----Webs-----

A -W	0.20	4035	C	WindLd
W -K	0.44	4801	T	
K -L	0.08	1082	C	
L -P	0.08	924	T	
F -B	0.02	279	T	
B -S	0.36	3955	T	
S -T	0.20	2037	C	
T -R	0.17	1902	T	
R -U	0.08	881	C	
U -Q	0.01	246	T	
Q -V	0.08	863	C	
Q -O	0.16	1781	T	
H -O	0.16	1632	C	
H -C	0.44	4817	T	
E -C	0.02	284	C	
E -P	0.07	781	T	
G -P	0.08	995	C	
G -X	0.40	4411	T	
D -X	0.18	3707	C	WindLd

TL Defl -0.70" in R -Q L/755
 LL Defl -0.28" in R -Q L/999
 Shear // Grain in B -T 0.19

Plates for each ply each face.

Plate - MT20	20 Ga,	Gross Area
Plate - MT2H	20 Ga,	Gross Area
Jt Type	Plt Size	X Y JSI
W	MT20	5.0x 5.0-0.4-0.3 0.97
L	MT20	3.0x 7.0 Ctr Ctr 0.28
B	MT20	6.0x10.0 Ctr Ctr 0.61
T	MT20	4.0x 6.0 Ctr Ctr 0.36
U	MT20	6.0x 6.0 Ctr Ctr 1.2 0.43
V	MT20	2.0x 4.0 Ctr Ctr 0.27
O	MT20	6.0x 6.0 Ctr Ctr 1.2 0.43
C	MT20	6.0x10.0 Ctr Ctr 0.61
P	MT20	3.0x 7.0 Ctr Ctr 0.23
X	MT20	5.0x 5.0 0.4-0.3 0.89
A	MT20	3.0x 4.0 Ctr Ctr 0.51
K	MT20	5.0x 5.0-2.2 0.2 0.83

APPROX. TRUSS WEIGHT: 406.9 LBS

F	MT20	4.0x 6.0 Ctr Ctr 0.17
S	MT20	6.0x 6.0 Ctr-1.2 0.75
R	MT20	4.0x 6.0 Ctr Ctr 0.36
Q	MT20	6.0x 8.0-0.5-1.2 0.88
H	MT20	4.0x 6.0 Ctr Ctr 0.90
E	MT20	6.0x 6.0 Ctr-1.2 0.43
G	MT20	4.0x 6.0 2.2 0.2 0.83
D	MT20	3.0x 4.0 Ctr Ctr 0.47

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.
 Analysis Conforms To:
 FBC2007
 TPI 2002
 2 COMPLETE TRUSSES REQUIRED.
 Fasten together in staggered
 pattern. (1/2" bolts -OR-
 SDS3 screws -OR- 10d nails
 as each layer is applied.)
 ----Spacing (In)----
 Rows Nails Screws Bolts
 TC 1 12 24 0
 BC 2 12 24 0
 WB 1 8 8
 Plus clusters of nails where
 shown.


OH Loading
 Soffit psf 2.0
 This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.
 Design checked for 10 psf non-
 concurrent LL on BC.
 Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0
 Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf

Max comp. force 10261 Lbs
 Max tens. force 10155 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

Job JOHNSON-SPEC	Mark B1	Quan 6	Type TR	Span 240000	Pl-Hl 7	Left OH 2- 0- 0	Right OH 2- 0- 0	Engineering T3555335
----------------------------	-------------------	------------------	-------------------	-----------------------	-------------------	---------------------------	----------------------------	--------------------------------

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 199.6 LBS
Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----
TC 0.20 2x 4 SP-#2
BC 0.32 2x 4 SP-#2
WB 0.53 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 24- 0- 0
BC Cont. 0- 0- 0 24- 0- 0

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz
A 1088 230 U 194 R
C 1088 230 U 194 R

Jt Brg Size Required
A 3.5" 1.5"
C 3.5" 1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Ax1-CSI-Bnd
-----Top Chords-----
F -I 0.17 83 T 0.01 0.16
I -J 0.20 1162 C 0.07 0.13
J -B 0.15 864 C 0.06 0.09
B -L 0.15 864 C 0.06 0.09
L -M 0.20 1162 C 0.07 0.13
M -G 0.17 83 T 0.01 0.16
-----Bottom Chords-----
A -H 0.32 1035 T 0.10 0.22
H -E 0.31 920 T 0.09 0.22
E -K 0.31 920 T 0.09 0.22
K -C 0.32 1035 T 0.10 0.22
-----Webs-----
A -F 0.03 253 T WindLd
A -I 0.53 1301 C

I -H 0.03 177 T
H -J 0.05 249 T
J -E 0.22 345 C
E -B 0.32 655 T
E -L 0.22 345 C
L -K 0.05 249 T
K -M 0.03 177 T
M -C 0.53 1301 C
C -G 0.03 253 T WindLd
TL Defl -0.10" in K -C L/999
LL Defl -0.04" in K -C L/999
Shear // Grain in F -I 0.16

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
F MT20 2.0x 4.0 Ctr Ctr 0.28
I MT20 3.0x 4.0-1.2-0.8 0.75
J MT20 5.0x 5.0-0.3 0.5 0.49
B MT20 4.0x 4.0 Ctr Ctr 0.42
L MT20 5.0x 5.0 0.3 0.5 0.49
M MT20 3.0x 4.0 1.2-0.8 0.75
G MT20 2.0x 4.0 Ctr Ctr 0.28
A MT20 3.0x 4.0 Ctr Ctr 0.85
H MT20 3.0x 4.0 Ctr Ctr 0.38
E MT20 5.0x 7.0 Ctr-0.5 0.45
K MT20 3.0x 4.0 Ctr Ctr 0.38
C MT20 3.0x 4.0 Ctr Ctr 0.85

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.


NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by

2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor: 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 1301 Lbs
Max tens. force 1035 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

Job JOHNSON-SPEC	Mark B2	Quan 1	Type HIPP	Span 240000	Pl-Hl 7	Left OH 2- 0- 0	Right OH 2- 0- 0	Engineering T3555336
----------------------------	-------------------	------------------	---------------------	-----------------------	-------------------	---------------------------	----------------------------	--------------------------------

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 194.9 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---
TC 0.34 2x 4 SP-#2
BC 0.32 2x 4 SP-#2
WB 0.31 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 24- 0- 0
BC Cont. 0- 0- 0 24- 0- 0

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 1088 230 U 182 R
D 1088 230 U 182 R

Jt Brg Size Required
A 3.5" 1.5"
D 3.5" 1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd
-----Top Chords-----
L -I 0.34 1219 C 0.00 0.34
I -B 0.34 903 C 0.00 0.34
B -C 0.11 800 C 0.06 0.05
C -J 0.34 903 C 0.00 0.34
J -M 0.34 1219 C 0.00 0.34
-----Bottom Chords-----
A -H 0.20 170 T 0.00 0.20
H -K 0.32 1066 T 0.11 0.21
K -G 0.32 1066 T 0.11 0.21
G -D 0.20 170 T 0.00 0.20
-----Webs-----
A -L 0.09 1040 C WindLd
L -H 0.19 1076 T

H -I 0.02 149 T
I -K 0.31 382 C
B -K 0.08 269 T
K -C 0.08 269 T
K -J 0.31 382 C
G -J 0.02 149 T
G -M 0.19 1076 T
D -M 0.09 1040 C WindLd
TL Defl -0.10" in H -K L/999
LL Defl -0.03" in H -K L/999
Shear // Grain in L -I 0.22

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
L MT20 3.0x 4.0 Ctr Ctr 0.71
I MT20 3.0x 4.0 Ctr Ctr 0.48
B MT20 4.0x 4.0 Ctr Ctr 0.58
C MT20 4.0x 4.0 Ctr Ctr 0.58
J MT20 3.0x 4.0 Ctr Ctr 0.48
M MT20 3.0x 4.0 Ctr Ctr 0.71
A MT20 2.0x 4.0 Ctr Ctr 0.44
H MT20 3.0x 4.0-2.0 0.1 0.77
K MT20 5.0x10.0 Ctr-0.5 0.49
G MT20 3.0x 4.0 2.0 0.1 0.77
D MT20 2.0x 4.0 Ctr Ctr 0.44

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide


will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 1219 Lbs
Max tens. force 1076 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

Job JOHNSON-SPEC	Mark B3	Quan 1	Type HIPP	Span 240000	Pl-H1 7	Left OH 2- 0- 0	Right OH 2- 0- 0	Engineering T3555337
----------------------------	-------------------	------------------	---------------------	-----------------------	-------------------	---------------------------	----------------------------	--------------------------------


SPEC LOT15 ROSEWOOD ESTATES



Online Plus -- Version 25.0.012 RUN DATE: 25-NOV-09 CSI -Size- ----Lumber---- TC 0.32 2x 4 SP-#2 BC 0.26 2x 4 SP-#2 WB 0.19 2x 4 SP-#2 Brace truss as follows: O.C. From To TC Cont. 0- 0- 0 24- 0- 0 BC Cont. 0- 0- 0 24- 0- 0 psf-Ld Dead Live TC 10.0 20.0 BC 10.0 0.0 TC+BC 20.0 20.0 Total 40.0 Spacing 24.0" Lumber Duration Factor 1.25 Plate Duration Factor 1.25 TC Fb=1.15 Fc=1.10 Ft=1.10 BC Fb=1.10 Fc=1.10 Ft=1.10 Total Load Reactions (Lbs) Jt Down Uplift Horiz- A 1088 230 U 153 R D 1088 230 U 153 R Jt Brg Size Required A 3.5" 1.5" D 3.5" 1.5" Plus 9 Wind Load Case(s) Plus 1 UBC LL Load Case(s) Plus 1 DL Load Case(s) Membr CSI P Lbs Axl-CSI-Bnd -----Top Chords----- K -I 0.22 1209 C 0.07 0.15 I -B 0.21 1051 C 0.06 0.15 B -C 0.32 909 C 0.00 0.32 C -J 0.21 1052 C 0.06 0.15 J -L 0.22 1209 C 0.07 0.15 -----Bottom Chords----- A -H 0.10 141 T 0.00 0.10 H -F 0.25 1052 T 0.17 0.08 F -E 0.24 906 T 0.15 0.09 E -G 0.26 1053 T 0.17 0.09 G -D 0.10 141 T 0.00 0.10 -----Webs----- A -K 0.09 1048 C WindLd		Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 190.3 LBS K -H 0.19 1069 T H -I 0.01 118 T I -F 0.12 246 C F -B 0.04 282 T B -E 0.08 86 T E -C 0.04 283 T C -J 0.12 248 C G -J 0.01 119 T G -L 0.19 1069 T D -L 0.09 1048 C WindLd TL Defl -0.10" in F -E L/999 LL Defl -0.03" in F -E L/999 Shear // Grain in B -C 0.21 Plates for each ply each face. Plate - MT20 20 Ga, Gross Area Plate - MT2H 20 Ga, Gross Area Jt Type Plt Size X Y JSI K MT20 3.0x 4.0 Ctr Ctr 0.71 I MT20 3.0x 4.0 Ctr Ctr 0.48 B MT20 4.0x 8.0 Ctr Ctr 0.58 C MT20 4.0x 4.0 Ctr Ctr 0.58 J MT20 3.0x 4.0 Ctr Ctr 0.48 L MT20 3.0x 4.0 Ctr Ctr 0.71 A MT20 2.0x 4.0 Ctr Ctr 0.45 H MT20 3.0x 4.0-2.0 0.2 0.75 F MT20 5.0x 5.0 Ctr-0.5 0.46 E MT20 3.0x 7.0 Ctr Ctr 0.41 G MT20 3.0x 4.0 2.0 0.2 0.75 D MT20 2.0x 4.0 Ctr Ctr 0.45 REVIEWED BY: Robbins Engineering, Inc. 6904 Parke East Blvd. Tampa, FL 33610 REFER TO ROBBINS ENG. GENERAL NOTES AND SYMBOLS SHEET FOR ADDITIONAL SPECIFICATIONS. NOTES: Trusses Manufactured by: Mayo Truss Co. Inc. Analysis Conforms To: FBC2007 TPI 2002 OH Loading Soffit psf 2.0 This truss has been designed for 20.0 psf LL on the B.C.		in areas where a rectangle 3- 6- 0 tall by 2- 0- 0 wide will fit between the B.C. and any other member. Design checked for 10 psf non- concurrent LL on BC. Wind Loads - ANSI / ASCE 7-05 Truss is designed as Components and Claddings* for Exterior zone location. Wind Speed: 120 mph Mean Roof Height: 15-0 Exposure Category: B Occupancy Factor : 1.00 Building Type: Enclosed TC Dead Load: 5.0 psf BC Dead Load: 5.0 psf Max comp. force 1209 Lbs Max tens. force 1069 Lbs Connector Plate Fabrication Tolerance = 20% This truss is designed for a creep factor of 1.5 which is used to calculate total load deflection.	
---	--	---	--	--	--

Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555


SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 219.0 LBS		FBC2007	
Online Plus -- Version 25.0.012		TPI 2002	
RUN DATE: 25-NOV-09		Girder Step Down Hip	
CSI -Size- ---Lumber---		Framing King Jacks	
TC 0.45 2x 4 SP-#2		Jack Open Faced	
-- 0.42 2x 6 SP-#2		Setback 7- 0- 0	
B -C		OH Loading	
BC 0.45 2x 6 SP-#2		Soffit psf 2.0	
WB 0.41 2x 4 SP-#2		Design checked for 10 psf non-	
-- 0.12 2x 6 SP-#2		concurrent LL on BC.	
A -O D -P		Wind Loads - ANSI / ASCE 7-05	
Brace truss as follows:		Truss is designed as	
O.C. From To		Components and Claddings*	
TC Cont. 0- 0- 0 24- 0- 0		for Exterior zone location.	
BC Cont. 0- 0- 0 24- 0- 0		Wind Speed: 120 mph	
psf-Ld Dead Live		Mean Roof Height: 15-0	
TC 10.0 20.0		Exposure Category: B	
BC 10.0 0.0		Occupancy Factor : 1.00	
TC+BC 20.0 20.0		Building Type: Enclosed	
Total 40.0 Spacing 24.0"		TC Dead Load: 5.0 psf	
Lumber Duration Factor 1.25		BC Dead Load: 5.0 psf	
Plate Duration Factor 1.25		Max comp. force 3145 Lbs	
TC Fb=1.00 Fc=1.00 Ft=1.00		Max tens. force 2532 Lbs	
BC Fb=1.00 Fc=1.00 Ft=1.00		Connector Plate Fabrication	
Total Load Reactions (Lbs)		Tolerance = 20%	
Jt Down Uplift Horiz		This truss is designed for a	
A 2146 450 U 124 R		creep factor of 1.5 which	
D 2143 450 U 124 R		is used to calculate total	
Jt Brg Size Required		load deflection.	
A 3.5" 2.5"			
D 3.5" 2.5"			
LC# 1 Girder Loading			
Dur Fctrs - Lbr 1.25 Plt 1.25			
plf - Dead Live* From To			
TC V 20 40 0.0' 24.0'			
BC V 20 0 0.0' 24.0'			
TC V 25 50 7.0' 17.0'			
BC V 25 0 7.1' 16.9'			
BC V 280 280 7.1' CL-LB			
BC V 280 280 16.9' CL-LB			
Plus 9 Wind Load Case(s)			
Plus 1 UBC LL Load Case(s)			
Plus 1 DL Load Case(s)			
Membr CSI P Lbs Axl-CSI-Bnd			
---Top Chords---			
O -J 0.21 2536 C 0.15 0.06			
J -B 0.45 2916 C 0.06 0.39			
B -K 0.42 3145 C 0.03 0.39			
K -C 0.42 3145 C 0.03 0.39			
C -L 0.45 2920 C 0.06 0.39			
L -P 0.23 2543 C 0.16 0.07			
---Bottom Chords---			
A -I 0.05 112 T 0.00 0.05			
I -F 0.37 2185 T 0.29 0.08			
F -H 0.45 2529 T 0.33 0.12			
H -E 0.45 2532 T 0.33 0.12			
E -G 0.37 2196 T 0.29 0.08			
G -D 0.05 112 T 0.00 0.05			
---Webs---			
A -O 0.12 2094 C WindLd			
O -I 0.41 2261 T			
I -J 0.06 539 C			
J -F 0.07 406 T			
F -B 0.09 552 T			
B -H 0.23 835 T			
H -K 0.25 849 C			
H -C 0.23 831 T			
E -C 0.09 553 T			
E -L 0.07 396 T			
G -L 0.06 543 C			
G -P 0.41 2273 T			
D -P 0.12 2091 C WindLd			
TL Defl -0.19" in H -E L/999			
LL Defl -0.08" in H -E L/999			
Shear // Grain in B -K 0.35			
Plates for each ply each face.			
Plate - MT20 20 Ga, Gross Area			
Plate - MT2H 20 Ga, Gross Area			
Jt Type Plt Size X Y JSI			
O MT20 3.0x 7.0 0.5-0.1 0.83			
J MT20 3.0x 4.0 Ctr Ctr 0.48			
B MT20 5.0x 9.0-0.5 Ctr 0.73			
K MT20 2.0x 4.0 Ctr Ctr 0.49			
C MT20 5.0x 9.0 0.5 Ctr 0.73			
L MT20 3.0x 4.0 Ctr Ctr 0.48			
P MT20 3.0x 7.0-0.5-0.1 0.84			
A MT20 2.0x 4.0 Ctr Ctr 0.81			
I MT20 4.0x 6.0-2.2 0.3 0.85			
F MT20 3.0x 7.0 Ctr Ctr 0.23			
H MT20 6.0x 6.0 Ctr-1.2 0.87			
E MT20 3.0x 7.0 Ctr Ctr 0.23			
G MT20 4.0x 6.0 2.2 0.3 0.85			
D MT20 2.0x 4.0 Ctr Ctr 0.81			
REVIEWED BY:			
Robbins Engineering, Inc.			
6904 Parke East Blvd.			
Tampa, FL 33610			
REFER TO ROBBINS ENG. GENERAL			
NOTES AND SYMBOLS SHEET FOR			
ADDITIONAL SPECIFICATIONS.			
NOTES:			
Trusses Manufactured by:			
Mayo Truss Co. Inc.			
Analysis Conforms To:			


Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



November 25, 2009

SPEC LOT15 ROSEWOOD ESTATES



Scale: 0.254" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 172.4 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	----Lumber----
TC	0.28	2x 4	SP-#2
BC	0.29	2x 4	SP-#2
WB	0.42	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	20- 1-11
BC	Cont.	0- 0- 0	20- 1-11

psf-Ld	Dead	Live	
TC	10.0	20.0	
BC	10.0	0.0	
TC+BC	20.0	20.0	
Total	40.0	Spacing	24.0"
Lumber	Duration Factor		1.25
Plate	Duration Factor		1.25
TC Fb=1.15	Fc=1.10	Ft=1.10	
BC Fb=1.10	Fc=1.10	Ft=1.10	

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
J	805	168 U	236 R
C	935	196 U	187 R

Jt	Brg Size	Required
J	3.5"	1.5"
C	3.5"	1.5"

```
Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)
```

Membr	CSI	P	Lbs	Ax1-CSI-Bnd	
-----Top Chords-----					
I -G	0.28	421	C	0.00	0.28
G -B	0.28	600	C	0.00	0.28
B -M	0.16	602	C	0.05	0.11
M -N	0.20	914	C	0.06	0.14
N -K	0.18	83	T	0.01	0.17

-----Bottom Chords-----					
J -F	0.13	189 T	0.00	0.13	
F -E	0.22	396 T	0.04	0.18	
E -L	0.28	691 T	0.07	0.21	
L -C	0.29	835 T	0.08	0.21	

```
-----Webs-----
J -I  0.12  799 C WindLd
I -F  0.12  695 T
```

F	G	0.13	475	C
G	E	0.05	143	T
E	B	0.16	356	T
E	M	0.22	344	C
M	L	0.06	269	T
L	N	0.03	192	T
N	C	0.42	1050	C
C	K	0.03	252	T

TL Defl	-0.09"	in L	-C	L/999
LL Defl	-0.04"	in L	-C	L/999
Shear //	Grain	in G	-B	0.21

Plates for each ply each face.						
Plate - MT20 20 Ga, Gross Area						
Plate - MT2H 20 Ga, Gross Area						
Jt	Type	Plt	Size	X	Y	JSI
I	MT20	3.0x	4.0	Ctr	Ctr	0.54
G	MT20	3.0x	4.0	Ctr	Ctr	0.48
B	MT20	4.0x	4.0	Ctr	Ctr	0.42
M	MT20	5.0x	5.0	0.3	0.5	0.49
N	MT20	3.0x	4.0	1.2-0.8		0.60
K	MT20	2.0x	4.0	Ctr	Ctr	0.28
J	MT20	2.0x	4.0	Ctr	Ctr	0.31
F	MT20	3.0x	4.0	Ctr	Ctr	0.55
E	MT20	5.0x	7.0	Ctr	-0.5	0.45
L	MT20	3.0x	4.0	Ctr	Ctr	0.38
C	MT20	3.0x	4.0	Ctr	Ctr	0.69

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:


FBC2007
TPI 2002
OH Loading
Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide

will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 1050 Lbs
Max tens. force 835 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 154.9 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----

TC 0.45 2x 4 SP-#2
BC 0.28 2x 4 SP-#2
WB 0.38 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 18- 1-11
BC Cont. 0- 0- 0 18- 1-11

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 725 156 U 263 R
C 855 175 U 180 R

Jt Brg Size Required
A 3.5" 1.5"
C 3.5" 1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd
-----Top Chords-----
G -B 0.45 421 C 0.04 0.41
B -J 0.26 449 C 0.05 0.21
J -K 0.20 783 C 0.06 0.14
K -H 0.18 84 T 0.01 0.17
-----Bottom Chords-----
A -E 0.22 182 T 0.00 0.22
E -I 0.27 574 T 0.05 0.22
I -C 0.28 730 T 0.07 0.21
-----Webs-----
A -G 0.28 673 C WindLd

G -E 0.16 522 T
E -B 0.03 189 T
E -J 0.24 365 C
J -I 0.06 276 T
I -K 0.04 197 C
K -C 0.38 917 C
C -H 0.03 253 T WindLd

TL Defl -0.09" in I -C L/999
LL Defl -0.04" in I -C L/999
Shear // Grain in G -B 0.27


Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
G MT20 3.0x 4.0 Ctr Ctr 0.45
B MT20 4.0x 4.0 Ctr Ctr 0.44
J MT20 5.0x 5.0 0.3 0.5 0.49
K MT20 3.0x 4.0 1.2-0.8 0.53
H MT20 2.0x 4.0 Ctr Ctr 0.28
A MT20 2.0x 4.0 Ctr Ctr 0.36
E MT20 4.0x 8.0 Ctr-1.0 0.53
I MT20 3.0x 4.0 Ctr Ctr 0.38
C MT20 3.0x 4.0 Ctr Ctr 0.60

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide

will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 917 Lbs
Max tens. force 730 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.




Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 70.3 LBS		Truss is designed as Components and Claddings* for Exterior zone location.	
Online Plus -- Version 25.0.012	G -C 0.02 218 C	Wind Speed: 120 mph	
RUN DATE: 25-NOV-09	C -F 0.00 52 T	Mean Roof Height: 15-0	
	F -D 0.00 54 T	Exposure Category: B	
CSI -Size- ---Lumber----	TL Defl -0.03" in F -E L/999	Occupancy Factor : 1.00	
TC 0.19 2x 4 SP-#2	LL Defl -0.01" in F -E L/999	Building Type: Enclosed	
BC 0.13 2x 4 SP-#2	Shear // Grain in D -E 0.15	TC Dead Load: 5.0 psf	
WB 0.02 2x 4 SP-#2		BC Dead Load: 5.0 psf	
Brace truss as follows:	Plates for each ply each face.	Max comp. force 251 Lbs	
O.C. From To	Plate - MT20 20 Ga, Gross Area	Max tens. force 193 Lbs	
TC Cont. 0- 0- 0 13- 5-14	Plate - MT2H 20 Ga, Gross Area	Connector Plate Fabrication	
BC Cont. 0- 0- 0 13- 5-14	Jt Type Plt Size X Y JSI	Tolerance = 20%	
psf-Ld Dead Live	A MT20 3.0x 4.0 Ctr Ctr 0.50	This truss is designed for a creep factor of 1.5 which is used to calculate total load deflection.	
TC 10.0 20.0	B MT20 4.0x 6.0 Ctr Ctr 0.58		
BC 10.0 0.0	C MT20 4.0x 4.0 Ctr Ctr 0.58		
TC+BC 20.0 20.0	D MT20 4.0x 4.0 Ctr Ctr 0.42		
Total 40.0 Spacing 24.0"	E MT20 3.0x 4.0 Ctr Ctr 0.50		
Lumber Duration Factor 1.25	H MT20 2.0x 4.0 Ctr Ctr 0.13		
Plate Duration Factor 1.25	G MT20 3.0x 4.0 Ctr Ctr 0.17		
TC Fb=1.15 Fc=1.10 Ft=1.10	F MT20 3.0x 4.0 Ctr Ctr 0.17		
BC Fb=1.10 Fc=1.10 Ft=1.10			
Total Load Reactions (Lbs)	REVIEWED BY:		
Jt Down Uplift Horiz	Robbins Engineering, Inc.		
A 945 203 U 68 R	6904 Parke East Blvd.		
Jt Brg Size Required	Tampa, FL 33610		
A 141.5" 0"-to- 142"	REFER TO ROBBINS ENG. GENERAL NOTES AND SYMBOLS SHEET FOR ADDITIONAL SPECIFICATIONS.		
Plus 9 Wind Load Case(s)	NOTES:		
Plus 1 UBC LL Load Case(s)	Trusses Manufactured by:		
Plus 1 DL Load Case(s)	Mayo Truss Co. Inc.		
Membr CSI P Lbs Ax1-CSI-Bnd	Analysis Conforms To:		
-----Top Chords-----	FBC2007		
A -B 0.05 200 C 0.00 0.05	TPI 2002		
B -C 0.02 151 C 0.01 0.01	OH Loading		
C -D 0.09 251 C 0.00 0.09	Soffit psf 2.0		
D -E 0.19 233 C 0.00 0.19	This truss has been designed for 20.0 psf LL on the B.C. in areas where a rectangle 3- 6- 0 tall by 2- 0- 0 wide will fit between the B.C. and any other member.		
-----Bottom Chords-----	Design checked for 10 psf non-concurrent LL on BC.		
A -H 0.03 2 T 0.00 0.03	Wind Loads - ANSI / ASCE 7-05		
H -G 0.03 0 T 0.00 0.03			
G -F 0.12 0 T 0.00 0.12			
F -E 0.13 2 T 0.00 0.13			
-----Webs-----			
H -B 0.00 41 C			
B -G 0.00 72 C			

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

SPEC LOT15 ROSEWOOD ESTATES



ALL PLATES ARE MT2020, # = PLATE SELECTED IN PLATE MONITOR

Scale: 0.471" = 1'

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber-----
TC 0.18 2x 4 SP-#2
BC 0.14 2x 4 SP-#2
WB 0.03 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 13- 5-14
BC Cont. 0- 0- 0 13- 5-14

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 945 203 U 69 R

Jt Brg Size Required
A 141.5" 0"-to- 142"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
A -K	0.00		89 C		
K -C	0.03		78 C	0.00	0.03
C -D	0.12		245 C	0.02	0.10
D -E	0.18		239 C	0.00	0.18
-----Bottom Chords-----					
A -H	0.01		5 T	0.00	0.01
H -G	0.05		0 T	0.00	0.05
G -F	0.14		0 T	0.00	0.14
F -E	0.14		2 T	0.00	0.14
-----Webs-----					

Robbins Engineering, Inc./Online Plus" APPROX. TRUSS WEIGHT: 65.4 LBS

H -K	0.01	80 T
G -C	0.03	314 C
C -F	0.02	130 T
F -D	0.00	48 C

TL Defl -0.03" in F -E L/999
LL Defl -0.01" in F -E L/999
Shear // Grain in D -E 0.15

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 3.0x 4.0 Ctr Ctr 0.50
K MT20 4.0x 4.0 Ctr Ctr 0.58
C MT20 4.0x 4.0 Ctr Ctr 0.58
D MT20 4.0x 4.0 Ctr Ctr 0.42
E MT20 3.0x 4.0 Ctr Ctr 0.50
H# MT20 2.0x 4.0-0.2-0.4 0.15
G# MT20 2.0x 4.0-0.1-0.3 0.18
F MT20 3.0x 4.0-1.5 Ctr 0.20

= Plate Monitor used
REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.


NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.

and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
NOTE: USER MODIFIED PLATES
This design may have plates
selected through a plate
monitor.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 314 Lbs
Max tens. force 260 Lbs
Fabrication Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which is
used to calculate total load
deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009


Job JOHNSON-SPEC	Mark P3	Quan 13	Type TR	Span 100001	Pl-Hl 7	Left OH 10- 3	Right OH 10- 3	Engineering T3555363
SPEC LOT15 ROSEWOOD ESTATES								



Online Plus -- Version 25.0.012		Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 41.6 LBS	
RUN DATE: 25-NOV-09		D -B 0.00 49 T	
CSI -Size- ----Lumber----		TL Defl -0.01" in A -D L/999	
TC 0.11 2x 4 SP-#2		LL Defl 0.00" in A -D L/999	
BC 0.11 2x 4 SP-#2		Shear // Grain in A -B 0.12	
WB 0.00 2x 4 SP-#2		Plates for each ply each face.	
Brace truss as follows:		Plate - MT20 20 Ga, Gross Area	
O.C. From To		Plate - MT2H 20 Ga, Gross Area	
TC Cont. 0- 0- 0 10- 0- 1		Jt Type Plt Size X Y JSI	
BC Cont. 0- 0- 0 10- 0- 1		A MT20 2.0x 4.0 Ctr Ctr 0.62	
psf-Ld Dead Live		B MT20 4.0x 4.0 Ctr Ctr 0.42	
TC 10.0 20.0		C MT20 2.0x 4.0 Ctr Ctr 0.62	
BC 10.0 0.0		D MT20 2.0x 4.0 Ctr Ctr 0.13	
TC+BC 20.0 20.0		REVIEWED BY:	
Total 40.0 Spacing 24.0"		Robbins Engineering, Inc.	
Lumber Duration Factor 1.25		6904 Parke East Blvd.	
Plate Duration Factor 1.25		Tampa, FL 33610	
TC Fb=1.15 Fc=1.10 Ft=1.10		REFER TO ROBBINS ENG. GENERAL	
BC Fb=1.10 Fc=1.10 Ft=1.10		NOTES AND SYMBOLS SHEET FOR	
Total Load Reactions (Lbs)		ADDITIONAL SPECIFICATIONS.	
Jt Down Uplift Horiz-		NOTES:	
A 667 146 U 57 R		Trusses Manufactured by:	
Jt Brg Size Required		Mayo Truss Co. Inc.	
A 99.7" 0"-to- 100"		Analysis Conforms To:	
Plus 9 Wind Load Case(s)		FBC2007	
Plus 1 UBC LL Load Case(s)		TPI 2002	
Plus 1 DL Load Case(s)		OH Loading	
Membr CSI P Lbs Axl-CSt-Bnd		Soffit psf 2.0	
-----Top Chords-----		This truss has been designed	
A -B 0.11 239 C 0.00 0.11		for 20.0 psf LL on the B.C.	
B -C 0.11 239 C 0.00 0.11		in areas where a rectangle	
-----Bottom Chords-----		3- 6- 0 tall by	
A -D 0.11 2 T 0.00 0.11		2- 0- 0 wide	
D -C 0.11 2 T 0.00 0.11		will fit between the B.C.	
-----Webs-----		and any other member.	
		Design checked for 10 psf non-	
		concurrent LL on BC.	
		Refer to Gen Det 3 series for	
		web bracing and plating.	
		Wind Loads - ANSI / ASCE 7-05	
		Truss is designed as	
		Components and Claddings*	
		for Exterior zone location.	
		Wind Speed: 120 mph	
		Mean Roof Height: 15-0	
		Exposure Category: B	
		Occupancy Factor : 1.00	
		Building Type: Enclosed	
		TC Dead Load: 5.0 psf	
		BC Dead Load: 5.0 psf	
		Max comp. force 239 Lbs	
		Max tens. force 181 Lbs	
		Connector Plate Fabrication	
		Tolerance = 20%	
		This truss is designed for a	
		creep factor of 1.5 which	
		is used to calculate total	
		load deflection.	
		Joaquin Velez, FL Lic. #68182	
		Robbins Engineering	
		6904 Parke East Blvd	
		Tampa, FL, 33610	
		FL Cert.#5555	
		November 25,2009	

Robbins Engineering, Inc./Online Plus™ © 1996-2009 Version 25.0.012 Engineering - Portrait 11/25/2009 1:12:50 PM Page 1

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 41.3 LBS

Online Plus -- Version 25.0.012

RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----

TC 0.11 2x 4 SP-#2

BC 0.11 2x 4 SP-#2

WB 0.00 2x 4 SP-#2

Brace truss as follows:

O.C. From To

TC Cont. 0- 0- 0 10- 0- 1

BC Cont. 0- 0- 0 10- 0- 1

psf-Ld Dead Live

TC 10.0 20.0

BC 10.0 0.0

TC+BC 20.0 20.0

Total 40.0 Spacing 24.0"

Lumber Duration Factor 1.25

Plate Duration Factor 1.25

TC Fb=1.15 Fc=1.10 Ft=1.10

BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)

Jt Down Uplift Horiz-

A 667 146 U 57 R

Jt Brg Size Required

A 99.7" 0"-to- 100"

Plus 9 Wind Load Case(s)

Plus 1 UBC LL Load Case(s)

Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-Csi-Bnd

-----Top Chords-----

A -B 0.11 239 C 0.00 0.11

B -C 0.11 239 C 0.00 0.11

-----Bottom Chords-----

A -D 0.11 2 T 0.00 0.11

D -C 0.11 2 T 0.00 0.11

-----Webs-----

TL Defl -0.01" in A -D L/999

LL Defl 0.00" in A -D L/999

Shear // Grain in A -B 0.12

Plates for each ply each face.

Plate - MT20 20 Ga, Gross Area

Plate - MT2H 20 Ga, Gross Area

Jt Type Plt Size X Y JSI

A MT20 2.0x 4.0 Ctr Ctr 0.62

B MT20 3.0x 4.0-0.5 Ctr 0.56

C MT20 2.0x 4.0 Ctr Ctr 0.62

D MT20 2.0x 4.0 Ctr Ctr 0.13

REVIEWED BY:

Robbins Engineering, Inc.

6904 Parke East Blvd.

Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL

NOTES AND SYMBOLS SHEET FOR

ADDITIONAL SPECIFICATIONS.

NOTES:

Trusses Manufactured by:

Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed

for 20.0 psf LL on the B.C.

in areas where a rectangle

3- 6- 0 tall by

2- 0- 0 wide

will fit between the B.C.

and any other member.

Design checked for 10 psf non-

concurrent LL on BC.

Refer to Gen Det 3 series for

web bracing and plating.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*

for Exterior zone location.

Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B

Occupancy Factor : 1.00

Building Type: Enclosed

TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf

Max comp. force 239 Lbs

Max tens. force 181 Lbs

Connector Plate Fabrication

Tolerance = 20%

This truss is designed for a

creep factor of 1.5 which

is used to calculate total

load deflection.

Joaquin Velez, FL Lic. #68182

Robbins Engineering

6904 Parke East Blvd

Tampa, FL, 33610

FL Cert.#5555

November 25,2009

SPEC LOT15 ROSEWOOD ESTATES

[illegible]

Scale: 0.617" = 1'

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

ROBBINS ENG. GENERAL NOTES & SYMBOLS

PLATE LOCATION






PLATE SIZE AND ORIENTATION




FLOOR TRUSS SPLICE (3X2, 4X2, 6X2)




DIMENSIONS

All dimensions are shown in FT-IN-SX (i.e. 6' 8 1/2" or 6-08-08). Dimensions less than one foot are shown in IN-SX only (i.e. 708).



LATERAL BRACING

Designates the location for continuous lateral bracing (CLB) for support of individual truss members only. CLBs must be properly anchored or restrained to prevent simultaneous buckling of adjacent truss members.



BEARING

When truss is designed to bear on multiple supports, interior bearing locations should be marked on the truss. Interior support or temporary shoring must be in place before erecting this truss. If necessary, shim bearings to assure solid contact with truss.

ROBBINS connector plates shall be applied on both faces of truss at each joint. Center the plates, unless indicated otherwise. No loose knots or wane in plate contact area. Splice only where shown. Overall spans assume 4" bearing at each end, unless indicated otherwise. Cutting and fabrication shall be performed using equipment which produces snug-fitting joints and plates. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication and the attached truss designs are not applicable for use with fire retardant lumber and some preservative treatments. Nails specified on truss design drawings refer to common wire nails, except as noted.

The attached design drawings were prepared in accordance with " National Design Specifications for Wood Construction" (AF & PA), " National Design Standard for Metal Plate Connected Wood Truss Construction" (ANSI/TPI 1), and HUD Design Criteria for Trussed Rafters.

FURNISH A COPY OF THE ATTACHED TRUSS DESIGN DRAWINGS TO ERECTION CONTRACTOR. IT IS THE RESPONSIBILITY OF THE BUILDING DESIGNER TO REVIEW THESE DRAWINGS AND VERIFY THAT DATA, INCLUDING DIMENSIONS & LOADS, CONFORM TO ARCHITECTURAL PLAN / SPECS AND THE TRUSS PLACEMENT DIAGRAM FURNISHED BY THE TRUSS FABRICATOR.


Robbins Eng. Co. bears no responsibility for the erection of trusses, field bracing or permanent truss bracing. Refer to BCSI 1-03 as published by Truss Plate Institute, 218 North Lee Street, Suite 312, Alexandria, Virginia 22314. Persons erecting trusses are cautioned to seek professional advice concerning proper erection bracing to prevent toppling and " dominoing ". Care should be taken to prevent damage during fabrication, storage, shipping and erection. Top and bottom chords shall be adequately braced in the absence of sheathing or rigid ceiling, respectively. It is the responsibility of others to ascertain that design loads utilized on these drawings meet or exceed the actual dead loads imposed by the structure and the live loads imposed by the local building code or historical climatic records.



6904 Parke East Blvd.
Tampa, FL 33610-4115
Tel: 813-972-1135 Fax: 813-971-6117

www.robbinseng.com

SPEC LOT15 ROSEWOOD ESTATES



Scale: 0.243" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 150.5 LBS

	CSI	-Size-	----Lumber----
TC	0.45	2x 4	SP-#2
BC	0.27	2x 4	SP-#2
WB	0.47	2x 4	SP-#2

psf-Ld	Dead	Live	
TC	10.0	20.0	
BC	10.0	0.0	
TC+BC	20.0	20.0	
Total	40.0	Spacing	24.0"
Lumber	Duration Factor		1.25
Plate	Duration Factor		1.25
TC Fb=1.15	Fc=1.10	Ft=1.10	
BC Fb=1.10	Fc=1.10	Ft=1.10	

Jt	Brg Size	Required
A	3.5"	1.5"
D	3.5"	1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P Lbs	Axl-CSI-Bnd
-----Top Chords-----			
I -B	0.29	315 T	0.04 0.25
B -C	0.45	278 T	0.03 0.42
C -H	0.25	636 C	0.05 0.20
H -J	0.10	709 C	0.00 0.10
-----Bottom Chords-----			
A -G	0.20	226 T	0.00 0.20
G -F	0.26	555 T	0.05 0.21
F -E	0.27	616 T	0.06 0.21
E -D	0.03	148 T	0.00 0.03

Inc./Online Plus		Web		APPROX. TRUSS WE	
A	-I	0.47	654	C	WindLd
I	-G	0.28	614	T	
G	-B	0.18	227	T	
G	-C	0.13	467	C	1 Br
F	-C	0.04	268	T	
F	-H	0.05	150	C	
E	-H	0.01	126	C	
E	-J	0.11	643	T	
D	-J	0.06	749	C	WindLd

TL Defl	-0.11"	in G -F	L/999
LL Defl	-0.05"	in G -F	L/999
Shear //	Grain	in B -C	0.29

Plates for each ply each face.						
Plate - MT20 20 Ga, Gross Area						
Plate - MT2H 20 Ga, Gross Area						
Jt	Type	Plt	Size	X	Y	JSI
I	MT20	3.0x	4.0	Ctr	Ctr	0.49
B	MT20	4.0x	4.0	Ctr	Ctr	0.44
C	MT20	4.0x	6.0	-1.4	0.6	0.58
H	MT20	3.0x	4.0	Ctr	Ctr	0.48
J	MT20	3.0x	4.0	Ctr	Ctr	0.40
A	MT20	2.0x	4.0	Ctr	Ctr	0.40
G	MT20	3.0x	7.0	Ctr	Ctr	0.65
F	MT20	4.0x	4.0	Ctr	-1.0	0.65
E	MT20	3.0x	4.0	1.5	0.3	0.62
D	MT20	2.0x	4.0	Ctr	Ctr	0.39


REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by

2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 749 Lbs
Max tens. force 643 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 112.6 LBS
Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----
TC 0.47 2x 4 SP-#2
BC 0.29 2x 4 SP-#2
WB 0.53 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 14- 1-11
BC Cont. 0- 0- 0 14- 1-11

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 564 134 U 288 R
D 695 131 U 34 R

Jt Brg Size Required
A 3.5" 1.5"
D 3.5" 1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Ax1-CSI-Bnd
-----Top Chords-----
B -G 0.44 136 C 0.00 0.44
G -C 0.47 547 C 0.04 0.43
C -H 0.08 601 C 0.04 0.04
-----Bottom Chords-----
A -F 0.29 520 T 0.05 0.24
F -E 0.29 528 T 0.05 0.24
E -D 0.07 22 T 0.00 0.07
-----Webs-----
A -B 0.33 192 T WindLd

A -G 0.53 629 C
F -G 0.04 284 T
F -C 0.01 76 T
E -C 0.01 123 T
E -H 0.10 554 T
D -H 0.06 679 C WindLd

TL Defl -0.09" in A -F L/999
LL Defl -0.04" in A -F L/999
Shear // Grain in B -G 0.27

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
B MT20 2.0x 4.0 Ctr Ctr 0.14
G MT20 3.0x 4.0 Ctr Ctr 0.30
C MT20 4.0x 6.0-1.4 0.6 0.58
H MT20 3.0x 4.0 Ctr Ctr 0.46
A MT20 3.0x 4.0 Ctr Ctr 0.41
F MT20 3.0x 4.0 Ctr Ctr 0.21
E MT20 3.0x 4.0 Ctr Ctr 0.39
D MT20 2.0x 4.0 Ctr Ctr 0.34

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.


and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 679 Lbs
Max tens. force 554 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

Job JOHNSON-SPEC	Mark B10	Quan 1	Type SP	Span 110003	Pl-H1 4.95	Left OH 0	Right OH 0	Engineering T3555344
----------------------------	--------------------	-----------	------------	----------------	---------------	--------------	---------------	--------------------------------


SPEC LOT15 ROSEWOOD ESTATES



Scale: 0.341" = 1'

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 79.2 LBS		Mean Roof Height: 15-0	
Online Plus -- Version 25.0.012		Exposure Category: B	
RUN DATE: 25-NOV-09		Occupancy Factor : 1.00	
		Building Type: Enclosed	
		TC Dead Load: 5.0 psf	
		BC Dead Load: 5.0 psf	
		Max comp. force 552 Lbs	
		Max tens. force 499 Lbs	
		Connector Plate Fabrication Tolerance = 20%	
		This truss is designed for a creep factor of 1.5 which is used to calculate total load deflection.	
CSI -Size- ----Lumber----			
TC	0.44 2x 4 SP-#2		
BC	0.26 2x 4 SP-#2		
WB	0.31 2x 4 SP-#2		
Brace truss as follows:			
O.C.	From To		
TC	Cont. 0- 0- 0 11- 0- 3		
BC	Cont. 0- 0- 0 11- 0- 3		
psf-Ld Dead Live			
TC	10.0 20.0		
BC	10.0 0.0		
TC+BC	20.0 20.0		
Total	40.0 Spacing 24.0"		
Lumber Duration Factor 1.25			
Plate Duration Factor 1.25			
TC Fb=1.15 Fc=1.10 Ft=1.10			
BC Fb=1.10 Fc=1.10 Ft=1.10			
Total Load Reactions (Lbs)			
Jt	Down Uplift Horiz-		
A	441 104 U 217 R		
C	441 77 U 7 R		
Jt Brg Size Required			
A	3.5" 1.5"		
C	3.4" 1.5"		
Plus 7 Wind Load Case(s)			
Plus 1 UBC LL Load Case(s)			
Plus 1 DL Load Case(s)			
Membr CSI P Lbs Ax1-CSI-Bnd			
-----Top Chords-----			
B -E	0.40 102 C 0.00 0.40		
E -F	0.44 513 C 0.04 0.40		
-----Bottom Chords-----			
A -D	0.26 488 T 0.05 0.21		
D -C	0.21 21 T 0.00 0.21		
-----Webs-----			
A -B	0.21 203 T WindLd		
A -E	0.31 552 C		
D -E	0.03 212 T		
D -F 0.09 493 T			
C -F 0.03 397 C WindLd			
TL Defl -0.05" in A -D L/999			
LL Defl -0.02" in A -D L/999			
Shear // Grain in B -E 0.26			
Plates for each ply each face.			
Plate - MT20 20 Ga, Gross Area			
Plate - MT2H 20 Ga, Gross Area			
Jt Type Plt Size X Y JSI			
B MT20 2.0x 4.0 Ctr Ctr 0.14			
E MT20 3.0x 4.0 Ctr Ctr 0.28			
F MT20 3.0x 4.0 Ctr Ctr 0.31			
A MT20 3.0x 4.0 Ctr Ctr 0.37			
D MT20 3.0x 4.0 1.5 0.1 0.50			
C MT20 2.0x 4.0 Ctr Ctr 0.22			
REVIEWED BY:			
Robbins Engineering, Inc.			
6904 Parke East Blvd.			
Tampa, FL 33610			
REFER TO ROBBINS ENG. GENERAL			
NOTES AND SYMBOLS SHEET FOR			
ADDITIONAL SPECIFICATIONS.			
NOTES:			
Trusses Manufactured by:			
Mayo Truss Co. Inc.			
Analysis Conforms To:			
FBC2007			
TPI 2002			
This truss has been designed			
for 20.0 psf LL on the B.C.			
in areas where a rectangle			
3- 6- 0 tall by			
2- 0- 0 wide			
will fit between the B.C.			
and any other member.			
Design checked for 10 psf non-			
concurrent LL on BC.			
Wind Loads - ANSI / ASCE 7-05			
Truss is designed as			
Components and Claddings*			
for Exterior zone location.			
Wind Speed: 120 mph			

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI	-Size-	----	Lumber----
TC	0.22	2x 4	SP-#2
BC	0.09	2x 4	SP-#2
WB	0.11	2x 4	SP-#2

Brace truss as follows:

O.C.	From	To
TC Cont.	0- 0- 0	7- 0- 3
BC Cont.	0- 0- 0	7- 0- 3

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"

Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	281	69 U	146 R
C	281	47 U	12 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.4"	1.5"

Plus 7 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Axl	CSI-Bnd
-----Top Chords-----					
B -F	0.20		71 C	0.00	0.20
F -D	0.22		275 C	0.02	0.20
-----Bottom Chords-----					
A -E	0.09		262 T	0.02	0.07
E -C	0.07		23 T	0.00	0.07
-----Webs-----					
A -B	0.11		172 T	WindLd	
A -F	0.07		388 T		
E -F	0.01		118 T		

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 51.0 LBS

E -D	0.04	269 T
C -D	0.02	251 C WindLd

TL Defl -0.01" in A -E L/999
LL Defl 0.00" in A -E L/999
Shear // Grain in B -F 0.23

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI

B	MT20	2.0x 4.0	Ctr	Ctr	0.12
F	MT20	3.0x 4.0	Ctr	Ctr	0.21
D	MT20	2.0x 4.0	Ctr	Ctr	0.28
A	MT20	2.0x 4.0	Ctr	Ctr	0.34
E	MT20	3.0x 4.0	1.0	0.1	0.45
C	MT20	2.0x 4.0	Ctr	Ctr	0.16

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610


REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph

Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 306 Lbs
Max tens. force 388 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 19.4 LBS
Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI	-Size-	---	Lumber----
TC	0.17	2x 4	SP-#2
BC	0.17	2x 4	SP-#2
WB	0.04	2x 4	SP-#2
SL	0.00	2x 6	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	3- 0- 3
BC	Cont.	0- 0- 0	3- 0- 3

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	121	32 U	62 R
C	121	18 U	6 R

Jt	Brg Size	Required
A	3.5"	1.5"
C	3.4"	1.5"

Plus 7 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Ax1-CSI-Bnd
-----Top Chords-----				
B -D	0.17	31 C	0.00	0.17
D -C	0.13	63 C	0.00	0.13
-----Bottom Chords-----				
A -C	0.17	112 T	0.01	0.16
-----Webs-----				
A -B	0.04	189 T	WindLd	
-----Sliders-----				
D -C	0.00	44 T		

TL Defl -0.01" in A -C L/999
LL Defl 0.00" in A -C L/999
Shear // Grain in B -D 0.17

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
B MT20 2.0x 4.0 Ctr Ctr 0.13
D MT20 3.0x 4.0 Ctr Ctr 0.08
C MT20 3.0x 9.0-1.5 0.3 0.61
A MT20 2.0x 4.0 Ctr Ctr 0.16

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.


Wind Loads - ANSI / ASCE 7-05
Truss is designed as

Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed

TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 82 Lbs
Max tens. force 189 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555


November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 238.3 LBS		as each layer is applied.)	
Online Plus -- Version 25.0.012		-----Spacing (In)-----	
RUN DATE: 25-NOV-09		Rows Nails Screws Bolts	
*****		TC 1 12 24 0	
* 2-Ply Truss *		BC 2 12 24 0	
*****		WB 1 8 8	
CSI -Size- ---Lumber---		Web Connection Exception --	
TC 0.33 2x 4 SP-#2		Space screws or nails for the	
BC 0.37 2x 8 SP-2400f-2.0E		following webs-	
WB 0.60 2x 4 SP-#2		C-U @ 6" o.c.	
-- 0.25 2x 6 SP-#2		Design checked for 10 psf non-	
C-U		concurrent LL on BC.	
PB --- 2x 4 SP-#2		Use properly rated hangers for	
Brace truss as follows:		loads framing into girder	
O.C. From To		truss.	
TC Cont. 0-0-0 24-4-13		NOTE: USER MODIFIED PLATES	
BC Cont. 0-0-0 24-4-13		This design may have plates	
psf-Ld Dead Live		selected through a plate	
TC 10.0 20.0		monitor.	
BC 10.0 0.0		Wind Loads - ANSI / ASCE 7-05	
TC+BC 20.0 20.0		Truss is designed as	
Total 40.0 Spacing 24.0"		Components and Claddings*	
Lumber Duration Factor 1.25		for Exterior zone location.	
Plate Duration Factor 1.25		Wind Speed: 120 mph	
TC Fb=1.00 Fc=1.00 Ft=1.00		Mean Roof Height: 15-0	
BC Fb=1.00 Fc=1.00 Ft=1.00		Exposure Category: B	
Total Load Reactions (Lbs)		Occupancy Factor : 1.00	
Jt Down Uplift Horiz		Building Type: Enclosed	
A 5816 1198 U 178 R		TC Dead Load: 5.0 psf	
C 5856 1207 U 190 R		BC Dead Load: 5.0 psf	
Jt Brg Size Required		Max comp. force 8034 Lbs	
A 4.9" 2.4"		Max tens. force 6913 Lbs	
C 3.5" 2.4"		Fabrication Tolerance = 20%	
LC# 1 Girder Loading		This truss is designed for a	
Dur Fctrs - Lbr 1.25 Plt 1.25		creep factor of 1.5 which is	
plf - Dead Live* From To		used to calculate total load	
TC V 20 40 0.0' 24.4'		deflection.	
BC V 219 199 0.0' 24.4'		REVIEWED BY:	
Plus 9 Wind Load Case(s)		Robbins Engineering, Inc.	
Plus 1 UBC LL Load Case(s)		6904 Parke East Blvd.	
Plus 1 DL Load Case(s)		Tampa, FL 33610	
Membr CSI P Lbs Axl-CSt-Bnd		REFER TO ROBBINS ENG. GENERAL	
-----Top Chords-----		NOTES AND SYMBOLS SHEET FOR	
A -N 0.33 8034 C 0.15 0.18		ADDITIONAL SPECIFICATIONS.	
N -O 0.29 6786 C 0.13 0.16		NOTES:	
O -B 0.21 5393 C 0.16 0.05		Trusses Manufactured by:	
B -P 0.21 5391 C 0.16 0.05		Mayo Truss Co. Inc.	
P -Q 0.26 6613 C 0.19 0.07		Analysis Conforms To:	
Q -U 0.28 7451 C 0.21 0.07		FBC2007	
-----Bottom Chords-----		TPI 2002	
A -M 0.37 6913 T 0.13 0.24		Girder Common	
M -L 0.29 6913 T 0.13 0.16		Loading BC	
L -E 0.18 5866 T 0.11 0.07		Span 21-11-0	
		2 COMPLETE TRUSSES REQUIRED.	
		Fasten together in staggered	
		pattern. (1/2" bolts -OR-	
		SDS3 screws -OR- 10d nails	

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 176.3 LBS

Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber-----
TC 0.39 2x 4 SP-#2
BC 0.32 2x 4 SP-#2
WB 0.32 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 24- 0- 0
BC Cont. 0- 0- 0 24- 0- 0

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 960 198 U 196 R
C 960 198 U 196 R

Jt Brg Size Required
A 3.5" 1.5"
C 3.5" 1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-Csi-Bnd
-----Top Chords-----
I -G 0.39 1220 C 0.00 0.39
G -B 0.39 885 C 0.00 0.39
B -H 0.39 885 C 0.00 0.39
H -J 0.39 1220 C 0.00 0.39
-----Bottom Chords-----
A -F 0.21 184 T 0.00 0.21
F -E 0.32 1070 T 0.11 0.21
E -D 0.32 1070 T 0.11 0.21
D -C 0.21 184 T 0.00 0.21
-----Webs-----
A -I 0.08 909 C WindLd
I -F 0.19 1080 T

F -G 0.02 159 T
G -E 0.32 405 C
E -B 0.23 550 T
E -H 0.32 405 C
D -H 0.02 159 T
D -J 0.19 1080 T
C -J 0.08 909 C WindLd

TL Defl -0.09" in E -D L/999
LL Defl -0.04" in A -F L/999
Shear // Grain in I -G 0.23

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
I MT20 3.0x 4.0 Ctr Ctr 0.66
G MT20 3.0x 4.0 Ctr Ctr 0.48
B MT20 4.0x 4.0 Ctr Ctr 0.42
H MT20 3.0x 4.0 Ctr Ctr 0.48
J MT20 3.0x 4.0 Ctr Ctr 0.66
A MT20 2.0x 4.0 Ctr Ctr 0.33
F MT20 3.0x 4.0-2.0 0.1 0.77
E MT20 5.0x 7.0 Ctr-0.5 0.44
D MT20 3.0x 4.0 2.0 0.1 0.77
C MT20 2.0x 4.0 Ctr Ctr 0.33

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.


NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-

concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 1220 Lbs
Max tens. force 1080 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.


Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ © 1996-2009 Version 25.0.012 Engineering - Portrait 11/25/2009 1:12:46 PM Page 1



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 33.0 LBS
Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	---	Lumber----
TC	0.11	2x 4	SP-#2	
BC	0.03	2x 4	SP-#2	
WB	0.06	2x 4	SP-#2	

Brace truss as follows:

	O.C.	From	To
TC Cont.	0- 0- 0	4- 0-13	
BC Cont.	0- 0- 0	4- 0-13	

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.00	Fc=1.00	Ft=1.00
BC Fb=1.00	Fc=1.00	Ft=1.00

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	102	107 U	62 R
C	38		
B	54	18 U	64 R

Jt	Brg Size	Required
A	4.9"	1.5"
C	1.5"	1.5"
B	1.5"	1.5"

LC# 1 Girder Loading

Dur Fctrs	- Lbr	1.25	Plt	1.25
plf	- Dead	Live*	From	To
TC V	20	40	0.0'	4.1'
BC V	20	0	0.0'	4.1'
TC V	-20	-40	0.0'	
	-7	-13		4.1'
BC V	-20	0	0.0'	
	-7	0		4.1'

Plus 7 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd
-----Top Chords-----

	D	-B	0.11	45 T	0.00	0.11
-----Bottom Chords-----						
	A	-C	0.03	82 T	0.00	0.03
-----Webs-----						
	A	-D	0.06	479 T	WindLd	
	D	-C	0.00	28 C		
	C	-B	0.02	0 T	WindLd	

TL Defl -0.01" in A -C L/999
LL Defl 0.00" in A -C L/999
Shear // Grain in D -B 0.10

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
D MT20 2.0x 4.0 Ctr Ctr 0.51
B MT20 2.0x 4.0 Ctr Ctr 0.13
A MT20 2.0x 4.0 Ctr Ctr 0.39
C MT20 2.0x 4.0 Ctr Ctr 0.28

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
Girder King Jack
Loading TC and BC
Setback 2-10- 8
OH Loading
Soffit psf 2.0
Design checked for 10 psf non-
concurrent LL on BC.
Use properly rated hangers for
loads framing into girder


truss.
Wind Loads - ANSI / ASCE 7-05
Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
Max comp. force 160 Lbs
Max tens. force 479 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

Job JOHNSON-SPEC	Mark J1	Quan 2	Type JCA2	Span 70000	Pl-Hl 7	Left OH 4- 0- 0	Right OH 0	Engineering T3555353
----------------------------	-------------------	-----------	--------------	---------------	------------	--------------------	---------------	-------------------------

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 37.6 LBS

Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----

TC	0.48	2x 4	SP-#2
BC	0.33	2x 4	SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	7- 0- 0
BC	Cont.	0- 0- 0	7- 0- 0

psf-Ld Dead Live

TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor	1.25	
Plate Duration Factor	1.25	
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	542	164 U	237 R
C	132		
B	221	114 U	100 R

Jt Brg Size Required

A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd

-----Top Chords-----			
A -B	0.48	118 C	0.00 0.48
-----Bottom Chords-----			
A -C	0.33	0 T	0.00 0.33

TL Defl -0.19" in A -C L/414
 LL Defl -0.08" in A -C L/999
 Shear // Grain in A -B 0.23

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area
 Jt Type Plt Size X Y JSI
 A MT20 2.0x 4.0 Ctr Ctr 0.62

REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

For proper installation of
 toe-nails, refer to the 2001
 National Design Specification
 (NDS) for Wood Construction

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.
 Analysis Conforms To:
 FBC2007
 TPI 2002
 OH Loading
 Soffit psf 2.0


Excessive Left OH condition.
 Max allowable length is
 3- 9-12. Support end or
 provide level return.

This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.
 Design checked for 10 psf non-
 concurrent LL on BC.
 Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0

Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 118 Lbs
 Max tens. force 94 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.


Joaquin Velez, FL Lic. #68182
 Robbins Engineering
 6904 Parke East Blvd
 Tampa, FL, 33610
 FL Cert.#5555

November 25,2009



Online Plus -- Version 25.0.012 RUN DATE: 25-NOV-09		Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 125.7 LBS		Jack Open Faced Setback 7- 0- 0	
CSI -Size- ---Lumber---		C -J 0.27 1939 C 0.02 0.25		OH Loading	
TC 0.29 2x 4 SP-#2		J -D 0.20 2108 C 0.13 0.07		Soffit psf 2.0	
-- 0.15 2x 6 SP-#2		-----Bottom Chords-----		Design checked for 10 psf non-	
B -C		A -H 0.31 1826 T 0.24 0.07		concurrent LL on BC.	
BC 0.34 2x 6 SP-#2		H -F 0.34 1826 T 0.24 0.10		Wind Loads - ANSI / ASCE 7-05	
WB 0.13 2x 4 SP-#2		F -E 0.31 1651 T 0.22 0.09		Truss is designed as	
Brace truss as follows:		E -G 0.30 1815 T 0.24 0.06		Components and Claddings*	
O.C. From To		G -D 0.31 1815 T 0.24 0.07		for Exterior zone location.	
TC Cont. 0- 0- 0 15- 8- 0		-----Webs-----		Wind Speed: 120 mph	
BC Cont. 0- 0- 0 15- 8- 0		H -I 0.02 151 T		Mean Roof Height: 15-0	
psf-Ld Dead Live		I -F 0.04 218 C		Exposure Category: B	
TC 10.0 20.0		F -B 0.11 636 T		Occupancy Factor : 1.00	
BC 10.0 0.0		B -E 0.02 127 T		Building Type: Enclosed	
TC+BC 20.0 20.0		E -C 0.13 703 T		TC Dead Load: 5.0 psf	
Total 40.0 Spacing 24.0"		E -J 0.03 183 C		BC Dead Load: 5.0 psf	
Lumber Duration Factor 1.25		G -J 0.01 108 T		Max comp. force 2121 Lbs	
Plate Duration Factor 1.25		TL Defl -0.11" in H -F L/999		Max tens. force 1826 Lbs	
TC Fb=1.00 Fc=1.00 Ft=1.00		LL Defl -0.05" in H -F L/999		Connector Plate Fabrication	
BC Fb=1.00 Fc=1.00 Ft=1.00		Shear // Grain in I -B 0.14		Tolerance = 20%	
Total Load Reactions (Lbs)		Plates for each ply each face.		This truss is designed for a	
Jt Down Uplift Horiz-		Plate - MT20 20 Ga, Gross Area		creep factor of 1.5 which	
A 1265 263 U 96 R		Plate - MT2H 20 Ga, Gross Area		is used to calculate total	
D 1395 296 U 96 R		Jt Type Plt Size X Y JSI		load deflection.	
Jt Brg Size Required		A MT20 4.0x 4.0 Ctr Ctr 0.90			
A 3.5" 1.5"		I MT20 3.0x 4.0 Ctr Ctr 0.21			
D 3.5" 1.6"		B MT20 5.0x 7.0-0.5 Ctr 0.73			
LC# 1 Girder Loading		C MT20 5.0x 5.0 Ctr-0.5 0.53			
Dur Fctrs - Lbr 1.25 Plt 1.25		J MT20 3.0x 4.0 Ctr Ctr 0.21			
plf - Dead Live* From To		D MT20 4.0x 4.0 Ctr Ctr 0.90			
TC V 20 40 0.0' 15.7'		H MT20 2.0x 4.0 Ctr Ctr 0.12			
BC V 20 0 0.0' 15.7'		F MT20 3.0x 4.0 Ctr Ctr 0.56			
TC V 25 50 7.0' 8.7'		E MT20 3.0x 7.0 Ctr Ctr 0.35			
BC V 25 0 7.1' 8.5'		G MT20 2.0x 4.0 Ctr Ctr 0.12			
BC V 280 280 7.1' CL-LB					
BC V 280 280 8.5' CL-LB					
Plus 9 Wind Load Case(s)		REVIEWED BY:			
Plus 1 UBC LL Load Case(s)		Robbins Engineering, Inc.			
Plus 1 DL Load Case(s)		6904 Parke East Blvd.			
Membr CSI P Lbs Axl-CSI-Bnd		Tampa, FL 33610			
-----Top Chords-----		REFER TO ROBBINS ENG. GENERAL			
A -I 0.20 2121 C 0.13 0.07		NOTES:			
I -B 0.29 1906 C 0.02 0.27		Trusses Manufactured by:			
B -C 0.15 1693 C 0.01 0.14		Mayo Truss Co. Inc.			
		Analysis Conforms To:			
		FBC2007			
		TPI 2002			
		Girder Step Down Hip			
		Framing King Jacks			

SPEC LOT15 ROSEWOOD ESTATES



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 17.4 LBS

Online Plus -- Version 25.0.012
 RUN DATE: 25-NOV-09

CSI	-Size-	----Lumber----
TC	0.08	2x 4 SP-#2
BC	0.09	2x 4 SP-#2
WB	0.12	2x 4 SP-#2

Brace truss as follows:

	O.C.	From	To
TC	Cont.	0- 0- 0	2-10- 8
BC	Cont.	0- 0- 0	2-10- 8

psf-Ld Dead Live

TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"

Lumber Duration Factor 1.25
 Plate Duration Factor 1.25
 TC Fb=1.15 Fc=1.10 Ft=1.10
 BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)

Jt	Down	Uplift	Horiz-
A	251	90 U	143 R
C	55	1 U	
B	105	58 U	55 R

Jt Brg Size Required

A	3.5"	1.5"
C	3.5"	1.5"
B	1.5"	1.5"

Plus 8 Wind Load Case(s)
 Plus 1 UBC LL Load Case(s)
 Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd

-----Top Chords-----				
D -B	0.08	59 C	0.00	0.08
-----Bottom Chords-----				
A -C	0.09	0 T	0.00	0.09
-----Webs-----				
A -D	0.12	224 C	0.02	0.10

TL Defl 0.00" in A -C L/999

LL Defl 0.00" in A -C L/999
 Shear // Grain in D -B 0.09

Plates for each ply each face.
 Plate - MT20 20 Ga, Gross Area
 Plate - MT2H 20 Ga, Gross Area
 Jt Type Plt Size X Y JSI
 D MT20 2.0x 4.0 Ctr Ctr 0.12
 A MT20 2.0x 4.0 Ctr Ctr 0.16


REVIEWED BY:
 Robbins Engineering, Inc.
 6904 Parke East Blvd.
 Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
 NOTES AND SYMBOLS SHEET FOR
 ADDITIONAL SPECIFICATIONS.

For proper installation of
 toe-nails, refer to the 2001
 National Design Specification
 (NDS) for Wood Construction

NOTES:
 Trusses Manufactured by:
 Mayo Truss Co. Inc.
 Analysis Conforms To:
 FBC2007
 TPI 2002
 OH Loading
 Soffit psf 2.0
 This truss has been designed
 for 20.0 psf LL on the B.C.
 in areas where a rectangle
 3- 6- 0 tall by
 2- 0- 0 wide
 will fit between the B.C.
 and any other member.
 Design checked for 10 psf non-
 concurrent LL on BC.
 Wind Loads - ANSI / ASCE 7-05
 Truss is designed as
 Components and Claddings*
 for Exterior zone location.
 Wind Speed: 120 mph
 Mean Roof Height: 15-0

Exposure Category: B
 Occupancy Factor : 1.00
 Building Type: Enclosed
 TC Dead Load: 5.0 psf
 BC Dead Load: 5.0 psf
 Max comp. force 224 Lbs
 Max tens. force 189 Lbs
 Connector Plate Fabrication
 Tolerance = 20%
 This truss is designed for a
 creep factor of 1.5 which
 is used to calculate total
 load deflection.



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 113.7 LBS

Online Plus -- Version 25.0.012

RUN DATE: 25-NOV-09

CSI -Size- ---Lumber---

TC 0.12 2x 4 SP-#2

-- 0.11 2x 6 SP-#2

B -C

BC 0.12 2x 6 SP-#2

WB 0.11 2x 4 SP-#2

-- 0.05 2x 6 SP-#2

A -I D -J

Brace truss as follows:

O.C. From To

TC Cont. 0- 0- 0 12-10- 0

BC Cont. 0- 0- 0 12-10- 0

psf-Ld Dead Live

TC 10.0 20.0

BC 10.0 0.0

TC+BC 20.0 20.0

Total 40.0 Spacing 24.0"

Lumber Duration Factor 1.25

Plate Duration Factor 1.25

TC Fb=1.00 Fc=1.00 Ft=1.00

BC Fb=1.00 Fc=1.00 Ft=1.00

Total Load Reactions (Lbs)

Jt Down Uplift Horiz-

A 777 184 U 64 R

D 772 182 U 64 R

Jt Brg Size Required

A 3.5" 1.5"

D 3.5" 1.5"

LC# 1 Girder Loading

Dur Fctrs - Lbr 1.25 Plt 1.25

plf - Dead Live* From To

TC V 20 40 0.0' 12.8'

BC V 20 0 0.0' 12.8'

TC V 4 9 2.9' 10.0'

BC V 4 0 3.0' 9.8'

BC V 36 36 3.0' CL-LB

BC V 36 36 9.8' CL-LB

Plus 9 Wind Load Case(s)

Plus 1 UBC LL Load Case(s)

Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd

-----Top Chords-----

I -B 0.10 715 C 0.05 0.05

B -H 0.11 925 C 0.06 0.05

H -C 0.11 925 C 0.06 0.05

C -J 0.12 720 C 0.06 0.06

-----Bottom Chords-----

A -F 0.02 53 T 0.00 0.02

F -G 0.12 619 T 0.08 0.04

G -E 0.11 628 T 0.08 0.03

E -D 0.02 53 T 0.00 0.02

-----Webs-----

A -I 0.05 738 C WindLd

I -F 0.11 637 T

F -B 0.01 83 T

B -G 0.06 357 T

G -H 0.03 264 C

G -C 0.06 345 T

E -C 0.01 85 T

E -J 0.11 647 T

D -J 0.05 734 C WindLd

TL Defl -0.03" in F -G L/999

LL Defl -0.01" in G -E L/999

Shear // Grain in I -I 0.15

Plates for each ply each face.

Plate - MT20 20 Ga, Gross Area

Plate - MT2H 20 Ga, Gross Area

Jt Type Plt Size X Y JSI

I MT20 3.0x 4.0 Ctr Ctr 0.50

B MT20 5.0x 7.0-0.5 Ctr 0.73

H MT20 2.0x 4.0 Ctr Ctr 0.21

C MT20 5.0x 7.0 0.5 Ctr 0.73

J MT20 3.0x 4.0 Ctr Ctr 0.50

A MT20 2.0x 4.0 Ctr Ctr 0.40

F MT20 3.0x 4.0-1.5 0.2 0.63

G MT20 3.0x 7.0 Ctr Ctr 0.30

E MT20 3.0x 4.0 1.5 0.2 0.64

D MT20 2.0x 4.0 Ctr Ctr 0.40

REVIEWED BY:

Robbins Engineering, Inc.

6904 Parke East Blvd.

Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL

NOTES AND SYMBOLS SHEET FOR

ADDITIONAL SPECIFICATIONS.

NOTES:

Trusses Manufactured by:

Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

Girder Step Down Hip

Framing King Jacks

Jack Open Faced

Setback 2-10- 8

OH Loading

Soffit psf 2.0

Design checked for 10 psf non-

concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*

for Exterior zone location.

Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B

Occupancy Factor : 1.00

Building Type: Enclosed

TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf

Max comp. force 925 Lbs

Max tens. force 647 Lbs

Connector Plate Fabrication

Tolerance = 20%

This truss is designed for a

creep factor of 1.5 which

is used to calculate total

load deflection.

Joaquin Velez, FL Lic. #68182

Robbins Engineering

6904 Parke East Blvd


Tampa, FL, 33610

FL Cert.#5555

November 25,2009

Robbins Engineering, Inc./Online Plus™ © 1996-2009 Version 25.0.012 Engineering - Portrait 11/25/2009 1:12:41 PM Page 1

Job JOHNSON-SPEC	Mark J15	Quan 2	Type JCA2	Span 50000	P1-H1 7	Left OH 2- 0- 0	Right OH 0	Engineering T3555357
SPEC LOT15 ROSEWOOD ESTATES								



Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 25.1 LBS
Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

CSI -Size- ----Lumber----
TC 0.23 2x 4 SP-#2
BC 0.17 2x 4 SP-#2

Brace truss as follows:
O.C. From To
TC Cont. 0- 0- 0 5- 0- 0
BC Cont. 0- 0- 0 5- 0- 0

psf-Ld Dead Live
TC 10.0 20.0
BC 10.0 0.0
TC+BC 20.0 20.0
Total 40.0 Spacing 24.0"
Lumber Duration Factor 1.25
Plate Duration Factor 1.25
TC Fb=1.15 Fc=1.10 Ft=1.10
BC Fb=1.10 Fc=1.10 Ft=1.10

Total Load Reactions (Lbs)
Jt Down Uplift Horiz-
A 333 92 U 174 R
C 94
B 161 82 U 71 R

Jt Brg Size Required
A 3.5" 1.5"
C 3.5" 1.5"
B 1.5" 1.5"

Plus 8 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr CSI P Lbs Axl-CSI-Bnd
-----Top Chords-----
A -B 0.23 87 C 0.00 0.23
-----Bottom Chords-----
A -C 0.17 0 T 0.00 0.17

TL Defl -0.05" in A -C L/999
LL Defl -0.02" in A -C L/999
Shear // Grain in A -B 0.16

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 2.0x 4.0 Ctr Ctr 0.62

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

For proper installation of
toe-nails, refer to the 2001
National Design Specification
(NDS) for Wood Construction

NOTES:

Trusses Manufactured by:

Mayo Truss Co. Inc.

Analysis Conforms To:

FBC2007

TPI 2002

OH Loading

Soffit psf 2.0

This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.

Design checked for 10 psf non-
concurrent LL on BC.

Wind Loads - ANSI / ASCE 7-05

Truss is designed as

Components and Claddings*

for Exterior zone location.

Wind Speed: 120 mph

Mean Roof Height: 15-0

Exposure Category: B

Occupancy Factor : 1.00

Building Type: Enclosed

TC Dead Load: 5.0 psf

BC Dead Load: 5.0 psf
Max comp. force 87 Lbs
Max tens. force 69 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

SPEC LOT15 ROSEWOOD ESTATES




Robbins Engineering, Inc./Online Plus™ © 1996-2009 Version 25.0.012 Engineering - Portrait 11/25/2009 1:12:47 PM Page 1

November 25, 2009

Job JOHNSON-SPEC	Mark J19	Quan 1	Type HHIP	Span 70000	P1-H1 7	Left OH 2- 0- 0	Right OH 0	Engineering T3555360
----------------------------	--------------------	------------------	---------------------	----------------------	-------------------	---------------------------	----------------------	--------------------------------

SPEC LOT15 ROSEWOOD ESTATES



Online Plus -- Version 25.0.012
RUN DATE: 25-NOV-09

	CSI	-Size-	----	Lumber----
TC	0.15	2x 4	SP-#2	
BC	0.26	2x 4	SP-#2	
WB	0.12	2x 4	SP-#2	
SL	0.02	2x 6	SP-#2	

Brace truss as follows:				
	O.C.	From	To	
TC	Cont.	0- 0- 0	7- 0- 0	
BC	Cont.	0- 0- 0	7- 0- 0	

psf-Ld	Dead	Live
TC	10.0	20.0
BC	10.0	0.0
TC+BC	20.0	20.0
Total	40.0	Spacing 24.0"
Lumber Duration Factor 1.25		
Plate Duration Factor 1.25		
TC Fb=1.15	Fc=1.10	Ft=1.10
BC Fb=1.10	Fc=1.10	Ft=1.10

Total Load Reactions (Lbs)				
Jt	Down	Uplift	Horiz	
A	411	170 U	54 R	
D	277	149 U	117 R	

Jt	Brg Size	Required
A	3.5"	1.5"
D	3.5"	1.5"

Plus 9 Wind Load Case(s)
Plus 1 UBC LL Load Case(s)
Plus 1 DL Load Case(s)

Membr	CSI	P	Lbs	Ax1	CSI-Bnd
-----Top Chords-----					
A -F	0.05	258	T	0.00	0.05
F -B	0.11	429	T	0.01	0.10
B -C	0.15	432	T	0.05	0.10
-----Bottom Chords-----					
A -E	0.26	241	C	0.00	0.26
E -D	0.15	99	T	0.01	0.14
-----Webs-----					
E -B	0.02	199	C		

Robbins Engineering, Inc./Online Plus™ APPROX. TRUSS WEIGHT: 53.8 LBS
E -C 0.12 513 C
D -C 0.07 526 T WindLd
-----Sliders-----
A -F 0.02 239 T

TL Defl -0.01" in A -E L/999
LL Defl 0.00" in A -E L/999
Shear // Grain in A -E 0.21

Plates for each ply each face.
Plate - MT20 20 Ga, Gross Area
Plate - MT2H 20 Ga, Gross Area
Jt Type Plt Size X Y JSI
A MT20 3.0x 9.0 1.5 0.3 0.58
F MT20 3.0x 4.0-0.1-0.1 0.09
B MT20 4.0x 4.0 Ctr Ctr 0.58
C MT20 2.0x 4.0 Ctr Ctr 0.54
E MT20 3.0x 4.0 Ctr Ctr 0.24
D MT20 2.0x 4.0 Ctr Ctr 0.43

REVIEWED BY:
Robbins Engineering, Inc.
6904 Parke East Blvd.
Tampa, FL 33610

REFER TO ROBBINS ENG. GENERAL
NOTES AND SYMBOLS SHEET FOR
ADDITIONAL SPECIFICATIONS.

NOTES:
Trusses Manufactured by:
Mayo Truss Co. Inc.
Analysis Conforms To:
FBC2007
TPI 2002
OH Loading
Soffit psf 2.0
This truss has been designed
for 20.0 psf LL on the B.C.
in areas where a rectangle
3- 6- 0 tall by
2- 0- 0 wide
will fit between the B.C.
and any other member.
Design checked for 10 psf non-
concurrent LL on BC.
Wind Loads - ANSI / ASCE 7-05

Truss is designed as
Components and Claddings*
for Exterior zone location.
Wind Speed: 120 mph
Mean Roof Height: 15-0
Exposure Category: B
Occupancy Factor : 1.00
Building Type: Enclosed
TC Dead Load: 5.0 psf
BC Dead Load: 5.0 psf
User-defined wind-exposed BC
regions --From-- ---To---
0- 0- 0 7- 0- 0
Max comp. force 513 Lbs
Max tens. force 526 Lbs
Connector Plate Fabrication
Tolerance = 20%
This truss is designed for a
creep factor of 1.5 which
is used to calculate total
load deflection.

Joaquin Velez, FL Lic. #68182
Robbins Engineering
6904 Parke East Blvd
Tampa, FL, 33610
FL Cert.#5555

November 25,2009

COLUMBIA COUNTY FLORIDA DEPARTMENT OF BUILDING AND ZONING OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 10-4S-16-02853-415

Building permit No. 000029234

Use Classification RE-NEW 28279, SFD

Fire: 6.42

Permit Holder PATRICIA JOHNSON

Waste: 16.75

Owner of Building PATRICIA JOHNSON

Total: 23.17

Location: 24 SW SCOTT PLACE, LAKE CITY, FL 32024

Date: 09/26/2011



Joe A.

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)

(877)-558-6262

7/12 W/11-14 OA HEEL
3/12 FRONT PORCH
2' OVERHANG
9' AND 10' BEARINGS
FLAT CEILING
BOX TRAY
SHOWN WALLS ARE BEARING

Account: CONTRACTORS
Job: JOHNSON-SPEC
Designer: C. LITTLE
Checker:
Date: 12-02-09

NOTICE OF COMMENCEMENT

Tax Parcel Identification Number:

10-45-16-02853-415

Clerk's Office Stamp

Inst: 201112003397 Date: 3/7/2011 Time: 10:26 AM
DC, P. DeWitt Cason, Columbia County Page 1 of 1 B: 1210 P: 2434

THE UNDERSIGNED hereby gives notice that improvements will be made to certain real property, and in accordance with Section 713.13 of the Florida Statutes, the following information is provided in this NOTICE OF COMMENCEMENT.

1. Description of property (legal description): Russwood Estates Unit 4 Lot 15
a) Street (job) Address: 234 SW Scott Place Lake City, FL 32024
2. General description of improvements: New Const of Single Family home
3. Owner Information
a) Name and address: John S and Patricia M Johnson 204 SW Dusty Gl
b) Name and address of fee simple titleholder (if other than owner): - Lake City, FL 32024
c) Interest in property: -
4. Contractor Information
a) Name and address: Patricia M. Johnson 204 SW Dusty Gl Lake City, FL 32024
b) Telephone No.: 386-255-4038 Fax No. (Opt.): -
5. Surety Information
a) Name and address: -
b) Amount of Bond: -
c) Telephone No.: - Fax No. (Opt.): -
6. Lender
a) Name and address: -
b) Phone No.: -
7. Identity of person within the State of Florida designated by owner upon whom notices or other documents may be served:
a) Name and address: -
b) Telephone No.: - Fax No. (Opt.): -
8. In addition to himself, owner designates the following person to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes:
a) Name and address: -
b) Telephone No.: - Fax No. (Opt.): -
9. Expiration date of Notice of Commencement (the expiration date is one year from the date of recording unless a different date is specified): -

WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY; A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.

STATE OF FLORIDA
COUNTY OF COLUMBIA

10. Patricia M Johnson
Signature of Owner or Owner's Authorized Officer/Director/Partner/Manager
Patricia M Johnson
Printed Name

The foregoing instrument was acknowledged before me, a Florida Notary, this 7 day of March, 2011, by:
Patricia Johnson as Owner (type of authority, e.g. officer, trustee, attorney
fact) for Patricia Johnson (name of party on behalf of whom instrument was executed).

Personally Known ☒ OR Produced Identification ☐ Type -

Notary Signature Laurie Hodson Notary Stamp or Seal:



11. Verification pursuant to Section 92.525, Florida Statutes. Under penalties of perjury, I declare that I have read the foregoing and that the facts stated in it are true to the best of my knowledge and belief.

Patricia M Johnson
Signature of Natural Person Signing (in line #10 above.)

DATE 03/07/2011

Columbia County Building Permit

PERMIT

This Permit Must Be Prominently Posted on Premises During Construction

000029234

APPLICANT PATRICIA JOHNSON PHONE 755-4038
ADDRESS 204 SW DUSTY GLEN LAKE CITY FL 32024
OWNER PATRICIA JOHNSON PHONE 755-4038
ADDRESS 234 SW SCOTT PLACE LAKE CITY FL 32024
CONTRACTOR PATRICIA JOHNSON PHONE 755-4038
LOCATION OF PROPERTY 90 W, L 247, R TROY ST, R RUSSWOOD TERR, L BETHANY PL,
R DOROTHY, R SCOTT PL, @ END ON RIGHT
TYPE DEVELOPMENT RE-NEW 28279, SFD ESTIMATED COST OF CONSTRUCTION 0.00
HEATED FLOOR AREA TOTAL AREA HEIGHT STORIES
FOUNDATION WALLS ROOF PITCH FLOOR
LAND USE & ZONING RSF-2 MAX. HEIGHT
Minimum Set Back Requirments: STREET-FRONT REAR SIDE
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 10-4S-16-02853-415 SUBDIVISION RUSSWOOD ESTATES
LOT 15 BLOCK PHASE UNIT TOTAL ACRES 0.75

RR28281158
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
EXISTING 09-0581-N BK HD N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: RE-NEWAL PERMIT # 28279-EXPIRED, 75% COMPLETED

EXISTING PLANS MOVED TO THIS FILE

NEW NOC RECORDED Check # or Cash 2213

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power Foundation Monolithic
date/app. by date/app. by date/app. by
Under slab rough-in plumbing Slab Sheathing/Nailing
date/app. by date/app. by date/app. by
Framing Insulation
date/app. by date/app. by
Rough-in plumbing above slab and below wood floor Electrical rough-in
date/app. by date/app. by
Heat & Air Duct Peri. beam (Lintel) Pool
date/app. by date/app. by date/app. by
Permanent power C.O. Final Culvert
date/app. by date/app. by date/app. by
Pump pole Utility Pole M/H tie downs, blocking, electricity and plumbing
date/app. by date/app. by date/app. by
Reconnection RV Re-roof
date/app. by date/app. by date/app. by

BUILDING PERMIT FEE \$ 0.00 CERTIFICATION FEE \$ 0.00 SURCHARGE FEE \$ 0.00
MISC. FEES \$ 288.75 ZONING CERT. FEE \$ FIRE FEE \$ 0.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ CULVERT FEE \$ TOTAL FEE 288.75
INSPECTORS OFFICE JK CLERKS OFFICE CH

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS OT THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

DATE 12/16/2009

Columbia County Building Permit
This Permit Must Be Prominently Posted on Premises During Construction**PERMIT**
000028279

APPLICANT PATRICIA JOHNSON PHONE 755-4038
ADDRESS 204 SW DUSTY GLEN LAKE CITY FL 32024
OWNER PATRICIA JOHNSON PHONE 755-4038
ADDRESS 234 SW SCOTT PLACE LAKE CITY FL 32024
CONTRACTOR PATRICIA JOHNSON PHONE 755-4038
LOCATION OF PROPERTY 90W, TL ON 247S, TR TROY ST., TR RUSSWOOD TERR.,
TL BETHANY PL, TR DOROTHY, TR SCOTT PL., AT END ON RIGHT
TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 230600.00
HEATED FLOOR AREA 3124.00 TOTAL AREA 4612.00 HEIGHT STORIES 1
FOUNDATION CONC WALLS FRAMED ROOF PITCH 7/12 FLOOR SLAB
LAND USE & ZONING RSF-2 MAX. HEIGHT 24
Minimum Set Back Requirments: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 10-4S-16-02853-415 SUBDIVISION RUSSWOOD ESTATES
LOT 15 BLOCK PHASE UNIT TOTAL ACRES 0.75

000001776

RR28281158


Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
WAIVER 09-581 BK WR Y
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: ONE FOOT ABOVE THE ROAD, NOC ON FILECheck # or Cash 1998**FOR BUILDING & ZONING DEPARTMENT ONLY**

(footer/Slab)

Temporary Power Foundation Monolithic
date/app. by date/app. by date/app. by
Under slab rough-in plumbing Slab Sheathing/Nailing
date/app. by date/app. by date/app. by
Framing Insulation
date/app. by date/app. by
Rough-in plumbing above slab and below wood floor Electrical rough-in
date/app. by date/app. by
Heat & Air Duct Peri. beam (Lintel) Pool
date/app. by date/app. by date/app. by
Permanent power C.O. Final Culvert
date/app. by date/app. by date/app. by
Pump pole Utility Pole M/H tie downs, blocking, electricity and plumbing
date/app. by date/app. by date/app. by
Reconnection RV Re-roof
date/app. by date/app. by date/app. by

BUILDING PERMIT FEE \$ 1155.00 CERTIFICATION FEE \$ 23.06 SURCHARGE FEE \$ 23.06
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ TOTAL FEE 1276.12

INSPECTORS OFFICE  CLERKS OFFICE 

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS OT THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.