

8'

2' 0"/H
6/12

NOTES:

- 1) REFER TO HIB 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING REQUIRED)
- 2) ALL TRUSSES, INCLUDING TRUSSES UNDER VALLEY BRACING, MUST BE CORRECTLY DECKED OR REFER TO DETAIL V05 FOR ALTERNATE BRACING REQUIREMENTS
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER
- 4) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED
- 6) 5X42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP
- 7) ALL ROOF TRUSSES HANGERS TO BE SAMPSON HUS26 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSSES HANGERS TO BE SAMPSON TH4422 UNLESS OTHERWISE NOTED
- 8) BEAM/HEADER/JOIST (HDB) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROV.

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND WALLS. ALL PREVIOUS ARCHITECTURAL OR TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. WEI CONDITIONS TO RESOLVE AGAINST CHANGES THAT WILL INCREASE CHARGES TO YOU.

Exterior Bearing Plan

Approved by _____ Date _____



Burnell

PHONE 904-437-3344 FAX 904-43

Jacksonville

PHONE 904-772-6100 FAX 904-77

Lake City

PHONE 904-755-6894 FAX 904-75

Sanford

PHONE 407-322-0094 FAX 407-32

BUILDER BRYAN ZECHER


LEGAL ADDRESS LOT 1 MAGNOLIA HILL

DRAWN BY SAMUEL

DATE 05-30-06

WVL

L1671



46-8-0

