

DURGIN

SCOPE OF WORK

****We propose to do the following:**

1. Remove garden tub, platform, sheetrock, walls, and existing tub plumbing
2. Cover existing window with durarock
3. Provide and install durarock on three walls (approx. 104 sq. ft.)
4. Provide and install handicap-accessible fiberglass, shower pan
5. Provide and install ceramic tile on three walls (approx. 104 sq. ft.)
6. Provide and install new shower valve
7. Provide and install three handicap bars
8. Provide and install shower curtain