

PLANS PREPARED FOR:


NEW MILLENNIUM BUILDING SYSTEMS, LLC 1992 NW BASCOM NORRIS DR LAKE CITY, FL

06/2020 **FINAL CONSTRUCTION PLANS**

SHEET INDEX

COVER SHEET	C- 1
GENERAL NOTES	C-2
DEMOLITION PLAN	C-3
OVERALL SITE PLAN	C-4
SITE PLAN	C-5
GRADING PLAN	C-6
STORMWATER PLAN	C-7
SWMF PLAN	C-8
EROSION CONTROL PLAN	C-9
EROSION CONTROL NOTES	C-1

ATTACHMENT: SURVEY BY J. SHERMAN FRIER & ASSOCIATES, INC.



THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND

CONSIDERED SIGNED AND SEALED. THE SIGNATURE MUST BE VERIFIED IN THE ELECTRONIC DOCUMENTS.

LAKE CITY, FL 32056 CERTIFICATE OF AUTHORIZATION: 29011

THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE FOLLOWING SHEETS IN ACCORDANCE WITH RULE 61G15-23.004, F.A.C.




SHEE COVER

- 2. THE CONTRACTOR SHALL COMPLY WITH ALL CONDITIONS AS SET FORTH BY THE ISSUED SUWANNEE RIVER WATER MANAGEMENT DISTRICT ENVIRONMENTAL RESOURCE PERMIT.
- 3. THE CONTRACTOR SHALL MAINTAIN THE CONSTRUCTION SITE IN A SECURE MANNER. ALL OPEN TRENCHES AND **EXCAVATED AREAS SHALL BE PROTECTED FROM ACCESS** BY THE GENERAL PUBLIC.
- 4. BOUNDARY INFORMATION SHOWN, WAS OBTAINED FROM A BOUNDARY SURVEY PREPARED BY J. SHERMAN FRIER & ASSOCIATES, FLORIDA CERTIFICATE NO. 6332.
- 5. ANY PUBLIC LAND CORNER WITHIN THE LIMITS OF CONSTRUCTION SHALL BE PROTECTED. IF A CORNER MONUMENT IS IN DANGER OF BEING DESTROYED AND HAS NOT BEEN PROPERLY REFERENCED, THE CONTRACTOR SHOULD NOTIFY THE ENGINEER.
- 6. THE SITE IS LOCATED IN SECTION 25, TOWNSHIP 3 SOUTH, RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA.
- 7. THE CONTRACTOR SHALL IMPLEMENT ALL COMPONENTS OF THE EROSION AND SEDIMENTATION CONTROL PLAN PRIOR TO ANY EARTH DISTURBING ACTIVITIES. ALL COMPONENTS SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL ALL VEGETATION IS ESTABLISHED, THE ENTIRE PROJECT AREA IS STABILIZED AND THE OWNER HAS ACCEPTED OPERATION AND MAINTENANCE.
- 8. THE STORMWATER BASIN IS DESIGNED IN ACCORDANCE WITH CHAPTER 40B-4 F.A.C.
- 9. ALL SLOPES OF THE STORMWATER BASIN SHALL BE GRASSED. ALL SLOPES STEEPER THAN 3:1 SHALL BE STAPLED SOD.
- 10. ALL DISTURBED AREAS NOT SODDED SHALL BE SEEDED WITH A MIXTURE OF LONG-TERM VEGETATION AND QUICK **GROWING SHORT-TERM VEGETATION FOR THE FOLLOWING** CONDITIONS. FOR THE MONTHS FROM SEPTEMBER THROUGH MARCH, THE MIX SHALL CONSIST OF 70 POUNDS PER ACRE OF LONG-TERM SEED AND 20 POUNDS PER ACRE OF WINTER RYE. FOR THE MONTHS OF APRIL THROUGH AUGUST, THE MIX SHALL CONSIST OF 70 POUNDS PER ACRE OF LONG-TERM SEED AND 20 POUNDS PER ACRE OF MILLET.
- 11. THE LOCATION OF THE UTILITIES SHOWN IN THE PLANS ARE APPROXIMATE ONLY. THE EXACT LOCATION SHALL BE DETERMINED BY THE CONTRACTOR DURING CONSTRUCTION. CONTRACTOR SHALL PROTECT ALL UTILITIES WITHIN THE PROJECT AREAS.
- 12. ALL SITE CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE COLUMBIA COUNTY LAND DEVELOPMENT REGULATIONS.
- 13. CONTRACTOR SHALL COORDINATE ALL WORK WITH OTHER CONTRACTORS WITHIN PROJECT AREA.

X:\Z018\L180314NMB\H.CADD\cNMBcov\Z GEN June 1, 2020 Date Last Saved: June 1, RECORD OF THIS SHEET IS THE ELECTRONI

- 14. THIS PROJECT IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE F.D.O.T. STANDARD PLANS FOR ROAD AND **BRIDGE CONSTRUCTION (CURRENT EDITION), FLORIDA** BUILDING CODE (CURRENT EDITION), A.W.W.A. SPECIFICATIONS, AND THE COLUMBIA COUNTY DEVELOPMENT STANDARDS UNLESS OTHERWISE NOTED.
- 15. IF UNSUITABLE MATERIAL IS ENCOUNTERED DURING GRADING, CONTRACTOR SHALL REMOVE UNSUITABLE MATERIAL TO A DEPTH OF 24" BELOW FINISHED GRADE WITHIN THE CONSTRUCTION LIMITS.

- 16. THE CONTRACTOR SHALL SUBMIT A NOTICE OF CONSTRUCTION COMMENCEMENT TO THE WATER MANAGEMENT DISTRICT AT LEAST 48 HOURS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- 17. CONTRACTOR SHALL PROVIDE AN AS-BUILT SURVEY MEETING THE REQUIREMENTS OF CHAPTER 61G17 F.A.C. FOR THE STORMWATER MANAGEMENT SYSTEMS. INCLUDE HORIZONTAL AND VERTICAL DIMENSIONAL DATA SO THAT IMPROVEMENTS ARE LOCATED AND DELINEATED RELATIVE TO THE BOUNDARY. PROVIDE SUFFICIENT DETAILED DATA TO DETERMINE WHETHER THE IMPROVEMENTS WERE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, A COPY OF THE AS-BUILT SURVEY (IN PAPER AND DIGITAL AUTOCAD FORMAT) MUST BE SUBMITTED TO COLUMBIA COUNTY, FLORIDA (DEPARTMENT OF GROWTH MANAGEMENT) AND THE ENGINEER.
- 18. THE CONTRACTOR SHALL SUBMIT A NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM NOTICE OF INTENT ALONG WITH SUPPORTING DOCUMENTATION TO THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION AT LEAST 48 HOURS PRIOR TO BEGINNING OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PERMIT FEES.
- 19. IF DURING CONSTRUCTION OR OPERATION OF THE STORMWATER MANAGEMENT SYSTEM, A STRUCTURAL FAILURE IS OBSERVED THAT HAS THE POTENTIAL TO CAUSE THE DIRECT DISCHARGE OF SURFACE WATER INTO THE FLORIDAN AQUIFER SYSTEM, CORRECTIVE ACTIONS DESIGNED OR APPROVED BY A REGISTERED PROFESSIONAL SHALL BE TAKEN AS SOON AS PRACTICAL TO CORRECT THE FAILURE. SEE KARST FEATURE REPAIR DETAIL ON SHEET C-5. IN ADDITION, A REPORT PREPARED BY A REGISTERED PROFESSIONAL MUST BE PROVIDED AS SOON AS PRACTICAL TO THE DEPARTMENT FOR REVIEW AND APPROVAL THAT PROVIDES REASONABLE ASSURANCE THAT THE BREACH WILL BE PERMANENTLY CORRECTED.



MIN. 1.5" MILLINGS **8" LIMEROCK BASE COURSE** 12" COMPACTED SUBGRADE MINIMUM L.B.R. 40


TYPICAL STORAGE YARD DETAIL


ERP 04-0393 PERMIT DATA VS. CONSTRUCTED DATA								
	ASPHALT	BUILDINGS	STORAGE YARD	STORMWATER				
	& SWALES			BASIN				
PERMITTED	168,149 SF	261,138 SF	805,293 SF (LARGE PERVIOUS AREA)	188,285 SF				
PERMITTED AND CONSTRUCTED	150,913 SF	261,138 SF	563,033 SF	188,574 SF				
PERMITTED BUT NOT CONSTRUCTED	17,236 SF (ASPHALT)	10,000 SF	242,260 SF	-				
NOT PERMITTED BUT CONSTRUCTED	-	-	232,196 SF (AFTER ORIGINAL PROJECT COMPLETION)	289 SF (MORE THAN PERMITTED)				


	SITE DATA TABLE				
	NEW MILLENNIUM BUILDING STORAGE YAR	D EXTENSION			
PARCEL ID NUMBER	25-3S-16-02277-102				
ZONING	INDUSTRIAL				
LAND USE	INDUSTRIAL				
CITY COUNCIL DISTRICT NUMBER	3				
PHYSICAL ADDRESS	1992 NW BASCOM NORRIS DR. LAKE CITY, FL 32055				
PROJECT PROPERTY BOUNDARY		SQ. FT.	ACRES	% OF SITE	% OF LOC
TOTAL PROPERTY B	DUNDARY AREA	3066188	70.39	100.00%	100.00%
PROJECT AREA / LIMITS OF CONST	RUCTION (LOC)	3066188	70.39	100.00%	100.00%
EXISTING IMPERVIOUS AREA ON-S	TE				
EXISTING ASPHALT F	PAVEMENT	131248	3.01	4.28%	4.28%
EXISTING CONCRETI		0	0.00	0.00%	0.00%
EXISTING BUILDING		261138	5.99	8.52%	8.52%
EXISTING STORAGE	YARD	838885	19.26	27.36%	27.36%
EXISTING GRASSED	SWALES	36901	0.85	1.20%	1.20%
EXISTING STORMWA	TER MANAGEMENT FACILITY	188574	4.33	6.15%	6.15%
TOTAL EXISTING IMP	ERVIOUS AREA ON-SITE	1456746	33.45	47.51%	47.51%
PROPOSED IMPERVIOUS AREA ON	SITE				
EXISTING ASPHALT F	PAVEMENT TO REMAIN	131248	3.01	4.28%	4.28%
EXISTING CONCRETI	TO REMAIN	0	0.00	0.00%	0.00%
EXISTING BUILDING	TO REMAIN	261138	5.99	8.52%	8.52%
EXISTING STORAGE	YARD TO REMAIN	837983	19.24	27.33%	27.33%
EXISTING GRASSED	SWALES TO REMAIN	36901	0.85	1.20%	1.20%
EXISTING STORMWA	TER MANAGEMENT FACILITY TO REMAIN	188574	4.33	6.15%	6.15%
PROPOSED ASPHAL	PAVEMENT	0	0.00	0.00%	0.00%
PROPOSED CONCRE	TE	0	0.00	0.00%	0.00%
PROPOSED BUILDING	3	0	0.00	0.00%	0.00%
PROPOSED STORAG	E YARD	179527	4.12	5.86%	5.86%
PROPOSED GRASSE	D SWALES	9205	0.21	0.30%	0.29%
PROPOSED STORMV	ATER MANAGEMENT FACILITY	69668	1.60	2.27%	2.27%
TOTAL PROPOSED IN	MPERVIOUS AREA ON-SITE (INCLUDING SWMF)	1714244	39.36	55.90%	55.90%
EXISTING PERVIOUS AREA ON-SITE					
EXISTING GREEN SP	ACE	1609442	36.95	52.47%	52.47%
TOTAL EXISTING PER	RVIOUS	1609442	36.95	52.47%	52.47%
PROPOSED PERVIOUS AREA ON-S	TE				
EXISTING GREEN SP	ACE TO REMAIN	1351944	31.04	44.10%	44.10%
TOTAL PROPOSED P	ERVIOUS AREA ON-SITE	1351944	31.04	44.10%	44.10%
PROPOSED PARKING LANDSCAPE	AREA ON-SITE	0	0.00	0.00%	0.00%
REQUIRED PARKING NO				JIRED	<u> </u>
PROVIDED PARKING		NO CHANGE REQUIRED			


NOTES: PROPOSED 100' X 100' OPEN STRUCTURE IN DRAINAGE BASIN. NO IMPERVIOUS AREA WILL BE ADDED.


M















- THE CONTRACTOR SHALL ADJUST AND REVISE THIS PLAN TO MEET ACTUAL FIELD CONDITIONS. ANY REVISIONS SHALL BE APPROVED BY THE REVIEWING AGENCIES.
- SEDIMENT AND EROSION CONTROL FACILITIES, STORM DRAINAGE FACILITIES AND DETENTION BASINS SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION.
- **EROSION CONTROL MEASURES SHALL BE INSPECTED WEEKLY AND AFTER EACH** RAINFALL OF 0.5 INCHES OR GREATER, AND REPAIRED OR REPLACED AS NECESSARY.
- SEDIMENT AND EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL ALL CONSTRUCTION IS COMPLETE AND UNTIL A PERMANENT GROUND COVER HAS BEEN
- ALL OPEN DRAINAGE SWALES SHALL BE GRASSED AND RIPRAP SHALL BE PLACED AS REQUIRED TO CONTROL EROSION.
- SILT FENCES SHALL BE LOCATED ON SITE TO PREVENT SEDIMENT AND EROSION FROM LEAVING PROJECT LIMITS.
- CONTRACTOR SHALL PLACE A DOUBLE ROW OF SILT FENCE IN AREAS WHERE RUNOFF FROM DISTURBED AREAS MAY ENTER WETLANDS.
- 10. DURING CONSTRUCTION AND AFTER CONSTRUCTION IS COMPLETE, ALL STRUCTURES SHALL BE CLEANED OF ALL DEBRIS AND EXCESS SEDIMENT.
- 11. ALL GRADED AREAS SHALL BE STABILIZED IMMEDIATELY WITH A TEMPORARY FAST-GROWING COVER AND/OR MULCH.
- 12. A PAD OF RUBBLE RIP RAP SHALL BE PLACED AT THE BOTTOM OF ALL COLLECTION FLUMES AND COLLECTION PIPE OUTLETS. GRANITE OR LIMESTONE RIPRAP IS REQUIRED, NO BROKEN CONCRETE WILL BE ACCEPTED.
- 13. ALL SIDE SLOPES STEEPER THAN 3:1 SHALL BE ADEQUATELY PROTECTED FROM EROSION THROUGH THE USE OF SYNTHETIC BALES OR SODDING.
- 14. ALL STABILIZATION PRACTICES SHALL BE INITIATED AS SOON AS PRACTICABLE IN AREAS OF THE JOB WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY STOPPED, BUT IN NO CASE SHALL THE DISTURBED AREA BE LEFT UNPROTECTED FOR MORE THAN SEVEN DAYS.
- 15. ALL WASTE GENERATED ON THE PROJECT SHALL BE DISPOSED OF BY THE CONTRACTOR IN AREAS PROVIDED BY CONTRACTOR.
- 16. LOADED HAUL TRUCKS SHALL BE COVERED WITH TARPS.
- 17. EXCESS DIRT SHALL BE REMOVED DAILY.

Plotted by: Robert (JR) R RULE 61G15-23.004,

- THIS PROJECT SHALL COMPLY WITH ALL WATER QUALITY STANDARDS. PERMIT REQUIRED FROM SRWMD HAS BEEN OBTAINED.
- 19. QUALIFIED PERSONNEL SHALL INSPECT THE AREA USED FOR STORAGE OF STOCKPILES, THE SILT FENCE AND STRAW BALES. THE LOCATION WHERE VEHICLES ENTER OR EXIT THE SITE, AND THE DISTURBED AREAS THAT HAVE NOT BEEN FINALLY STABILIZED, AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM OF 0.5 INCHES OR GREATER.
- 20. SITES THAT HAVE BEEN FINALLY STABILIZED WITH SOD OR GRASSING SHALL BE INSPECTED AT LEAST ONCE EVERY WEEK.



TYPE IV SILT FENCE DETAIL

EROSION CONTROL NOTES MILLENNIUM BUILDING STORAGE YARD EXTENSION LAKE CITY, FL

ĕ