

DATE 03/28/2007

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000025673

APPLICANT LINDA RODER PHONE 623-2383
ADDRESS PO BOX 1921 LAKE CITY FL 32056
OWNER ADAM'S FRAMING & CONSTRUCTION PHONE 623-2383
ADDRESS 147 SW WIS DR LAKE CITY FL 32024
CONTRACTOR ADAM PAKKA PHONE 623-2383
LOCATION OF PROPERTY 47 S, R ON CR 242, R ON SW WISE DR, 9TH LOT ON THE LEFT

TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 76550.00
HEATED FLOOR AREA 1531.00 TOTAL AREA 2247.00 HEIGHT 19.70 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 7/12 FLOOR SLAB
LAND USE & ZONING RSF-2 MAX. HEIGHT 35
Minimum Set Back Requirments: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00
NO. EX.D.U. 0 FLOOD ZONE XPP DEVELOPMENT PERMIT NO. _____

PARCEL ID 24-4S-16-03113-122 SUBDIVISION WISE ESTATES
LOT 2 BLOCK B PHASE _____ UNIT _____ TOTAL ACRES 0.58

000001357 CBC1253409
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
CULVERT 07-249 BK JH N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: PLAT REQUIRES FIRST FLOOR TO BE 99.0 FEET, ELEVATION LETTER
REQUIRED, NOC

Check # or Cash 3434

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power _____ Foundation _____ Monolithic _____
date/app. by date/app. by date/app. by
Under slab rough-in plumbing _____ Slab _____ Sheathing/Nailing _____
date/app. by date/app. by date/app. by
Framing _____ Rough-in plumbing above slab and below wood floor _____
date/app. by date/app. by
Electrical rough-in _____ Heat & Air Duct _____ Peri. beam (Lintel) _____
date/app. by date/app. by date/app. by
Permanent power _____ C.O. Final _____ Culvert _____
date/app. by date/app. by date/app. by
M/H tie downs, blocking, electricity and plumbing _____ Pool _____
date/app. by date/app. by
Reconnection _____ Pump pole _____ Utility Pole _____
date/app. by date/app. by date/app. by
M/H Pole _____ Travel Trailer _____ Re-roof _____
date/app. by date/app. by date/app. by

BUILDING PERMIT FEE \$ 385.00 CERTIFICATION FEE \$ 11.23 SURCHARGE FEE \$ 11.23
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$ _____
FLOOD DEVELOPMENT FEE \$ _____ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ 25.00 TOTAL FEE 507.46
INSPECTORS OFFICE L. J. Hoban CLERKS OFFICE CN

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Lot 2 Block B

ok 3434

Columbia County Building Permit Application

1357/15673

For Office Use Only Application # 0703-53 Date Received 3/20/07 By CF Permit # _____
Application Approved by - Zoning Official BLK Date 28-03-07 Plans Examiner AKJH Date 3-22-07
Floor & Zone 2nd Floor Development Permit N/A Zoning RSF-2 Land Use Plan Map Category Res. Land Dev.
Comments Plat Revisions 1st Floor to be at 99.0ft Elevation letter Required
☒ NO ☒ EH ☐ Dead or PA ☐ Site Plan ☐ State Road Info. ☐ Parent Parcel # ☐ Development Permit

Name of Authorized Person Signing Permit Adam Papka Phone 623-2383 Fax 752-2281
Address P.O. Box 1921 Lake City FL 32056
Owner's Name Adam's Framing & Construction Phone 623-2383
911 Address 147 SW Wise Dr Lake City FL 32024
Contractor's Name Adam Papka Phone _____
Address P.O. Box 1921 Lake City FL 32056
Fee Sample Owner Name & Address NA
Bonding Co. Name & Address NA
Architect/Engineer Name & Address William Myers/Nick Geisler
Mortgage Lenders Name & Address Columbia Bank

Circle the correct power company - ☒ FL Power & Light - ☐ Clay Elec. - ☐ Suwannee Valley Elec. - ☐ Progress Energy
Property ID Number 24-45-16-031B-122 Estimated Cost of Construction 125,000
Subdivision Name Wise Estates Lot 2 Block B Unit _____ Floor _____
Driving Directions 475, Bon CR 242, Bon SW Wise Dr, turn lot down on L

Type of Construction SFD Number of Existing Dwellings on Property 0
Total acreage 0.580 Lot Size _____ Do you need a ☒ Culvert Permit or Culvert Water or Have an Existing Drive
Actual Distance of Structure from Property Lines - Front 50' Side 73'-11" Side 50' Rear 31'-10"
Total Building Height 19'-7" Number of Stories 1 Heated Floor Area 1531 Roof Pitch 7-12
TOTAL 2247

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.
OWNER'S AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.
WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU LOVING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Owner/Builder or Authorized Person by Notarized Letter _____
Notary Public for Linda R. Röder Commission #DD303276 Expires: Mar 24, 2008 Bonded Through Atlantic Bonding Co., Inc.
Contractor Signature _____ Contractor's License Number CBC1253409 Competency Card Number _____
NOTARY STAMP/SEAL _____
Sworn to (or affirmed) and subscribed before me this _____ day of _____ 20____
Personally known _____ or Produced Identification _____
Notary Signature _____ (Revised Sept. 2006)

Columbia County Building Department Culvert Permit

Culvert Permit No.
000001357

DATE 03/28/2007 PARCEL ID # 24-4S-16-03113-122

APPLICANT LINDA RODER PHONE 623-2383

ADDRESS PO BOX 1921 LAKE CITY FL 32056

OWNER ADAM'S FRAMING & CONSTRUCTION PHONE 623-2383


ADDRESS 147 SW WIS DR LAKE CITY FL 32024

CONTRACTOR ADAM PAPKA PHONE 623-2383

LOCATION OF PROPERTY 47 S, R ON CR 242, R ON SW WISE DR, 9TH LOT ON THE LEFT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT WISE ESTATES 2 B

SIGNATURE



INSTALLATION REQUIREMENTS



Culvert size will be 18 inches in diameter with a total length of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
- b) the driveway to be served will be paved or formed with concrete.

Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.



Culvert installation shall conform to the approved site plan standards.



Department of Transportation Permit installation approved standards.



Other _____

**ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALLATION OF THE CULVERT.**

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00



FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs

Residential Whole Building Performance Method A

Project Name:	Adam's Framing & Construction - Derrosett	Builder:	Adam's Framing & Const.
Address:	Lot: 2B, Sub: Wise Estates, Plat:	Permitting Office:	Columbia County
City/State:	Lake City, FL 32025-	Permit Number:	25673
Owner:	Derrosett Residence	Jurisdiction Number:	221000
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 37.0 kBtu/hr SEER: 11.00
3. Number of units, if multi-family	1	b. N/A	
4. Number of Bedrooms	3	c. N/A	
5. Is this a worst case?	No		
6. Conditioned floor area (ft²)	1531 ft²	13. Heating systems	
7. Glass type and area: (Label reqd. by 13-104.4.5 if not default)		a. Electric Heat Pump	Cap: 37.0 kBtu/hr HSPF: 6.80
a. U-factor: Description Area		b. N/A	
(or Single or Double DEFAULT) 7a(Sngle Default) 191.0 ft²		c. N/A	
b. HGC:		14. Hot water systems	
(or Clear or Tint DEFAULT) 7b. (Clear) 191.0 ft²		a. Electric Resistance	Cap: 50.0 gallons EF: 0.90
8. Floor types		b. N/A	
a. Lab-On-Grade Edge Insulation	R=0.0, 210.0(p) ft	c. N/A	
b. N/A			
c. N/A		15. HVAC credits	PT,
9. Wall types		(CF-Ceiling fan, CV-Cross ventilation, HF-Whole house fan, PT-Programmable Thermostat, MZ-C-Multizone cooling, MZ-H-Multizone heating)	
a. Frame, Wood, Exterior	R=13.0, 1189.0 ft²		
b. Frame, Wood, Adjacent	R=13.0, 222.0 ft²		
c. N/A			
d. N/A			
e. N/A			
10. Ceiling types			
a. Under Attic	R=30.0, 1600.0 ft²		
b. N/A			
c. N/A			
11. Ducts(Leak Free)			
a. Sup: Unc. Ret Unc. AH: Garage	Sup. R=6.0, 50.0 ft		
b. N/A			

Glass/Floor Area: 0.12

Total as-built points: 22685

Total base points: 23955

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Justin M. [Signature]

DATE: 3-14-07

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: Spide [Signature]

DATE: 3-20-07

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____

DATE: _____



SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18	Conditioned X BSPM = Points Floor Area			Type/SC	Overhang Ornt	Len	Hgt	Area X	SPM X	SOF = Points	
.18	1531.0	20.04	5522.6	Single, Clear	W	1.5	8.0	6.0	43.84	0.96	252.0
				Single, Clear	N	1.5	8.0	16.0	21.73	0.97	336.3
				Single, Clear	W	1.5	8.0	9.0	43.84	0.96	378.0
				Single, Clear	W	11.5	8.0	40.0	43.84	0.46	799.6
				Single, Clear	W	1.5	8.0	30.0	43.84	0.96	1260.0
				Single, Clear	E	1.5	8.0	60.0	47.92	0.96	2753.1
				Single, Clear	S	1.5	8.0	30.0	40.81	0.92	1130.4
				As-Built Total:						191.0	6909.4
WALL TYPES		Area X BSPM = Points		Type	R-Value		Area X SPM = Points				
Adjacent	222.0	0.70	155.4	Frame, Wood, Exterior	13.0	1189.0	1.50	1783.5			
Exterior	1189.0	1.70	2021.3	Frame, Wood, Adjacent	13.0	222.0	0.60	133.2			
Base Total:		1411.0	2176.7	As-Built Total:		1411.0	1916.7				
DOOR TYPES		Area X BSPM = Points		Type	Area X SPM = Points						
Adjacent	18.0	1.60	28.8	Exterior Insulated			20.0	4.10	82.0		
Exterior	20.0	4.10	82.0	Adjacent Insulated			18.0	1.60	28.8		
Base Total:		38.0	110.8	As-Built Total:		38.0	110.8				
CEILING TYPES		Area X BSPM = Points		Type	R-Value		Area X SPM X SCM = Points				
Under Attic	1531.0	1.73	2648.6	Under Attic	30.0	1600.0	1.73 X 1.00	2768.0			
Base Total:		1531.0	2648.6	As-Built Total:		1600.0	2768.0				
FLOOR TYPES		Area X BSPM = Points		Type	R-Value		Area X SPM = Points				
Slab	210.0(p)	-37.0	-7770.0	Slab-On-Grade Edge Insulation	0.0	210.0(p)	-41.20	-8652.0			
Raised	0.0	0.00	0.0								
Base Total:		-7770.0		As-Built Total:		210.0	-8652.0				
INFILTRATION		Area X BSPM = Points		Area X SPM = Points							
		1531.0	10.21	15631.5			1531.0	10.21	15631.5		

SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

PERMIT #:

BASE				AS-BUILT					
Summer Base Points: 18320.3				Summer As-Built Points:					18684.4
Total Summer Points	X System Multiplier	= Cooling Points		Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points
18320.3	0.4266	7815.4		18684.4	1.00	1.090	0.310	0.950	6003.1

(sys 1: Central Unit 37000 btuh ,SEER/EFF(11.0) Ducts:Unc(S),Unc(R),Gar(AH),R6.0(INS)

18684 1.00 (1.09 x 1.000 x 1.00) 0.310 0.950 6003.1

18684.4 1.00 1.090 0.310 0.950 6003.1

WINTER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

PERMIT #:

BASE				AS-BUILT						
GLA	S TYPES	Conditioned X BWPM = Points		Type/SC	Overhang					
.18		Floor Area			Ornt	Len	Hgt	Area	X WPM	X WOF = Points
.18	1531.1	12.74	3510.9	Single, Clear	W	1.5	8.0	6.0	28.84	1.01 175.0
				Single, Clear	N	1.5	8.0	16.0	33.22	1.00 532.0
				Single, Clear	W	1.5	8.0	9.0	28.84	1.01 262.4
				Single, Clear	W	11.5	8.0	40.0	28.84	1.20 1385.3
				Single, Clear	W	1.5	8.0	30.0	28.84	1.01 874.8
				Single, Clear	E	1.5	8.0	60.0	26.41	1.02 1616.0
				Single, Clear	S	1.5	8.0	30.0	20.24	1.04 632.1
As-Built Total:							191.0	5477.6		
WALL TYPES	Area X BWPM = Points		Type	R-Value	Area X WPM = Points					
Adjacent	222.0	3.60 799.2	Frame, Wood, Exterior	13.0	1189.0	3.40 4042.6				
Exterior	1189.0	3.70 4399.3	Frame, Wood, Adjacent	13.0	222.0	3.30 732.6				
Base Total:	1411.0	5198.5	As-Built Total:	1411.0	4775.2					
DOOR TYPES	Area X BWPM = Points		Type	Area X WPM = Points						
Adjacent	18.0	8.00 144.0	Exterior Insulated	20.0	8.40 168.0					
Exterior	20.0	8.40 168.0	Adjacent Insulated	18.0	8.00 144.0					
Base Total:	38.0	312.0	As-Built Total:	38.0	312.0					
CEILING TYPES	Area X BWPM = Points		Type	R-Value	Area X WPM X WCM = Points					
Under Attic	1531.0	2.05 3138.6	Under Attic	30.0	1600.0	2.05 X 1.00 3280.0				
Base Total:	1531.0	3138.6	As-Built Total:	1600.0	3280.0					
FLOOR TYPES	Area X BWPM = Points		Type	R-Value	Area X WPM = Points					
Slab	210.0(p)	8.9 1869.0	Slab-On-Grade Edge Insulation	0.0	210.0(p)	18.80 3948.0				
Raised	0.0	0.00 0.0								
Base Total:	1869.0	As-Built Total:	210.0	3948.0						
INFILTRATION	Area X BWPM = Points		Area X WPM = Points							
	1531.0	-0.59 -903.3	1531.0	-0.59 -903.3						

WINTER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

PERMIT #:

BASE				AS-BUILT									
Winter Base Points:			13125.6	Winter As-Built Points:						16889.5			
Total Winter Points	X	System Multiplier	= Heating Points	Total Component (System - Points)	X	Cap Ratio (DM x DSM x AHU)	X	Duct Multiplier	X	System Multiplier	X	Credit Multiplier	= Heating Points
13125.6		0.6274	8235.0	(sys 1: Electric Heat Pump 37000 btuh ,EFF(6.8) Ducts:Unc(S),Unc(R),Gar(AH),R6.0 16889.5 1.000 (1.069 x 1.000 x 1.00) 0.501 0.950 8601.3									
13125.6		0.6274	8235.0	16889.5	1.00	1.069		0.501		0.950		8601.3	

WATER HEATING & CODE COMPLIANCE STATUS**Residential Whole Building Performance Method A - Details**

ADDRESS: Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

PERMIT #:

BASE				AS-BUILT					
WATER HEATING									
Number of Bedrooms	X	Multiplier	= Total	Tank Volume	EF	Number of Bedrooms	X Tank X Ratio	Multiplier X	Credit = Total Multiplier
3		2635.00	7905.0	50.0	0.90	3	1.00	2693.56	1.00 8080.7
				As-Built Total:					8080.7

CODE COMPLIANCE STATUS							
BASE				AS-BUILT			
Cooling Points	+	Heating Points	+ Hot Water Points = Total Points	Cooling Points	+	Heating Points	+ Hot Water Points = Total Points
7115		8235	7905 23955	6003		8601	8081 22685

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

PERMIT #:

6A-1 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-2 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Showers	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

Tested sealed ducts must be certified in this house.

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 84.3

The higher the score, the more efficient the home.

Derrosett Residence, Lot: 2B, Sub: Wise Estates, Plat: , Lake City, FL, 32025-

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 37.0 kBtu/hr
3. Number of units if multi-family	1		SEER: 11.00
4. Number of Bedrooms	3	b. N/A	
5. Is this a worst case?	No	c. N/A	
6. Conditioned floor area (ft ²)	1531 ft ²		
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		13. Heating systems	
a. Factor:	Description Area	a. Electric Heat Pump	Cap: 37.0 kBtu/hr
or Single or Double (DEFAULT) 7a(Sngle Default)	191.0 ft ²		HSPF: 6.80
b. IGC:		b. N/A	
or Clear or Tint (DEFAULT) 7b. (Clear)	191.0 ft ²	c. N/A	
8. Door types		14. Hot water systems	
a. Above-Grade Edge Insulation	R=0.0, 210.0(p) ft	a. Electric Resistance	Cap: 50.0 gallons
b. /A			EF: 0.90
c. /A		b. N/A	
9. Wall types		c. Conservation credits	
a. Frame, Wood, Exterior	R=13.0, 1189.0 ft ²	(HR-Heat recovery, Solar	
b. Frame, Wood, Adjacent	R=13.0, 222.0 ft ²	DHP-Dedicated heat pump)	
c. /A		15. HVAC credits	PT,
d. /A		(CF-Ceiling fan, CV-Cross ventilation,	
e. /A		HF-Whole house fan,	
10. Ceiling types		PT-Programmable Thermostat,	
a. Under Attic	R=30.0, 1600.0 ft ²	MZ-C-Multizone cooling,	
b. /A		MZ-H-Multizone heating)	
c. /A			
11. Ducts(Leak Free)			
a. Type: Unc. Ret: Jnc. AH: Garage	Sup. R=6.0, 50.0 ft		
b. /A			

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



*NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCPB v4.1)

Energy Code Compliance

Duct System Performance Report

Project Name:	Adam's Framing & Construction - Derrosett	Builder:	Adam's Framing & Const.
Address:		Permitting Office:	
City, State:	Lake City, FL 32025-	Permit Number:	
Owner:	Derrosett Residence	Jurisdiction Number:	
Climate Zone:	North		

Total Duct System Leakage Test Results

CFM25 Total Duct Leakage Test Values			
Line	System	Duct Leakage Total	Duct Leakage to Outdoors
1	System1	_____ cfm25(tot)	_____ cfm25(out)
2	System2	_____ cfm25(tot)	_____ cfm25(out)
3	System3	_____ cfm25(tot)	_____ cfm25(out)
4	System4	_____ cfm25(tot)	_____ cfm25(out)
5	Total House Duct System Leakage	Sum lines 1-4 _____ Divide by _____ (Total Conditioned Floor Area) = _____ (Q _{n,tot}) ☐ Receive credit if Q _{n,tot} ≤ 0.03	Sum lines 1-4 _____ Divide by _____ (Total Conditioned Floor Area) = _____ (Q _{n,out}) ☐ Receive credit if Q _{n,out} ≤ 0.03 AND Q _{n,tot} ≤ 0.09

I hereby certify that the above duct testing performance results demonstrate compliance with the Florida Energy Code requirements in accordance with Section 610.1.A.1, Florida Building Code, Building Volume, Chapter 13 for leak free duct system credit.

Signature: _____
 Printed Name: _____
 Florida Rater Certification #: _____
 Date: _____

Florida Building Code requires that testing to confirm leak free duct systems be performed by a Class 1 Florida Energy Gauge Certified Energy Rater. Certified Florida Class 1 raters can be found at:
<http://energygauge.com/search.htm>



BUILDING OFFICIAL: _____
 DATE: _____

Application for Onsite Sewage Disposal System

Construction Permit. Part II Site Plan


Permit Application Number: 123456789 07-249

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

ADAM'S FRAMING/CR 06-3928

No. 1

Lot 2
Wise
States



1 inch = 50 feet

Site Plan Submitted By Paul L. [Signature] Date 3/21/07

Plan Approved [Signature] Not Approved [Signature] Date 3/21/07

By [Signature] Columbia PHU

Notes: _____

0703-53

Permit Number:
Tax Folio Number:
State of: Florida
County of: Columbia
File Number: 07-0106



STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY, that the above and foregoing
is a true copy of the original filed in this office.
P. DOMIT CASON, CLERK OF COURTS
By: P. Domit Cason
Date: 3-20-07

Inst: 2007000396 Date: 03/20/2007 Time: 13:06
P. Domit Cason, Columbia County B: 1114 P: 55

NOTICE OF COMMENCEMENT

The undersigned hereby gives notice that improvement will be made to certain real property, and, in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.


1. Description of Property:
Lot 2, Block B, of Wise Estates, a subdivision according to the plat thereof as recorded in Plat Book 7, Pa 164-167, of the Public Records of Columbia County, Florida.
2. General Description of Improvements: Construction of Single Family Residence
3. Owner Information:
 - a. Name and Address: Adam's Framing and Construction LLC, P.O. Box 1921, Lake City, Florida 32016
 - b. Interest in property: Fee Simple
 - c. Name and address of fee simple title holder (if other than owner):
4. Contractor: Adam's Framing & Construction LLC, PO Box 1921, Lake City, FL 32056
5. Surety:
6. Lender: First Federal Savings Bank of Florida, 2571 West US Highway 90, Lake City, Florida 32025
7. Persons within the State of Florida designated by Owner upon whom notices or other documents may be served as provided by Section 713.13(1)(a)7, Florida Statutes.
8. In addition to himself, Owner designates the following persons to receive a copy of the Lender's Notice as provided in Section 713.13(1)(b), Florida Statutes.
9. Expiration date of Notice of Commencement (the expiration date is 1 year from date of recording unless a different date is specified):

Adam's Framing and Construction LLC, a
Florida Limited Liability Company

Adam Papka, Managing Member

Sworn to and subscribed before me March 19, 2007 by Adam Papka, Managing Member of Adam's Framing and Construction LLC, a Florida Limited Liability Company who is personally known to me or who did provide A. Papka as identification.

[Signature]
Notary Public
My Commission Expires: _____



Letter of authorization

Notice of Authorization


I Adam Papka, do hereby authorize Linda or Melanie Roder

to be my representative and act on my behalf in all aspects of applying for a septic

building permit to be located in Columbia county.


The name of the home owner is 24-45-16-03113-122.

Legal description Lot 2 Block B


Contractor's signature

3-19-07
Date

Sworn and subscribed before me this 19 day of March, 2007.


Notary Public

My commission expires: _____

Commission No. _____

Personally Known ☒ _____

Produced ID (type): _____



Linda R. Roder
Commission #DD303275
Expires: Mar 24, 2008
Bonded Thru
Atlantic Bonding Co., Inc.

Corporate Warranty Deed

Inst:2007006394 Date:03/20/2007 Time:13:08

Doc Stamp-Deed : 300.30

DC, P. DeWitt Cason, Columbia County B:1114 1:247

This Indenture, made this 19th day of March, 2007 A.D.

Between

MARTIN HOME BUILDERS, INC., whose post office address is: PO Box 1831, Lake City, FL 32056, a Florida Corporation existing under the laws of the State of Florida, Grantor and Adam's Framing and Construction LLC, a Florida Limited Liability Company whose post office address is: PO Box 1921, Lake City, FL 32056, Grantee,

STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY, that the above and foregoing is a true copy of the original filed in this office.
P. DeWITT CASON, CLERK OF COURTS.

By P. DeWitt Cason
Date 3-20-07

(Whenever used herein the term "grantor" and "grantee" include all the parties to this instrument and the heirs, legal representatives and assigns of individuals, and the successors and assigns of corporations)

Witnesseth, that the grantor, for and in consideration of the sum of TEN AND NO/100 DOLLARS (\$10.00) and other valuable considerations, receipt whereof is hereby acknowledged, hereby grants, bargains, sells, alien, remises, releases, conveys and confirms unto the grantee, all that certain land situate in Columbia County, Florida, viz:

Lot 2, Block B of WISE ESTATES, a subdivision according to the plat thereof as recorded in Plat Book 7, Pages 164 through 167, of the Public Records of Columbia County, Florida.

The above described property does not constitute the homestead property of the grantor described herein.

Subject to taxes for the current year, covenants, restrictions and easements of record, if any.

And the grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land; that the grantor hereby fully warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances, except taxes accruing subsequent to December 31, 2006.

And the said Grantor does hereby fully warrant the title to said land, and will defend the same against the lawful claims of all persons whomsoever.

In Witness Whereof, the said Grantor has caused this instrument to be executed in its name by its duly authorized officer and caused its corporate seal to be affixed the day and year first above written.

MARTIN HOME BUILDERS,
INC., a Florida corporation

By: Bennett G. Martin
Bennett G. Martin
Its: President

Signed and Sealed in Our Presence:

Witness Printed Name: Matthew D. Rocco

Witness Printed Name: Robert S. Stewart

State of Florida
County of Columbia

The foregoing instrument was acknowledged before me this 19th day of March, 2007, by Bennett G. Martin, President of MARTIN HOME BUILDERS, INC., a Corporation existing under the laws of the State of Florida, on behalf of the corporation.

He is personally known to me or has produced A Drivers License as identification.


Notary Public

Notary Printed Name: _____

My Commission Expires: _____

#07-0100

Prepared by & Return to:
Matthew D. Rocco
Sierra Title, LLC,
619 SW Baya Drive, Suite 102
Lake City, Florida 32025



Permit Number:

Tax Folio Number:

State of: Florida
County of: Columbia

File Number: 07-0100



STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY that the above and foregoing
is a true copy of the original filed in this office.
P. DEWITT CASON, CLERK OF COURTS

By: P. Dewitt Cason
Date: 3-20-07

Inst: 2007006395 Date: 03/20/2007 Time: 13:08

DC, P. Dewitt Cason, Columbia County B: 1114 P: 55

NOTICE OF COMMENCEMENT

The undersigned hereby gives notice that improvement will be made to certain real property, and, in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.


1. Description of Property:
Lot 2, Block B, of Wise Estates, a subdivision according to the plat thereof as recorded in Plat Book 7, Page 164-167, of the Public Records of Columbia County, Florida.
2. General Description of Improvements: Construction of Single Family Residence
3. Owner Information:
 - a. Name and Address: Adam's Framing and Construction LLC, P.O. Box 1921, Lake City, Florida 32016
 - b. Interest in property: Fee Simple
 - c. Names and address of fee simple title holder (if other than owner):
4. Contractor: Adam's Framing & Construction LLC, PO Box 1921, Lake City, FL 32056
5. Surety:
6. Lender: First Federal Savings Bank of Florida, 2571 West US Highway 90, Lake City, Florida 32024
7. Persons within the State of Florida designated by Owner upon whom notices or other documents may be served as provided by Section 713.13(1)(a)7., Florida Statutes.
8. In addition to himself, Owner designates the following persons to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes.
9. Expiration date of Notice of Commencement (the expiration date is 1 year from date of recording unless a different date is specified):


Adam's Framing and Construction LLC, a
Florida Limited Liability Company

By: [Signature]
Adam Papka, Managing Member

Sworn to and subscribed before me March 19, 2007 by Adam Papka, Managing Member of Adam's Framing and Construction LLC, a Florida Limited Liability Company who is personally known to me or who did provide A. Papka License as identification.

Notary Public
My Commission Expires: _____





FROM :

FAX NO. : 386-755-7022

Sep. 17 2002 01:53PM P1

HALL'S PUMP & WELL SERVICE, INC.

SPECIALIZING IN 4"-6" WELLS



DONALD AND MARY HALL
OWNERS

PHONE 904 755-1824
FAX (813) 755-7022
LAKE CITY, FLORIDA 32056
904 NW Main Blvd


June 12, 2002

NOTICE TO ALL CONTRACTORS

Please be advised that due to the new building codes we will use a large capacity diaphragm tank on all new wells. This will insure a minimum of one (1) minute draw down or one (1) minute refill. If a smaller diaphragm tank is used then we will install a cycle stop valve which will produce the same results.

If you have any questions please feel free to call our office anytime.

Thank you,


Donald D. Hall
DDH/jk

☒ ☐
☒ ☐
☒ ☐

☐ ☐

☐ ☐

☒ ☐

☒ ☐

☒ ☐

☒ ☐

☒ ☐

☐ ☐

☐ ☐

Floor Plan including:

- a) Rooms labeled and dimensioned
- b) Shear walls
- c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown)
- d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth
- e) Stairs with dimensions (width, tread and riser) and details of guardrails and handrails
- f) Must show and identify accessibility requirements (accessable bathroom)

Foundation Plan including:

- a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling
- d) Location of any vertical steel

Roof System:

- a) Truss package including:
 - 1. Truss layout and truss details signed and sealed by Fl. Pro. Eng.
 - 2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- b) Conventional Framing Layout including:
 - 1. Rafter size, species and spacing
 - 2. Attachment to wall and uplift
 - 3. Ridge beam sized and valley framing and support details
 - 4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections including:

- a) Masonry wall
 - 1. All materials making up wall
 - 2. Block size and mortar type with size and spacing of reinforcement
 - 3. Lintel, tie-beam sizes and reinforcement
 - 4. Gable ends with rake beams showing reinforcement or gable truss and wall bracing details
 - 5. All required connectors with uplift rating and required number and size of fasteners for continuous tie from roof to foundation
 - 6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with resistance rating)
 - 7. Fire resistant construction (if required)
 - 8. Fireproofing requirements
 - 9. Shoe type of termite treatment (termicide or alternative method)
 - 10. Slab on grade
 - a. Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
 - 11. Indicate where pressure treated wood will be placed
 - 12. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☒☐**b) Wood frame wall**

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
 - a. Vapor retarder (6Mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☐☐**c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)****Floor Framing System:**

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout**Electrical layout including:**

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment

HVAC information

- a) Manual J sizing equipment or equivalent computation
- b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)**Gas System Type (LP or Natural) Location and BTU demand of equipment****Disclosure Statement for Owner Builders****Notice Of Commencement****Private Potable Water**

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

☒☐☒☐☒☐☒☐☒☐☒☐☒☐☒☐☒☐☒☐☒☐

Florida Building Code Online



The Florida Building Code Information System

FLORIDA BUILDING CODE

Overview User Registration Organization Approval Search Organization Activation

Select the organization type, status, or name to find an organization

Organization Type: Product Manufacturer



Manufact.
Buildings

Approval Status: (All)

Organization Name: General American Door - Product Manufacturer

Cancel

Search

Result List for Organizations

Displaying 1-1 of 1

Name	City	Contact	Phone	Type	Expire	Status
General American Door	Montgomery	James Campbell	6308591000	Product Manufacturer	01/01/2009	Approved

Org Code: PDM System ID: 3585

Site Link: www.gadco.com


Displaying 1-1 of 1

http://www.floridabuilding.org/Common/c_org_reg_SRCH.asp

REV. DATE BY DESCRIPTION
A-11-10-00 000 SET ELEM. 001

NOTES:


1. TESTED IN POSITIVE AND NEGATIVE 20 PSF WIND, AND POSITIVE AND NEGATIVE 30 PSF TEST PRESSURES PER ASTM E-330
2. MAXIMUM SECTION HEIGHT = 21'
3. SECTION HEIGHTS OF 21.0' AND 19.5' ARE AVAILABLE AND MAY BE USED IN ANY COMBINATION TO ACHIEVE VARIOUS RISE HEIGHTS.
4. WINDOWS MAY BE INSTALLED IN THE TOP SECTION, OR IN THE SECTION IMMEDIATELY BELOW THE TOP SECTION.
5. MODIUM LENGTH OF ROLLER STEM IS 54" OR AS TESTED
6. THE STRUT PLACEMENT ON DOOR MUST BE CONSISTENT WITH THE DOOR SCHEDULE
7. STRUTS SECURED AT ALL LOCATIONS WITH TIE SCREWS.
8. QUANTITY OF SIDE LOCKS CAN BE 0, 1, OR 2 AS TESTED.
9. DROP IN TYPE OF INSULATION IS OPTIONAL.



INSIDE ELEVATION

TEST REPORTS ON FILE VIDEO 10/19/00 0002933

DESIGN LOAD +200 PSF & -200 PSF
TEST LOAD +300 PSF & -300 PSF



GABCO DOORS					
SERIES 7480, EXTERIOR STEEL - 0.07 MIN G.S. TESTED					
SERIES 7485, EXTERIOR STEEL - 0.07" MIN G.S. TESTED					
SERIES 7524, EXTERIOR STEEL - 0.024" MIN G.S. TESTED WITH WINDOWS					
MAXIMUM DOOR WIDTH	MAXIMUM DOOR HEIGHT	TYPICAL CTR. STILE SPACING	STRUTS 60 KSI GRT.	VERTICAL TRACK	
16'	7'	23"	3"	5	2 IN.

	
GENERAL AMERICAN DOOR COMPANY	
5050 BASELINE ROAD	
MONTGOMERY, IL 60538	
SCALE: 1/2" = 1'-0"	APPROVED BY: _____
DRAWN BY: J. WILKINSON	DATE: 10-20-80
REVISED: (CA) 11-10-80	REASON: 15' X 7' MAX. RAISED PANEL STEEL DOOR - 1/4" MIN. LIFT 320 PSF
PAGE 1 OF 2	
DRAWING NUMBER: V13220-1	




FEDERAL AMERICAN DOOR COMPANY
5050 BASELINE ROAD
MIDLAND, TX 79701

SCALE: 1/8" = 1'-0"

APPROVED BY

DESIGNED BY: A. VETTER

DATE: 10-20-00
REVISION: (A) 11-10-00
15' X 7' MAX. RAISED PANEL STEEL DOOR - WINDLOAD ±20 PSF
TEST NUMBER: V13220-1



2x6 JAMB TO SUPPORTING STRUCTURE ATTACHMENT

2x6 PRESSURE TREATED GRADE #2 OR BETTER SOUTHERN PINE)
WOOD JOIST SHALL BE ANCHORED TO BUILDING WOOD FRAME,
GROUTED AND REINFORCED CONCRETE MASONRY UNIT (CMU) WALLS
OR COLUMNS, OR REINFORCED CONCRETE COLUMNS.

NOTES:
1) ALL DOOR OPENING SURROUNDING STRUCTURE TO BE DESIGNED BY REGISTERED ENGINEER OR ARCHITECT WITH DUE CONSIDERATION GIVEN TO INSTALLATIONS USING CENTER "HURRICANE" POSTS.

1) ALL DOOR OPENING SURROUNDING STRUCTURE TO BE DESIGNED BY REGISTERED ENGINEER OR ARCHITECT WITH DUE CONSIDERATION GIVEN TO INSTALLATIONS USING CENTER "HURRICANE" POSTS.

2) ALL DOOR OPENING STRUCTURE AND FASTENERS TO COMPLY WITH ALL APPLICABLE CODES INCLUDING SBCCI "STANDARD FOR HURRICANE RESISTANT RESIDENTIAL CONSTRUCTION" SSTB 10, CURRENT EDITION.

3) ALL FASTENERS TO BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS, INSTRUCTIONS AND RECOMMENDATIONS.

4) WOOD FRAME BUILDINGS STUDS AT EACH SIDE OF DOOR OPENING SHALL BE PROPERLY DESIGNED, CONNECTED, ANCHORED AND SHALL CONSIST OF A MINIMUM OF THREE (3) LAMINATIONS OF 2X6 PRESSURE TREATED SOUTHERN PINE #2 GRADE OR BETTER WALL STUDS CONTINUOUS FROM FOOTING TO DOUBLE TOP PLATE.

5) REINFORCED CHAIR CONCRETE: 206 VOID JAMB SHALL BE ANCHORED TO SOLIDLY GROUTED AND REINFORCED CONCRETE MASONRY UNIT (COW WALLS OR COLUMNS, OR REINFORCED CONCRETE COLUMNS, ANCHOR SPACING AND EMBEDMENT IS BASED ON CONCRETE MASONRY UNITS COMPLYING WITH ASTM C90 WITH A MINIMUM NET AREA COMPRESSIVE STRENGTH OF 2150 PSI GROUT WITH A MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI REINFORCED CONCRETE COLUMNS WITH A MINIMUM COMPRESSIVE STRENGTH OF 2500 PSI.

6) EMBEDMENTS LISTED ARE THE MINIMUM ALLOWABLE EMBEDMENTS.


7) ANCHORS FOR CONCRETE AND CONCRETE MASONRY UNITS SHALL HAVE A MINIMUM 3" EDGE DISTANCE FROM ALL EDGES OF CONCRETE OR CONCRETE MASONRY UNITS. ANCHORS FOR CONCRETE AND CMU SHALL HAVE A MINIMUM SPACING OF 3'-3/4"

8) LAG SCREWS SHALL BE CENTERED IN ONE OF THE 1-1/2" DIMENSION FACES OF THE TRIPLE 2X6 WALL STUDS.

9) WASHERS ARE REQUIRED ON ALL FASTENERS.

10) THE WIND LOAD VS. ANCHOR SPACING CHART IS FOR A MAXIMUM DOOR SIZE OF 18' X 8' AT A MAXIMUM 42 PSF DESIGN WIND LOAD.

11) FOR THE UPPER THREE INDIVIDUAL STEEL JAMB BRACKETS, BRACKETS SHALL BE CENTERED BETWEEN THE TWO CLOSEST 2X6 WOOD JAMB ANCHORS. IF THE STEEL JAMB BRACKET IS NOT CENTERED BETWEEN THE TWO CLOSEST 2X6 WOOD JAMB ANCHORS, ADD AN ADDITIONAL 2X6 WOOD JAMB ANCHOR NEAR THAT STEEL BRACKET TO INSURE THAT THE LEAD FROM THE STEEL BRACKET IS EQUALLY TRANSFERRED TO TWO WOOD JAMB ANCHORS.




DESIGN (1 PCS) X GARAGE DOOR AREA(WIDTH-FT X HEIGHT-FT) = WIND LOAD(LBS)

EXAMPLE

30 LBS X 16 FT WIDE X 8 FT HIGH = 3840 LBS

- (21) USE 22" SPACING
 (22) USE 21" SPACING
 (23) USE 19" SPACING
 (24) USE 16" SPACING
 (25) USE 10" SPACING
 SEE NOTE 11 FOR ADDITIONAL INFORMATION

SEE NOTE 11 FOR ADDITIONAL
REQUIRED 2X6 VEEB JAMB ANCHORS



GENERAL AMERICAN DIET COMPANY

5050 BASELINE ROAD
MONTGOMERY, IL 60538

NUMBER OF	ISSUED IN	BY
-----------	-----------	----

QUESTIONS

EXHIBIT 100-1

STRUCTURE ATTACHMENT
AND LOADED GARAGE DOORS

ROBERTO TRIVIA	ALBERTO DELA TORRE
----------------	--------------------

AL0560

Window

FLORIDA DEPARTMENT OF Community Affairs



- COMMUNITY PLANNING
- HOUSING & COMMUNITY DEVELOPMENT
- EMERGENCY MANAGEMENT
- OFFICE OF THE SECRETARY

BCIS Home | Log In | Hot Topics | Submit Surcharge | Stats & Facts | Publications | FBC Staff | BCIS Site Map | Links | Search



Product Approval
USER: Public User

[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > [Application Detail](#)

FL # FL5108
Application Type New
Code Version 2004
Application Status Approved
Comments
Archived ☐

Product Manufacturer MI Windows and Doors
Address/Phone/Email 650 W Market St
Gatz, PA 17030
(717) 365-3300 ext 2101
surich@miwd.com

Authorized Signature Steven Ulrich
surich@miwd.com

Technical Representative
Address/Phone/Email

Quality Assurance Representative
Address/Phone/Email



DCA HOME ABOUT DCA DCA PROGRAMS CONTACT DCA



(Validator / Operations Administrator)

AAMA CERTIFICATION PROGRAM



AUTHORIZATION FOR PRODUCT CERTIFICATION

MI Windows & Doors, Inc.
P.O. Box 370
Gratz, PA 17030-0370

Attn: Bill Emley

The product described below is hereby approved for listing in the next issue of the AAMA Certified Products Directory. The approval is based on successful completion of tests, and the reporting to the Administrator of the results of tests, accompanied by related drawings, by an AAMA Accredited Laboratory.

- The listing below will be added to the next published AAMA Certified Products Directory.

SPECIFICATION	RECORD OF PRODUCT TESTED				LABEL ORDER NO.
AAMA/NWDA 101/L.S. 2-97 H-RSS-36-62					
COMPANY AND PLANT LOCATION	CODE NO.	SERIES MODEL & PRODUCT DESCRIPTION	MAXIMUM SIZE TESTED		
MI Windows & Doors, Inc. (Oldemar, FL) MI Windows & Doors, Inc. (Smyrna, TN)	MTL-8 MTL-9	183/3165 SH (Fin) (AL)(OP)(OG) (ASTM)	<u>FRAME</u> 20' x 52'	<u>SASH</u> 2'10" x 27'	By Request

- This Certification will expire May 14, 2008 and requires validation until then by continued listing in the current AAMA Certified Products Directory.
- Product Tested and Reported by: Architectural Testing, Inc.

Report No.: 01-50360.02

Date of Report: June 14, 2004

NOTE: PLEASE REVIEW,
AND ADVISE AIA IMMEDIATELY
IF DATA, AS SHOWN, NEEDS
CORRECTION.

Date: August 1, 2005

cc: AAMA
JGS/dt
ACP-04 (Rev. 5/03)


Validated for Certification:

Associated Laboratories, Inc.

Authorized for Certification:


American Architectural Manufacturers Association

Concrete header (shown) or steel lintel By Others



1. Before installation, caulk back of flange, or face of buck.
2. 3/16" dia. masonry Topcon must be of a length to have 1 1/4" embedment into masonry or concrete.
3. Shim as required with load bearing shims at each installation anchor as shown.
4. All factory applied holes not designated for Topcon anchor should be filled with #10 screws of sufficient length to provide min. 5/8" embedment into wood buck.
5. Letter designations on the Topcon location chart indicate where anchors are to be installed using the elevation as a key.
6. If exact window size is not given, use anchor quantity for next larger window in chart.
7. For continuous head and sill limbs & triple, use the same fastener schedule for each unit in the main frame except ignore the intermediate joints.

ONE BY (3/4) BUCKS (SHOWN)



*TAPCON TYPE HARDENED MASONRY SCREENS INCLUDE TAPCON, RAIL, & SIMPSON

TWO BY (1 1/2) BUCKS

TWO BY buck are engineered and fastened to the masonry opening BY OTHERS.

Follow the same instructions and fastener requirements for one by buck except use #10 screws of sufficient length for 1 1/4" minimum embedment into buck.

* TAPCON LOCATION CHART

DOSE SIZE	WINDOW ID	UP TO D935	D935.1 TO D956	D956.1 TO D983.3
12	18 1/8 x 25 3/8	A D E	A D E	A D E
13	18 1/8 x 37 3/8	A D E	A D E	A D E
14	18 1/8 x 49 5/8	A D E	A D E	A D E
15	18 1/8 x 61 7/8	A D E	A D E	A D E
16	18 1/8 x 73 7/8	A D E	A D E	A D E
17	18 1/8 x 85 7/8	A D E	A D E	A D E
18	25 1/2 x 25 3/8	A D E	A D E	A D E
19	25 1/2 x 37 3/8	A D E	A D E	A D E
20	25 1/2 x 49 5/8	A D E	A D E	A D E
21	25 1/2 x 61 7/8	A D E	A D E	A D E
22	25 1/2 x 73 7/8	A D E	A D E	A D E
23	36 x 25 3/8	A D E	A D E	A D E
24	36 x 37 3/8	A D E	A D E	A D E
25	36 x 49 5/8	A D E	A D E	A D E
26	36 x 61 7/8	A D E	A D E	A D E
27	36 x 73 7/8	A D E	A D E	A D E
28	48 x 25 3/8	A D E	A D E	A D E
29	48 x 37 3/8	A D E	A D E	A D E
30	48 x 49 5/8	A D E	A D E	A D E
31	48 x 61 7/8	A D E	A D E	A D E
32	48 x 73 7/8	A D E	A D E	A D E
33	60 x 25 3/8	A D E	A D E	A D E
34	60 x 37 3/8	A D E	A D E	A D E
35	60 x 49 5/8	A D E	A D E	A D E
36	60 x 61 7/8	A D E	A D E	A D E
37	60 x 73 7/8	A D E	A D E	A D E
38	72 x 25 3/8	A D E	A D E	A D E
39	72 x 37 3/8	A D E	A D E	A D E
40	72 x 49 5/8	A D E	A D E	A D E
41	72 x 61 7/8	A D E	A D E	A D E
42	72 x 73 7/8	A D E	A D E	A D E
43	84 x 25 3/8	A D E	A D E	A D E
44	84 x 37 3/8	A D E	A D E	A D E
45	84 x 49 5/8	A D E	A D E	A D E
46	84 x 61 7/8	A D E	A D E	A D E
47	84 x 73 7/8	A D E	A D E	A D E
48	96 x 25 3/8	A D E	A D E	A D E
49	96 x 37 3/8	A D E	A D E	A D E
50	96 x 49 5/8	A D E	A D E	A D E
51	96 x 61 7/8	A D E	A D E	A D E
52	96 x 73 7/8	A D E	A D E	A D E
53	108 x 25 3/8	A D E	A D E	A D E
54	108 x 37 3/8	A D E	A D E	A D E
55	108 x 49 5/8	A D E	A D E	A D E
56	108 x 61 7/8	A D E	A D E	A D E
57	108 x 73 7/8	A D E	A D E	A D E

MI HOME PRODUCTS
GRATZ, PA


185/3185 SINGLE HUNG FRAME
INSTALLATION DETAILS & FASTENER SCHEDULE

ITE
Product Technology Department
Phone: 412-233-3333 Fax: 412-233-3333

DATE: 08/15/04
REV: 001
N.T.S.
SHEET 1 OF 1

XX**Glazed Outswing Unit**

COP WL JH162-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:**

Double Door
Maximum unit size = 6'0" x 6'0"

Design Pressure
+40.5/-40.5

Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

Note:

Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'6".

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed -- see MAD-WL-MA0012-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed -- see MID-WL-MA0002-02.

APPROVED DOOR STYLES:**1/4 GLASS:**

100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:

105 Series*



106, 160 Series*



120 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems

March 29, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.


PREMIERE Collection
Premium Quality Doors




Exclusively from

Masonite
Masonite International Corporation

GLASS INSERT IN DOOR OR SIDELITE PANEL



SECTION A-A TYPICAL RIGID PLASTIC LIP LITE SURROUND



XX

Glazed Outswing Unit

COP-WL-JH4162-02

WOOD-EDGE STEEL DOORS**APPROVED DOOR STYLES:****3/4 GLASS:**

404 Series




418 Series



450 Series

FULL GLASS:

100 Series

114, 120, 122
Series

152 Series



140 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1864-5, 6, 7, 8; NCTL 210-2178-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum bumper threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533

Johnson
EntrySystems

March 28, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.

PREMIER
Premium Quality Doors



Exclusively from


Masonite
Masonite International Corporation

XX
Unit


IPAD WL-MA0012-02

OUTSWING UNITS WITH DOUBLE DOOR

TYPICAL HINGE ATTACHMENT



TYPICAL ASTRAGAL PROFILES



ALUMINUM EXTRUDED ASTRAGAL (0.05\"/>


TYPICAL HEADER & SIDE JAMB ATTACHMENT

FINGER-JOINTED KILN DRY WOOD
FRAME HEADER (1-1/4\"/>

(3) 2\"/>

FINGER-JOINTED
KILN DRY WOOD
SIDE JAMB
(1-1/4\"/>

TYPICAL THRESHOLD & SIDE JAMB ATTACHMENT



March 29, 2002
Our continuing program of product improvement makes specifications,
design and product detail subject to change without notice.

PREMIER Collection
Premium Quality Doors




Exclusively from

Masonite
Masonite International Corporation

XX
Unit

IND-WL-MA0002-02

DOUBLE DOOR



Minimum Fastener Count

- 6 per vertical framing member
- 3 per horizontal framing member

Hinge and strike plates require two 2-1/2" long screws per location.

Latching Hardware:

- Compliance requires that GRADE 2 or better (ANSI/BHMA A156.2) cylindrical and deadlock hardware be installed.

Notes:

1. Anchor calculations have been carried out with the lowest (least) fastener rating from the different fasteners being considered for use. Fasteners analyzed for this unit include #6 and #10 wood screws or 3/16" Tapcons.
2. The wood screw single shear design values come from Table 11.3A of ANSI/AF & PA NDS for southern pine lumber with a side member thickness of 1-1/4" and achievement of minimum embedment. The 3/16" Tapcon single shear design values come from the ITW and ELCO Dade County approvals respectively, each with minimum 1-1/4" embedment.
3. Wood bucks by others, must be anchored properly to transfer loads to the structure.

March 29, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.

PREMIER Collection
Premium Quality Doors



Exclusively from
Masonite
Masonite International Corporation

Shingle

http://www.floridabuilding.org/pr/pr_app_dtl.aspx?param=wGEVXQwtdqs%2fmGFoyT6..

FLORIDA DEPARTMENT OF Community Affairs



Product Approval
USER: Public User

[BCIS Home](#) | [Log In](#) | [Hot Topics](#) | [Submit Surcharge](#) | [Stats & Facts](#) | [Publications](#) | [FBC Staff](#) | [BCIS Site Map](#) | [Links](#) | [Search](#)

[DCA HOME](#) | [ABOUT DCA](#) | [DCA PROGRAMS](#) | [CONTACT DCA](#)

[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > **[Application Detail](#)**

- ▶ COMMUNITY PLANNING
- ▶ HOUSING & COMMUNITY DEVELOPMENT
- ▶ EMERGENCY MANAGEMENT
- ▶ OFFICE OF THE SECRETARY

FL # FL1956-R1
Application Type Revision
Code Version 2004
Application Status Approved
Comments
Archived ☐

Product Manufacturer
Address/Phone/Email

TAMKO Building Products, Inc.
 PO Box 1404
 Joplin, MO 64802
 (800) 641-4691 ext 2394
 fred_oconnor@tamko.com

Authorized Signature

Frederick O'Connor
 fred_oconnor@tamko.com

Technical Representative
Address/Phone/Email

Frederick J. O'Connor
 PO Box 1404
 Joplin, MO 64802
 (800) 641-4691
 fred_oconnor@tamko.com

Quality Assurance Representative
Address/Phone/Email

Category
Subcategory

Roofing
Asphalt Shingles

Compliance Method

Certification Mark or Listing

Certification Agency

Underwriters Laboratories Inc.

Referenced Standard and Year (of
Standard)

Standard
ASTM D 3462

Year
2001

Equivalence of Product Standards
Certified By

Product Approval Method

Method 1 Option A

Date Submitted
Date Validated
Date Pending FBC Approval
Date Approved

06/09/2005
06/20/2005
06/25/2005
06/29/2005

Summary of Products

FL #	Model, Number or Name	Description

slopes of 2:12 or greater. Not approved for use in HVHZ.

[Back](#)

[Next](#)

DCA Administration

**Department of Community Affairs
Florida Building Code Online
Codes and Standards**

2555 Shumard Oak Boulevard
Tallahassee, Florida 32399-2100
(850) 487-1824, Suncom 277-1824, Fax (850) 414-8436

© 2000-2005 The State of Florida. All rights reserved. Copyright and Disclaimer

Product Approval Accepts:





Underwriters
Laboratories Inc.

June 17, 2005

Tamko Roofing Products
Mr. Kerri Eden
P.O. Box 1404
220 W. 4th Street
Joplin, MO 64802-1404

Our Reference: R2919

This is to confirm that "Elite Glass-Seal AR", "Heritage 30 AR", "Heritage 50 AR", "Glass-Seal AR" manufactured at Tuscaloosa, AL and "Elite Glass-Seal AR", "Heritage 30 AR", "Heritage XL AR", "Heritage 50 AR" manufactured at Frederick, MD and "Heritage 30 AR", "Heritage XL AR", and "Heritage 50 AR" manufactured in Dallas, TX are UL Listed asphalt glass mat shingles and have been evaluated in accordance with ANSI/UL 790, Class A (ASTM E108), ASTM D3462, ASTM D3161 or UL 997 modified to 110 mph when secured with four nails.

Let me know if you have any further questions.

Very truly yours,

Alpesh Patel (Ext. 42522)
Engineer Project
Fire Protection Division

Reviewed by,

Randall K. Laymon (Ext. 42687)
Engineer Sr Staff
Fire Protection Division

Northbrook Station
333 Pringle Road
Northbrook, IL 60062-2006 USA
www.ill.com
tel: 1 847 272 6600

4

4

THESE ARE THE MANUFACTURER'S APPLICATION INSTRUCTIONS FOR THE ROOFING CONDITIONS DESCRIBED. TAMKO BUILD-
 ING PRODUCTS, INC. ASSUMES NO RESPONSIBILITY FOR LEAKS OR OTHER ROOFING DEFECTS RESULTING FROM FAILURE TO
 FOLLOW THE MANUFACTURER'S INSTRUCTIONS.
 THIS PRODUCT IS COVERED BY A LIMITED WARRANTY, THE TERMS OF WHICH ARE PRINTED ON THE WRAPPER.
 IN COLD WEATHER (BELOW 40°F), CARE MUST BE TAKEN TO AVOID DAMAGE TO THE EDGES AND CORNERS OF THE SHINGLES.
 IMPORTANT: It is not necessary to remove the plastic strip from the back of the shingles.

1. ROOF DECK

These shingles are for application to roof decks capable of receiving
 and retaining fasteners, and to inclines of not less than 2 in. per foot.
 For roofs having pitches 2 in. per foot to less than 4 in. per foot, refer
 to special instructions titled "Low Slope Application". Shingles must be
 applied properly. TAMKO assumes no responsibility for leaks or defects
 resulting from improper application, or failure to properly prepare the
 surface to be roofed over.

NEW ROOF DECK CONSTRUCTION: Roof deck must be smooth,
 dry and free from warped surfaces. It is recommended that metal drip
 edges be installed at eaves and rakes.

PLYWOOD: All plywood shall be exterior grade as defined by the
 American Plywood Association. Plywood shall be a minimum of 3/8 in.
 thickness and applied in accordance with the recommendations of the
 American Plywood Association.

SHEATHING BOARDS: Boards shall be well-seasoned tongue-and-
 groove boards and not over 6 in. nominal width. Boards shall be a
 1 in. nominal minimum thickness. Boards shall be properly spaced
 and nailed.

TAMKO does not recommend re-roofing over existing roof.

2. VENTILATION

Inadequate ventilation of attic spaces can cause accumulation of
 moisture in winter months and a build up of heat in the summer. These
 conditions can lead to:

1. Vapor Condensation
2. Buckling of shingles due to deck movement
3. Rotting of wood members
4. Premature failure of roof.

To insure adequate ventilation and circulation of air, place louvers of
 sufficient size high in the gable ends and/or install continuous ridge and
 soffit vents. FHA minimum property standards require one square foot of
 net free ventilation area to each 150 square feet of space to be vented,
 or one square foot per 300 square feet if a vapor barrier is installed on
 the warm side of the ceiling or if at least one half of the ventilation is
 provided near the ridge. If the ventilation openings are screened, the
 total area should be doubled.

IT IS PARTICULARLY IMPORTANT TO PROVIDE ADEQUATE VENTILATION.


3. FASTENERS

WIND CAUTION: Extreme wind velocities can damage these shingles
 after application when proper sealing of the shingles does not occur.
 This can especially be a problem if the shingles are applied in cooler
 months or in areas on the roof that do not receive direct sunlight.
 These conditions may impede the sealing of the adhesive strips on the
 shingles. The inability to seal down may be compounded by prolonged
 cold weather conditions and/or blowing dust. In these situations, hand
 sealing of the shingles is recommended. Shingles must also be fas-
 tened according to the fastening instructions described below.

Correct placement of the fasteners is critical to the performance of the
 shingle. If the fasteners are not placed as shown in the diagram and
 described below, this will result in the termination of TAMKO's liabilities
 under the limited warranty. TAMKO will not be responsible for damage
 to shingles caused by winds in excess of the applicable miles per hour
 as stated in the limited warranty. See limited warranty for details.

FASTENING PATTERNS: Fasteners must be placed 6 in. from the
 top edge of the shingle located horizontally as follows:

1) Standard Fastening Pattern. (For use on decks with slopes 2 in.
 per foot to 21 in. per foot.) One fastener 1-1/2 in. back from each end,
 one 10-3/4 in. back from each end and one 20 in. from one end of
 the shingle for a total of 5 fasteners. (See standard fastening pattern
 illustrated below.)



2) Mansard or Steep Slope Fastening Pattern. (For use on decks
 with slopes greater than 21 in. per foot.) Use standard nailing instruc-
 tions with four additional nails placed 6 in. from the butt edge of the
 shingle making certain nails are covered by the next (successive)
 course of shingles.

(Continued)

Central District
 Northeast District
 Southeast District
 Southwest District
 Western District
 220 West 4th St., Joplin, MO 64801
 4500 Tamko Dr., Frederick, MD 21701
 2300 35th St., Tuscaloosa, AL 35401
 7910 S. Central Exp., Dallas, TX 75216
 5300 East 43rd Ave., Denver, CO 80216
 800-641-4691
 800-368-2055
 800-228-2656
 800-443-1834
 800-530-8868

Visit Our Web Site at
www.tamko.com


(CONTINUED from Pg. 1)

HERITAGE® VINTAGE™ AR - Phillipsburg, KS
LAMINATED ASPHALT SHINGLES




Each shingle tab must be sealed underneath with quick setting asphalt adhesive cement immediately upon installation. Spots of cement must be equivalent in size to a \$.25 piece and applied to shingles with a 5 in. exposure, use 9 fasteners per shingle.

MANSARD FASTENING PATTERN



NAILS. TAMKO recommends the use of nails as the preferred method of application. Standard type roofing nails should be used. Nail shanks should be made of minimum 12 gauge wire, and a minimum head diameter of 3/8 in. Nails should be long enough to penetrate 3/4 in. into the roof deck. Where the deck is less than 3/4 in. thick, the nails should be long enough to penetrate completely through plywood decking and extend at least 1/8 in. through the roof deck. Drive nail head flush with the shingle surface.



4. UNDERLAYMENT

An underlayment consisting of asphalt saturated felt must be applied over the entire deck before the installation of TAMKO shingles. Failure to add underlayment can cause premature failure of the shingles and leaks which are not covered by TAMKO's limited warranty. Apply the felt when the deck is dry. On roof decks 4 in. per foot the felt over the lower course at least 2 in. Where ends join, lap the felt 4 in. If left exposed, the underlayment felt may be adversely affected by moisture and weathering. Laying of the underlayment and the shingle application must be done together.


Products which are acceptable for use as underlayment are:

- TAMKO No. 15 Asphalt Saturated Organic Felt
- A non-petroleum asphalt saturated organic felt which meets ASTM: D226, Type I or ASTM D4869, Type I
- Any TAMKO non-petroleum asphalt saturated organic felt
- TAMKO TW Metal and Tile Underlayment
- TW Underlayment and Moisture Guard Plus® (additional ventilation may be required. Contact TAMKO's technical services department for more information)

In areas where ice builds up along the eaves or a back-up of water from frozen or clogged gutters is a potential problem, TAMKO's Moisture Guard Plus® waterproofing underlayment (or any specialty eaves flash-ing product) may be applied to eaves, rakes, ridges, valleys, around chimneys, skylights or dormers to help prevent water damage. Contact TAMKO's Technical Services Department for more information. TAMKO does not recommend the use of any substitute products as shingle underlayment.

5. APPLICATION INSTRUCTIONS

STARTER COURSE: Two starter course layers must be applied prior to application of Heritage Vintage AR Shingles. The first starter course may consist of TAMKO Shingle Starter, three tab self-sealing type shingles or a 9 inch wide strip of mineral surface roll roofing. If three tab self-sealing shingles are used, remove the exposed tab portion and install with the factory applied adhesive adjacent to the eaves. If using tab self-sealing shingles or shingle starter, remove 18 in. from first shingle to offset the end joints of the Vintage Starter. Attach the first starter course with approved fasteners along a line parallel to and 3 in. to 4 in. above the eave edge. The starter course should overhang both the eave and rake edge 1/4 in. to 3/8 in. Over the first starter course, install Heritage Vintage Starter AR and begin at the left rake edge with a full size shingle and continue across the roof nailing the Heritage Vintage Starter AR along a line parallel to and 6 in. from the eave edge.




HERITAGE VINTAGE STARTER AR
 12 1/2" x 36" 20 PIECES PER BUNDLE
 60 LINEAL FT. PER BUNDLE

(Continued)

Central District
 220 West 4th St., Joplin, MO 64801
 800-641-4691
 Northeast District
 4500 Tamko Dr., Frederick, MD 21701
 800-368-2055
 Southeast District
 2300 35th St., Tuscaloosa, AL 35401
 800-228-2656
 Southwest District
 7910 S. Central Exp., Dallas, TX 75216
 800-443-1834
 Western District
 5300 East 43rd Ave., Denver, CO 80216
 800-530-8868

Visit Our Web Site at
www.tamko.com

SHINGLE APPLICATION: Start the first course at the left rake edge with a full size shingle and overhang the rake edge $1/4$ in. to $3/8$ in. To begin the second course, align the right side of the shingle with the $5-1/2$ in. alignment notch on the first course shingle making sure to align the exposure notch. (See shingle illustration on next page) Cut the appropriate amount from the rake edge so the overhang is $1/4$ to $3/8$ in. For the third course, align the shingle with the $15-1/2$ in. alignment notch at the top of the second course shingle, again being sure to align the exposure notch. Cut the appropriate amount from the rake edge. To begin the fourth course, align the shingle with the $5-1/2$ in. alignment notch from the third course shingle while aligning the exposure notch. Cut the appropriate amount from the rake edge. Continue up the rake in as many rows as necessary using the same formula as outlined above. Cut pieces may be used to complete courses at the right side. As you work across the roof, install full size shingles taking care to align the exposure notches. Shingle joints should be no closer than 4 in.




6. LOW SLOPE APPLICATION

On pitches 2 in. per foot to 4 in. per foot cover the deck with two layers of underlayment. Begin by applying the underlayment in a 19 in. wide strip along the eaves and overhanging the drip edge by $1/4$ to $3/4$ in. Place a full 36 in. wide sheet over the 19 in. wide starter piece, completely overlapping it. All succeeding courses will be positioned to overlap the preceding course by 19 in. If winter temperatures average 25°F or less, thoroughly cement the laps of the entire underlayment to each other with plastic cement from eaves and rakes to a point of at least 24 in. inside the interior wall line of the building. As an alternative, TAMKO's Moisture Guard Plus self-adhering waterproofing underlayment may be used in lieu of the cemented felts.

7. VALLEY APPLICATION

TAMKO recommends an open valley construction with Heritage Vintage AR shingles. To begin, center a sheet of TAMKO Moisture Guard Plus, TW Underlayment or TW Metal & Tile Underlayment in the valley. After the underlayment has been secured, install the recommended corrosion resistant metal (26 gauge galvanized metal or an equivalent) in the valley. Secure the valley metal to the roof deck. Overlaps should be $12"$ and cemented.



- Clip $1"$ from the upper corner of each shingle on a 45° angle to direct water into the valley and prevent it from penetrating between the courses.
- Form a tight seal by cementing the shingle to the valley lining with a $3"$ width of asphalt plastic cement (conforming to ASTM D 4586).

As shingles are applied toward the valley, trim the last shingle in each course to fit on the chalk line. Never use a shingle trimmed to less than $12"$ in length to finish a course running into a valley. If necessary, trim the adjacent shingle in the course to allow a longer portion to be used. Clip $1"$ from the upper corner of each shingle on a 45° angle to direct water into the valley and prevent it from penetrating between the courses.

SHINGLE APPLICATION INSTRUCTIONS (OPEN VALLEY)

- Snap two chalk lines, one on each side of the valley centerline over the full length of the valley flashing. Locate the upper ends of the chalk lines $3"$ to either side of the valley centerline. Thus, for an 8' long valley, the chalk lines should be $7"$ either side of the centerline at the eaves and for a $16'$ valley $6"$.
- The lower end should diverge from each other by $1/8"$ per foot. Thus, for an 8' long valley, the chalk lines should be $7"$ either side of the centerline at the eaves and for a $16'$ valley $6"$.

Following valley metal application, a $9"$ to $12"$ wide strip of TAMKO Moisture Guard Plus, TW Underlayment or TW Metal & Tile Underlayment should be applied along the edges of the metal valley flashing (max. $6"$ onto metal valley flashing) and on top of the valley underlayment. The valley will be completed with shingle application.

• CAUTION:

Adhesive must be applied in smooth, thin, even layers. Excessive use of adhesive will cause blistering to this product. TAMKO assumes no responsibility for blistering.

(Continued)

Visit Our Web Site at
www.tamko.com


Central District
Northeast District
Southeast District
Southwest District
Western District

220 West 4th St., Joplin, MO 64801
4500 Tamko Dr., Frederick, MD 21701
7910 S. Central Exp., Dallas, TX 75216
5300 East 43rd Ave., Denver, CO 80216

800-641-4691
800-368-2055
800-228-2656
800-443-1834
800-530-8688

8. HIP AND RIDGE FASTENING DETAIL

Apply the shingles with a 5 in. exposure beginning at the bottom of the hip or from the end of the ridge opposite the direction of the prevailing winds. Secure each shingle with one fastener on each side, 5-1/2 in. back from the exposed end and 1 in. up from the edge. TAMKO recommends the use of TAMKO Heritage Vintage Hip & Ridge shingle products. Fasteners should be 1/4 in. longer than the ones used for shingles. IMPORTANT: PRIOR TO INSTALLATION, CARE NEEDS TO BE TAKEN TO PREVENT DAMAGE WHICH CAN OCCUR WHILE BENDING SHINGLE IN COLD WEATHER.



THESE ARE THE MANUFACTURER'S APPLICATION INSTRUCTIONS FOR THE ROOFING CONDITIONS DESCRIBED. TAMKO BUILDING PRODUCTS, INC. ASSUMES NO RESPONSIBILITY FOR LEAKS OR OTHER ROOFING DEFECTS RESULTING FROM FAILURE TO FOLLOW THE MANUFACTURER'S INSTRUCTIONS.

TAMKO®, Moisture Guard Plus®, Nail Fast® and Heritage® are registered trademarks and Vintage™ is a trademark of TAMKO Building Products, Inc.

Visit Our Web Site at
www.tamko.com

Central District	220 West 4th St., Joplin, MO 64801	800-641-4691
Northeast District	4500 Tamko Dr., Frederick, MD 21701	800-368-2055
Southeast District	2300 35th St., Tuscaloosa, AL 35401	800-228-2656
Southwest District	7910 S. Central Exp., Dallas, TX 75216	800-443-1834
Western District	5300 East 43rd Ave., Denver, CO 80216	800-530-8868

Residential System Sizing Calculation

Summary

Derrosett Residence

Project Title:
Adam's Framing & Construction - Derrosett

Code Only
Professional Version
Climate: North

Laurel City, FL 32025-


3/14/2007

Location for weather data: Gainesville - Defaults: Latitude(29) Altitude(152 ft.) Temp Range(M)			
Humidity data Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(54gr.)			
Winter design temperature	33 F	Summer design temperature	92 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	37 F	Summer temperature difference	17 F
Total heating load calculation	30943 Btuh	Total cooling load calculation	34825 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	119.6 37000	Sensible (SHR = 0.75)	100.3 27750
Heat Pump + Auxiliary(0.0kW)	119.6 37000	Latent	129.0 9250
		Total (Electric Heat Pump)	106.2 37000

WINTER CALCULATIONS

Winter Heating Load (for 1531 sqft)


Load component		Load	
Window total	191 sqft	8975	Btuh
Wall total	1411 sqft	4634	Btuh
Door total	38 sqft	492	Btuh
Ceiling total	1600 sqft	1885	Btuh
Floor total	210 sqft	9169	Btuh
Infiltration	143 cfm	5788	Btuh
duct loss		0	Btuh
Sensible total		30943	Btuh
Ventilation	0 cfm	0	Btuh
TOTAL HEAT LOSS		30943	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 1531 sqft)

Load component		Load	
Window total	191 sqft	15000	Btuh
Wall total	1411 sqft	2815	Btuh
Door total	38 sqft	372	Btuh
Ceiling total	1600 sqft	2650	Btuh
Floor total		0	Btuh
Infiltration	163 cfm	3039	Btuh
Internal gain		3780	Btuh
duct gain		0	Btuh
Ins. Ventilation	0 cfm	0	Btuh
Total sensible gain		27657	Btuh
latent gain (ducts)		0	Btuh
latent gain (infiltration)		5968	Btuh
latent gain (ventilation)		0	Btuh
latent gain (internal/occupants/other)		1200	Btuh
Total latent gain		7168	Btuh
TOTAL HEAT GAIN		34825	Btuh



For Florida residences only

EnergyGauge® System Sizing

PREPARED BY:

DATE:

John A. Smith
3-14-07

System Sizing Calculations - Winter

Residential Load - Whole House Component Details

Derrosett Residence

Project Title:

Adam's Framing & Construction - Derrosett

Code Only

Professional Version

Climate: North

Lak City, FL 3: 025-

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

3/14/2007

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft)	X	HTM=	Load
1	1, Clear, Metal, 1.27	W	6.0		47.0	282 Btuh
2	1, Clear, Metal, 1.27	N	16.0		47.0	752 Btuh
3	1, Clear, Metal, 1.27	W	9.0		47.0	423 Btuh
4	1, Clear, Metal, 1.27	W	40.0		47.0	1880 Btuh
5	1, Clear, Metal, 1.27	W	30.0		47.0	1410 Btuh
6	1, Clear, Metal, 1.27	E	60.0		47.0	2819 Btuh
7	1, Clear, Metal, 1.27	S	30.0		47.0	1410 Btuh
	Window Total		191(sqft)			8975 Btuh
Walls	Type	R-Value	Area	X	HTM=	Load
1	Frame - Wood - Ext(0.09)	13.0	1189		3.3	3905 Btuh
2	Frame - Wood - Adj(0.09)	13.0	222		3.3	729 Btuh
	Wall Total		1411			4634 Btuh
Doors	Type		Area	X	HTM=	Load
1	Insulated - Adjacent		18		12.9	233 Btuh
2	Insulated - Exterior		20		12.9	259 Btuh
	Door Total		38			492 Btuh
Ceilings	Type/Color/Surface	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shin)	30.0	1600		1.2	1885 Btuh
	Ceiling Total		1600			1885 Btuh
Floors	Type	R-Value	Size	X	HTM=	Load
1	Slab On Grade	0	210.0 ft(p)		43.7	9169 Btuh
	Floor Total		210			9169 Btuh
	Zone Envelope Subtotal:					25155 Btuh
Infiltration	Type	ACH	Zone Volume		CFM=	
	Natural	0.70	12248		142.9	5788 Btuh
Ductload	Proposed leak free, R6.0, Supply(Attic), Return(Attic) (DLM of 0.00)					0 Btuh
Zone #1	Sensible Zone Subtotal					30943 Btuh

	Subtotal Sensible	30943 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	30943 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Derrosett Residence

Project Title:

Adam's Framing & Construction - Derrosett

Code Only

Professional Version

Climate: North

Lake City, FL 32025-

Key Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear (Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)

Key Floor size (perimeter(p) for slab-on-grade or area for all other floor types)

01/1/2027



For Florida residences only

System Sizing Calculations - Winter

Residential Load - Room by Room Component Details

Derrosett Residence

Project Title:
Adam's Framing & Construction - Derrosett

Code Only
Professional Version
Climate: North

Location City, FL 32025-

Reference City Gainesville (Defaults) Winter Temperature Difference: 37.0 F

3/14/2007

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft)	X	HTM=	Load
1	1, Clear, Metal, 1.27	W	6.0		47.0	282 Btuh
2	1, Clear, Metal, 1.27	N	16.0		47.0	752 Btuh
3	1, Clear, Metal, 1.27	W	9.0		47.0	423 Btuh
4	1, Clear, Metal, 1.27	W	40.0		47.0	1880 Btuh
5	1, Clear, Metal, 1.27	W	30.0		47.0	1410 Btuh
6	1, Clear, Metal, 1.27	E	60.0		47.0	2819 Btuh
7	1, Clear, Metal, 1.27	S	30.0		47.0	1410 Btuh
Window Total			191(sqft)			8975 Btuh
Walls	Type	R-Value	Area	X	HTM=	Load
1	Frame - Wood - Ext(0.09)	13.0	1189		3.3	3905 Btuh
2	Frame - Wood - Adj(0.09)	13.0	222		3.3	729 Btuh
Wall Total			1411			4634 Btuh
Doors	Type		Area	X	HTM=	Load
1	Insulated - Adjacent		18		12.9	233 Btuh
2	Insulated - Exterior		20		12.9	259 Btuh
Door Total			38			492 Btuh
Ceilings	Type/Color/Surface	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shin)	30.0	1600		1.2	1885 Btuh
Ceiling Total			1600			1885 Btuh
Floors	Type	R-Value	Size	X	HTM=	Load
1	Slab On Grade	0	210.0	ft(p)	43.7	9169 Btuh
Floor Total			210			9169 Btuh
Zone Envelope Subtotal:						25155 Btuh
Infiltration	Type	ACH	X	Zone Volume	CFM=	Load
	Natural	0.70		12248	142.9	5788 Btuh
Ductload	Proposed leak free, R6.0, Supply(Attic), Return(Attic) (DLM of 0.00)					0 Btuh
Zone #1	Sensible Zone Subtotal					30943 Btuh

Subtotal Sensible		30943 Btuh
Ventilation Sensible		0 Btuh
Total Btuh Loss		30943 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Derrosett Residence

Project Title:

Adam's Framing & Construction - Derrosett

Code Only

Professional Version

Climate: North

Lake City, FL 32025-

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear (Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



For Florida residences only

System Sizing Calculations - Summer

Residential Load - Whole House Component Details

Derrosett Residence

Project Title:

Adam's Framing & Construction - Derrosett

Code Only

Professional Version

Climate: North

Location City, FL : 2025-

Reference City : Gainesville (Defaults)

Summer Temperature Difference: 17.0 F

3/14/2007

Type*												
Window	P	V/SHGC/U/InSh/ExSh/IS	Omt	Overhang		Window Area(sqft)			HTM		Load	
				Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded		
1	1	Clear, 1.27, None,N,N	W	1.5ft	8ft.	6.0	0.0	6.0	37	94	564 Btuh	
2	1	Clear, 1.27, None,N,N	N	1.5ft	8ft.	16.0	0.0	16.0	37	37	599 Btuh	
3	1	Clear, 1.27, None,N,N	W	1.5ft	8ft.	9.0	0.0	9.0	37	94	846 Btuh	
4	1	Clear, 1.27, None,N,N	W	11.5f	8ft.	40.0	40.0	0.0	37	94	1498 Btuh	
5	1	Clear, 1.27, None,N,N	W	1.5ft	8ft.	30.0	0.0	30.0	37	94	2821 Btuh	
6	1	Clear, 1.27, None,N,N	E	1.5ft	8ft.	60.0	0.0	60.0	37	94	5643 Btuh	
7	1	Clear, 1.27, None,N,N	S	1.5ft	8ft.	30.0	30.0	0.0	37	43	1124 Btuh	
Excursion											1904 Btuh	
Window Total						191 (sqft)					15000 Btuh	
Walls				Type		R-Value/U-Value		Area(sqft)		HTM		Load
1				Frame - Wood - Ext		13.0/0.09		1189.0		2.1		2480 Btuh
2				Frame - Wood - Adj		13.0/0.09		222.0		1.5		335 Btuh
				Wall Total				1411 (sqft)				2815 Btuh
Doors				Type				Area (sqft)		HTM		Load
1				Insulated - Adjacent				18.0		9.8		176 Btuh
2				Insulated - Exterior				20.0		9.8		196 Btuh
				Door Total				38 (sqft)				372 Btuh
Ceilings				Type/Color/Surface		R-Value		Area(sqft)		HTM		Load
1				Vented Attic/DarkShingle		30.0		1600.0		1.7		2650 Btuh
				Ceiling Total				1600 (sqft)				2650 Btuh
Floors				Type		R-Value		Size		HTM		Load
1				Slab On Grade		0.0		210 (ft(p))		0.0		0 Btuh
				Floor Total				210.0 (sqft)				0 Btuh
Zone Envelope Subtotal:											20837 Btuh	
Infiltration				Type		ACH		Volume(cuft)		CFM=		Load
				SensibleNatural		0.80		12248		163.3		3039 Btuh
Internal gain						Occupants		Btuh/occupant		Appliance		Load
						6		X 230 +		2400		3780 Btuh
Duct load				Proposed leak free, R6.0, Supply(Attic), Return(Attic)						DGM = 0.00		0.0 Btuh
Sensible Zone Load											27657 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

Derrosett Residence

Project Title:

Code Only

Adam's Framing & Construction - Derrosett

Professional Version

Leesville City, FL 32025-

Climate: North

3/14/2007

Whole House Totals for Cooling	Sensible Envelope Load All Zones	27657 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	27657 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	27657 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	5968 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	7168 Btuh
	TOTAL GAIN	34825 Btuh

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Omt - compass orientation)



For Florida residences only

System Sizing Calculations - Summer

Residential Load - Room by Room Component Details

Derrosett Residence

Project Title:

Adam's Framing & Construction - Derrosett

Code Only

Professional Version

Climate: North

Location City, FL : 2025-

Reference City : Gainesville (Defaults)

Summer Temperature Difference: 17.0 F

3/14/2007

Window	Type*	Omt	Overhang		Window Area(sqft)			HTM		Load
	P /SHGC/U/InSh/ExSh/IS		Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded	
1	1 Clear, 1.27, None,N,N	W	1.5ft	8ft.	6.0	0.0	6.0	37	94	564 Btuh
2	1 Clear, 1.27, None,N,N	N	1.5ft	8ft.	16.0	0.0	16.0	37	37	599 Btuh
3	1 Clear, 1.27, None,N,N	W	1.5ft	8ft.	9.0	0.0	9.0	37	94	846 Btuh
4	1 Clear, 1.27, None,N,N	W	11.5f	8ft.	40.0	40.0	0.0	37	94	1498 Btuh
5	1 Clear, 1.27, None,N,N	W	1.5ft	8ft.	30.0	0.0	30.0	37	94	2821 Btuh
6	1 Clear, 1.27, None,N,N	E	1.5ft	8ft.	60.0	0.0	60.0	37	94	5643 Btuh
7	1 Clear, 1.27, None,N,N	S	1.5ft	8ft.	30.0	30.0	0.0	37	43	1124 Btuh
Excursion										1904 Btuh
Window Total					191 (sqft)					15000 Btuh
Walls	Type	R-Value/U-Value		Area(sqft)		HTM		Load		
1	Frame - Wood - Ext	13.0/0.09		1189.0		2.1		2480 Btuh		
2	Frame - Wood - Adj	13.0/0.09		222.0		1.5		335 Btuh		
Wall Total					1411 (sqft)				2815 Btuh	
Doors	Type			Area (sqft)		HTM		Load		
1	Insulated - Adjacent			18.0		9.8		176 Btuh		
2	Insulated - Exterior			20.0		9.8		196 Btuh		
Door Total					38 (sqft)				372 Btuh	
Ceilings	Type/Color/Surface	R-Value		Area(sqft)		HTM		Load		
1	Vented Attic/DarkShingle	30.0		1600.0		1.7		2650 Btuh		
Ceiling Total					1600 (sqft)				2650 Btuh	
Floors	Type	R-Value		Size		HTM		Load		
1	Slab On Grade	0.0		210 (ft(p))		0.0		0 Btuh		
Floor Total					210.0 (sqft)				0 Btuh	
Zone Envelope Subtotal:									20837 Btuh	
Infiltration	Type	ACH		Volume(cuft)		CFM=		Load		
Sensible/Natural		0.80		12248		163.3		3039 Btuh		
Internal gain	Occupants		Btuh/occupant		Appliance		Load			
		6		X 230 +		2400		3780 Btuh		
Duct load	Proposed leak free, R6.0, Supply(Attic), Return(Attic)							DGM = 0.00		0.0 Btuh
Sensible Zone Load									27657 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

Derrosett Residence

Project Title:

Adam's Framing & Construction - Derrosett

Code Only

Professional Version

Climate: North

Leesville City, FL : 2025-

3/14/2007

Whole House Totals for Cooling	Sensible Envelope Load All Zones	27657 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	27657 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	27657 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	5968 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	7168 Btuh
	TOTAL GAIN	34825 Btuh

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Omt - compass orientation)



For Florida residences only

Residential Window Diversity

MidSummer

Derrosett Residence

Project Title:
Adam's Framing & Construction - Derrosett


Code Only
Professional Version
Climate: North

Latitude City, FL 32025-

3/14/2007

Summer design temperature	92 F	Average window load for July	11446 Btu
Summer setpoint	75 F	Peak window load for July	16784 Btu
Summer temperature difference	17 F	Excursion limit(130% of Ave.)	14880 Btu
Latitude	29 North	Window excursion (July)	1904 Btu

WINDOW Average and Peak Loads



Warning: This application has glass areas that produce relatively large heat gains for part of the day. Variable air volume devices may be required to overcome spikes in solar gain for one or more rooms. A zoned system may be required or some rooms may require zone control.

EnergyGauge® System Sizing for Florida residences only

PREPARED BY: _____

DATE: _____

EnergyGauge® FLRCPB v4.1



Project Information for:		L230379					
Builder:	ADAMS FRAMING	Date:	3/13/2007				
Lot:	LOT 2B LOT 10 WISE ESTATES	Start Number:	1003				
Subdivision:	N/A	SEI Ref:	L230379				
County or City:	COLUMBIA COUNTY						
Truss Page Count:	48						
Truss Design Load Information (UNO)		Design Program: MiTek					
Gravity	Wind	Build					
Roof (psf): 42	Wind Standard: ASCE 7-02						
Floor (psf): 55	Wind Speed (mph): 110						
Note: See individual truss drawings for special loading conditions							
Building Designer, responsible for Structural Engineering: (See attached)							
PAPKA, ADAM R. CBC1253409							
Address: P.O. BOX 1921		Des. 138					
LAKE CITY, FL 32056							
Truss Design Engineer: Thomas, E. Miller, P.E., 56877 - Byron K. Anderson, PE FL 60987							
Company: Structural Engineering and Inspections, Inc. EB 9196							
Address: 16105 N. Florida Ave, Ste B, Lutz, FL 33549		Phone: 813-849-5769					
Notes:							
1. Truss Design Engineer is responsible for the individual trusses as components only.							
2. Determination as to the suitability and use of these truss components for the structure is the responsibility of the Building Designer of Record, as defined in ANSI/TPI							
3. The seal date shown on the individual truss component drawings must match the seal date on this index sheet.							
4. Trusses designed for vertical loads only, unless noted otherwise.							
5. Where hangers are shown, Carried Member hanger capacity per Simpson C-2006 (SYP/Full Nailing Value) as an individual component. Building Designer shall verify the suitability and use of Carrying Member hanger capacity.							
#	Truss ID	Dwg. #	Seal Date	#	Truss ID	Dwg. #	Seal Date
1	CJ1	0313071003	3/13/2007	41	T28	0313071043	3/13/2007
2	CJ3	0313071004	3/13/2007	42	T29	0313071044	3/13/2007
3	CJ5	0313071005	3/13/2007	43	T30	0313071045	3/13/2007
4	EJ2	0313071006	3/13/2007	44	T31	0313071046	3/13/2007
5	EJ3	0313071007	3/13/2007	45	T31G	0313071047	3/13/2007
6	EJ5	0313071008	3/13/2007	46	V5	0313071048	3/13/2007
7	EJ7	0313071009	3/13/2007	47	V7	0313071049	3/13/2007
8	EJ7G	0313071010	3/13/2007	48	V9	0313071050	3/13/2007
9	HJ2	0313071011	3/13/2007				
10	HJ4	0313071012	3/13/2007				
11	HJ7	0313071013	3/13/2007				
12	HJ9	0313071014	3/13/2007				
13	PB01	0313071015	3/13/2007				
14	T01	0313071016	3/13/2007				
15	T02	0313071017	3/13/2007				
16	T03	0313071018	3/13/2007				
17	T04	0313071019	3/13/2007				
18	T05	0313071020	3/13/2007				
19	T06	0313071021	3/13/2007				
20	T07	0313071022	3/13/2007				
21	T08	0313071023	3/13/2007				
22	T09	0313071024	3/13/2007				
23	T10	0313071025	3/13/2007				
24	T11	0313071026	3/13/2007				
25	T12	0313071027	3/13/2007				
26	T13	0313071028	3/13/2007				
27	T14	0313071029	3/13/2007				
28	T15	0313071030	3/13/2007				
29	T16	0313071031	3/13/2007				
30	T17	0313071032	3/13/2007				
31	T18	0313071033	3/13/2007				
32	T19	0313071034	3/13/2007				
33	T20	0313071035	3/13/2007				
34	T21	0313071036	3/13/2007				
35	T22	0313071037	3/13/2007				
36	T23	0313071038	3/13/2007				
37	T24	0313071039	3/13/2007				
38	T25	0313071040	3/13/2007				
39	T26	0313071041	3/13/2007				
40	T27	0313071042	3/13/2007				

WISE ESTATES
 LOT 2B

MAR 13 2007

LATERAL TOE-NAIL DETAIL

ST-TOENAIL

MITek Industries, Chesterfield, MO Page 1 of 1



NOTES:

- TOE-NAILS SHALL BE DRIVEN AT AN ANGLE OF 30 DEGREES WITH THE MEMBER AND STARTED 1/3 THE LENGTH OF THE NAIL FROM THE MEMBER END AS SHOWN.
- THE END DISTANCE, EDGE DISTANCE, AND SPACING OF NAILS SHALL BE SUCH AS TO AVOID UNUSUAL SPLITTING OF THE WOOD.
- ALLOWABLE VALUE SHALL BE THE LESSER VALUE OF THE BOTTOM CHORD SPECIES FOR MEMBERS OF DIFFERENT SPECIES.

TOE-NAIL SINGLE SHEAR VALUES PER NDS 2001 (lb/nail)

	DIAM.	SYP
3.5" LONG	.131	83.3
	.135	89.6
	.162	118.3
3.25" LONG	.128	80.5
	.131	83.3
	.148	102.1
3.0" LONG	.120	70.5
	.128	80.5
	.131	83.3
	.148	102.1


SQUARE CUT



VALUES SHOWN ARE CAPACITY PER TOE-NAIL.
APPLICABLE DURATION OF LOAD INCREASES MAY BE APPLIED.

45 DEGREE ANGLE BEVEL CUT

This detail may only be applied to Pre-engineered truss drawings signed and sealed by Structural Engineering and Inspections Inc.



VIEWS SHOWN ARE FOR ILLUSTRATION PURPOSES ONLY

The seal on this drawing indicates acceptance of professional engineering responsibility solely for the truss component design shown. The suitability and use of this component for any particular building design is the responsibility of the building designer.

MAR 13 2007


[Log On](#)
[DBPR Home](#) | [Online Services Home](#) | [Help](#) | [Site Map](#)

1:16:18 PM 12/6/200

Public Services

[Search for a Licensee](#)
[Apply for a License](#)
[View Application Status](#)
[Apply to Retake Exam](#)
[Find Exam Information](#)
[File a Complaint](#)
[AB&T Delinquent Invoice & Activity List Search](#)

User Services

[Renew a License](#)
[Change License Status](#)
[Maintain Account](#)
[Change My Address](#)
[View Messages](#)
[Change My PIN](#)
[View Continuing Ed](#)

Licensee Details

Licensee Information

Name: PAPKA, ADAM RUSSELL (Primary Name)
ADAM S FRAMING AND CONSTRUCTION LLC (DBA Name)
Main Address: PO BOX 1921
 LAKE CITY Florida 32056
County: COLUMBIA

License Mailing:
License Location:


License Information

License Type: Certified Building Contractor
Rank: Cert Building
License Number: CBC1253409
Status: Current, Active
Licensure Date: 09/26/2005
Expires: 08/31/2008

Special Qualifications	Qualification Effective
Qualified Business License Required	09/26/2005

[View Related License Information](#)
[View License Complaint](#)
[Terms of Use](#) | [Privacy Statement](#)

Job L230379	Truss CJ3	Truss Type JACK	Qty 6	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 09:57:08 2007 Page 1		



Scale = 1:11.6

Plate Offsets (X,Y): [2-0-3-3-0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.17	Vert(LL)	-0.00	2-4	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.05	Vert(TL)	-0.01	2-4	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 12 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=48/Mechanical, 2=233/0-4-0, 4=42/Mechanical
Max Horz 2=135(load case 5)
Max Uplift 3=42(load case 5), 2=-148(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/40, 2-3=-55/18
BOT CHORD 2-4=0/0

JOINT STRESS INDEX


2 = 0.10

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 3 and 148 lb uplift at joint 2.

LOAD CASE(S) Standard

Job L230379	Truss CJ5	Truss Type JACK	Qty 2	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055					Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 09:57:35 2007 Page 1



Scale = 1:16.2

Plate Offsets (X,Y): [2-0-3-3-0-1-8]							
LOADING (psf)	SPACING 2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES
TCLL 20.0	Plates Increase 1.25	TC 0.22	Vert(LL)	-0.03	2-4	>999	MT20
TCDL 7.0	Lumber Increase 1.25	BC 0.16	Vert(TL)	-0.05	2-4	>999	GRIP
BCLL 10.0	Rep Stress Incr YES	WB 0.00	Horz(TL)	-0.00	3	n/a	244/190
BCDL 5.0	Code FBC2004/TPI2002	(Matrix)					Weight: 19 lb

LUMBER TOP CHORD 2 X 4 SYP No.2 BOT CHORD 2 X 4 SYP No.2	BRACING TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
---	---


REACTIONS (lb/size) 3=113/Mechanical, 2=306/0-4-0, 4=72/Mechanical
 Max Horz 2=189(load case 5)
 Max Uplift 3=110(load case 5), 2=149(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-85/46
 BOT CHORD 2-4=0/0

JOINT STRESS INDEX
 2 = 0.12

NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 2) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 3 and 149 lb uplift at joint 2.

LOAD CASE(S) Standard



Job L230379	Truss EJ7	Truss Type MONO TRUSS	Qty 25	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055					Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 11:37:45 2007 Page 1

Scale = 1:20.8

Plate Offsets (X,Y): [2:0-0-11,Edge]					
LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.46	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.37	Vert(LL) -0.13 2-4 >607 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.00	Vert(TL) -0.22 2-4 >366 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) -0.00 3 n/a n/a		
	Code FBC2004/TPI2002			Weight: 25 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=165/Mechanical, 2=385/0-4-0, 4=109/Mechanical
 Max Horz 2=242(load case 5)
 Max Uplift 3=-151(load case 5), 2=-159(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-107/66
 BOT CHORD 2-4=0/0

JOINT STRESS INDEX
 2 = 0.75

NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 2) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 151 lb uplift at joint 3 and 159 lb uplift at joint 2.

LOAD CASE(S) Standard

Job L230379	Truss HJ4	Truss Type JACK	Qty 2	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 11:49:25 2007 Page 1		

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.33	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.07	Vert(LL) 0.02 2-4 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.00	Vert(TL) -0.01 2-4 >999 180		
BCDL 5.0	Rep Stress Incr NO	(Matrix)	Horz(TL) -0.00 3 n/a n/a		
	Code FBC2004/TPI2002			Weight: 17 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-2-15 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=38/Mechanical, 2=231/0-6-7, 4=42/Mechanical
 Max Horz 2=94(load case 4)
 Max Uplift 3=-15(load case 4), 2=-234(load case 4), 4=-41(load case 2)


FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/43, 2-3=-33/7
 BOT CHORD 2-4=0/0


JOINT STRESS INDEX
 2 = 0.09


NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60.
 2) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 15 lb uplift at joint 3, 234 lb uplift at joint 2 and 41 lb uplift at joint 4.
 4) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-2=-54
 Trapezoidal Loads (plf)
 Vert: 2=-4(F=25, B=25)-to-3=-57(F=-2, B=-2), 2=0(F=15, B=15)-to-4=-32(F=-1, B=-1)


MARCH 13, 2007 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549








MARCH 13, 2007 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549





Job L230379	Truss T03	Truss Type COMMON	Qty 2	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:13:41 2007 Page 1		

Plate Offsets (X,Y): [2-0-3-3-0-1-8], [4-0-3-3-0-1-8]	
---	--

LOADING (psf) TCLL 20.0 TCDL 7.0 BCCL 10.0 BCDL 5.0	SPACING 2-0-0 Plates Increase 1.25 Lumber Increase 1.25 Rep Stress Incr YES Code FBC2004/TPI2002	CSI TC 0.38 BC 0.47 WB 0.09 (Matrix)	DEFL in (loc) l/defl L/d Vert(LL) -0.10 4-6 >999 240 Vert(TL) -0.15 4-6 >999 180 Horz(TL) 0.01 4 n/a n/a	PLATES GRIP MT20 244/190 Weight: 59 lb
--	---	---	--	---

LUMBER TOP CHORD 2 X 4 SYP No.2 BOT CHORD 2 X 4 SYP No.2 WEBS 2 X 4 SYP No.3	BRACING TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
--	---


REACTIONS (lb/size) 2=692/0-4-0, 4=692/0-4-0
 Max Horz 2=154(load case 4)
 Max Uplift 2=-291(load case 5), 4=-291(load case 6)


FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-781/236, 3-4=-781/236, 4-5=0/40
 BOT CHORD 2-6=-105/595, 4-6=-105/595
 WEBS 3-6=0/276


JOINT STRESS INDEX
 2 = 0.54, 3 = 0.79, 4 = 0.54 and 6 = 0.20


NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 291 lb uplift at joint 2 and 291 lb uplift at joint 4.

LOAD CASE(S) Standard









Job L230379	Truss T08	Truss Type SPECIAL	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:27:18 2007 Page 1		

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2'-0"-0"	TC 0.83	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.87	Vert(LL) -0.16 7-8 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.69	Vert(TL) -0.26 7-8 >766 180		
BCDL 5.0	Rep Stress Incr NO	(Matrix)	Horz(TL) 0.02 7 n/a n/a		
	Code FBC2004/TPI2002			Weight: 139 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2 *Except*
 B1 2 X 4 SYP No.1D
 WEBS 2 X 4 SYP No.3 *Except*
 W1 2 X 4 SYP No.2, W1 2 X 4 SYP No.2

BRACING
 TOP CHORD Structural wood sheathing directly applied or 5-1-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 3-11

REACTIONS (lb/size) 12=193/Mechanical, 7=1418/Mechanical, 11=2722/0-4-0
 Max Uplift 12=-70(load case 2), 7=-534(load case 2), 11=-1032(load case 2)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-12=-51/202, 1-2=-181/465, 2-3=-181/465, 3-4=-1402/527, 4-5=-1402/527, 5-6=-1402/527, 6-7=-1008/430
 BOT CHORD 11-12=-42/109, 10-11=-379/1011, 9-10=-379/1011, 8-9=-379/1011, 7-8=-48/127
 WEBS 1-11=-685/265, 2-11=-333/237, 3-11=-1885/714, 3-9=-151/606, 3-8=-189/499, 5-8=-315/230, 6-8=-571/1520

JOINT STRESS INDEX
 1 = 0.78, 2 = 0.34, 3 = 0.92, 4 = 0.25, 5 = 0.34, 6 = 0.52, 7 = 0.77, 8 = 0.70, 9 = 0.44, 10 = 0.59, 11 = 0.44 and 12 = 0.78

NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
 2) Provide adequate drainage to prevent water ponding.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 70 lb uplift at joint 12, 534 lb uplift at joint 7 and 1032 lb uplift at joint 11.
 5) Girder carries tie-in span(s): 7-0-0 from 0-0-0 to 23-6-8
 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-6=-54, 7-12=-132(F=-102)

MARCH 13, 2007 TRUSS DESIGN ENGINEER:

 THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
 STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
 16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job L230379	Truss T09	Truss Type SPECIAL	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES Job Reference (optional)
Builders FirstSource, Lake City, FL 32055			6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:29:12 2007 Page 1		

Scale = 1:40.8

LOADING (psf) TCCL 20.0 TCDL 7.0 BCCL 10.0 BCDL 5.0	SPACING 2-0-0 Plates Increase 1.25 Lumber Increase 1.25 Rep Stress Incr YES Code FBC2004/TPI2002	CSI TC 0.61 BC 0.46 WB 0.64 (Matrix)	DEFL in (loc) l/defl L/d Vert(LL) -0.21 8-10 >943 240 Vert(TL) -0.37 8-10 >544 180 Horz(TL) 0.01 7 n/a n/a	PLATES MT20 GRIP 244/190 Weight: 145 lb
--	---	---	--	---

LUMBER TOP CHORD 2 X 4 SYP No.2 BOT CHORD 2 X 4 SYP No.2 WEBS 2 X 4 SYP No.3	BRACING TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS 1 Row at midpt 1-10
--	---

REACTIONS (lb/size) 11=70/Mechanical, 7=632/Mechanical, 10=1251/0-4-0
 Max Uplift 11=-31(load case 3), 7=-240(load case 3), 10=-466(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-11=-4/41, 1-2=-69/159, 2-3=-69/159, 3-4=-513/181, 4-5=-513/181, 5-6=-513/181, 6-7=-563/249
 BOT CHORD 10-11=-15/27, 9-10=-141/299, 8-9=-141/299, 7-8=-17/31
 WEBS 1-10=-242/109, 2-10=-346/242, 3-10=-653/299, 3-8=-58/305, 5-8=-340/240, 6-8=-214/627

JOINT STRESS INDEX
 1 = 0.66, 2 = 0.34, 3 = 0.37, 4 = 0.19, 5 = 0.34, 6 = 0.66, 7 = 0.56, 8 = 0.61, 9 = 0.40, 10 = 0.61 and 11 = 0.56

NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCCL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 2) Provide adequate drainage to prevent water ponding.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 11, 240 lb uplift at joint 7 and 466 lb uplift at joint 10.

LOAD CASE(S) Standard

Job L230379	Truss T10	Truss Type SPECIAL	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:29:59 2007 Page 1		

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.71	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.37	Vert(LL) -0.11 6-7 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.31	Vert(TL) -0.20 6-7 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.01 6 n/a n/a		
	Code FBC2004/TPI2002			Weight: 145 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2 X 4 SYP No.3	WEBS 1 Row at midpt 1-10, 1-9, 3-9


REACTIONS (lb/size) 10=140/Mechanical, 9=1154/0-4-0, 6=659/Mechanical
 Max Horz 10=-247(load case 6)
 Max Uplift 10=-81(load case 4), 9=-392(load case 3), 6=-184(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-10=-54/95, 1-2=-12/65, 2-3=-12/66, 3-4=-561/177, 4-5=-394/113, 5-6=-298/133
 BOT CHORD 9-10=-30/242, 8-9=-49/451, 7-8=-49/451, 6-7=-124/545
 WEBS 1-9=-125/31, 2-9=-420/368, 3-9=-674/266, 3-7=-75/338, 4-7=-129/207, 4-6=-342/121


JOINT STRESS INDEX
 1 = 0.44, 2 = 0.34, 3 = 0.70, 4 = 0.29, 5 = 0.37, 6 = 0.71, 7 = 0.35, 8 = 0.27, 9 = 0.57 and 10 = 0.64


NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 2) Provide adequate drainage to prevent water ponding.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 81 lb uplift at joint 10, 392 lb uplift at joint 9 and 184 lb uplift at joint 6.

LOAD CASE(S) Standard



MARCH 13, 2007 TRUSS DESIGN ENGINEER:
 THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
 STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
 16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549





Job L230379	Truss T14	Truss Type MONO HIP	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:40:12 2007 Page 1		

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.94	Vert(LL)	-0.46 11-13	>904	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-0.74 11-13	>563	180	MT20H	187/143
BCLL 10.0	Rep Stress Incr	NO	WB 0.95	Horz(TL)	0.18 9	n/a	n/a	MT18H	244/190
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						Weight: 211 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2 X 6 SYP No.1D	BOT CHORD Rigid ceiling directly applied or 4-2-7 oc bracing.
WEBS 2 X 4 SYP No.3 *Except*	WEBS 1 Row at midpt 4-14, 6-10, 7-9
W6 2 X 4 SYP No.2	

REACTIONS (lb/size) 9=3196/0-4-0, 2=3071/0-4-0
Max Horz 2=247(load case 4)
Max Uplift 9=-1860(load case 2), 2=-1539(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/43, 2-3=-5443/2850, 3-4=-4687/2539, 4-5=-6673/3735, 5-6=-6613/3738, 6-7=-4479/2532, 7-8=-107/73, 8-9=-320/320
BOT CHORD 2-14=-2501/4607, 13-14=-3674/6442, 12-13=-4006/6903, 11-12=-4006/6903, 10-11=-3526/6021, 9-10=-2245/3808
WEBS 3-14=-1167/2206, 4-14=-2199/1497, 4-13=-190/718, 5-13=-321/379, 5-11=-514/483, 6-11=-385/1052, 6-10=-2158/1391, 7-10=-890/2081, 7-9=-4550/2670

JOINT STRESS INDEX
2 = 0.85, 3 = 0.94, 4 = 0.69, 5 = 0.41, 6 = 0.91, 7 = 0.99, 8 = 0.69, 9 = 0.78, 10 = 0.79, 11 = 0.76, 12 = 0.98, 13 = 0.66 and 14 = 0.61

NOTES
1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
2) Provide adequate drainage to prevent water ponding.
3) All plates are MT20 plates unless otherwise indicated.
4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1860 lb uplift at joint 9 and 1539 lb uplift at joint 2.
6) Girder carries hip end with 0-0-0 right side setback, 7-0-0 left side setback, and 7-0-0 end setback.
7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 539 lb down and 374 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-8=-117(F=63), 2-14=-30, 9-14=-65(F=35)
Concentrated Loads (lb)
Vert: 14=-539(F)

Job L230379	Truss T15	Truss Type MONO HIP	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:40:58 2007 Page 1		

-1-6-0	4-8-13	9-0-0	15-5-2	21-10-4	28-3-6	35-0-0
1-6-0	4-8-13	4-3-3	6-5-2	6-5-2	6-5-2	6-8-10

Scale = 1:62.7

Plate Offsets (X,Y): [2:0-1-14,0-0-11], [6:0-3-0,0-3-0], [11:0-3-1,0-3-5]	
LOADING (psf)	SPACING 2-0-0
TCLL 20.0	Plates Increase 1.25
TCDL 7.0	Lumber Increase 1.25
BCLL 10.0	Rep Stress Incr YES
BCDL 5.0	Code FBC2004/TPI2002
CSI	DEFL in (loc) l/defl L/d
TC 0.55	Vert(LL) -0.22 10-11 >999 240
BC 0.67	Vert(TL) -0.36 10-11 >999 180
WB 0.66	Horz(TL) 0.11 9 n/a n/a
(Matrix)	
PLATES MT20	GRIP 244/190
Weight: 191 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 3-9-3 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2	Rigid ceiling directly applied or 6-6-11 oc bracing.
WEBS 2 X 4 SYP No.3	1 Row at midpt 5-12, 7-9

REACTIONS (lb/size) 9=1455/0-4-0, 2=1549/0-4-0
 Max Horz 2=299(load case 5)
 Max Uplift 9=624(load case 3), 2=493(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-2405/709, 3-4=-2204/693, 4-5=-1878/637, 5-6=-2387/893, 6-7=-1810/720, 7-8=-54/16, 8-9=-169/136
 BOT CHORD 2-12=-715/2018, 11-12=-898/2363, 10-11=-921/2235, 9-10=-644/1489
 WEBS 3-12=-188/202, 4-12=-178/784, 5-12=-636/464, 5-11=0/88, 6-11=-44/241, 6-10=-678/320, 7-10=-204/859, 7-9=-1845/807

JOINT STRESS INDEX
 2 = 0.86, 3 = 0.34, 4 = 0.66, 5 = 0.48, 6 = 0.50, 7 = 0.76, 8 = 0.41, 9 = 0.74, 10 = 0.76, 11 = 0.74 and 12 = 0.57

NOTES
 1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 2) Provide adequate drainage to prevent water ponding.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 624 lb uplift at joint 9 and 493 lb uplift at joint 2.

LOAD CASE(S) Standard

Job L230379	Truss T16	Truss Type HIP	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 13:41:33 2007 Page 1		

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.76	Vert(LL)	-0.37	2-13	>999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.85	Vert(TL)	-0.64	2-13	>651		
BCLL 10.0	Rep Stress Incr	YES	WB 0.94	Horz(TL)	0.10	9	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 195 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 3-5-13 oc purlins, except end
BOT CHORD 2 X 4 SYP No.2	verticals.
WEBS 2 X 4 SYP No.3	BOT CHORD Rigid ceiling directly applied or 7-3-6 oc bracing.
	WEBS 1 Row at midpt 5-13, 5-10

REACTIONS (lb/size) 2=1549/0-4-0, 9=1455/0-4-0
 Max Horz 2=239(load case 4)
 Max Uplift 2=-523(load case 5), 9=-410(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-2351/695, 3-4=-2078/651, 4-5=-1747/610, 5-6=-1580/556, 6-7=-1863/588, 7-8=-455/130, 8-9=-338/145
 BOT CHORD 2-13=-749/1977, 12-13=-719/1990, 11-12=-719/1990, 10-11=-719/1990, 9-10=-414/1497
 WEBS 3-13=-288/268, 4-13=-115/673, 5-13=-439/344, 5-11=0/174, 5-10=-631/376, 6-10=-107/571, 7-10=-181/219, 7-9=-1520/494

JOINT STRESS INDEX
 2 = 0.85, 3 = 0.34, 4 = 0.76, 5 = 0.57, 6 = 0.76, 7 = 0.45, 8 = 0.48, 9 = 0.73, 10 = 0.57, 11 = 0.34, 12 = 0.68 and 13 = 0.57

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Provide adequate drainage to prevent water ponding.
 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 523 lb uplift at joint 2 and 410 lb uplift at joint 9.

LOAD CASE(S) Standard

Job L230379	Truss T17	Truss Type SPECIAL	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Tue Mar 13 08:55:04 2007 Page 1		

LOADING (psf)	SPACING	2'-0"	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.70	Vert(LL)	-0.46	8-9	>809	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.93	Vert(TL)	-0.75	8-9	>493		
BCLL 10.0	Rep Stress Incr	YES	WB 0.92	Horz(TL)	0.36	8	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 193 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 2-3-0 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2 X 4 SYP No.3	


REACTIONS (lb/size) 8=1266/0-4-0, 13=1648/0-4-0
 Max Horz 13=-230(load case 3)
 Max Uplift 8=-384(load case 6), 13=-455(load case 5)


FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-15=-34/51, 1-2=-261/246, 2-3=-423/444, 3-4=-1440/424, 4-5=-1189/410, 5-6=-2184/638, 6-7=-3861/922, 7-8=-4238/1223
 BOT CHORD 14-15=-14/18, 13-14=-238/302, 12-13=-437/992, 11-12=-474/1397, 10-11=-502/1501, 9-10=-531/2339, 8-9=-1016/3805
 WEBS 1-14=-248/284, 2-14=-185/0, 2-13=-95/240, 3-13=-1842/822, 3-12=-231/277, 4-12=-163/545, 5-12=-565/369, 5-11=-321/182, 5-10=-219/918, 6-10=-611/191, 6-9=-478/2398, 7-9=-300/409


JOINT STRESS INDEX
 1 = 0.35, 2 = 0.83, 3 = 0.61, 4 = 0.34, 5 = 0.87, 6 = 0.89, 7 = 0.34, 8 = 0.82, 9 = 0.71, 10 = 0.55, 11 = 0.60, 12 = 0.64, 13 = 0.57, 14 = 0.51 and 15 = 0.34

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; cantilever left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Provide adequate drainage to prevent water ponding.
 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 5) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 384 lb uplift at joint 8 and 455 lb uplift at joint 13.


LOAD CASE(S) Standard








MARCH 13, 2007 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



MARCH 13, 2007 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



Job L230379	Truss T23	Truss Type SPECIAL	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:18:14 2007 Page 1		

Scale = 1:65.4

1-6-0	6-8-13	13-0-0	14-8-9	18-4-5	25-6-0	29-10-13	35-0-0	36-6-0
1-6-0	6-8-13	6-3-3	1-8-9	3-7-11	7-1-11	4-4-13	5-1-3	1-6-0

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.97	Vert(LL)	-0.61 11-12	>678	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 1.00	Vert(TL)	-0.99 11-12	>418	180	MT18H	244/190
BCLL 10.0	Rep Stress Incr	YES	WB 0.69	Horz(TL)	0.53 9	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						

Weight: 208 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2 X 4 SYP No.3 *Except*	WEBS 1 Row at midpt 6-11
WT 2 X 4 SYP No.2	


REACTIONS (lb/size) 2=1546/0-4-0, 9=1546/0-4-0
 Max Horz 2=344(load case 4)
 Max Uplift 2=-571(load case 5), 9=-559(load case 6)


FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-2439/756, 3-4=-1883/658, 4-5=-1559/638, 5-6=-1706/681, 6-7=-4737/1375, 7-8=-4699/1222, 8-9=-4936/1408, 9-10=0/38
 BOT CHORD 2-14=-661/2015, 13-14=-661/2015, 12-13=-392/1599, 11-12=-290/1522, 9-11=-1124/4416
 WEBS 3-14=0/233, 3-13=-558/307, 4-13=-126/564, 5-13=-252/113, 5-12=-637/363, 6-12=-238/502, 6-11=-938/3579, 7-11=-327/339, 8-11=-174/279

JOINT STRESS INDEX
 2 = 0.81, 3 = 0.42, 4 = 0.69, 5 = 0.47, 6 = 0.69, 7 = 0.65, 8 = 0.34, 9 = 0.96, 11 = 0.83, 12 = 0.62, 13 = 0.70 and 14 = 0.34

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Provide adequate drainage to prevent water ponding.
 4) All plates are MT20 plates unless otherwise indicated.
 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 6) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 571 lb uplift at joint 2 and 559 lb uplift at joint 9.

LOAD CASE(S) Standard





Job L230379	Truss T26	Truss Type HIP	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055					Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:36:30 2007 Page 1

Scale = 1:23.5

Plate Offsets (X,Y): [2:0-3-3,0-1-8], [5:0-3-3,0-1-8]				
LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc) l/defl L/d	PLATES GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.23	Vert(LL) 0.04 7-8 >999 240	MT20 244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.22	Vert(TL) -0.05 7-8 >999 180	
BCLL 10.0	Rep Stress Incr NO	WB 0.07	Horz(TL) 0.01 5 n/a n/a	
BCDL 5.0	Code FBC2004/TPI2002	(Matrix)		Weight: 51 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 8-7-10 oc bracing.
WEBS 2 X 4 SYP No.3	


REACTIONS (lb/size) 2=635/0-4-0, 5=635/0-4-0
 Max Horz 2=67(load case 3)
 Max Uplift 2=429(load case 4), 5=429(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-856/581, 3-4=-713/536, 4-5=-857/582, 5-6=0/40
 BOT CHORD 2-8=-519/697, 7-8=-530/713, 5-7=-460/698
 WEBS 3-8=-132/194, 3-7=-61/61, 4-7=-146/205

JOINT STRESS INDEX
 2 = 0.51, 3 = 0.57, 4 = 0.48, 5 = 0.51, 7 = 0.13 and 8 = 0.14

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60.
 3) Provide adequate drainage to prevent water ponding.
 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 429 lb uplift at joint 2 and 429 lb uplift at joint 5.
 6) Girder carries hip end with 3-0-0 end setback.
 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 63 lb down and 44 lb up at 8-0-0, and 63 lb down and 44 lb up at 3-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-3=-54, 3-4=-63(F=-9), 4-6=-54, 2-8=-30, 7-8=-35(F=-5), 5-7=-30
 Concentrated Loads (lb)
 Vert: 8=-63(F) 7=-63(F)



Job L230379	Truss T28	Truss Type COMMON	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:36:53 2007 Page 1		

Scale = 1:19.7

Plate Offsets (X,Y): [1:0-3-3,0-1-8], [3:0-3-3,0-1-8]					
LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.30	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.30	Vert(LL) 0.07 3-4 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.07	Vert(TL) -0.06 3-4 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.01 3 n/a n/a		
	Code FBC2004/TPI2002			Weight: 40 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 9-5-9 oc bracing.
WEBS 2 X 4 SYP No.3	

REACTIONS (lb/size) 1=448/0-4-0, 3=448/0-4-0
 Max Horz 1=-113(load case 3)
 Max Uplift 1=-277(load case 5), 3=-277(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-595/555, 2-3=-595/555
 BOT CHORD 1-4=-414/455, 3-4=-414/455
 WEBS 2-4=-358/216

JOINT STRESS INDEX
 1 = 0.38, 2 = 0.60, 3 = 0.38 and 4 = 0.16

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 277 lb uplift at joint 1 and 277 lb uplift at joint 3.

LOAD CASE(S) Standard

Job L230379	Truss T29	Truss Type COMMON	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:46:52 2007 Page 1		

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/def	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.53	Vert(LL)	-0.13 2-11	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.98	Vert(TL)	-0.21 2-11	>999	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.73	Horz(TL)	0.04 6	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 126 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 3-4-15 oc purlins.
BOT CHORD 2 X 6 SYP No.1D	BOT CHORD Rigid ceiling directly applied or 9-0-0 oc bracing.
WEBS 2 X 4 SYP No.3	

REACTIONS (lb/size) 2=2372/0-4-0, 6=2372/0-4-0
 Max Horz 2=-219(load case 2)
 Max Uplift 2=-909(load case 4), 6=-909(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/43, 2-3=-2487/824, 3-4=-1393/515, 4-5=-1393/516, 5-6=-2487/825, 6-7=0/43
 BOT CHORD 2-12=-695/2109, 11-12=-695/2109, 10-11=-695/2109, 9-10=-695/2109, 8-9=-611/2109, 8-13=-611/2109, 6-13=-611/2109
 WEBS 3-11=-233/855, 3-9=-1164/512, 4-9=-351/1078, 5-9=-1164/513, 5-8=-232/855

JOINT STRESS INDEX
 2 = 0.84, 3 = 0.64, 4 = 0.54, 5 = 0.64, 6 = 0.84, 8 = 0.28, 9 = 0.57, 10 = 0.58 and 11 = 0.28

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 909 lb uplift at joint 2 and 909 lb uplift at joint 6.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1400 lb down and 529 lb up at 2-0-0, and 1400 lb down and 529 lb up at 19-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)
 Vert: 1-4=-54, 4-7=-54, 2-6=-30

Concentrated Loads (lb)
 Vert: 12=-1400(F) 13=-1400(F)

MARCH 13, 2007 TRUSS DESIGN ENGINEER:
 THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
 STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
 16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job L230379	Truss T30	Truss Type COMMON	Qty 1	Ply 2	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:52:42 2007 Page 1		

Scale = 1:38.2

Plate Offsets (X,Y): [2-0-3-0,0-2-11], [6-0-3-0,0-2-11]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.37	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.58	Vert(LL) -0.14 8-10 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.65	Vert(TL) -0.22 8-10 >999 180		
BCDL 5.0	Rep Stress Incr NO	(Matrix)	Horz(TL) 0.05 6 n/a n/a		
	Code FBC2004/TPI2002			Weight: 247 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 4-11-3 oc purlins.
BOT CHORD 2 X 6 SYP No.1D	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2 X 4 SYP No.3	

REACTIONS (lb/size) 6=4350/0-4-0, 2=3233/0-4-0
 Max Horz 2=236(load case 3)
 Max Uplift 6=1635(load case 5), 2=1253(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/43, 2-3=-5957/2164, 3-4=-4397/1690, 4-5=-4402/1687, 5-6=-6539/2440
 BOT CHORD 2-10=-1859/5048, 10-11=-1859/5048, 11-12=-1859/5048, 9-12=-1859/5048, 8-9=-1859/5048, 8-13=-2020/5585, 7-13=-2020/5585, 6-7=-2020/5585
 WEBS 3-10=-437/1388, 3-8=-1555/661, 4-8=-1523/4069, 5-8=-2189/947, 5-7=-712/1982

JOINT STRESS INDEX
 2 = 0.82, 3 = 0.74, 4 = 0.47, 5 = 0.74, 6 = 0.82, 7 = 0.32, 8 = 0.51, 9 = 0.75 and 10 = 0.32

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2 X 6 - 2 rows at 0-7-0 oc.
 Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1635 lb uplift at joint 6 and 1253 lb uplift at joint 2.
- Girder carries tie-in span(s): 16-10-0 from 8-0-0 to 15-0-0; 19-2-0 from 15-0-0 to 21-4-0
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1418 lb down and 535 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-4=-54, 4-6=-54, 2-12=-30, 12-13=-335(F=-305), 6-13=-384(F=-354)
 Concentrated Loads (lb)
 Vert: 11=-1418(F)

Job L230379	Truss T31	Truss Type COMMON	Qty 2	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055					Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:52:57 2007 Page 1

Plate Offsets (X,Y): [2:0-3-3,0-1-8], [4:0-3-3,0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.16	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.10	Vert(LL) -0.01 4-6 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.04	Vert(TL) -0.01 4-6 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.00 4 n/a n/a		
	Code FBC2004/TPI2002			Weight: 34 lb	

LUMBER TOP CHORD 2 X 4 SYP No.2 BOT CHORD 2 X 4 SYP No.2 WEBS 2 X 4 SYP No.3	BRACING TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
--	---

REACTIONS (lb/size) 2=412/0-4-0, 4=412/0-4-0
 Max Horz 2=87(load case 4)
 Max Uplift 2=302(load case 5), 4=302(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-373/334, 3-4=-373/334, 4-5=0/40
 BOT CHORD 2-6=-170/272, 4-6=-170/272
 WEBS 3-6=-214/124

JOINT STRESS INDEX
 2 = 0.42, 3 = 0.24, 4 = 0.42 and 6 = 0.09

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) All bearings are assumed to be SYP No.2 crushing capacity of 585.00 psi
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 302 lb uplift at joint 2 and 302 lb uplift at joint 4.


LOAD CASE(S) Standard

Job L230379	Truss V5	Truss Type VALLEY	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
----------------	-------------	----------------------	----------	----------	-------------------------------------

Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:53:56 2007 Page 1



Scale = 1:15.4

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.19	Vert(LL) n/a	-	n/a	999	
TCDL 7.0	Lumber Increase 1.25	BC 0.09	Vert(TL) n/a	-	n/a	999	
BCLL 10.0	Rep Stress Incr YES	WB 0.03	Horz(TL) 0.00		n/a	n/a	
BCDL 5.0	Code FBC2004/TPI2002	(Matrix)					
						Weight: 23 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3
 OTHERS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 5-9-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=155/5-9-0, 4=2/5-9-0, 5=268/5-9-0
 Max Horz 1=87(load case 5)
 Max Uplift 1=46(load case 5), 4=-35(load case 6), 5=-75(load case 5)
 Max Grav 1=155(load case 1), 4=2(load case 4), 5=268(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-51/43, 2-3=-12/19, 3-4=-29/29
 BOT CHORD 1-5=0/0, 4-5=0/0
 WEBS 2-5=-137/101


JOINT STRESS INDEX
 1 = 0.04, 2 = 0.05, 3 = 0.02, 4 = 0.02 and 5 = 0.06

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Gable requires continuous bottom chord bearing.
 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 46 lb uplift at joint 1, 35 lb uplift at joint 4 and 75 lb uplift at joint 5.

LOAD CASE(S) Standard

MARCH 13, 2007 TRUSS DESIGN ENGINEER:
 THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
 STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
 16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job L230379	Truss V7	Truss Type VALLEY	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055					Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:54:08 2007 Page 1



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.34	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.26	Vert(TL)	n/a	-	n/a		
BCLL 10.0	Rep Stress Incr	YES	WB 0.10	Horz(TL)	-0.00	4	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 33 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3
 OTHERS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 7-9-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 1=192/7-9-0, 4=-282/7-9-0, 5=684/7-9-0
 Max Horz 1=140(load case 5)
 Max Uplift 1=-28(load case 5), 4=-306(load case 9), 5=-340(load case 5)
 Max Grav 1=192(load case 1), 4=159(load case 5), 5=684(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-91/106, 2-3=-71/118, 3-4=-134/179
 BOT CHORD 1-5=-12/4, 4-5=-12/4
 WEBS 2-5=-404/318

JOINT STRESS INDEX
 1 = 0.52, 2 = 0.65, 3 = 0.31, 4 = 0.29 and 5 = 0.18

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Gable requires continuous bottom chord bearing.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 1, 306 lb uplift at joint 4 and 340 lb uplift at joint 5.

LOAD CASE(S) Standard

Job L230379	Truss V9	Truss Type VALLEY	Qty 1	Ply 1	ADAMS FRAMING - LOT 10 WISE ESTATES
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.300 s Apr 19 2006 MiTek Industries, Inc. Mon Mar 12 15:58:35 2007 Page 1		

Scale: 1/2"=1'

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20
TCDL 7.0	Lumber Increase	1.25	BC 0.04	Vert(TL)	n/a	-	n/a	999	244/190
BCLL 10.0	Rep Stress Incr	YES	WB 0.04	Horz(TL)	-0.00	7	n/a	n/a	
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						Weight: 50 lb

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3
 OTHERS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=104/9-9-0, 7=179/9-9-0, 9=181/9-9-0, 8=179/9-9-0, 10=232/9-9-0
 Max Horz 1=179(load case 5)
 Max Uplift 7=-19(load case 3), 9=-104(load case 5), 8=-62(load case 5), 10=-130(load case 5)
 Max Grav 1=104(load case 1), 7=30(load case 10), 9=182(load case 9), 8=179(load case 1), 10=232(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-168/39, 2-3=-161/46, 3-4=-88/36, 4-5=-36/33, 6-7=-25/20, 5-6=-13/22
 BOT CHORD 1-10=-1/1, 9-10=-1/1, 8-9=-1/1, 7-8=-1/1
 WEBS 4-9=-120/120, 5-8=-113/77, 3-10=-148/135



JOINT STRESS INDEX
 1 = 0.16, 2 = 0.00, 2 = 0.11, 2 = 0.11, 3 = 0.07, 4 = 0.06, 5 = 0.11, 6 = 0.02, 7 = 0.02, 8 = 0.04, 9 = 0.07 and 10 = 0.08

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Gable requires continuous bottom chord bearing.
 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 7, 104 lb uplift at joint 9, 62 lb uplift at joint 8 and 130 lb uplift at joint 10.

LOAD CASE(S) Standard

MARCH 13, 2007 TRUSS DESIGN ENGINEER:
 THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
 STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
 16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

PLATE LOCATION AND ORIENTATION




- This symbol indicates the required direction of slots in connector plates

The first dimension is the width perpendicular to slots. Second dimension is the length parallel to slots.

Indicates location of required continuous lateral bracing.

Indicates location of joints at which loadings (supports) occur

22



WEBS ARE NUMBERED FROM LEFT TO RIGHT

CONNECTION PLATE CODE APPROVALS


$B(\cdot) \subset A$ 96-31, 96-67

ICBO 3907, 4922

9667.9432A

WISC-III IR 960022.W, 97M36-11

11ER 561



Hill Engineering Reference Sheet: H11-7473

Failure to Follow Could Cause Properly Damage or Personal Injury

1. Provide copies of this russ design to the building designer, erection supervisor, properly owner and all other interested parties.
2. Cut members to bear tightly against each other.
3. Place plates on each face of russ at each joint and embed fully. Avoid knots and wane at joint locations.
4. Unless otherwise noted, locate chord splices at 1/2 panel length (1.5' from adjacent joint)
5. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
6. Unless expressly noted, this design is not applicable for use with live retention or preservative treated lumber.
7. Gable is a non-structural consideration and is the responsibility of russ fabricator. General practice is to gable for dead load deflection.
8. Plate type, size and location dimensions shown indicate minimum piling requirements.
9. Lumber shall be of the species and size, cut in all respects, equal to or better than the grade specified.
10. Top chords must be sheathed or purlins provided at spacing shown on design.
11. Bottom chords require lateral bracing at 10 ft spacing, or less. If no ceiling is installed, unless otherwise noted.
12. Anchorage and / or load transferring connections to lusses are the responsibility of others unless shown.
13. Do not overboard roof or floor lusses with stacks of construction materials.
14. Do not cut or alter russ member or plate without prior approval of a professional engineer.
15. Care should be exercised in handling, erection and installation of lusses.

New Construction Subterranean Termite Soil Treatment Record

OMB Approval No. 2502-0525

This form is completed by the licensed Pest Control Company.

Public reporting burden for this collection of information is estimated to average 15 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. This information is mandatory and is required to obtain benefits. HUD may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number.

Section 24 CFR 200.926d(b)(3) requires that the sites for HUD insured structures must be free of termite hazards. This information collection requires the builder to certify that an authorized Pest Control company performed all required treatment for termites, and that the builder guarantees the treated area against infestation for one year. Builders, pest control companies, mortgage lenders, homebuyers, and HUD as a record of treatment for specific homes will use the information collected. The information is not considered confidential.

This report is submitted for informational purposes to the builder on proposed (new) construction cases when soil treatment for prevention of subterranean termite infestation is specified by the builder, architect, or required by the lender, architect, FHA, or VA.

All contracts for services are between the Pest Control Operator and builder, unless stated otherwise.

25673

Section 1: General Information (Treating Company Information)

Company Name: Aspen Pest Control, Inc.
Company Address: 321 N.W. Cole Terrace, Suite 107 City Lake City State FL Zip 32055
Company Business License No. JB102475 Company Phone No. 386-755-3811 • 352-494-5751
FHA/VA Case No. (if any) _____

Section 2: Builder Information

Company Name: Adam Pupko Company Phone No. _____

Section 3: Property Information

Location of Structure(s) Treated (Street Address or Legal Description, City, State and Zip) 147 SW Wines Avenue
Lake City, FL 32055
Type of Construction (More than one box may be checked) ☒ Slab ☐ Basement ☐ Crawl ☐ Other _____
Approximate Depth of Footing: Outside 12 Inside 12 Type of Fill Block

Section 4: Treatment Information

Date(s) of Treatment(s) 4-9-07
Brand Name of Product(s) Used Bifen XTS
EPA Registration No. 63443-149
Approximate Final Mix Solution % 106
Approximate Size of Treatment Area: Sq. ft. 2247 Linear ft. 252 Linear ft. of Masonry Voids 252
Approximate Total Gallons of Solution Applied 500
Was treatment completed on exterior? ☐ Yes ☒ No
Service Agreement Available? ☒ Yes ☐ No Upon Completion
Note: Some state laws require service agreements to be issued. This form does not preempt state law.

Attachments (List) _____

Comments Treated main body Garage + 2 Porches

Name of Applicator(s) Steve Brannon Certification No. (if required by State law) _____

The applicator has used a product in accordance with the product label and state requirements. All treatment materials and methods used comply with state and federal regulations.

Authorized Signature [Signature] Date 4-9-07

Warning: HUD will prosecute false claims and statements. Conviction may result in criminal and/or civil penalties. (18 U.S.C. 1001, 1010, 1012; 31 U.S.C. 3729, 3802)

Form NPCA-99-B may still be used

form HUD-NPCA-99-B (04/2003)



Donald F. Lee & Associates, Inc.
Surveyors & Engineers

25673

140 NW Ridgewood Avenue
Lake City, Florida 32055
(386) 755-6166
Fax (386) 755-6167
donald@dlfa.com

Tuesday, April 10, 2007

FROM: Tim Delbene, P.L.S.

TO: Columbia County Building & Zoning Dept.

CC: Adams Framing

RE: Foundation Elevation Check – Lot 2, Block B, Wise Estates

We have obtained elevations on a foundation under construction on the above referenced lot. The elevations are based on Local Benchmark Datum. The results are as follows:

Floor Elevation (at Stemwall): 99.72'

Porch Elevations (at Stemwall): 99.07'

Highest Adjacent Grade (HAG): 98.75'

Lowest Adjacent Grade (LAG): 97.18'

The record subdivision plat for Wise Estates indicates a minimum floor elevation of 99.00' for the subject Lot 2, Block B.

SIGNED:

Timothy A. Delbene, P.L.S.
Florida Reg. Cert. No. 5594

DATE: 4/10/2007.

CERTIFICATE OF OCCUPANCY

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 24-4S-16-03113-122

Building permit No. 000025673

Use Classification SFD, UTILITY

Fire: 16.74

Permit Holder ADAM PAPKA

Waste: 50.25

Owner of Building ADAM'S FRAMING & CONSTRUCTION

Total: 66.99

Location: 147 SW WISE DRIVE, LAKE CITY, FL



Date: 07/18/2007

Tony Dick


Building Inspector



POST IN A CONSPICUOUS PLACE
(Business Places Only)



***** - DENOTES
INTERIOR LOAD
BEARING WALLS



18" O/H
7/12

NOTES:

- 1) REFER TO HUB 91 (RECOMMENDATIONS FOR REINFORCED INSTALLATION AND TEMPORARY BRACKING) REFER TO NUMBERED DRAWINGS FOR PERMANENT BRACKING REQUIRED.
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V05 FOR ALTERNATE BRACKING REQUIREMENTS.
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
- 4) ALL TRUSSES ARE DESIGNED FOR 2' O.C. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6) 5"x2" TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
- 7) ALL ROOF TRUSSES HANGERS TO BE SWAPSON HUS26 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSSES HANGERS TO BE SWAPSON TH4422 UNLESS OTHERWISE NOTED.
- 8) BEAM/HEADER/INTEL. (HDS) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND V005 ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Expenditure Entry Date: _____

Approved By: _____ Date: _____



Bunnell
PHONE: 904-437-3549 FAX: 904-437-3904
Jacksonville
PHONE: 904-772-6100 FAX: 904-772-1973
Lake City
PHONE: 904-755-6894 FAX: 904-755-7973
Sanford
PHONE: 407-322-0094 FAX: 407-322-9953
BUILDER: ADAM'S FRAMING

TEAM ADDRESS: LOT 18 WISE ESTATES

MODEL:

DATE: 3/12/07 DRAWN BY: WWL CHECKED BY: L230379