






ONE STORY WALL SECTION
SCALE: 3/4" = 1'-0"




(TYP.) INTERSECTING WALL FRAMING
WOOD FRAME




(TYP.) CORNER FRAMING
WOOD FRAME

Wind Speed	Sheathing Thickness Plywood Or OSB	Required Nail	Nail spacing along panel edges	Nail spacing along intermediate supports in the panel field
120 mph Exp. B	7/16"	ASTM F1667 RRS-01 (2 3/8" x 0.131")	6" oc	12" oc
120 mph Exp. C	7/16"	ASTM F1667 RRS-03 (2 1/2" x 0.131") or ASTM F1667 RRS-04 (3" x 0.120")	6" oc	6" oc
130 mph Exp. B	7/16"	ASTM F1667 RRS-01 (2 3/8" x 0.131")	6" oc	6" oc
130 mph Exp. C	15/32"	ASTM F1667 RRS-03 (2 1/2" x 0.131") or ASTM F1667 RRS-04 (3" x 0.120")	6" oc	6" oc
140 mph Exp. B	7/16"	ASTM F1667 RRS-01 (2 3/8" x 0.131")	6" oc	6" oc
140 mph Exp. C	15/32"	ASTM F1667 RRS-03 (2 1/2" x 0.131") or ASTM F1667 RRS-04 (3" x 0.120")	6" oc	6" oc
150 mph Exp. C	15/32"	ASTM F1667 RRS-03 (2 1/2" x 0.131") or ASTM F1667 RRS-04 (3" x 0.120")	6" oc	6" oc
150 mph Exp. D	15/32"	ASTM F1667 RRS-03 (2 1/2" x 0.131") or ASTM F1667 RRS-04 (3" x 0.120")	4" oc	4" oc


Note: For sheathing located a minimum of 4 feet from the perimeter edge of the roof, including 4 feet on each side of ridges and hips, nail spacing is permitted to be 6 inches on center along panel edges and 6 inches on center along intermediate supports in the panel field. Note: This table specifies the code minimum thickness of roof sheathing. The thickness of the sheathing may need to be increased based on the type of roofing material being used. See manufacturer Florida product approval.




(TYP.) GABLE BRACING DETAIL
WOOD FRAME




TYPICAL HEADER STRAPPING OR SCREWS DETAIL
ONE STORY WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) WALL CONNECTIONS
ONE STORY WOOD FRAME



SHEATHING FOR UPLIFT ATTACHMENT DETAILS
ONE STORY WOOD FRAME



(TYP.) GABLE WALL w/ VAULTED CEILING
WOOD FRAME


Option	Uplift	Top Connection	Bottom Connection
#1	< 51k	Attach king stud to top plate w/ (1) Simpson SDWC15600	Attach king stud to bottom plate w/ (2) Simpson SDWC15450 1/2" x 10" Anchor bolt w/ 3" x 3" x 1/4" washer must be located within 6" of king stud @ all door locations
#2	< 89k	Attach king stud to top plate w/ (2) Simpson SDWC15600	Attach king stud to bottom plate w/ (3) Simpson SDWC15450 1/2" x 10" Anchor bolt w/ 3" x 3" x 1/4" washer must be located within 6" of king stud @ all door locations

Option	Uplift	Top Connection	Bottom Connection
#3	< 123k	LSTA24, (14) 148" x 1 1/2" wrap over plate	LSTA24, (14) 148" x 1 1/2" wrap under plate 1/2" x 10" Anchor bolt w/ 3" x 3" x 1/4" washer must be located within 6" of king stud @ all door locations
#4	< 145k	MSTA24, 18-148"x1 1/2" header to jacks	DTT22
#5	< 180k	MSTA24, 18-148"x1 1/2" header to jacks	DTT22
#6	< 291k	MSTA24, 18-148"x1 1/2" header to jacks	HTT4


DESIGN WIND SPEED	MAX. SPANS FOR SFF #2	(1) 2x4	(2) 2x4	(1) 2x6	(2) 2x6
130 MPH EXP. C	5'-2"	7'-9"	7'-7"	11'-3"	

BASED ON WFCM TABLE A-3-208 FOR OTHER WALL HEIGHTS (H) SILL SPAN SHALL BE DIVIDED BY (H/10)


(TYP.) BEAM TO WALL
WOOD FRAME w/ STRAPS & ANCHORS




(TYP.) WALL CONNECTIONS
ONE STORY WOOD FRAME




(TYP.) INTERIOR BEARING WALL
ONE STORY WOOD FRAME w/ STRAPS & ANCHORS




(TYP.) PORCH POST
ONE STORY WOOD




(TYP.) GARAGE DOOR BUCK INSTALLATION
WOOD FRAME




(TYP.) GARAGE DOOR BUCK ATTACHMENT
WOOD FRAME w/ STRAPS & ANCHORS




(TYP.) GIRDER TRUSS HOLD DOWN DETAIL
WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) GIRDER TRUSS HOLD DOWN DETAIL
WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) GIRDER TRUSS HOLD DOWN DETAIL
WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) GIRDER TRUSS HOLD DOWN DETAIL
WOOD FRAME w/ STRAPS & ANCHORS


Uplift SP	Uplift SFF	Truss Connector	To Plate	To Truss/Rafter
805	505	SDWC15600	-	-
400	290	H3	4-131"x1 1/2"	4-131"x1 1/2"
625	540	H2.5A	5-131"x1 1/2"	5-131"x1 1/2"
1030	1015	H10A	9-148"x1 1/2"	9-148"x1 1/2"
645	515	LTS12-20	6-148"x1 1/2"	6-148"x1 1/2"
990	850	MTS12-30	7-148"x1 1/2"	7-148"x1 1/2"
1415	1215	HTS16-30	8-148"x1 1/2"	8-148"x1 1/2"
Uplift SP	Uplift SFF	Strap Ties	To One Member	To Other Member
1235	1235	LSTA21	8-148"x1 1/2"	8-148"x1 1/2"
1640	1460	MSTA24	9-148"x1 1/2"	9-148"x1 1/2"
1030	1030	CS20	7-148"x1 1/2"	7-148"x1 1/2"
Uplift SP	Uplift SFF	Stud Plate Ties	To Stud	To Plate
555	535	SP1	4-148"x3"	4-148"x3"
1010	805	SP2	6-148"x3"	6-148"x3"
1280	1100	SPH46	12-148"x1 1/2"	wrap under or over plate
771	771	LSTA24	10-148"x1 1/2"	wrap under or over plate
1235	1235	LSTA24	10-148"x1 1/2"	wrap under or over plate
Uplift SP	Uplift SFF	Holdowns @ Stewall	To Stud / Post	Anchor
2145	1835	DTT22	8-SDS 1/4"x1 1/2"	12"x12" Titen HD
4235	3640	HTT4	18-162"x2 1/2"	12"x12" Titen HD
Uplift SP	Uplift SFF	Holdowns @ Mono	To Stud / Post	Anchor
2145	1835	DTT22	8-SDS 1/4"x1 1/2"	12"x12" Titen HD
4235	3640	HTT4	18-162"x2 1/2"	12"x12" Titen HD
Uplift SP	Uplift SFF	Post Bases @ Stewall	To Post	Anchor
1900	ABU442	ABU442	12-162"x3 1/2"	5/8"x12" Drill & Epoxy
2475	ABU662	ABU662	12-162"x3 1/2"	5/8"x12" Drill & Epoxy

Uplift	Top Connection	Bottom Connection
up to 905 lb	(2) SDWC15600	(3) SDWC15450 w/ anchor bolt within 6"
up to 1215 lb	HTS16	LSTA24, 14-10d Wrap under plate w/ anchor bolt within 6"
up to 2430 lb	(2) HTS16	HTT4

(TYP.) GIRDER TRUSS HOLD DOWN DETAIL
WOOD FRAME w/ STRAPS & ANCHORS

THIS STUD HEIGHT TABLE IS PER 2012 WFCM, TABLE 3.20B5, EXTERIOR LOAD BEARING & NON LOAD BEARING STUD LENGTHS FOR WALLS WITH OSB EXTERIOR AND 1/2" GYP INTERIOR RESISTING INTERIOR ZONE WIND LOADS, 130 MPH, EXPOSURE C, STUD DEFLECTION LIMIT H/240 (NOT OK FOR BRITTLE FINISH), STUD SPACINGS SHALL BE MULTIPLIED BY 0.8 FOR FRAMING LOCATED WITHIN 4 FEET OF CORNERS FOR END ZONE LOADING. (END ZONE EXAMPLE 16" O.C. x 0.8 = 12.8" O.C.)			
(1) 2x4 @ 16" OC	TO 10'-1" STUD HEIGHT		
(1) 2x4 @ 12" OC	TO 11'-2" STUD HEIGHT		
(1) 2x6 @ 16" OC	TO 15'-7" STUD HEIGHT		
(1) 2x6 @ 12" OC	TO 17'-3" STUD HEIGHT		

		Fb	E
2x8	SP #2	925	1.4
2x10	SP #2	800	1.4
2x12	SP #2	750	1.4
GLB	24F-V3 SP	2600	1.9
LVL	TIMBERSTRAND	1700	1.7
LVL	MICROLAM	2950	2.0
PSL	PARALAM	2900	2.0




(TYP.) INTERIOR SHEAR WALL
ONE STORY WOOD FRAME w/ STRAPS & AB

DESIGN CRITERIA & LOADS:	
BUILDING CODE	8TH EDITION FLORIDA BUILDING CODE RESIDENTIAL (2023)
CODE FOR DESIGN LOADS	ASCE 7-22
WIND	


TALL STEM WALL TABLE:						
The table assumes 40 ksi for #5 rebar and 60 ksi for #7 & #8 rebar with 6" hook in the footing and bent 24" into the reinforced slab at the top. The vertical steel is to be placed toward the tension side of the CMU wall (away from the soil pressure, within 2" of the exterior side of the wall). If the wall is over 8' high, add Duowall ladder reinforcement at 16"OC vertically or a horizontal bond beam with 1#5 continuous as shown in the table below.						
STEM WALL HEIGHT (FEET)	UNBALANCED BACKFILL HEIGHT	VERTICAL REINFORCEMENT FOR 8" CMU STEM WALL (INCHES O.C.)			VERTICAL REINFORCEMENT FOR 12" CMU STEM WALL (INCHES O.C.)	
		#5	#7	#8	#5	#7
3.3	3.0	96	96	96	96	96
4.0	3.7	96	96	96	96	96
4.7	4.3	88	96	96	96	96
5.3	5.0	56	96	96	96	96
6.0	5.7	40	80	96	80	96
6.7	6.3	32	56	80	56	96
7.3	7.0	24	40	56	40	80
8.0	7.7	16	32	48	32	64
8.7	8.3	8	24	32	24	48
9.3	9.0	8	16	24	16	40

MASONRY NOTE:
MASONRY CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL CONFORM TO ALL REQUIREMENTS OF "SPECIFICATION FOR MASONRY STRUCTURES" (ACI 530.1/ASCE 6/TMS 602). THE CONTRACTOR AND MASON MUST IMMEDIATELY, BEFORE PROCEEDING, NOTIFY THE ENGINEER OF ANY CONFLICTS BETWEEN ACI 530.1-02 AND THESE DESIGN DRAWINGS. ANY EXCEPTIONS TO ACI 530.1-02 MUST BE APPROVED BY THE ENGINEER IN WRITING.


	ACI530.1-02 Section	Specific Requirements
1.4A	Compressive strength	8" block bearing walls F'm = 1500 psi
2.1	Mortar	ASTM C 270, Type N, UNO
2.2	Grout	ASTM C 476, admixtures require approval
2.3	CMU standard	ASTM C 90-02, Normal weight, Hollow, medium surface finish, 8"x8"x16" running bond and 12"x12" or 16"x16" column block
2.3	Clay brick standard	ASTM C 216-02, Grade SW, Type FBS, 5.5"x2.75"x11.5"
2.4	Reinforcing bars, #3 - #11	ASTM B15, Grade 40, Fy = 40 ksi, Lap splices min 40 bar dia. (25" for #5)
2.4F	Coating for corrosion protection	Anchors, sheet metal ties completely embedded in mortar or grout. ASTM A525, Class G60, 0.60 oz/lb2 or 304SS
2.4F	Coating for corrosion protection	Joint reinforcement in walls exposed to moisture or wire ties, anchors, sheet metal ties not completely embedded in mortar or grout. ASTM A153, Class B2, 1.50 oz/lb2 or 304SS
3.3.E.2	Pipes, conduits, and accessories	Any not shown on the project drawings require engineering approval.
3.3.E.7	Movement joints	Contractor assumes responsibility for type and location of movement joints if not detailed on project drawings.




F1 S-2 STEM WALL FOOTING
SCALE: 1/2" = 1'-0"



F1 S-2 OPTIONAL MONOLITHIC FOOTING
SCALE: 1/2" = 1'-0"




F2 S-2 INTERIOR BEARING FOOTING
SCALE: 1/2" = 1'-0"




F3 S-2 INTERIOR BEARING STEP FOOTING
SCALE: 1/2" = 1'-0"


F4 S-2 OPTIONAL MONOLITHIC CURB FOOTING
SCALE: 1/2" = 1'-0"



F4 S-2 STEM WALL CURB FOOTING
SCALE: 1/2" = 1'-0"



F5 S-2 GARAGE DOOR POCKET FOOTING
SCALE: 1/2" = 1'-0"



FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

FOUNDATION NOTES	
FN - 1	DIMENSIONS ON FOUNDATION & STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL PLANS FOR ACTUAL DIMENSIONS, RECESSES IN SLAB, STEP DOWNS, ETC. DISOSWAY DESIGN GROUP OR MARK DISOSWAY, P.E. IS NOT RESPONSIBLE FOR DIMENSION ERRORS ON THIS PLAN.
FN - 2	CONTRACTOR SHALL VERIFY NEED FOR INTERIOR BEARING (BY THE SUPPLIER) BEFORE FINALIZING FOUNDATION PLAN.
FN - 3	THE SLAB SHALL BE: 4" CONCRETE SLAB REINFORCED w/ 8X6-1.411.4 WELDED WIRE MESH PLACED ON CHAIRS @ 1 1/2" DEPTH OR FIBER MESH CONCRETE, 6-MIL POLY VAPOR BARRIER w/ 8" LAPS SEALED w/ POLY TAPE OVER TERMITES, TREATED & COMPACTED FILL (ALSO, ANY OTHER CODE APPROVED TERMITES-TREATMENT METHOD CAN BE USED INSTEAD).

Amira Custom Homes

Bousquet Residence

PROJECT ADDRESS:
SW 13th Ave
(Columbia County), FL 32643

FL PE 53915

This item has been digitally signed and sealed by Mark Disosway P.E. on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US,
O=Unaffiliated,
dnQualifier=A014
10C00001949239
A3F70003AF06,
CN=Mark d
Disosway
2025-04-14 09:15:
31

DIMENSIONS:
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disosway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 8th Edition Florida Building Code Residential (2023) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.


Mark Disosway P.E.
163 SW Midtown Place
Suite 103
Lake City, Florida 32025
386.754.5419
disoswaydesign@gmail.com

JOB NUMBER:
250370

S-2
OF 3 SHEETS

LUMBER SIZE & GRADE MINIMUM REQUIREMENTS

RISE BOARD	2X6 SYP #2
RAFTER SPANS 20'-0" OR LESS	2X4 SYP #2
PURLIN (LATERAL BRACING)	2X4 SPF #2
BLEEPERS	2" WIDTH OF RAFTER (BEAT CUT) SPF #3 OR 2" PARALLEL 2X4 SPF #3
CRIPPLES & BLOCKING	2X4 SPF #2 OR BETTER
TRUSS BELOW	SEE TRUSS DESIGN - SOUTHERN PINE MATERIAL



SECTION CUT PARALLEL TO VALLEY RAFTER

VALLEY ROOF PLAN MEMBER LEGEND


— TRUSS
 --- TRUSS UNDER VALLEY FRAMING
 --- VALLEY RAFTER OR RIDGE
 --- CRIPPLE
 CRIPPLES 4'-0" O.C. FOR 20 psf (TL) AND 10 psf (TD) (TYP. SHINGLE ROOF) MAX

CONNECTION REQUIREMENT NOTES

1. 2X4 RAFTERS TO RIDGE	3-16d OR 6-... 131 x 3" TOE NAILS
2. CRIPPLE TO RIDGE	3-16d OR 6-... 131 x 3" FACE NAILS
3. CRIPPLE TO RAFTERS	3-16d OR 6-... 131 x 3" FACE NAILS
4. RAFTER TO SLEEPER OR BLOCKING	3-16d OR 6-... 131 x 3" TOE NAILS
5. SLEEPER TO TRUSS	4-16d OR 8-... 131 x 3" FACE NAILS EACH TRUSS
6. RIDGE BOARD TO ROOF BLOCK	3-16d OR 6-... 131 x 3" TOE NAILS
7. RIDGE BOARD TO TRUSS	3-16d OR 6-... 131 x 3" TOE NAILS
8. PURLIN TO TRUSS (TYP)	3-16d OR 6-... 131 x 3" NAILS
9. PURLIN TO TRUSS IF CRIPPLE IS ATTACHED TO PURLIN	4-16d OR 8-... 131 x 3" NAILS
10. TRUSS TO BLOCKING	3-16d OR 6-... 131 x 3" END NAILS
11. CRIPPLE TO PURLIN	3-16d OR 6-... 131 x 3" FACE NAILS

ROOF OVER FRAMING & BRACING DETAIL

SCALE: N.T.S.



ALTERNATE IF TRUSSES ARE PERPENDICULAR TO SHEARWALL

NOTE:
 IF THE ABOVE DETAIL IS USED ON THE REAR PORCH WALL, THE REAR PORCH CEILING DOES NOT NEED TO BE SHEATHED

* ATTACHMENT CAN BE MADE DIRECTLY OR THROUGH PLYWOOD SHEATHING BY CUTTING A 2" x 4" NOTCH IN SHEATHING

BEVEL RAFTER CUT AS REQ'D FOR PITCH

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER

2X4 BLOCKING

2X4 PURLIN 24" O.C. (WHERE NO SHEATHING IS APPLIED)

EXISTING 12" SHEATHING (NOT REQUIRED IF SLEEPERS ARE USED)

2X4 VALLEY RAFTER


STRUCTURAL PLAN

SCALE: 1/4" = 1'-0"

STRUCTURAL PLAN NOTES

SN-1 DIMENSIONS ON STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS

SN-2 PERMANENT TRUSS BRACING IS TO BE INSTALLED AT LOCATIONS AS SHOWN ON THE SEALED TRUSS DRAWINGS. LATERAL BRACING IS TO BE RESTRAINED PER BCS1-03, BCS1-B1, BCS1-B2, & BCS1-B3. BCS1-B1, BCS1-B2, & BCS1-B3 ARE FURNISHED BY THE TRUSS SUPPLIER, WITH THE SEALED TRUSS PACKAGE



HEADER LEGEND

(2) 2X6X8'-1J 1K	HEADER/BEAM CALL-OUT (U.N.O.)
↑	NUMBER OF KING STUDS EACH SIDE OF OPENING (FULL LENGTH)
↑	NUMBER OF JACK STUDS EACH SIDE OF OPENING (UNDER HEADER)
↑	SPAN OF HEADER
↑	SIZE OF HEADER MATERIAL
↑	NUMBER OF PLIES IN HEADER

UNLESS NOTED OTHERWISE (MINIMUM REQUIREMENTS)	
SEE STRUCTURAL PLAN FOR ANY SPECIFIC CALL OUTS	
BEAM / HEADERS (SIZE)	ALL LOAD BEARING FRAME WALL & PORCH HEADERS SHALL BE A MINIMUM OF (2) 2X6 SP #2 (UNO)
HEADERS (JACK & KING STUDS)	ALL LOAD BEARING FRAME WALL HEADERS SHALL HAVE: (1) JACK STUD & (1) KING STUD EACH SIDE (UNO)
HEADERS (STRAPPING)	ALL HEADERS w/ UPLIFT TO BE STRAPPED DOWN @ EACH SIDE WITH (1) LSTA24, 14-10d @ TOP & BOTTOM OF WALL WRAP UNDER BOTTOM PLATE & OVER TOP PLATE 1/2" X 10" ANCHOR BOLT w/ 3" X 3" X 1/4" WASHER MUST BE LOCATED WITHIN 6" OF KING STUD @ ALL DOOR LOCATIONS (U.N.O.)
JACK STUDS UNDER GIRDER TRUSS	USE ONE JACK STUD GIRDER SUPPORT PER 2000 LB LOAD

ACTUAL vs REQUIRED SHEARWALL

	TRANSVERSE	LONGITUDINAL
ACTUAL	33254 LBF	16160 LBF
REQUIRED	21216 LBF	15031 LBF

CONNECTIONS, WALL, & HEADER DESIGN IS BASED ON REACTIONS & UPLIFTS FROM TRUSS ENGINEERING FURNISHED BY BUILDER. BUILDERS FIRST SOURCE JOB #4496337

Amira Custom Homes

Bouquet Residence

PROJECT ADDRESS:
 SW Maynack Drive, High Springs
 (Columbia County), FL 32645

FL PE 53915

This item has been digitally signed and sealed by Mark Disoway P.E. on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US, O=Unaffiliated, dnQualifier=A01410C00001949239A3F70003AF06, CN=Mark d Disoway 2025-04-14 09:15:46

DIMENSIONS: Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disoway P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disoway P.E. hereby expressly reserves all common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 8th Edition Florida Building Code Residential (2023) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

Mark Disoway P.E.
 163 SW Midtown Place
 Suite 103
 Lake City, Florida 32025
 386.754.5419
 disowaydesign@gmail.com

JOB NUMBER:
 250370

S-3
 OF 3 SHEETS