ABBREVIATIONS

4	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
10.0		
	A/C	AIR COOLING UNIT
	ADJ	ADJACENT
	AFF	ABOVE FINISHED FLOOR
	AHU	AIR HANDLING UNIT
	ALUM	ALUMINUM
	BLK	BLOCK
	вот	воттом
	BRG	BEARING
	CJ	CONTROL JOINT
	CLG	CEILING
	COL	COLUMN
	CONC	CONCRETE
	CONT	CONTINUOUS
	CPT	CARPET
	DIA	DIAMETER
	DN	DOWN
	DWG	DRAWING
	EA	EACH
	ELEC	ELECTRIC
	EQ	EQUAL
	FF	FINISH FLOOR
	FTG	FOOTING
	НВ	HOSE BIB
	HDR	HEADER
	HGT	HEIGHT
	MAX	MAXIMUM
	MIN	MINIMUM
	NTS	NOT TO SCALE
	OPNG	OPENING
	SIM	SIMILAR
	TYP	TYPICAL
	VLT	VAULT
	UNO	UNLESS NOTED OTHERWISE

area toulation 'a'

GARAGE	401 SF
FRONT PORCH	21 SF
REAR PATIO	72 SF
FLOOR 1 LIVING	1,607 SF
TOTAL LIVING	1,607 SF

area tabulation 'b'

GARAGE	401	SF
FRONT PORCH	108	SF
REAR PATIO	72	SF
FLOOR 1 LIVING	1,607	SF
TOTAL LIVING	1,607	SF

Covington

38' - 1607 - LH Florida Region (Frame)

INDEX

ARCHITECTURAL

CS COVER SHEET

1 EXTERIOR ELEVATIONS

2 SLAB PENETRATION PLAN

3 FLOOR PLANS

4 SECTIONS & DETAILS
5 INTERIOR DETAILS

5 INTERIOR DETAIL

6 ROOF PLAN

E1 ELECTRICAL PLANS

CD CONSTRUCTION DETAILS

REVISIONS

NUMBER	DATE	DESCRIPTION
01		Added Elevations A1& B1
02	06.14.21	Added outlet to O.Suite & noted outlets to meet 6' max from wall break & 12' max between outlet spacing at at habitable rooms (E1.1)
-		
ll processor de la companya de la co		

Florida Building Code - Residential, 7th Edition (2020)

1. Provide temporary toilet facilities on site (Plumbing Sec 311.1).

2. Provide professional termite treatment of soil per R318.

3. Meet 2017 N.E.C. on all electrical work.

4. Provide passed compaction test to 95% density per R403.

5. Garage door(s) & windows to meet required wind load Sec R301.2.1.

6. All stairs, hand/guard rails to meet Sec R312.

7. Meet emergency egress requirements for bedrooms per R310.


8. Meet tempered glass requirements of Sec R308.4.

9. Roof shingles must meet Section 905.

10. Install smoke detectors in & outside sleeping rooms & at each level per Sec R314 & NFPA 72. Install carbon monoxide alarms per R315.

11. Install 4" high house address number of SFR, identification shall be legible & placed in a position that is visible from the street R319.

12. Meet all 2020 Florida Building Code Requirements.



BUILDING CODE COMPLIANCE

ALL CONSTRUCTION TO COMPLY WITH LOCAL CODES AND ORDINANCE CURRENTLY IN USE WITH THE LOCAL JURISDICTION.

PRODUCT: NEW SINGLE FAMILY DETACHED

OCCUPANCY CLASSIFICATION:

RESIDENTIAL R-3

CONSTRUCTION CLASS:

UNPROTECTED

CONSTRUCTION TYPE:

TYPE VB

EMERGENCY ESCAPE:

EGRESS OR RESCUE WINDOWS FROM SLEEPING ROOMS SHALL HAVE MINIMUM OF 5.7 SQUARE FEET

APPLICABLE CODES:

FOLLOW ALL APPLICABLE STATE AND LOCAL CODES.
FLORIDA STATE SUPPLEMENTS AND AMENDMENTS.

2020 Florida Building Code, Residential, 7th Edition

2017 National Electrical Code, NFPA 70







Lot 003 Reserve at Jewel Lake 33-3S-16-02439-203 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

33811607
RELEASE DATE:
01.11.2021

COVING TITLE:

ET NO:

SHEET NO:

CS


Keynotes | Legend

- CORROSION RESISTANT ROOF TO WALL FLASHING AT ALL ROOF / WALL INTERSECTIONS. CORROSION RESISTANT SCREEN LOUVERED VENTS, SIZE AS NOTED.
- BRICK WAINSCOT WITH SLOPED BRICK ROWLOCK CAP.
 STONE WAINSCOT WITH SLOPED STONE CAP.
 3 1/2" VINYL TRIM SURROUND




REAR ELEVATION 'A1'

1/8" = 1'-0" @ 11x17 1/4" = 1'-0" @ 22x34



FRONT ELEVATION 'A1' 1/8" = 1'-0" @ 11x17 1/4" = 1'-0" @ 22x34









Lot 003


Reserve at Jewel Lake 33-3S-16-02439-203 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

PLAN NUMBER:	33811607	RELEASE DATE:	VS 01.11.2021
MODEL:	COVINGTON	DRAWING TITLE:	EXTERIOR ELEVATIONS


SHEET NO:

1.1-A1



LEFT SIDE ELEVATION 'A1'

1/8" = 1'-0" @ 11x17 1/4" = 1'-0" @ 22x34



RIGHT SIDE ELEVATION 'A1'

1/8" = 1'-0" @ 11x17 1/4" = 1'-0" @ 22x34





Lot 003 Reserve at Jewel Lake 33-3S-16-02439-203 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

33811607 33811607 RELEASE DATE: 01.11.2021

COVINGTON

PRAWING TITLE:


EXTERIOR ELEVATIONS

1.2-A1

SHEET NO:

GENERAL SLAB FOUNDATION NOTES

- PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL PLUMBING LOCATIONS.
- REFER TO EXTERIOR ELEVATIONS FOR BRICK/STONE LOCATIONS.
- GARAGE SLAB SHALL SLOPE TOWARD GARAGE DOOR OPENING.



NOTES & LEGENDS

- 1. REFER TO ENGINEERING STRUCTURAL DRAWINGS (S-#) FOR BEARING WALL LOCATIONS AND FOR ALL BEAM & HEADER SIZES AND BEARING WALL LOCATIONS
- 2. ALL BEARING WALLS SHALL BE 16" O.C. WALL CONST. W/ DOUBLE TOP PLATE U.N.O.
- 3. ALL INTERIOR NON BEARING DOOR & WINDOW HEADERS SHALL BE (1) 2x4 OR (1) 2x6 W/VERTICAL CRIPPLERS @ 2'-0" O.C. TO MATCH WALL WIDTH UNLESS NOTED OTHERWISE.
- 4. (2) HOSE BIBS SHALL BE INSTALLED, LOCATION TO BE DETERMINED BY PLUMBING CONTRACTOR

OPTIONAL WINDOW

2X4 FRAME WALL


2X6 FRAME WALL BALLOON FRAME WALL (PER STRUCTURALS)

KEYNOTES

- A1 GARAGE CEILING 5/8" TYPE X DRYWALL,
- VERTICAL SURFACE WALLS 1/2" DRYWALL A2 22"X30" ATTIC ACCESS CONSTRUCTED WITH GYP. BD. (5/8" TYPE X
- AT GARAGE) WITH DOOR TRIM FRAME ACCESS SUPPORT
- A3 PROVIDE 6" MIN. FLAT CLG AT ANGLED CLG CONDITION
- A4 PULL DOWN STAIRS 25.5" x 54" A5 TEMPERED SAFETY GLASS PER IRC R308.4
- A6 HOUSE TO GARAGE DOOR SEPARATION. PROVIDE APPROVED 20
- MINUTE RATED DOOR PER IRC 302.5.1
- A7 A/C CONDENSER PAD. REFER TO SITE PLAN FOR FINAL LOCATION. VERIFY CONNECTION TO CONC. PAD W/ MANUF. SPECS
- A8 5/8" TYPE X DRYWALL AT ACCESSIBLE AREAS UNDER STAIRS
- D1 DRYWALL SOFFIT 12" DROP FROM CEILING LINE
- D2 DRYWALL SOFFIT 8" DROP FROM CEILING LINE
- K1 39" KNEE WALL WITH CAP PER SPECS
- K2 38" KNEE WALL WITH 1x CAP
- K3 46" KNEE WALL WITH CAP PER SPECS
- K4 34 1/2" KNEE WALL
- K5 42" KNEE WALL WITH 1x CAP
- K6 KNEE WALL WITH 1x CAP 42" ABOVE STAIR NOSING OR LANDING
- P1 30" X 60" SHOWER ENCLOSURE PER SPECS P2 30"X60" TUB PER SPECS
- S1 BOX STAIR WITH 38" KNEE WALL & 1X CAP S2 1X CAPPED STRINGER, TOP AT 3" ABOVE TREAD

area tabulation 'a'

GARAGE	401 SF
FRONT PORCH	21 SF
REAR PATIO	72 SF
FLOOR 1 LIVING	1,607 SF
TOTAL LIVING	1,607 SF



ATTIC VENT CALCULATION

ATTIC VENTILATION TO COMPLY W/ F.B.C RESIDENTIAL CODE. THE REQUIRED NET FREE VENTILATING AREA OF NOT LESS THAN 1/150 OF THE SPACE VENTILATED. AREA MAY BE REDUCED TO 1/300 PROVIDED THAT 50 PERCENT (BUT NOT MORE THAN 80%) OF THE REQ'D VENTILATING AREA IS PROVIDED IN THE UPPER PORTION OF THE SPACE TO BE VENTILATED AT LEAST 3 FEET ABOVE EAVE OR CORNICE WITH THE BALANCE OF THE REQ'D VENTILATION PROVIDED BY THE EAVE OR CORNICE VENTS.

MANUFACTURE SELECTED TO VERIFY THE NET FREE VENTILATION OF THE VENT PRODUCT SELECTED AND TO MAINTAIN THE REQUIRED VENTILATION.

DO NOT LOCATE VENTS ON ROOF PLANE(S) FACING STREET.

ROOF VENTIL	ATION CAL	CULATIONS	
OOF AREA	2,296 SF		
OTAL NET FREE AREA REQ'D (1 TO 300)	1102.1 SQ. IN.		
AIN HOUSE INLET (SOFFIT) VENTILATION	154.0 LF x	6.4 SQ. IN / LINEAR FT =	985.6 SQ. IN
OD VENT(S) REQUIRED WITH BASE HOUSE	8	VENTS AT 70.0 SQ. IN EA. =	560.0 SQ. IN
OWER VENTING PROVIDED (551.0 SQ. IN. REQ'D)	985.6 SQ. IN		
PPER VENTING PROVIDED (551.0 SQ. IN. REQ'D)	560.0 SQ. IN		


OTE: TYPICAL VENTILATION INCLUDES:

SOFFIT VENTS

(AREA: 6.4 SQ. IN PER FOOT - VERIFY WITH MANUFACTURE)

2. LOMANCO 770* ATTIC VENT LOCATED 12" MIN. FROM RIDGE

(AREA: 70 SQ. IN. - VERIFY W MANUFACTURE)
*(1) LOMANCO 770D VENT AT 140 S.I. EA.CAN BE USED IN PLACE OF (2) 770 VENTS.







Lot 003 Reserve at Jewel Lake 33-3S-16-02439-203 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

MODEL:	COVING TITLE: SRAVING TITLE: OCCUPANI OCCUP
--------	--

ROOF PLAN 'A' 1/8" = 1'-0" @ 11x17

6.1-A 1/4" = 1'-0" @ 22x34


ELECTRICAL LEGEND

- 110v RECEPTACLE **SWITCH** 110v SWITCHED RECEPTACLE \$3 3 WAY SWITCH 110v ABOVE COUNTER RECEPTACLE. GFI PROTECTED AT KITCHEN, BATH & LAUNDRY \$4 4 WAY SWITCH 110v DEDICATED RECEPTACLE FOR SECURITY/STRUCTURED WIRING PANEL WALL MOUNTED LIGHT GFI OUTLET LED DOWNLIGHT VP=VAPOR PROTECTED 220v RECEPTACLE 110v FLOOR RECEPTACLE DISCONNECT -CEILING FIXTURE OUTLET B = BRACE FOR FUTURE FAN H = HANGING P = OPT. PENDANT BATH EXHAUST FAN S SMOKE DETECTOR CEILING FAN PREWIRE WITH BRACING FOR FUTURE FAN C SMOKE/CARBON MONOXIDE ALARM PROVIDE ADDITIONAL EXTERIOR WEATHERPROOF RECEPTACLE WITHIN 15 FEET OF CONDENSING UNITS
- INSTALL GFCI AND ARC FAULT CIRCUIT IINTERRUPTER PROTECTION PER NEC SECTIONS 210.52G
- ALL GARAGE OUTLETS SHALL BE ON A DEDICATED CIRCUIT
- DWGS. ARE DIAGRAMMATICAL & INDICATE THE GENERAL ARRANGEMENT OF THE ELECTRICAL WORK. ANY DISCREPANCIES ON
- THE DOCUMENTS SHALL BE CALLED TO THE ARCHITECT'S ATTENTION PRIOR TO THE COMMENCEMENT OF WORK. DO NOT SCALE ELECTRICAL DRAWINGS.

- **KEYNOTES**
- E1 ELECTRICAL PANEL PER SPECS
- E2 INSTALL OUTLET UNDER SINK FOR FUTURE DISPOSAL


E5 COACH LIGHT ONLY IF REQUIRED BY LOCAL MUNICIPALITY

- E3 DOOR CHIME TRANSFORMER LOCATION
- E4 MECHANICAL ROOMS TO INCLUDE KEYLESS LIGHT, PLUG AND DISCONNECT FOR AIR HANDLER



FIRST FLOOR ELECTRICAL PLAN 'A'

1/8" = 1'-0" @ 11x17 1/4" = 1'-0" @ 22x34





Lot 003 Reserve at Jewel Lake 33-3S-16-02439-203 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

MODEL:	PLAN NUMBER:
COVINGTON	33811607
DRAWING TITLE:	RELEASE DATE:
FIRST FLOOR ELECTRICAL	01.11.2021

E1.1

SHEET NO:

REVISION SUMMARY DESIGNER REVISION DESCRIPTION NO. DATE ABBREVIATIONS PSF Pounds per square foot Flr. Sys. Floor System Anchor Bolt P.T. Pressure Treated F.O.M. Face Of Masonry Ft. Foot / Feet Rad. Radius Adjustable Above Finished Floor Rnd. Round General Contractor Ground Fault Interrupter S.F. Square Ft B/Beam Bottom of Beam SHT Sheet Girder Truss S.L. Side Lights S.P.F. Spruce Pine Fir Circle Sa. Square Interior S.Y.P. Southern Yellow Pine Control Joint Thik'n. Thicken T.O.B. Top of Block T.O.M. Top of Masonry T.O.P. Top of Plate Trans. Transom Window Typ. Typical Each Way U.N.O. Unless Noted Otherwise N.T.S. Not to Scale Vert. Vertical Elevation Engineering or Record VTR Vent through Roof W.A. Wedge Anchor Fin. Flr. Finished Floor PLF Pounds per linear foot Foundation TERMITE SPECIFICATIONS SECTION R318 PROTECTION AGAINST TERMITES FERMITE PROTECTION SHALL BE PROVIDED BY REGISTERED TERMITICIDES, INCLUDING SOIL APPLIED ESTICIDES, BAITING SYSTEMS, AND PESTICIDES APPLIED TO WOOD, OR OTHER APPROVED CONSTRUCTION (SEE SECTION 202, REGISTERED TERMITICIDE). UPON COMPLETION OF THE APPLICATION OF THE TERMITE PROTECTIVE TREATMENT. A CERTIFICATE OF COMPLIANCE SHALL BE SSUED TO THE BUILDING DEPARTMENT BY THE LICENSED PEST CONTROL COMPANY THAT CONTAINS THE FOLLOWING STATEMENT: "THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. TREATMENT IS IN ACCORDANCE WITH RULES AND LAWS ESTABLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES." PER DETAIL MS05/D1 METHOD OF TREATMENT SHALL BE APPROVED BY THE GOVERNING JURISDICTION "LIQUID BORATE OR BOR-A-COR" PRODUCT METHODS MUST BE DETERMINED AT PERMIT STAGE AND PRODUCT APPROVAL DATA MUST BE ON FILE WITH THE BUILDING DEPARTMENT. PRESSURE TREATED LUMBER THAT HAS BEEN CUT OR DRILLED THAT EXPOSES UNTREATED PORTIONS OF WOOD ARE REQUIRED TO BE FIELD TREATED TO PREVENT INSECT INFESTATION. OPTIONAL BORATE APPLIED TO ALL FRAME MEMBERS WITHIN 24" A.F.F. STRENGTH OF 2000 PSfm = 2000 PSI -- NOTICE TO BUILDER AND ALL SUBCONTRACTORS- -T IS THE INTENT OF THE ENGINEER LISTED IN THE TITLEBLOCK OF THESE DOCUMENTS THAT THESE DOCUMENTS BE ACCURATE, PROVIDING LICENSED PROFESSIONALS CLEAR INFORMATION. EVERY ATTEMPT HAS BEEN MADE TO PREVENT ERROR. THE BUILDER AND ALL SUBCONTRACTORS ARE REVIEW ALL THE INFORMATION CONTAINED IN THESE DOCUMENTS, PRIOR TO THE COMMENCEMENT OF ANY WORK. THE ENGINEER ARE NOT RESPONSIBLE FOR ANY PLAN ERRORS, OMISSIONS, OR MISINTERPRETATIONS UNDETECTED AND NOT REPORTED TO THE ENGINEER SHALL STRICTLY OBSERVE ALL APPLICATION CODES DURING THE COURSE OF CONSTRUCTION INCLUDING ALL STATE, CITY, AND COUNTY BUILDING, ZONING, ELECTRICAL, MECHANICAL. PLUMBING AND FIRE CODES. CONTRACTOR SHALL VERIFY ALL CODE REQUIREMENTS PRIOR TO THE ARCHITECT / ENGINEER SHALL NOT BE RESPONSIBLE FOR SAFETY PROCEDURES, THE MEANS AND METHODS OF CONSTRUCTION, TECHNOLOGIES, OR THE CONTRACTION TO CARRY OUT THE

WORK IN ACCORDANCE WITH THE DRAWINGS AND SPECIFICATIONS OR RELATED CODES.

DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION

TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO

ACCORDANCE TO THE TERMS OF THE AGREEMENT.

ALL CONSTRUCTION MUST BE IN ACCORDANCE TO THE INFORMATION FOUND IN THESE

CHARGES WILL BE CONSIDERED FOR REIMBURSEMENT BY THE THE ENGINEER WITHOUT

ADVANCED NOTIFICATION AND APPROVAL BY THE ENGINEER. PAYMENTS WILL BE MADE IN

CONSTRUCTION.

TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER

(DELEGATED ENGINEER) HAS FINAL, RESPONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS

PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS

ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT

DOCUMENTS. ANY QUESTIONS REGARDING THE INFORMATION FOUND IN THESE PLANS SHOULD

BE DIRECTED TO OUR QUALITY ASSURANCE MANAGER AT 321-972-0491 IMMEDIATELY. NO BACK

CENTURY COMPLETE 38-1607 COVINGTON A LH

GENERAL STRUCTURAL NOTES

CAST IN PLAC REINFORCED CONCRETE

ALL CONCRETE SHALLIVE A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 2500 PSI (SLABS) 3000 PSI (COLUMNS AND BEAMS), A SLUMP OF 5" PLUS OR MINUS 1", ANIAVE 2 TO 5% AIR ENTRAINMENT, AND A MAXIMUM WATER/CEMENT RATIO OF 0.63 HOOKS SHALL BE PROJED AT DISCONTINUOUS ENDS OF ALL TOP BARS OF BEAMS.

HORIZONTAL FOOTINGARS SHALL BE BENT 25" AROUND CORNERS OR CORNER BARS WITH A 25" LAP PROVIDED EA WAY. CONCRETE COVER MIN" WHEN EXPOSED TO EARTH OR 1 1/2" TO FORM U.N.O.

FIBER MESH LENGTH SLL BE 1/2" TO 2", DOSAGE AMOUNT SHALL BE FROM 1.0 TO 1.5 LBS PER CUBIC YARD IN ACCORDANCE WITH THE MANUFACTURER'S AN[HALL COMPLY WITH ASTM C1116 ALL REINFORCING STE / STIRRUPS AND TIES SHALL BE NEW DOMESTIC DEFORMED BARS FREE FROM RUST, SCALE & OIL & SHALL MEET ASTM A615/ REINFORCING SHALL POSITIVELY SUPPORTED BY TEMPORARY STRINGERS. DOWELS FOR COLUMNS & FILLED CELLS SHALL BE SECURED IN PLACE BY USING ADDINAL CROSS- REINFORCING TIED TO FOOTING REINFORCING. SPLICES IN REINFORCING WHERE PERMITTED SHALL BE AS

HIGH STRENGTH SIMP'N SET EPOXY-TIE WAS USED IN THE DESIGN OF THIS PRODUCT. IF CONTRACTORS WISH TO USE A DIFFERENT EPOXY, THEY MUST FIRST CONTACTIE ENGINEER OF RECORD FOR WRITTEN APPROVAL. WHERE PROJECT IS T(E LOCATED IN KNOWN RADON GAS PREVALENT AREAS, APPENDIX "F" OF THE FLORIDA BUILDING CODE 7TH EDITION (2020)

RESIDENTIAL IS TO BEPLEMENTED. F303.4 CONCRETE STRENGTH IN THESE AREAS ARE TO BE A MINIMUM OF 3000 P.S.I. THEREFORE, ANY AND ALL NOTES ON THESE ANS THAT INDICATE 2500 P.S.I. SHALL BE REPLACED WITH 3000 P.S.I. FOR THE CONCRETE STRENGTH.

HOLLOW LOAD BEARINUNITS SHALL BE NORMAL WEIGHT, GRADE N, TYPE 2, CONFORMING TO ASTM C90-014, WITH A MINIMUM NET COMPRESSIVE

MORTAR SHALL BE TYF"S", CONFORMING TO ASTM C270-14A COARSE GROUT SHALIONFORM TO ASTM C476-10 WITH A MAXIMUM AGGREGATE SIZE OF 3/8" AND A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 3000 PSI SLUI 8" TO 11". CONTINUOUS MASONRY INSPECTIONS ARE REQUIRED DURING CONSTRUCTION

GRADE 60 U.N.O. VERTAL REINFORCEMENT SHALL BE AS NOTED ON THE DRAWINGS WITH THE CELLS FILLED WITH COARSE GROUT GRADE 60 U.N.O. VERTIL REINFORCEMENT SHALL BE HELD IN POSITION AT THE TOP AND BOTTOM AND AT A MAXIMUM SPACING OF 192 DIA OR 10FT WHICH EVER IS LESS. INFORCING SHALL BE PLACED IN THE CENTER OF THE MASONRY CELL WITH MIN 1/2" CLEARANCE TO INSIDE FACE. REINFORCING STEEL SLL BE LAPPED PER DETAIL MS05/D1, UNLESS OTHERWISE NOTED ON THE DRAWINGS.

GROUT STOPS SHALL [PROVIDED BELOW BOND BEAM. PLASTIC SCREEN, METAL LATH STRIP OR CAVITY CAPS MAY BE USED TO PREVENT THE FLOW OF GROUT INTCELLS BELOW. THE USE OF FELT PAPER AS A STOP IS PROHIBITED. TEMPORARY BRACING OF SHORING OF WALL TO PROVIDE STABILITY DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TYPICAL FILLED CELL FNFORCING SIZE AND SPACING SHALL BE ABOVE AND BELOW ALL WALL OPENINGS

DO NOT APPLY UNIFOFLOADS TO MASONRY WALLS FOR (3) DAYS AND NO CONCENTRATED LOADS FOR (7) DAYS. PER CODE ACI 318-14 CONSOLIDATE POURS CEEDING 12" IN HEIGHT BY MECHANICAL VIBRATION, AND RECONSOLIDATE BY MECHANICAL VIBRATION AFTER INITIAL WATER LOSS AND SETEMENT HAS OCCURRED. GROUT SHALL BE FLUSH WITH TOP OF WALL.

ALL EXTERIOR WOOD 9DS WALLS, BEARING WALLS, SHEAR WALLS, AND MISC. STRUCTURAL WOOD FRAMING MEMBERS, (I.E. BLOCKING OR GABLE END BRACING) SHALL (EITHER AS SPECIFIED IN PLAN OR IN DETAILS. IF CONFLICTS OCCUR BETWEEN PLAN AND DETAILS, THE STRONGEST MATERIAL SHÁLL BE UD. AT A MINIMUM, ALL WOOD STRUCTURAL FRAMING MEMBERS SHALL BE SPF #2.

ALL LUMBER SPECIFIEDN DRAWINGS ARE INTENDED FOR DRY USE ONLY (MOISTURE CONTENT 19% OR LESS), U.N.O. ALL WATERPROOFING AND FIRE SAFETY SYSTEMSE THE RESPONSIBILITY OF THE CONTRACTOR AND ARE TO BE DESIGNED AND DETAILED BY OTHERS ANY WOOD FRAME INRIOR BEARING WALL STUDS THAT HAVE HOLES IN THE CENTER OF THE STUD UP TO 1" DIA. SHALL HAVE STUD PROTECTION THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE SHIELDS. ALL HOLES €R 1" IN DIA. FOR PLUMBING LINES, ETC. SHALL BE REPAIRED WITH SIMPSON HSS2 STUD SHOES, TYP., U.N.O. MANY OF THE NEW PRBURE TREATED WOODS USE CHEMICALS THAT ARE CORROSIVE TO STEEL. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE TYPE OF VOD TREATMENT AND TO SELECT APPROPRIATE CONNECTORS THAT RESIST CORROSION. FOR EXAMPLE, ACQ-C, ACQ-D, CBA-A OR CA-B REQUIFHOT-DIPPED GALVANIZED OR STAINLESS STEEL FASTENERS. DOT SODIUM BORATE (SBX) DOES NOT.

ALL EXPOSED WOOD GWOOD IN CONTACT WITH EARTH OR CONCRETE TO BE PRESSURE TREATED UNTREATED WOOD SHL NOT BE IN DIRECT CONTACT WITH CONCRETE OR MASONRY. SEAT PLATES SHALL BE PROVIDED AT BEARING LOCATIONS WITHOUT WOODEN TO'LATES.

SEE PLAN FOR STUD PK AND BEAM NAILING PATTERNS ALL ENGINEERED LUMR TO HAVE THE FOLLOWING MIN VALUES U.N.O. PARALLAM COLUM: 1.8E Fb = 2400 PSI

OR C1787, OR AS OTHE/ISE APPROVED (REF. 2020 FBC-R-R703.7.1).

MICROLAM (LVL) BMS: 2.0E Fb= 2600 PS GLULAM BEAMS: SSP 24F-V5 LAYUP (1.7E FB=2400 PSI) MIN.

SEE PLAN NOTE FOR AITIONAL ROOF, WALL, SHEAR WALL AND FLOOR SHEATHING REQUIREMENTS ALONG W/ NAILING INFORMATION OTHERWISE: 9.1. ROOF DECK: PLYWD C-C/C-D, EXTERIOR OR OSB 9.2. FLOOR SHEATHING&G A-C GROUP 1 APA RATED (48/24) SHEATHING SHALL FINISH FLUSH TO EXTERIOR WALL FACE.

WALL SHEATHING; "STRUCTURAL I OSB EXPOSURE 1 OR 15/32" RATED OSB EXPOSURE 1 (SPECIFIC GRAVITY, G=0.50, MIN.). A MINIMUM 1/8" SPACE IS RECOMMENDED:TWEEN PANELS AT EDGE AND END JOINTS TO ALLOW FOR EXPANSION. PER R604.3 SHEATHING SHALL NOT BE USED AS LATH AND LATH ATTACIENTS SHALL BE OF CORROSION-RESISTANT MATERIALS. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED TO

WOOD SHEATHING WITI LONG, 11 GAGE NAILS HAVING A 7/6" HEAD, OR 1 1/2" LONG, 16 GAGE STAPLES, SPACED IN ACCORDANCE WITH ASTM C1062

STRUCTURAL STTEEL

MATERIAL SPECIFICATIONS: S: WIDE FLANGE SECTIONS: ASTM A992, GRADE 50, Fy=50 KSI TUBE STEEL (HSS): ASTM A500, GRADE B, Fy = 46 KSI PIPE STEEL: ASTM F3125, TYPE E (E OR S, Fy = 35 KSI ALL OTHER STRUCTURAL & MISC. STEEL: A36 Fy=36 KSI STRUCTURAL CONNECTIONS: ALL STRUCTURAL

STRUCTURAL BOLTS SMALLE LER THAN 5/8" DIA. TO BE A307 THREADED ROD SHALL CONFORM TO A36 OR A307 ANCHOR BOLTS SHALL CONFORM TO ASTM F1554 ALL BOLTS CASTST IN CONCRETE: ASTM A36 OR ASTM A-307 SHOP AND FIELD WELDS: E70XX ELECTRODES STEEL REINFORCEMENT SHOP

DRAWINGS TO BE PROVIDEDED TO ENGINEER OF RECORD BEFORE FABRICATION FOR REVIEW AND APPROVAL STRUCTURAL CONNECTIONS NS: ALL STRUCTURAL BOLTS TO BE A325N U.N.O. ALL A325N BOLTS SHALL BE BROUGHT TO A "SNUG-TIGHT" CONDITION , AS DEFINED IN THE SPECIFICAT ATION. SLIP CRITICAL (SC) BOLTS MUST BE FULLY TENSIONED PER SPECIFICATION STRUCTURAL BOLTS SMALLER THAN 5/8

ASTM A36 OR ASTM A-307 SHSHOP AND FIELD WELDS: E70XX ELECTRODES STEEL REINFORCEMENT SHOP DRAWINGS TO BE PROVIDED TO ENGINEER OF RECORD BEFORE FABRICATION FOR REVIEW AND APPROVAL. WELDED CONNECTIONS: ELECTRODES - E70XX UNO (LOW HYDROGEN). FILLET WELDS SHALL BE 3/16" UNO.

SUBMIT SHOP DRAWINGS ININDICATING ALL SHOP AND ERECTION DETAILS INCLUDING PROFILES, SIZES, SPACING, AND LOCATIONS OF STRUCTURAL MEMBERS, CONNECTION AT TACHMENTS, FASTENERS, LOAD, AND TOLERANCES.

STRUCTURAL STEEL SHALL IL RECEIVE SHOP COAT OF PRIMER (COLOR AS DIRECTED BY ARCHITECT) EXCEPT FOR AREAS WHICH WILL RECEIVE SPRAY-ON FIRE PROTECTION

6. A CERTIFIED TESTING AGEN NCY SHALL BE ENGAGED TO PERFORM INDUSTRY STANDARD INSPECTIONS TO ENSURE CONFORMANCE WITH PLANS AND SPECIFICATIONS (IF PROVIDINED). SUBMIT REPORTS TO ARCHITECT AND ENGINEER.

PRE ENGINEEREED WOOD TRUSSES

ALL PREFABRICATED WOOD, D TRUSSES SHALL BE SECURELY FASTENED TO THEIR SUPPORTING WALLS OR BEAMS WITH HURRICANE CLIPS OR

ANCHORS PER STRUCTURAL AL PLAN PREFABRICATED WOOD TRUGUSSES SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF THE "NATIONAL DESIGN SPECIFICATION FOR STRESS-GRADE LUMBER AN IND ITS FASTENERS" AS RECOMMENDED BY THE NATIONAL FOREST PRODUCTS ASSOCIATION.

TRUSS MEMBERS AND CONNINECTIONS SHALL BE PROPORTIONED (WITH A MAXIMUM ALLOWABLE STRESS INCREASE FOR LOAD DURATION OF 25%) TO WITHSTAND THE LIVE LOADS GIVEN IN THE NOTES AND TOTAL DEAD LOAD

BRIDGING FOR PRE-ENGINE BEERED TRUSSES SHALL BE AS REQUIRED BY THE TRUSS MANUFACTURER UNLESS NOTED ON THE PLANS. TRUSS ELEVATIONS AND SEJECTIONS ARE FOR GENERAL CONFIGURATION OF TRUSSES ONLY. WEB MEMBERS ARE NOT SHOWN, BUT SHALL BE DESIGNED BY THE TRUSS MMANUFACTURER IN ACCORDANCE WITH THE FRAMING DESIGN LOADS:

DESIGN SPECIFICATIONS FO-OR LIGHT WEIGHT METAL PLATE CONNECTED WOOD TRUSSES PER THE TRUSS PLATE INSTITUTE TPI LATEST EDITION PRE-ENGINEERED WOOD TRITRUSSES SHALL BE DESIGNED BY THE MANUFACTURER IN ACCORDANCE WITH SPECIFIED LOADS AND GOVERNING CODES SUBMITTALS SHALL INCLUDED TRUSS FRAMING PLANS AND DETAILS SHOWING MEMBER SIZES, BRACING, ANCHORAGE, CONNECTIONS, TRUSS LOCATIONS, AND PERMANENERT BRACING AND/OR BRIDGING AS REQUIRED FOR ERECTION AND FOR THE PERMANENT STRUCTURE. EACH SUBMITTAL SHALL BE SIGNED AND SEALALED BY A FLORIDA REGISTERED STRUCTURAL ENGINEER. SUBMIT 3 COPIES FOR REVIEW AND APPROVAL PRIOR TO

8. THE TRUSS MANUFACTUREFER SHALL DETERMINE ALL SPANS WORKING POINTS, BEARING POINTS, AND SIMILAR CONDITIONS. TRUSS SHOP DRAWINGS SHALL SHOW ALL TRUSSES, S, ALL BRACING MEMBERS, AND ALL TRUSS TO TRUSS HANGERS.

UPLIFT CONNECTORS

UPLIFT CONNECTORS SUCH; HAS HURRICANE CLIPS, TRUSS ANCHORS AND ANCHOR BOLTS ARE ONLY REQUIRED ON MEMBERS IN WALLS THAT ARE EXPOSED TO UPLIFT OR LATATERAL FORCES. INTERIOR LOAD BEARING WALLS ARE NOT ALWAYS EXPOSED TO UPLIFT FORCES. THE MEMBERS OF THESE WALLS WOULD NOT TO HAVE CONNECTORS APPLIED. PLEASE COORDINATE THE TRUSS ENGINEER FOR THE LOCATION OF THESE WALLS.AND STRUCTURAL PLPLANS FOR MORE INFO.

FIELD REPAIR NOTES

MISSED "J" BOLTS FOR WOO OD BEARING WALLS MAY BE SUBSTITUTED WITH 1/2" DIA. EPOXY ANCHORS WITH 7" EMBEDMENT. SIMPSON "SET" EPOXY ADHESIVE BINDER FOLLOWIJNING ALL MANUFACTURER'S RECOMMENDATIONS OR SIMPSON 1/2" TITEN HD BOLTS WITH MINIMUM 7" EMBEDMENT. SEE PLAN FOR EMBEDMENT DEPETH AT FLOOR STEPS.

FOR MISSED VERT. DOWELS, DRILL A 3/4" DIAMETER HOLE 6" DEEP AT THE LOCATION OF THE OMITTED REBAR AND INSTALL A 32" LONG #5 BAR INTO THE EPOXY FILLED HOLE. USUSE A TWO PART EMBEDMENT EPOXY (SIMPSON HIGH STRENGTH EPOXY-TIE ANCHORING ADHESIVE) MIXED PER THE MANUFACTURER'S INSTRUC JCTIONS. ASSURE THAT ALL DUST AND DEBRIS FROM DRILLING ARE REMOVED FROM THE HOLE BY BRUSHING AND USING COMPRESSED AIR PRIOR TO APPLYING THE EPOXY. ALLOW THE EPOXY TO CURE TO THE MANUFACTURER'S SPECIFICATIONS, THEN FILL THE CELL IN THE NORMAL WAY DURING E BOND BEAM POUR.

FOR MORTAR JOINTS LESS TO THAN 1/4", PROVIDE (1) #5 VERT. IN CONC. FILLED CELL EACH SIDE OF THE JOINT (BAR DOES NOT HAVE TO BE CONT. TO

MISSED LINTEL STRAPS FOR MASONRY CONSTRUCTION MAY BE SUBSTITUTED WITH (1) SIMPSON MTSM16 TWIST STRAP W/ (4) 1/4"x 21/4" TITENS TO MASONRY AND (7)-10d NAILS_LS TO TRUSS FOR UPLIFTS LESS THAN 860 LBS (USE (2) MTSM16 FOR UPLIFTS LESS THAN 1660#). IF CORNER STRAP IS MISSED, CONTRACTOR IS TO INSTALL (2) SIMPSON HGAM10 W/ (4) 1/4" x 1 1/2" SDS SCREWS AND (5) 1/4" x 2 1/4" TITENS ONE EACH SIDE OF TRUSS. NO MORE THAN 10 STRAPS AS MAY BE SUBSTITUTED OR NO MORE THAN 3 IN A ROW WITHOUT APPROVAL FROM EOR. IF GIRDER TRUSS CONNECTIONS

ARE MISSED, CONTACT THE JE EOR FOR SUBSTITUTION. IF MISSED, MSTAM36 OR MS ISTAM40 STRAP IS MISSED FOR 2ND FLOOR JAMB STUD CONNECTION, CONTRACTOR MAY INSTALL SIMPSON HTT5 W/ (26) 16d x 21/2" NAILS AND 5/8" ANANCHOR BOLT SET IN SIMPSON HIGH STRENGTH EPOXY W/ MIN 6" EMBEDMENT AND MIN 3" EDGE DISTANCE. CONTACT EOR IF STRAPS ARE MISSED UND DER GIRDER JAMB STUD LOCATIONS.

STRUCTURAL DESIGN CRITERIA

CODE CRITERIA

- FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIA
- FLORIDA FIRE PREVENTION CODE 7TH EDITION (2020)
- FLORIDA BUILDING CODE ACCESSIBILITY 7TH EDITION (2020)

- NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION 2018 EDITION

BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE - (ACI 318-14

- APA PLYWOOD DESIGN SPECIFICATION E30-16
- AMERICAN SOCIETY OF CIVIL ENGINEERS: ASCE/SEI 7-16 ALUMINUM DESIGN MANUAL - AAF-20

GENERAL ROOF LOADING

	SHINGLE ROOF (PSF)	METAL ROOF (PSF)	TILE ROOF (PSF)	HEAVY ROOF (PSF
TOP CHORD LL TOP CHORD DL	20 10	20 10	20 15	20 25
BOTTOM CHORD LL* BOTTOM CHORD DL	0 10	0 10	0 10	0 10
TOTAL (PSF)	40	40	45	55
BOTTOM CHORD LL (OPT) ATTICS W/ LIMITED STORAGE ATTICS W/ HEAVY STORAGE * ATTICS W/ NO STORAGE (NON-CONCURRENT)	20 50 10			

NOTE: LL REDUCTIONS ARE ALLOWED PER CODE BUT ONLY WITH WRITTEN APPROVAL FROM EOR OR INDICATED ON PLAN

GENERAL FLOOR LOADING

40 (PSF) 10 (PSF)	COMMENTS:
0 (PSF)	
	10 (PSF)

PASSENGER VEHICLE GARAGES

SPECIAL FLOOR LOADING BALCONIES/ DECKS d. A SINGLE CONCENTRATED LOAD BALCONIES OVER 100 SQ:FT APPLIED IN ANY DIRECTION AT AN LIGHT STORAGE POINT ALONG THE TOP. GUARDRAILS AND HANDRAILS 200(LBS)(d) f. BALUSTERS AND PANELS FILLERS GUARDRAIL IN-FILL COMPONENTS 50 (LBS)(f) SHALL BE DESIGNED TO WITHSTAND STAIRS / NON SLEEPING ROOMS 40 (PSF) A HORIZONTALLY APPLIED NORMAL LOAD OF 50 POUNDS ON AN AREA IBRARIES - STACK ROOMS EQUAL TO 1 SQ. FT. HABITABLE ATTICS SERVED w/ FIXED STAIRS

DEFLECTION CRITERIA

****TL MAX 1/4" DIFFERENTIAL BETWEEN

WIND LOADING CRITERIA

WIND SPEED (ALLOWARI F 101.0 MPH XPOSURE CATEGORY **ENCLOSURE CLASSIFICATION** ENCLOSED

NOTE: MEAN ROOF HEIGHT FOR TYPICAL SINGLE STORY HOME IS 15FT, AND FOR STORY HOME IS 30FT

ASCE 7-16 WALL DESIGN ALLOWABLE COMPONENTS

AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 60 ft FFECTIVE WIND PRESSURE AND SUCTION (PSF)

VIND AREA (SQ FEET)	(+) VALUE DEN -) VALUE DE	NOTES F		WIND PRESSURE AND SUCTION DIAGRAM
AREA		4		(5)	
10 - 19.99	(A)	(+) 25.5 (-) 26.6	B	(+) 25.5 (-) 33.6	
20 - 49.99	0	(+) 24.4 (-) 26.6	D	(+) 24.4 (-) 30.8	
50 - 99.99	E	(+) 22.8 (-) 23.8	F	(+) 22.8 (-) 28.0	5
> 100	G	(+) 21.7 (-) 23.8	H	(+) 21.7 (-) 26.6	4 5 5
GARA	AGE D	OORS*		SOFFIT	
9'-0" x 7'-0'	'	16'-0" x 7'-0	n		10
(+) 22.5 (-) 25.5	J	(+) 21.7	(K)	(+) 25.5 (-) 33.6	DIAGRAM

GENERAL PRESSURE NOTES

D2 FRAMING DETAILS

D3 FRAMING DETAILS

D4 FRAMING DETAILS

D5 FRAMING DETAILS

MULTIPLY THE ABOVE PRESSURES BY 1.67 TO GET ULTIMATE WIND

INDICATED PRESSURES CAN BE INTERPOLATED FOR OTHER DOOR SIZES, OTHERWISE USE LOAD ASSOCIATED WITH THE LOWER EFFECTIVE AREAS. DESIGNATED AREAS WHERE THE ULTIMATE WIND SPEED IS 140 MPH OR GREATER AND IS CONSIDER TO BE IN THE WIND-BOURNE DEBRIS AREA. CONTRACTOR TO PROVIDED ADDITIONAL INFO AS REQUIRED FOR

SO NOTES & SCHEDULES S1 FOUNDATION PLAN A S2 ROOF FRAMING PLAN A SN NOTES & SCHEDULES ewed for Code Compliance D1 FOUNDATION DETAILS

SHEET INDEX








LOT 3 RESERVE AT JEWEL LAKE 33-3S-16-02439-203 LAKE CITY, FL 32024

33811607

OVINGTON

SHEET



FOUNDATION PLLAN A

SCALE: 1/4" = 1'1'-0" @ 22x34 SCALE: 1/8" = 1'1'-0" @ 11x17

FOUNDATION LEGEND

DESIGN DESCRIPTION
INDICATES CONCRETE FOOTING W/ MINIMUM SOIL BEARING CAPACITY OF 20 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SI FOR DESIGN SPECIFICATIONS.

INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE ½" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12'x12' SQUARE MAXIMUM

#" INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET **D1**4" 2500 PSI CONC. SLAB W/ REINF. PER S0

W/6 MIL VISQUEEN VAPOR BARRIER &
TREATED FOR TERMITES. SEE
FOUNDATION SCHEDULE ON SN

INDICATES BUILT UP COLUMN, SEE
FRAMING PLAN FOR SIZE, DETAIL WF37/SN
FOR PLY ATTACHMENT, AND UPLIFT
CONNECTION SCHEDULE ON SN FOR
CONNECTION TO SLAB

GENERAL NOTES:

 TYPICAL CORNER FRAMING PER DETAIL FM19/D1
 SEE ARCHITECTURAL PLANS FOR ALL SLAB STEP DEPTHS IF SHOW SHOWN WITHIN THESE DOCUMENTS

PLAN KEY NOTES



LOT 3 RESERVE AT JEWEL LAKE

33-3S-16-02439-203

LAKE CITY, FL 32024

BUILDER NOTE:

ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES
SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN
PROFESSIONAL FOR CLARIFICATION PRIOR TO
COMMENCEMENT OF CONSTRUCTION


WALL TYPE			
SYMBOL	DESIGN DESCRIPTION		
	2x_ INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.		
[1:1:1:1:1:1]	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN		
	2x WOOD FRAME EXTERIOR WALL		

PLAN NUMBER: 33811607 RELEASE DATE:

COVINGTON

SHEET NO:

La Cel R42707 EXAMINER - LICENSE NO. S1




NOTE:

WIND AREA


DESIGN DESCRIPTION SYMBOL ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft INDICATES BEARING WALL SEE BEARING WIND SPEED (ULTIMATE) 130 MPH WIND SPEED (ALLOWABLE) 100.7 MPH WOOD BEARING SCHEDULE ON SN, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, EXPOSURE CATEGORY C 2x4 MINIMUM U.O.N. WIND PRESSURE AND SUCTION (PSF) HIP ROOF >20 TO 27 DEG. (+) VALUE DENOTES PRESSURE [4:12]-[6:12] (-) VALUE DENOTES SUCTION INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN AREA | ROOF | 1 | 2e | 2n | 2r | 3 | 3e | 3r FOR PLY ATTACHMENT AND UPLIFT HIP -33.0 -45.50 -45.50 -45.50 CONNECTION SCHEDULE ON SN FOR GABLE -35.0 -35.0 -55.90 -55.90 **CONNECTION TO SLAB** ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE): INDICATES NO BOTTOM CONNECTOR ZONE 1: ASTM F1667 RSRS-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C IN FIELD REQUIRED ZONE 2e, 2n, 2r: ASTM F1667 RSRS-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C IN FIELD ZONE 3, 3e, 3r: ASTM F1667 RSRS-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C IN FIELD INDICATES UPLIFT CONNECTION ROOF SHEATHING: CONSTRUCTED PER DETAIL UPLIFT SHINGLE: 7/16" EXP. 1 (24/16) or 15/32" EXP. 1 (32/16) CONNECTOR SCHEDULE ON SHEET SN TILE: 15/32" EXP. 1 (32/16) FRAMING NOTES: PER CODE ASTM F1667 RSRS-01 REFERENCE TO 8d (2 %" x 0.113") NAILS SEE WIND SPEED CHART ON SO FOR WINDOW WHERE THE SHEATHING THICKNESS IS GREATER THAN 15/32", SHEATHING SHALL BE FASTENED hat hard hat WITH ASTM F1667 RSRS-03 10d (21/2" x 0.131") NAILS OR ASTM F1667 RSRS-04 (3" x .120") NAILS PRESSURES GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER GABLE ROOF > 20 TO 27 DEG. AT SECOND FLOOR FOR TYPICAL CORNER FRAMING RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING [4:12]-[6:12] SEE DETAIL FB06/D4 @ 16" O.C FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE. GENERAL NOTES: THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION. SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES. PLAN KEY NOTES LOT 3 RESERVE AT JEWEL LAKE 33-3S-16-02439-203 SIMPSON MGT w/ (22) 0.148 x 1 1/2" & (1) 5/8" ATR & LAKE CITY, FL 32024 SIMPSON HDU4-SDS 2.5 w/ (10) 1/4" x 2 1/2" SDS SCREWS **BUILDER NOTE:** IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND CALL THE ENGINEER OF RECORD PRIOR TO PLAN NUMBER: 33811607 **WALL TYPE** DESIGN DESCRIPTION 2x_INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS. INDICATES BEARING WALL SEE <u>BEARING</u> WOOD BEARING SCHEDULE ON SN 2x WOOD FRAME EXTERIOR WALL


ROOF FRAMING PLAN A

SCALE: 1/4" = 1'-0" @ 22x34 SCALE: 1/8" = 1'-0" @ 11x17



COVINGTON





SPF SYP

535 565

850 990

2250 2620

3240-F 3770-F

5010-F | 6960-F

U#1135 U#1135

SYP-F SYP-M

770 910

8750 10180

-SEE SCHEDULE


DOUBLE 2 x #2 S.Y.P. HEADER w/ 1/2" FLITCH PLATE HEADER. (U.N.O.)


FILLING AND BLOCKING AS

-2 x 4 STUDS TYP.

P.T. BOT. PLATE

U#1895






M


WWW FDSENG COM


RESERVE AT JEWEL LAKE


33-3S-16-02439-203


LAKE CITY, FL 32024












SCALE: 3/8" = 1'-0" @ 11x17

SECTION AT HIP GABLE



INTERIOR BEARING STEP-DOWN
SHEARWALL w/UPLIFT


SCALE: 3/4" = 1'-0"@ 22x34
SCALE: 3/8" = 1'-0"@ 11x17

10d NAILS AT 6" O.C. -= FLOOR TRUSS SEE PLAN (2)-12d TOENAILS _ ÈÁCH JOIST — (2) 2x TOP PLATE CONST. GRADE SPF FLOOR TRUSS SPLICE MIN. OF 24" APART RIM JOIST BLOCKING CUT TO FIT TIGHTLY BETWEEN FLOOR JOIST TOP & BOTTOM CHORD W/ STRUCTURAL SHEATHING 1/8" GAP MAX W/ 10d TOENAILS (MIN. 15/32") w/8d. NAIL 3" O.C. TOP & BOTTOM, 4" SIDES & 4" O.C. @ 6" O.C. TO TOP PLATE EACH SPACE TYP. & 10d-TOENAILS TO EACH INTERIOR. SHEATHING MAY TOP & BOTTOM CHORD EACH END. ---RUN HORIZ. SEE BRG. WALL SCHEDULE FOR STUD SIZE & GRADE & CONNECTION INFO.


> UPLIFT VALUES - (DOUBLE SIDE PLYWOOD DOUBLES VALUE BELOW) SHEATHING I-SIDE - 860 LBS. PER TRUSS/JOIST/RAFTER

SW02 INTERIOR SHEAR WALL

SCALE: 3/4" = 1'-0" @ 22x34
SCALE: 3/8" = 1'-0" @ 11x17







WWW.FDSENG.COM

LOT 3 RESERVE AT JEWEL LAKE 33-3S-16-02439-203 LAKE CITY, FL 32024

ABBREVIATIONS

	THE RESIDENCE OF THE PARTY OF T
A/C	AIR COOLING UNIT
ADJ	ADJACENT
AFF	ABOVE FINISHED FLOOR
AHU	AIR HANDLING UNIT
ALUM	ALUMINUM
BLK	BLOCK
вот	воттом
BRG	BEARING
CJ	CONTROL JOINT
CLG	CEILING
COL	COLUMN
CONC	CONCRETE
CONT	CONTINUOUS
CPT	CARPET
DIA	DIAMETER
DN	DOWN
DWG	DRAWING
EA	EACH
ELEC	ELECTRIC
EQ	EQUAL
FF	FINISH FLOOR
FTG	FOOTING
НВ	HOSE BIB
HDR	HEADER
HGT	HEIGHT
MAX	MAXIMUM
MIN	MINIMUM
NTS	NOT TO SCALE
OPNG	OPENING
SIM	SIMILAR
TYP	TYPICAL
VLT	VAULT
UNO	UNLESS NOTED OTHERWISE

area tbulation 'a'

GARAGE	403 SF
FRONT PORCH	38 SF
REAR PATIO	104 SF
FLOOR 1 LIVING	1,776 SF
TOTAL LIVING	1,776 SF

area tabulation 'b'

GARAGE	403 SF
FRONT PORCH	117 SF
REAR PATIO	104 SF
FLOOR 1 LIVING	1,776 SF
TOTAL LIVING	1,776 SF

Radford

39' - 1776 - RH Florida Region (Frame)

INDEX

ARCHITECTURAL

CS	COVER	SHEET

1 EXTERIOR ELEVATIONS

2 SLAB PENETRATION PLAN

SECTIONS & DETAILS

3 FLOOR PLANS

5 INTERIOR DETAILS

5 INTERIOR DETA

6 ROOF PLAN

E1 ELECTRICAL PLANS

CD CONSTRUCTION DETAILS

REVISIONS

NUMBER	DATE	DESCRIPTION
01	03.04.202	Added Elevations A1 & B1
02	06.14.21	Added outlet to BR2, Relocate & noted outlets to meet 6' max from wall break & 12' max between outlet spacing at habitable rooms (E1.1)

Florida Building Code - Residential, 7th Edition (2020)

1. Provide temporary toilet facilities on site (Plumbing Sec 311.1).

2. Provide professional termite treatment of soil per R318.

3. Meet 2017 N.E.C. on all electrical work.

4. Provide passed compaction test to 95% density per R403.

5. Garage door(s) & windows to meet required wind load Sec R301.2.1.

6. All stairs, hand/guard rails to meet Sec R312.

7. Meet emergency egress requirements for bedrooms per R310.

8. Meet tempered glass requirements of Sec R308.4.


9. Roof shingles must meet Section 905.

10. Install smoke detectors in & outside sleeping rooms & at each level per Sec R314 & NFPA 72. Install carbon monoxide alarms per R315.

11. Install 4" high house address number of SFR, identification shall be

egible & placed in a position that is visible from the street R319.

Meet all 2020 Florida Building Code Requirements.



BUILDING CODE COMPLIANCE

ALL CONSTRUCTION TO COMPLY WITH LOCAL CODES AND ORDINANCE CURRENTLY IN USE WITH THE LOCAL JURISDICTION.

PRODUCT: NEW SINGLE FAMILY DETACHED

OCCUPANCY CLASSIFICATION:

RESIDENTIAL R-3

CONSTRUCTION CLASS:

UNPROTECTED

CONSTRUCTION TYPE:

TYPE VB

EMERGENCY ESCAPE:

EGRESS OR RESCUE WINDOWS FROM SLEEPING ROOMS SHALL HAVE MINIMUM OF 5.7 SQUARE FEET

APPLICABLE CODES:

FOLLOW ALL APPLICABLE STATE AND LOCAL CODES. FLORIDA STATE SUPPLEMENTS AND AMENDMENTS.

2020 Florida Building Code, Residential, 7th Edition

2017 National Electrical Code, NFPA 70







Lot 002 Reserve at Jewel Lake 33-3S-16-02439-202 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

= DATE	.2021
A H	02.22
	REI FASE DATE:

RADFORD
DRAWING TITLE:
COVER SHEET

CS

SHEET NO: