METAL PANELS MUST BE FASTENED TO 1x4 FURRING PURLINS OR 1/2" PLYWOOD CAULKING:

MUST BE APPROVED BY THE MANUFACTURER, BUTYL SEALANT SUPPLIED IN TAPE OR GUN-GRADE FORM.

METAL PANEL:

METAL PANELS SHALL BE

MIN. 29 GUAGE AND COMPLY WITH ASTM A-792 AND D 7-98

FASTENERS:

FASTENERS FOR METAL PANELS SHALL BE GALVANIZED

WOOD FAST SCREW, MINIMUM OF #9 X 1 1/2" HEX HEAD.

METAL PANELS SHALL BE SECURED TO THE ROOF WITH NOT LESS THAN 24" O.C. WHERE ROOF IS LOCATED IN BASIC WIND SPEED OF 110 MPH OR GREATER, SPECIAL METHODS OF FASTENING ARE REQUIRED. UNLESS OTHERWISE NOTED, ATTACHMENT OF METAL PANELS SHALL CONFORM

BASE AND CAP FLASHINGS:

WITH ASTM E 330 OR PA 125.

BASE AND CAP FLASHING SHALL BE INSTALLED IN ACCORDANCE W/ MFGR'S INSTALLATION INSTRUCTIONS.

- 1, RC-1 RIDGE CAP
- 2. ED-1 EAVE DRIP
- 3, EF-3 EAVE FLASHING
- 4. SW-1 SIDEWALL FLASHING
- 5, EW-1 ENDWALL FLASHING
- 6. GR-4 GABLE END OR RAKE BOARD FLASHING
- 7. TF-1 TRANSITION FLASHING
- 8. PV-2 PREFORMED VALLEY FLASHING
- 9. BUTYL TAPE 10. SEALANT TAPE
- 11. PIPEBOOT

UNDERLAYMENT APPLICATION:

UNDERLAYMENT SHALL BE A MINIMUM OF TWO LAYERS APPLIED AS FOLLOWS: 1. STARTING AT THE EAVE, A 19 INCH STRIP OF UNDERLAYMENT SHALL BE APPLIED PARALLEL WITH THE EAVE AND FASTENED SUFFICIENTLY TO STAY IN PLACE,

2. STARTING AT THE EAVE, 36 INCH WIDE STRIPS OF UNDERLAYMENT FELT SHALL BE APPLIED OVERLAPPING SUCCESSIVE SHEETS 19 INCHES AND FASTENED SUFFICIENTLY TO STAY IN PLACE.

BASE AND CAP FLASHINGS:


BASE AND CAP FLASHING SHALL BE INSTALLED IN ACCORDANCE W/ MFGR'S INSTALLATION INSTRUCTIONS, BASE FLASHING SHALL BE EITHER CORROSION RESISTANT METAL OF MINIMUM NOMINAL THICKNESS 0.019 INCH OR MINERAL SURFACE ROLL ROOFING WEIGHING A MINIMUM OF 17 LBS PER 100 SQUARE FEET, CAP FLASHING SHALL BE CORROSION RESISTANT METAL OF MINIMUM NOMINAL THICKNESS OF 0,019 INCH.

VALLEY LININGS SHALL BE INSTALLED IN ACCORDANCE W/ MANUFACTURER'S INSTALLATION INSTRUCTIONS BEFORE APPLYING ROOFING MATERIAL, VALLEY LININGS OF THE FOLLOWING TYPES SHALL BE PERMITTED.

- 1, OPEN VALLEYS LINED WITH METAL: THE VALLEY LINING SHALL BE AT LEAST 16" WIDE AND OF ANY OF THE CORROSION RESISTANT METALS
- IN FBC TABLE 1507.3.9.2. 2. OPEN VALLEYS: VALLEY LINING OF TWO PLIES OF MINERAL SURFACE
- ROLL ROOFING SHALL BE PERMITTED. THE BOTTOM LAYER SHALL BE 18 INCHES AND THE TOP LAYER A MINIMUM OF 36 INCHES WIDE, 3, CLOSED VALLEYS: VALLEY LINING SHALL BE ONE OF THE FOLLOWING:
- 1. BOTH TYPES 1 AND 2 ABOVE, COMBINED. 2. ONE PLY OF SMOOTH ROLL ROOFING AT LEAST 36 INCHES WIDE AND
- COMPLYING WITH ASTM D 224. 3. SPECIALTY UNDERLAYMENT AT LEAST 36 INCHES WIDE & COMPLYING

WITH ASTM D 1970.


YENT SLOT AT RIDGE, PER PLAN ROOF SHEATHING, PER PLAN CONT. 2X4 BLOCKING BETWEEN TRUSSES ALONG BOTH SIDES OF VENT SLOTS TRUSSES PER LAN



Yent DETAIL SCALE: NONE








Ridge DETAIL SCALE: NONE





NAIL PLYWOOD FLITCH BEAM TOGETHER W/ 16d NAILS STAGGERED TOP AND BOTTOM, EACH FACE

WHERE BEAM SPAN IS GREATER THAN 8'-0", CENTER 8'-0" LONG PLYWOOD AT CENTER OF BEAM SPAN, BUTT ADJACENT PLYWOOD PIECES TIGHT TO CENTER PIECE. STAGGER JOINTS AT BEAMS WITH MORE THAN ONE PLYWOOD PLATE.

B

MULTIPLE GANG LAM, DETAIL NOT TO SCALE

EACH FACE

PLYWOOD FLITCH BEAM DETAIL NOT TO SCALE

B/U Beam DETAILS

- VALLEY FLASHING

- METAL PANELS

ROOF SHEATHING -

30* FELT ----

SCALE: NONE

EAVE DRIP

1x4 SYP#3

OR BTR -

YALLEY FLASHING

- FLASHING PLACED UPSLOPE FROM

EXPOSED EDGE OF METAL PANEL

EXTENDING 4 INCHES OVER METAL

UNDER WALL FINISH,

- METAL PANELS

PEEL N STICK FELT

- ROOF SHEATHING

--- 1x4 SYP#3

OR BTR

PANEL AND 4 INCHES UP VERTICAL

x - x -



× - × -

SM-RIB METAL ROOFING PANELS ALTERNATE FASTENER SCHEDULE FOR VARIOUS WIND VELOCITIES MANUFACTURER'S RECOMMENDED FASTENER SCHEDULE FOR BUILDINGS W/ 35' MEAN ROOF HEIGHT, MIN. 3/12 PITCH

BASED ON ASCE 1-98, EXPOSURE "C"

ROOF	FASTENER	FASTENER SIZE	PLACEMENT TO	100 - 110		120 - 130		140 - 150	
ZONE	TYPE			O/C SPACING	TRIM	O/C SPACING	TRIM	O/C SPACING	TRIM
1	WD, SCREW	#9 × 1 1/2"	WOOD	36"	18"	24"	12"	24"	12"
	MTL, SCR,	#12 × 1" #14 × 7/8"	< 18 GA > 18 GA	- 36"	18"	24"	12"	24"	12"
2 \$ 3	WD, SCREW	#9 × 1 1/2"	WOOD	36"	18"	24"	12"	24"	8"
	MTL, SCR,	#12 × 1" #14 × 7/8"	< 18 GA > 18 GA	36"	18"	24"	12"	24"	8"

FRAMING ANCHOR SCHEDULE

APPLICATION MANUF'R/MODEL CAP. TRUSS TO WALL: SIMPSON H2.5a or SDWC15600 600# GIRDER TRUSS TO POST/HEADER: SIMPSON LGT, W/ 28 - 16d NAILS 1785# HEADER TO KING STUD(S): 1370# NO CONNECTION REQ. WHEN USING WINDSTORM BOARD PLATE TO STUD:

STUD TO SILL: NO CONNECTION REQ. WHEN USING WINDSTORM BOARD SIMPSON PC44 or (2) 5/8" LAG BOLTS EA, POST PORCH BEAM TO POST: PORCH POST TO FND .: SIMPSON ABU44 2200# MISC, JOINTS SIMPSON A34 315#/240#


ALL ANCHORS SHALL BE SECURED W/ NAILS AS PRESCRIBED BY THE MANUFACTURER FOR MAXIMUM JOINT STRENGTH, UNLESS NOTED OTHERWISE.

REFER TO THE INCLUDED STRUCTURAL DETAILS FOR ADDITIONAL ANCHORS/ JOINT REINFORCEMENT AND FASTENERS.

ALL UNLISTED JOINTS IN THE LOAD PATH SHALL BE REINFORCED WITH SIMPSON A34 FRAMING ANCHORS, TYPICAL T.O.

"SEMCO" PRODUCT APPROVAL: MIAMI/DADE COUNTY REPORT #95-0818,15

"SIMPSON" PRODUCT APPROVALS: MIAMI/DADE COUNTY REPORT #97-0107.05, #96-1126.11, #99-0623.04 SBCC1 NER-443, NER-393



PENETRATIONS

SOFFIT/DROPPED CLG.

FIREBLOCKING NOTES:


FIREBLOCKING SHALL BE INSTALLED IN WOOD FRAME CONSTRUCTION IN THE FOLLOWING LOCATIONS:

- 1. IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS INCLUDING FURRED SPACES AT CEILING AND FLOOR LEVELS.
- 2. AT ALL INTERCONNECTIONS BETWEEN CONCEALED YERTICAL AND HORIZONTAL SPACES SUCH AS OCCUR AT SOFFITS, DROP CEILINGS, COVE CEILINGS, ETC.
- 3. AT OPENINGS AROUND YENTS, PIPES, DUCTS, CHIMNEYS AND FIREPLACES AT CEILING AND FLOOR LEVELS WITH "PYROPANEL MULTIFLEX SEALANT"
- 4. AT ALL INTERCONNECTIONS BETWEEN CONCEALED YERTICAL STUD WALL OR PARTITION SPACES AND CONCEALED SPACES CREATED BY AN ASSEMBLY OF FLOOR JOISTS, FIREBLOCKING SHALL BE PROVIDED FOR THE FULL DEPTH

Fire Stopping DETAILS

OF THE JOISTS AT THE ENDS AND OVER THE SUPPORTS.

SCALE: NONE



	4		27	BUILDING (MEAN BUIL		# CLADDING = 30.0', EXF	
		ZONE	AREA	Yult 110 MPH	Vult 120 MPH	Vult 130 MPH	Yult 140 MPH
	27.	1 1 1	10 20 50	12.0 / -19.9 11.4 / -19.4 10.0 / -18.6	14.9 / -23.7 13.6 / -23.0 11.9 / -22.2	17.5 / -27.8 16.0 / -27.0 13.9 / -26.0	20.3 / -32.3 18.5 / -31.4 16.1 / -30.2
	÷ 5	2 2 2	10 20 50	12.5 / -34.7 11.4 / -31.9 10.0 / -28.2	14.9 / -41.3 13.6 / -38.0 11.9 / -33.6	17.5 / -48.4 16.0 / -44.6 13.9 / -39.4	20.3 / -56.2 18.5 / -51.7 16.1 / -45.7
020	ROOF	3 3 3	10 20 50	12.5 / -51.3 11.4 /-47.9 10.0 / -43.5	14.9 / -61.0 13.6 / -57.1 11.9 / -51.8	17.5 / -71.6 16.0 / -67.0 13.9 / -60.8	20.3 / -83.1 18.5 / -77.7 16.1 / -70.5
	MALL	4 4 4	10 20 50	21.8 / -23.6 20.8 / -22.6 19.5 / -21.3	25.9 / -34.7 24.7 / -26.9 23.2 / -25.4	30.4 / -33.0 29.0 / -31.6 27.2 / -29.8	35.3 / -38.2 33.7 / -36.7 31.6 / -34.6
	AW.	555	10 20 50	21.8 / -29.1 20.8 / -27.2 19.5 / -24.6	25.9 / -34.7 24.7 / -32.4 23.2 / -29.3	30.4 /-40.7 29.0 / -38.0 27.2 / -34.3	35.3 / -47.2 33.7 / -44. <i>0</i> 31.6 / -39.8

	EIGHT & EXPOSURE ADJUSTMENT COEFFICIENTS OR BUILDING COMPONENTS & CLADDING					
BLDG	EXPOSURE	EXPOSURE	EXPOSURE "D"			
HEIGHT	"B"	"C"				
15	.82	1.21	1.47			
20	.89	1.29	1.55			
25	.94	1.35	1.61			
30	1.00	1.40	1.66			

FLORIDA BUILDING CODE

Compliance Summary

TYPE OF CONSTRUCTION

Roof: Gable Construction, Wood Trusses @ 24" O.C. Walls: 2x4 Wood Studs @ 16" O.C.

Floor: 4" Thk. Concrete Slab W/ Fibermesh Concrete Additive

Foundation: Continuous Footer/Stem Wall

ROOF DECKING Material: 1/2" CDX Plywood or 7/16" O.S.B.

Sheet Size: 48"x96" Sheets Perpendicular to Roof Framing Fasteners: .113 RING SHANKED Nails per schedule on sheet 5.4

SHEARWALLS

7/16" O.S.B. WINDSTORM BOARD 48"x96" Sheets Placed Vertical

.113 COMMON Nails @ 4" O.C. Edges \$ 8" O.C. Interior Double Top Plate (S.Y.P.) W/16d Nails @ 12" O.C.

Dragstrut: Wall Studs: 2x4 Studs a 16" O.C.

HURRICANE UPLIFT CONNECTORS

SIMPSON H2.5a @ Ea. Truss End (Typ. U.O.N.) Wall Tension: Wall Sheathing Nailing is Adequate - 8d @ 4" O.C. Top & Bot. Anchor Bolts: 1/2" A307 Bolts @ 48" O.C. - 1st Bolt 6" from corner Corner Hold-down Device: (1) HD5a @ each corner

Porch Column Base Connector: Simpson ABU66 @ each column Porch Column to Beam Connector: Simpson MSTA20 (2 ea. side) or Simpson EPC66 or 2 - 5/8" thru bolts

FOOTINGS AND FOUNDATIONS

Footing: 20"x10" Cont. W/ 2 - #5 Bars Cont. on wire/plastic chairs @ 48" o.c. Stemwall: 8" C.M.U. W/1-#5 Vertical Dowel @ 48" O.C. Int. Footings: 12" x 12" x Cont. W/ 2 - #5 Bars Cont. on wire/plastic chairs @ 48" o.c.

STRUCTURAL DESIGN CRITERIA:

THE DESIGN COMPLIES WITH THE REQUIREMENTS OF THE 2023 FLORIDA, 8th EDITION BUILDING CODE - SECTION 1609 AND OTHER REFERENCED CODES AND SPECIFICATIONS. ALL CODES AND SPECIFICATIONS SHALL BE LATEST EDITION AT TIME OF PERMIT.

2. WIND LOAD CRITERIA: RISK CATAGORY: 2, EXPOSURE: "B"

BASED ON ANSI/ASCE 7-22. 2023 FBC 1609-A WIND VELOCITY: YULT = 130 MPH

3. ROOF DESIGN LOADS: SUPERIMPOSED DEAD LOADS: 20 PSF

SUPERIMPOSED LIVE LOADS: 20 PSF

4. FLOOR DESIGN LOADS: SUPERIMPOSED DEAD LOADS: . SUPERIMPOSED LIVE LOADS: 40 PSF

5. WIND NET UPLIFT: ARE AS INDICATED ON PLANS

TERMITE PROTECTION NOTES:

SOIL CHEMICAL BARRIER METHOD:

1. A PERMANENT SIGN WHICH IDENTIFIES THE TERMITE TREATMENT PROVIDER AND NEED FOR REINSPECTION AND TREATMENT CONTRACT RENEWAL SHALL BE PROVIDED. THE SIGN SHALL BE POSTED NEAR THE WATER HEATER OR ELECTRIC PANEL. FBC 104.2.6 2. CONDENSATE AND ROOF DOWNSPOUTS SHALL DISCHARGE AT LEAST 1'-O"

AWAY FROM BUILDING SIDE WALLS. FBC 1503.4.4 3. IRRIGATION/6PRINKLER SYSTEMS INCLUDING ALL RISERS AND SPRAY

HEADS SHALL NOT BE INSTALLED WITHIN 1'-O" FROM BUILDING SIDE WALLS. FBC 1503,4,4 4. TO PROVIDE FOR INSPECTION FOR TERMITE INFESTATION, BETWEEN WALL

COVERINGS AND FINAL EARTH GRADE SHALL NOT BE LESS THAN 6".

EXCEPTION: PAINT AND DECORATIVE CEMENTIOUS FINISH LESS THAN 5/8" THICK ADHERED DIRECTLY TO THE FOUNDATION WALL. FBC 1403.1.6 5. INITIAL TREATMENT SHALL BE DONE AFTER ALL EXCAVATION AND

BACKFILL IS COMPLETE, FBC 1816.1.1 6. SOIL DISTURBED AFTER THE INITIAL TREATMENT SHALL BE RETREATED INCLUDING SPACES BOXED OR FORMED. FBC 1816.1.2

7. BOXED AREAS IN CONCRETE FLOOR FOR SUBSEQUENT INSTALLATION OF TRAPS, ETC., SHALL BE MADE WITH PERMANENT METAL OR PLASTIC FORMS, PERMANENT FORMS MUST BE OF A SIZE AND DEPTH THAT WILL ELIMINATE THE DISTURBANCE OF SOIL AFTER THE INITIAL TREATMENT. FBC 1816.1.3

8, MINIMUM 6 MIL YAPOR RETARDER MUST BE INSTALLED TO PROTECT AGAINST RAINFALL DILUTION, IF RAINFALL OCCURS BEFORE VAPOR RET-ARDER PLACEMENT, RETREATMENT IS REQUIRED. FBC 1816.1.4 9, CONCRETE OVERPOUR AND MORTAR ALONG THE FOUNDATION PERIMETER

MUST BE REMOVED BEFORE EXTERIOR SOIL TREATMENT. FBC 1816.1.5 10. SOIL TREATMENT MUST BE APPLIED UNDER ALL EXTERIOR CONCRETE OR GRADE WITHIN 1'-O" OF THE STRUCTURE SIDEWALLS, FBC 1816.1.6 II. AN EXTERIOR VERTICAL CHEMICAL BARRIER MUST BE INSTALLED AFTER


CONSTRUCTION IS COMPLETE INCLUDING LANDSCAPING AND IRRIGATION.

ANY SOIL DISTURBED AFTER THE VERTICAL BARRIER IS APPLIED, SHALL BE RETREATED, FBC 1816,1,6 12. ALL BUILDINGS ARE REQUIRED TO HAVE PER-CONSTRUCTION TREATMENT.


13, A CERTIFICATE OF COMPLIANCE MUST BE ISSUED TO THE BUILDING DEPART-MENT BY # LICENSED PEST CONTROL COMPANY BEFORE A CERTIFICATE OF OCCUPANCY WILL BE ISSUED. THE CERTIFICATE OF COMPLIANCE SHALL STATE: THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES, THE TREATMENT IS IN ACCORDANCE WITH THE RULES AND LAWS OF THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONS-UMER SERVICES", FBC 1816.1.7

14. AFTER ALL WORK IS COMPLETED, LOOSE WOOD AND FILL MUST BE REMOVE DICHO(AS Nicholas P Geisler FROM BELOW AND WITHIN 1'-O" OF THE BUILDING, THIS INCLUDES ALL GRADE STAKES, TUB TRAP BOXES, FORMS, SHORING OR OTHER CELLULOSE CONTAINING Geisler C = US O = MATERIAL, FBC 2303.1.3

15. NO WOOD, YEGETATION, STUMPS, CARDBOARD, TRASH, ETC., SHALL BE BURIED WITHIN 15'-0" OF ANY BUILDING OR PROPOSED BUILDING, FBC 2303.1.4



SHEET NUMBER OF 4 SHEETS



SCALE: NONE

METAL ROOFING, DET,

SIDE WALL FLASHING