

Manual J Winter Calculations

Residential Load - Component Details (continued)

Peter & Anna Lev

Project Title:

Lot 10 Creek Run Plantation

Lake City, FL 32055

Building Type: User

7/1/2021

WHOLE HOUSE TOTALS

Totals for Heating	Subtotal Sensible Heat Loss	29510 Btuh
	Ventilation Sensible Heat Loss	0 Btuh
	Total Heat Loss	29510 Btuh

EQUIPMENT

1. Electric Heat Pump	#	29510 Btuh
-----------------------	---	------------

Key: Window types - NFRC (Requires U-Factor and Shading coefficient(SHGC) of glass as numerical values)
or - Glass as 'Clear' or 'Tint' (Uses U-Factor and SHGC defaults)
U - (Window U-Factor)
HTM - (ManualJ Heat Transfer Multiplier)



Version 8

Manual J Summer Calculations

Residential Load - Component Details (continued)

Peter & Anna Lev

Project Title:

Climate: FL_GAINESVILLE_REGIONAL_A

Lake City, FL 32055

Lot 10 Creek Run Plantation

7/1/2021

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	12113 Btuh
	Sensible Duct Load	4635 Btuh
	Total Sensible Zone Loads	16747 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	16747 Btuh
	Latent infiltration gain (for 51 gr. humidity difference)	1213 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	1390 Btuh
	Latent occupant gain (6.0 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	3802 Btuh
	TOTAL GAIN	20549 Btuh

EQUIPMENT

1. Central Unit	#	20549 Btuh
-----------------	---	------------

*Key: Window types (Panels - Number and type of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value)

(U - Window U-Factor)

(InSh - Interior shading device: none(No), Blinds(B), Draperies(D) or Roller Shades(R))

- For Blinds: Assume medium color, half closed

For Draperies: Assume medium weave, half closed

For Roller shades: Assume translucent, half closed

(IS - Insect screen: none(N), Full(F) or Half(½))

(Ornt - compass orientation)



Version 8