






SHED BASE DETAIL
SCALE: NO SCALE:



FLOOR FRAMING PLAN
SCALE: 1/4" = 1'-0"

- AUGER ANCHOR NOTES:**
- OT36448GMP = 5/8"x 36" (36" min. EMBED)
GLAZIUNIZED AUGER REPORT NO. 1640-30/60
OT17SWB-SIDEWALL BRACKET FOR USE WITH
THRU-BOLTS REPORT NO. LO-FJ90129-A
-OR-
 - OT24SWB-SIDEWALL BRACKET FOR USE IWTH
THRU-BOLTS, REPORT NO. LO-FJ90129-B.
 - WORKING LOAD FOR ANCHOR SYSTEM IS 3,150 LBS.
WITH THE MAX. LOAD OF 4,725 LBS.

- SHED FOUNDATION (WOOD):**
- 3/4" APA OR TECO RATED T & G FLOOR DECKING. 24" MAX PANEL SPAN. STAGGER PANEL LAYOUT.
 - FASTEN FLOOR DECKING TO JOISTS W/ #8 X 1 5/8" ZINC PLATED SCREWS @ 8" O.C. (BLOCKING REQUIRED) ALL EDGE SHALL LIE ON FLOOR JOISTS.
 - FASTEN SOLE PLATE THROUGH FLOOR DECKING INTO JOISTS WITH (2) #12-14 X 3" DECK SCREWS @ 12" O.C. CONTINUOUSLY SUPPORTED FOR 50 PSF ON BLOCKING.
 - USE OPTIONAL CONCRETE BLOCKS AS REQUIRED TO LEVEL STRUCTURE. (SUGGESTED SIZES: 2'x 8'x 16", OR 8'x 8'x 16" BLOCKS UNDER JOISTS, SPACED 7'-0" O.C. MAX)



WOOD FLOOR DETAIL
SCALE: 1" = 1'-0"

ELECTRICAL LEGEND	
	CEILING FAN (PRE-WIRE FOR LIGHT KIT)
	DOUBLE SECURITY LIGHT
	RECESSED CAN LIGHT
	BATH EXHAUST FAN
	LIGHT FIXTURE
	DUPLEX OUTLET (AFCI & TAMPER RESISTANT)
	220v OUTLET
	GFI DUPLEX OUTLET (PER NEC 406.8)
	TELEVISION JACK
	CIRCUIT FOR MINI-SPLIT A/C UNIT
	SMOKE / CARBON MONOXIDE DETECTOR (see note below)
	WALL SWITCH
	3 WAY WALL SWITCH
	WATER PROOF GFI OUTLET
	2 OR 4 TUB FLUORESCENT FIXTURE


NOTE:
ALL INTERIOR RECEPTACLES SHALL BE AFCI
(ARC FAULT CIRCUIT INTERRUPT) PER NEC 210.12 & TAMPER RESISTANT PER
NEC 406.11

ALL INTERIOR & EXTERIOR LIGHTING SHALL MEET OR EXCEED THE MIN. 75% HIGH-EFFICIENCY
LIGHTING PER FBC-ENERGY CONSERVATION R404.


ALL SMOKE DETECTORS BE A COMBO SMOKE & CARBON MONOXIDE DETECTOR
AND SHALL HAVE BATTERY BACKUP POWER
AND ALL WIRED TOGETHER SO IF ANY ONE UNIT IS ACTUATED THEY
ALL ACTIVATE.

THE ELECTRICAL SERVICE OVERCURRENT PROTECTION DEVICE SHALL BE
INSTALLED ON THE EXTERIOR OF STRUCTURES TO SERVE AS A DISCONNECT MEANS.
CONDUCTORS USED FROM THE EXTERIOR DISCONNECTING MEANS TO A PANEL OR SUB
PANEL SHALL HAVE FOUR-WIRE CONDUCTORS, OF WHICH ONE CONDUCTOR
SHALL BE USED AS AN EQUIPMENT GROUND.

IT IS THE LICENSED ELECTRICAL CONTRACTORS RESPONSIBILITY TO INSURE THAT ALL
WORK PERFORMED AND EQUIPMENT INSTALLED MEETS OR EXCEEDS THE 2020 (NFPA-70) NATIONAL
ELECTRIC CODE AND ALL OTHER LOCAL CODES AND ORDINANCES.



2ND FLOOR ELECTRICAL
SCALE: 1/4" = 1'-0"



ELECTRICAL PLAN
SCALE: 1/4" = 1'-0"

NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS

REVISIONS

July 17, 2025	
September 05, 2025	

SOFTPLAN

ARCHITECTURAL DESIGN SOFTWARE

Will C. My

A 16 x 30 STORAGE BUILDING FOR:

Kurt Schretzmann

PROJECT ADDRESS: 6588 SW CR 240, Lake City, Florida 32024

BAM

BUILDINGS AND MORE

AR0007005

NICHOLAS PAUL GEISLER ARCHITECT

1755 NW Brown Rd.
Lake City, FL 32055
(386) 365-4355

N.C.A.R.B. Certified

JOINT VENTURED WITH

WM DESIGN ASSOCIATES INC.

428 SW COMMERCE DR., STE 130
LAKE CITY, FL 32025
(386) 758-8406
will@wmyers.net

JOB NUMBER

20250717

DATE:

SHEET NUMBER

A.2