## Cool and Cobb Engineering Company

Date: <u>10/31/2025</u> <u>Project: 25-1414</u>

Job: <u>Christy Mcdaniel</u>

Location: 4743 N US Hwy 441, Lake City, FL 32055

#### **CRAWL SPACE JACK - DESIGN ANALYSIS**

The load requirements for the Crawl Space Jacks designed to assist in supporting the identified areas of the subject residence were determined. The selected Crawl Space Jack locations and the specific Crawl Space Jacks are identified on the Plan attached. The calculated total loads on the Crawl Space Jacks in the specific location, including both dead and live loads are documented in the attached table which is designated as Attachment "A". This Crawl Space Jack design is approved and certified as meeting all the requirements of the Florida Building Code 2023 8th Edition, and good engineering practice. This is not to be the primary support structure, but a supplement support to assist in support of the weight of the structure, which will reduce the total pressure on the existing soils and reduce deflection in beams.

### **General Notes:**

- 1. The Crawl Space Bracket attached in this design is approved as minimum size required for the loads.
- 2. Top plate to be secured to beam by: Wood Beam (2) Min. #9 2 ½" galv. deck screws
- 3. This design is developed per field assessment data by contractor and is based on agreement between contractor and owner. Cool and Cobb Engineering Co. Engineer has not performed an on-site structural assessment of the structure.
- 4. This design provides stabilization to the area receiving supplemental support only. Structure may require additional stabilization to other affected areas not addressed in the contractor/owner agreement.
- 5. This design is based on Assumed allowable soil loading of 2,000 psf. No deep soils geotechnical testing information was provided for this design.
- 6. This design does not address any possible sink hole activity as defined in Florida Statute § 627.706.
- 7. Contractor to document and certify any changes (with reason for field changes) on CCEC design plan and redline for "As Built" report.


#### 10/31/2025

Kenneth F Wheeler, P.E. State of Florida Professional Engineer No. 60417

This item has been digitally signed and sealed by Kenneth F. Wheeler, P.E. on the date adjacent to the seal.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.





Crawl Space Jack to Wood Beam Detail
Scale - N.T.S.

203 W. Main St. Avon Park, FL 33825 Office: (863) 657-2323 Fax: (863) 657-2324

Contractor: Solid Foundations

## **Solid Foundations**

1910 SW Main Blvd Lake City, FL 32025 855-227-0300



SF Representative: Jimbo Willis

Cell: 386-288-3240

Email: <u>Jimmie@solidfoundations.com</u>

www.solidfoundations.com

**CONTRACT DATE:** 10/6/2025

suвміттер то: Christy

ADDRESS: 4743 N. US HWY 441

Helical Pier:

Crawl Space Pier:

Lake City, Fl. 32055

EMAIL: rmcrr.office@gmail.com

Phone: 386-361-0723

# SISTER UPTO 10 2X8X12 FLOOR JOIST AS NEEDED 10/31/2025 Kenneth F. Wheeler, PE #60417 Cool and Cobb Engineering Co. 203 W. Main Street, Avon Park, FL 33825 12 This item has been digitally signed and sealed by Kenneth F. Wheeler, P.E. on the date adjacent to the seal. 20 UOI Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies. CCEC # 25-1414 Push Pier Model 300: Interior Pier: NCFI-24-120 Push Pier Model 250: Low Profile Bracket: NCFI-24-010

Porch Bracket:

4x6 Wood Beam:

Existing Beams■

Floor Joist:

## Cool and Cobb Engineering Company

Date:	10/31/25	Project #	25-1414
Job:	Christy Mcdaniel		
Location:	4743 N US Hwy 441, Lake City, FL 32055		

# Attachment "A" Total Load on Support (Live Load + Dead Load)

SUPPORT NO.	TOTAL CALCULATE LOAD		
1	1,280 lbs		
2	1,900 lbs		
3	1,900 lbs		
4	1,900 lbs		
5	1,900 lbs		
6	1,900 lbs		
7	1,900 lbs		
8	1,900 lbs		
9	1,280 lbs		
10	1,280 lbs		
11	1,900 lbs		
12	1,900 lbs		
13	1,900 lbs		
14	1,900 lbs		
15	1,900 lbs		
16	1,900 lbs		
17	1,900 lbs		
18	1,280 lbs		

N. 17 1 29	1 000	
Maximum Total Load on Pile:	1,900	lbs


This item has been digitally signed and sealed by Kenneth F. Wheeler, P.E. on the date adjacent to the seal.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

10/31/25

Kenneth F Wheeler, P.E. PE# 60417

Cool and Cobb Engineering Co. 203 W. Main St. Avon Park, FL 33825



SHEET 1 OF 1

QTY.

2

В