

Description of work to be done.

Deck will consist of framing of 2X8X16 PT on joist hangers, set on 6X6 PT. posts. Post will be either set in ground or on concrete forms. 1 X 6PT deck boards will be used as decking. Steps will have 4 ft. landing with steps going to existing deck where the Jacuzzi is located.

Deck will be approximately 32 ft on ends, and approximately 72 ft long on side will be 16ft wide.