

Daniel Shaheen
Daniel Shaheen


25 JUL 2005



D.D.S. STUDIOS
P.O. Box 273
Lake City, FL 32056
(386) 754-0181

NEW FACILITIES FOR:
RIMROCK DESIGN

COPYRIGHT: 2005 D.D.S. STUDIOS




Front ELEVATION

SCALE: 3/16" = 1'-0"

SPLIT FACE CONCRETE BLOCK
STOREFRONT W/ TEMPERED GLASS
REFER TO SHEET A8 FOR DETAILS

OPEN FRAMED ALUMINUM SASH PYRAMID ROOF
ACCENT DESIGN FEATURE AS PER ENGINEERED
SHOP DRAWINGS - SEE ALSO ROOF PLAN ON A8



Rear ELEVATION

SCALE: 1/8" = 1'-0"



Right Side ELEVATION


SCALE: 1/8" = 1'-0"



Left Side ELEVATION

SCALE: 1/8" = 1'-0"

BUILDING USE, CLASSIFICATION & OCCUPANCY AS PER TABLES 500 & 1003.1, FLORIDA BUILDING CODE, 2001 ED.	
BUILDING GROUP OCCUPANCY	GROUP S
TABLE 500 TYPE OF CONSTRUCTION	TYPE IV - UNPRO.
TABLE 500 AREA/HEIGHT LIMITATIONS	160 KSF/2 STORY
OCCUPANCY	
WAREHOUSE AREA: 1,300 SF GROSS 4000 SF / 300 = 13.33	14 OCCUPANTS



DRAWN BY:
MPB
CHECKED:

NICHOLAS GEISLER
ARCHITECT
N.C.A.R.B. Certified
1728 NW Brown Road
Lake City, FL 32056
386/754-0021

SHEET NUMBER
A.1 of 6

All work shall comply with the standard building code, and all applicable local codes and ordinances.
Contractor shall verify all dimensions prior to commencing construction.

PROJECT NUMBER
2K530

APPROVED
(Subject to Revisions)
Inspection Department
Lake City Fire Dept.
State Fire Inspector
License # 112877
Date: 11/29/05

Daniel Shaheen
Daniel Shaheen


25 JUL 2005



D.D.S. STUDIOS
P.O. Box 213
Lake City FL 32056
(386) 754-0181

NEW FACILITIES for:
RIMROCK DESIGN

COPYRIGHT: 2005 D.D.S. STUDIOS




Floor PLAN

SCALE: 3/16" = 1'-0"

GENERAL PLUMBING NOTES:

- SUB-CONTRACTORS PROVIDING PLUMBING MATERIALS AND INSTALLATION SHALL BE SUBJECT TO THE PROVISIONS OF NOTES 1 THRU 6.
- ALL WORKMANSHIP AND MATERIALS SHALL BE IN STRICT ACCORDANCE WITH APPLICABLE LOCAL CODES, RULES AND ORDINANCES.
- ALL MATERIALS SHALL BE NEW.
- ALL WORK SHALL BE PERFORMED BY A LICENSED PLUMBING CONTRACTOR IN A FIRST CLASS WORKMANLIKE MANNER. THE COMPLETED SYSTEM SHALL BE FULLY OPERATIONAL.
- ALL EXCAVATION & BACKFILL AS REQUIRED FOR THIS PHASE OF THE CONSTRUCTION SHALL BE PART OF THE PLUMBING SUB-CONTRACTOR'S RESPONSIBILITIES.
- PLUMBING FLAT PLANS AND RISER DIAGRAMS (IF INCLUDED) ARE DIAGRAMATIC. DO NOT SCALE THE DRAWINGS FOR EXACT LOCATIONS OF THE PLUMBING FIXTURES.
- ALL WORK SHALL BE COORDINATED WITH OTHER TRADES TO AVOID INTERFERENCE WITH THE PROGRESS OF THE CONSTRUCTION.
- WATER PIPING SHALL BE TYPE L COPPER UP TO 1", & TYPE K FOR ALL LARGER SIZES. ALL UNDERGROUND PIPING SHALL BE TYPE K COPPER. AT THE OWNERS OPTION SUPPLY PIPING MAY BE CPVC, SCHEDULE 40 OR SCHEDULE 80.
- DO NOT USE LEAD BASED SOLDER FOR JOINING SUPPLY PIPING.
- SOIL, WASTE, VENT & RAINWATER PIPING SHALL BE CAST IRON NO-HUB 301-12 ABOVE GRADE WITH NEOPRENE GASKETS AND STAINLESS STEEL BANDS & BELL & SPIGOT CAST IRON BELOW GRADE W/ LEAD & OAKUM JOINTS OR AT THE OWNERS OPTION P.V.C., SCHEDULE 40, SEE NOTE 12.
- AIR CONDITIONING CONDENSATE DRAIN PIPING SHALL BE THREADED STEEL PIPE, COPPER DRAIN, WASTE OR VENT PIPE AND FITTINGS, OR P.V.C. SEE NOTE 12, BELOW. INSULATE ALL CONDENSATE PIPING EXCEPT WHERE UNDERGROUND, AND ELECTRIC HEAT WRAP WHERE EXPOSED TO FREEZING CONDITIONS.
- P.V.C. SCHEDULE 40 PIPE AND FITTINGS MAY BE USED FOR SOIL, WASTE, VENT, RAINWATER OR CONDENSATE PIPING AS APPROPRIATE, WHERE APPROVED BY LOCAL BUILDING CODES & OFFICIALS. P.V.C. MAY NOT BE USED TO PENETRATE CHASES OR FIRE RATED WALLS / CEILING.
- ALL FIXTURES MUST BE PROVIDED WITH READILY ACCESSIBLE STOPS AND WHERE PROVIDED, MARKED ACCESS PANELS.
- FURNISH AND INSTALL APPROVED AIR CHAMBERS AT EACH PLUMBING FIXTURE AND APPROVED SHOCK ARRESTERS ON MAIN LINE OR RISERS.
- DIELECTRIC COUPLINGS ARE REQUIRED BETWEEN ALL DISSIMILAR METALS IN PIPING AND EQUIPMENT CONNECTIONS.
- ISOLATE COPPER PIPING FROM HANGERS OR SUPPORTS W/ HAIR FELT INSULATOR PADS.
- PROVIDE 1/2" TRAP PRIMER LINE FOR ALL FLOOR DRAINS FROM NEAREST PLUMBING FIXTURE, DO NOT MANIFOLD.
- PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES.
- PROVIDE COMBINATION COVERPLATE / CLEANOUT PLUG FOR ALL WALL CLEANOUTS, FINISH AS DIRECTED BY THE OWNER.
- FIXTURES, HARDWARE, EQUIPMENT, COLORS AND FINISHES SHALL BE AS SELECTED BY THE OWNER.




Typical Stair DETAIL

SCALE: 3/4" = 1'-0"



REVISIONS:




DRAWN BY:
MFG
CHECKED:

NICHOLAS GEISLER
PAUL
ARCHITECT
N.C.A.R.B. Certified


SHEET NUMBER
A.2 of 8

All work shall comply with the standard building code, and all applicable local codes and ordinances.
Contractor shall verify all dimensions prior to commencing construction.

PROJECT NUMBER
2K530



PROVIDE VERTICAL LIFT WHEELCHAIR PLATFORM LIFT AS PER ENCLOSURE MODEL BY "GARAVENTA"



2nd FLOOR PLAN


SCALE: 3/16" = 1'-0"

GENERAL INTERIOR FINISH SCHEDULE:

FLOOR AREA:	CARPET AND PAD, PATTERN & COLOR AS PER THE OWNER OR LAMINATE STRIP WOOD - SEE OWNER FOR CHANGES
R/R FLOOR AREA:	SHEET VINYL OR CERAMIC TILE PAT. & COLOR AS SELECTED BY THE OWNER
BASE:	WOOD TRIM, PATTERN AND FINISH AS SELECTED BY THE OWNER OR RUBBER COVE OR CERAMIC TILE - MATCH WITH FLOORING
TRIM:	COVES, CROWN, CASING & CHAIRRAILS AND THE LIKE AS PER OWNER'S DIRECTIONS, STAIN & VARNISH OR PAINT COLOR AS PER OWNER
WALLS:	1/2" GIB, PRIMED AND PAINTED 2 COATS LATEX WALL PAINT, COLOR & GLOSS AS SELECTED BY THE OWNER
MAIN CEILING:	5/8" GIB, DIRECT HUNG, TAPED & FINISHED, W/ 2 COATS OF LATEX CEILING PAINT, COLOR & GLOSS AS SELECTED BY THE OWNER
APPLIED FINISHES:	APPLIED FINISHED TO GIB, i.e. SPRAY, KNOCK-DOWN, SKIP-TROUVEL AND SIMILAR TREATMENTS AS DIRECTED BY THE OWNER
CABINETS:	AS SELECTED BY THE OWNER, MINIMUM API GRADE: "CUSTOM" - ALL COUNTERTOPS SHALL BE AS SELECTED BY THE OWNER

ADA NOTES: ACCESSIBILITY

RESTROOM NOTES
WATERCLOSETS: SHALL COMPLY WITH SEC. 4.16 OF ADA HEIGHT OF SEAT SHALL BE IN ACCORDANCE WITH SEC. 4.16.3 OF ADA FLUSH CONTROLS SHALL BE IN ACCORDANCE WITH SEC. 4.16.5 OF ADA
GRAB BARS: SHALL COMPLY WITH SEC. 4.16.4 OF ADA
DISPENSERS: SHALL COMPLY WITH SEC. 4.16.6 OF ADA
LAVATORIES, SINKS & MIRRORS: SHALL COMPLY W/ SECTION 4.19 OF ADA HEIGHTS SHALL COMPLY WITH SEC. 4.19.2.1 OF ADA EXPOSED PIPES & SURFACES SHALL COMPLY W/ SECTION 4.19.4 OF ADA FAUCETS SHALL COMPLY WITH SEC. 4.19.5 OF ADA MIRRORS SHALL COMPLY WITH SEC. 4.19.6 OF ADA
OWNER SELECTED MATERIAL AND INSTALLATION OF FINISH FLOORING MATERIALS TO COMPLY WITH THE FOLLOWING: SEC. 4.05 OF ADA SEC. 4.03 OF ADA APPLICABLE SECTIONS OF NFPA FIRE CODES APPLICABLE SECTIONS OF NFPA 101-LATEST LIFE SAFETY CODE
FIXTURES, DEVICES AND RELATED HARDWARE NOT SPECIFICALLY DEFINED OR MENTIONED ELSEWHERE ARE TO BE OWNER SELECTED AND INSTALLED TO COMPLY WITH THE ABOVE APPLICABLE ADA SECTIONS.




H/C RESTROOM ELEVATION
SCALE: 1" = 1'-0"

REVISIONS:

DRAWN BY:
MPB


CHECKED:



SHEET NUMBER
A.3 of 8

All work shall comply with the standard building code, and all applicable local codes and ordinances.
Contractor shall verify all dimensions prior to commencing construction.

PROJECT NUMBER
2K530



1st Floor ELECTRICAL PLAN

SCALE: 3/16" = 1'-0"

NOTE!
EMERGENCY LIGHTING AND EXIT SIGNS SHALL BE PROVIDED AS DIRECTED BY THE FIRE MARSHAL, AND SHALL BE WIRED PER NEC 100-12F.

NOTE!
HOUSE LIGHTING TO BE WIRED THROUGH LOCAL PANEL T/C (AREA "A" THRU PNL "A")


ELECTRICAL PLAN NOTES

1. WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS.
2. CONSULT THE OWNER FOR THE NUMBER OF SEPERATE TELEPHONE LINES TO BE INSTALLED.
3. INSTALLATION SHALL BE PER NAT'L. ELECTRIC CODE.
4. ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE, AND SHALL BE INTERLOCKED TOGETHER.
5. TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNER'S DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF NEC-LATEST EDITION.
6. ELECTRICAL CONTR' SHALL PREPARE "AS-BUILT" SHOP DWGS INDICATING ALL ELECTRICAL WORK, INCLUDING ANY CHANGES TO THE ELEC. PLAN, ADD'NS TO THE ELEC. PLAN, RISER DIAGRAM, AS-BUILT PANEL SCHEDULE W/ ALL CKTS IDENTIFIED W/ CKT N°, DESCRIPTION & BRKR SERVICE ENT. & ALL UNDERGROUND WIRE LOCATIONS/ROUTING/DEPTH. RISER DIA. SHALL INCLUDE WIRE SIZES/TYPE & EQUIPMENT TYPE W/ RATINGS & LOADS. CONTRACTOR SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER & 1 COPY TO THE PERMIT ISSUING AUTHORITY.

ELECTRICAL NOTES - General

1. DO NOT SCALE THE ELECTRICAL DRAWINGS. REFER TO ARCHITECTURAL PLANS AND ELEVATIONS FOR EXACT LOCATION OF ALL EQUIPMENT. CONFIRM WITH OWNER.
2. INSTALL ALL ELECTRICAL WORK IN CONFORMANCE WITH THE NEC 1991 EDITION, AND ITS AMENDMENTS AS ADOPTED BY THE PERMIT ISSUING AUTHORITY AT THE TIME OF CONSTRUCTION.
3. GROUNDING: GROUND ALL MAIN DISCONNECTS TO STANDARD GROUND ROD(S) AND TO COLD WATER SUPPLY AS PER ARTICLE 250 OF NEC-1994.
4. INSTALL ONLY COPPER WIRING ON THIS PROJECT; THW, TW, THHN, THWN OR NM CABLE, UNLESS NOTED OTHERWISE. ALL CONDUCTORS 1/0 & SMALLER MAY BE SOLID. ALL CONDUCTORS 1/2" AND LARGER SHALL BE STRANDED TYPE.
5. PROVIDE CONTINUITY OF NEUTRAL ON MULTI-BRANCH CIRCUITS BY SPLICING AND BRINGING OUT A TAP, ASSURING NO OPENINGS OF NEUTRAL IN REPLACEMENT OF A DEVICE.
6. COLOR CODE MULTI-CIRCUIT WIRING AS FOLLOWS: NEUTRAL - WHITE, GROUND - GREEN, LINE - ALL OTHER COLORS.
7. INSTALL ONLY HIGH POWER FACTOR BALLASTS AT FLUORESCENT FIXTURES.
8. INSTALL GFI BREAKERS ON DEVICES AT ALL BATHROOM, RESTROOM, KITCHEN, GARAGE AND EXTERIOR RECEPTACLES AND AS NOTED ON THE DRAWINGS.
9. INSTALL ONLY THOSE ELECTRICAL DEVICES THAT BEAR A "UL" OR OTHER RECOGNIZED TESTING LAB LABEL. ALL MATERIALS SHALL BE NEW.
10. INSTALL NON-FUSED DISCONNECT SWITCHES AT ALL PIECES OF ELECTRICAL EQUIPMENT LOCATED WHERE SAID EQUIPMENT IS NOT VISIBLE FROM THE CIRCUIT BREAKER THAT PROTECTS IT; SIZE IN ACCORD WITH THE LOAD. ALL DISCONNECT SWITCHES SHALL BE HP RATED, HEAVY DUTY, QUICK-MAKE - QUICK-BREAK TYPE - ENCLOSURES SHALL BE AS REQ'D FOR EXPOSURE.
11. MOTOR STARTERS SHALL BE MANUAL OR MAGNETIC WITH OVERLOAD RELAYS IN EACH HOT LEG.
12. ISOLATE DISSIMILAR CONDUIT AND TUBING METALS FROM SOIL, WATER AND GAS PIPING AND OTHER BUILDING MATERIALS WHERE DAMAGE BY FRICTION OR ELECTROLYSIS MAY OCCUR EXCEPT WHERE ELECTRICAL GROUND IS PROVIDED.
13. FURNISH AND INSTALL ALL ELECTRICAL DEVICES AND ITEMS REQUIRED FOR A COMPLETE OPERATING SYSTEM, PROVIDING THE FUNCTIONS AS DETAILED IN THE PLANS (AND SPECS).
14. OUTLET BOXES SHALL BE PRESSED STEEL OR PLASTIC OR ALL DRY LOCATIONS, FOR WET LOCATIONS, CAST ALLOY WITH THREADED HUB OUTLET BOXES SHALL BE INSTALLED.
15. HOT CHECK ALL SYSTEMS WITH THE OWNER'S REPRESENTATIVE PRESENT TO VERIFY PROPER FUNCTION PRIOR TO C.O.
16. COORDINATE ALL WORK THROUGH GC TO AVOID CONFLICTS. COORDINATE WITH HVAC CONTRACTOR AND ELECTRONICS SYSTEMS CONTRACTORS SO THAT A COMPLETE, FUNCTIONING SYSTEM IS INSTALLED, IN EACH CASE, WITH NO EXTRA COST TO THE OWNER.
17. EMERGENCY LIGHTING AND EXIT SIGNS, IF INDICATED ON THE PLANS, SHALL BE WIRED PER NEC 100-12F.
18. ALL PANEL SCHEDULES SHALL BE FULLY FILLED OUT AND SHALL BE TYPEWRITTEN. EA. CIRCUIT SHALL BE CLEARLY IDENTIFIED A TO WHAT IS INCLUDED ON SAID CIRCUIT.
19. IT IS NOT THE INTENT OF THESE DRAWINGS TO SHOW EVERY MINOR DETAIL OF THE CONSTRUCTION.
20. THE ELECTRICAL INSTALLATION SHALL MEET ALL STANDARD REQUIREMENTS OF THE POWER COMPANY & TELEPHONE COMPANY.
21. FURNISH AND INSTALL DISCONNECT SWITCHES AND WIRING FOR HVAC SYSTEM AS PER MANUFACTURER'S RECOMMENDATIONS. CONTROLS ARE TO BE SUPPLIED BY THE HVAC CONTRACTOR AND CONNECTED BY THE ELECTRICAL CONTRACTOR.
22. ALL RACEWAYS BELOW GROUND SHALL BE A MINIMUM OD 3/4".
23. ALL CIRCUIT BREAKERS, TWO AND THREE POLE, SHALL BE COMMON TRIP, NO TIE HANDLES OR TANDEMS SHALL BE ACCEPTABLE.
24. ALL FUSES, UNLESS NOTED OTHERWISE ON THE DRAWINGS, SHALL BE CURRENT LIMITED TYPE (CL) RATED 200,000 AIC.
25. ELECTRICAL CONTRACTOR SHALL VERIFY ALL COMPONENTS FOR ALL ELECTRICAL APPLICATIONS & DETERMINE THE CORRECTNESS OF SAME. ANY DISCREPANCY SHALL BE REPORTED TO THE OWNER PRIOR TO FABRICATING ANY MATERIALS, ORDERING COMPONENTS OR DOING ANY WORK.
26. CIRCUITS ON PANEL SCHEDULE (AND PLANS) ARE TO DETERMINE LOAD DATA AND SIZE. THE CONTRACTOR SHALL PROVIDE CIRCUITS AND ROUTING OF CONDUITS AND WIRING TO SUIT JOB CONDITIONS, AND BALANCE THE JOB, THROUGHOUT.
27. CHECK EQUIPMENT FOR PROPER VOLTAGE, PHASE AND AMPERAGE RATING PRIOR TO CONNECTION TO CIRCUITS.
28. PANEL BOARDS SHALL BE CIRCUIT BREAKER TYPE. VERIFY NUMBER AND SIZES OF CIRCUITS.
29. WHEN CONDUIT RUNS EXCEED 100 FEET, PULL BOXES SHALL BE INSTALLED SO THAT NO PULL EXCEEDS THIS DISTANCE.
30. ELECTRICAL EQUIPMENT AIC RATINGS AND FEEDER SIZE SHOWN ON THE PLANS ARE DESIGNED FOR MAX. AVAILABLE FAULT CURRENT AND MAX. ALLOWABLE VOLTAGE DROP, RESPECTIVELY.

REVISIONS:



DRAWN BY:

MPB

CHECKED:

NICHOLAS GESLER
ARCHITECT
N.C.A.R.B. Certified
17268 N.W. Brown Road
Lenoir City, TN 37056
386/755-4021

SHEET NUMBER

A.4 of 8


All work shall comply with the standard building codes, and all applicable local codes and ordinances.
Contractor shall verify all dimensions prior to commencing construction.

PROJECT NUMBER

2K530

Daniel Shaheen
Daniel Shaheen

25 JUL 2005



D.D.S. STUDIOS
P.O. Box 213
Lake City, FL 32056
(386) 754-0101

NEW FACILITIES FOR:
RIMROCK DESIGN

COPYRIGHT: 2005 D.D.S. STUDIOS

REVISIONS:



DRAWN BY:

YFB

CHECKED:

NICHOLAS PAUL GEISLER ARCHITECT
N.C.A.R.B. Certified
1000 NW Broward Blvd
Suite 1200
Lakeland, FL 33809
386/755-9021


SHEET NUMBER

A.6 of 8

All work shall comply with the standard building codes, and all applicable local codes and ordinances.
Contractor shall verify all dimensions prior to commencing construction.


PROJECT NUMBER

2K530



Foundation PLAN

SCALE: 3/16" = 1'-0"



Anchor Bolt DETAILS

SCALE: 1" = 1'-0"

NOTE: THIS FOUNDATION PLAN IS REPRESENTATIVE OF THE REQUIRED CONSTRUCTION AND WILL CHANGE AS REQUIRED BY THE ENGINEERED SHOP DRAWINGS FOR THE STEEL BUILDING AS PREPARED BY THE METAL BUILDING MANUFACTURER. THE FOUNDATION PLAN SHALL BE REVISED AS NEEDED TO INCLUDE ANY REQUIRED SHOP DRAWING DETAILS AND LOADS FOLLOWING RECEIPT OF SAME FROM THE OWNER, PRIOR TO POURING ANY CONCRETE.


NOTE!
REFER TO THE METAL BUILDING SHOP DRAWINGS PREPARED BY MANUFACTURER FOR EXACT LOCATION OF ALL EMBEDDED ANCHOR BOLTS.

NOTE!
ADDED FILL SHALL BE APPLIED IN 12" LIFTS - EA. LIFT SHALL BE COMPACTED TO 98% DRY COMPACTION PER THE "MODIFIED PROCTOR" METHOD.

NOTE!
THE DESIGN WIND SPEED FOR THIS PROJECT IS 110 MPH PER 2001 FBC 1606 AND LOCAL JURISDICTION REQUIREMENTS

CONCRETE / MASONRY / METALS GENERAL NOTES:

- DESIGN SOIL BEARING PRESSURE: 1000 PSF.
- EXPANSIVE SOILS: WHERE DIRECTED BY THE SOILS ENGINEER, SOIL AUGMENTATION PER THE SOILS ENGINEER'S SPECIFICATIONS SHALL BE IMPLEMENTED PRIOR TO PLACING ANY FOUNDATIONS - TESTS AS SPECIFIED SHALL BE PERFORMED TO DETERMINE THE SUITABILITY OF THE SUB-GRADE TO SUPPORT THE DESIGN LOADS.
- CLEAN SAND FILL OVER STRIPPED AND COMPACTED EXISTING GD. SHALL BE PLACED IN 12" LIFTS, BOTH SUB-SOIL AND FILL COMPACTION SHALL BE NOT LESS THAN 98% AS MEASURED BY A MODIFIED PROCTOR TEST AT THE RATE OF ONE TEST FOR EACH 1500 SF OF BUILDING PAD AREA, OR FRACTION THEREOF, FOR EACH 12" LIFT.
- REINFORCING STEEL SHALL BE GRADE 60 AND MEET THE REQUIREMENTS OF ASTM A615, ALL BENDS SHALL BE MADE COLD.
- WELDED WIRE MESH SLAB REINFORCING SHALL MEET THE REQUIREMENTS OF ASTM A185 - MIN. YIELD STRESS = 85 KSI.
- CONCRETE SHALL BE STANDARD MIX FC = 3000 PSI FOR ALL FTGS, SLABS, COLUMNS AND BEAMS OR SHALL BE STANDARD PUMP MIX FC = 3000 PSI. STRENGTH SHALL BE ATTAINED WITHIN 28 DAYS OF PLACEMENT, MIXING, PLACING AND FINISHING SHALL BE AS PER ACI STANDARDS.
- CONCRETE BLOCK SHALL BE AS PER MANUFACTURER'S PRODUCT GUIDE FOR ASTM C-90 REQUIREMENTS WITH MEDIUM SURFACE FINISH - Fm = 1500 PSI.
- MORTAR SHALL BE TYPE "M" OR "N" FOR ALL MASONRY UNITS.
- STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 STANDARDS FOR STRENGTH, BOLTS SHALL BE ASTM A307 / GRADE 1 OR A325, AS PER PLAN REQUIREMENTS.
- WELDS SHALL BE AS PER "AMERICAN WELDING SOCIETY" STANDARDS FOR STRUCTURAL STEEL APPLICATIONS.




Outdoor Cleanout
N.T.S.

Daniel Shaheen
Daniel Shaheen

25 JUL 2005


D.D.S. Studios
D.D.S. STUDIOS
P.O. Box 213
Lakes City, FL 32056
(386) 754-0181

NEW FACILITIES for:
RIMROCK DESIGN
COPYRIGHT: 2005 D.D.S. STUDIOS



Roof PLAN


SCALE: 1/4" = 1'-0"



Door/Window ELEV.


SCALE: 1/4" = 1'-0"

FIELD MEASUREMENTS:
FIELD VERIFY ALL OVERALL FRAME SIZES PRIOR TO METALS FABRICATION



VERTICAL SECTION

SCALE: 3" = 1'-0"




HORIZ. SECTION

SCALE: 3" = 1'-0"

GENERAL SHOP DRAWING NOTES:

- ENTRANCES & STOREFRONTS**
- MANUFACTURER:**
YKK AP AMERICA, INC.
1606 CURRENCY DRIVE
ORLANDO, FL 32801
- FINISH:**
IN ACCORDANCE WITH AA-M2C22A31 (91 CLEAR)
COLOR: CLEAR
- GLAZING:**
STOREFRONT DOORS - MEDIUM STYLE 35D:
1/4" TEMPERED GLASS
STOREFRONT 1 3/4" X 4 1/2" "C-SLOT":
1/4" TEMPERED GLASS
- DOOR HARDWARE:**
CLOSER - CONCEALED, SELECTIVE HOLD OPEN
OFFSET PIVOTS
LOCKS - "ADAMS-RITE" N: 4010, DEAD LATCH, LEVER 4560 ON EXTERIOR IN COMBINATIN w/ PANIC DEVICES, EA. LEAF.
FULL HANDLES: STANDARD ALUMINUM UNITS
PUSH BARS: STANDARD ALUMINUM UNITS
PANIC HARDWARE: CONCEALED ROD TYPE, w/ FULL WIDTH ACTUATOR BAR
THRESHOLD: MILL FINISH EXTRUDED ALUMINUM
- INSTALLATION REQUIREMENTS:**
CONTRACTOR SHALL PREPARE OPENINGS IN ACCORDANCE WITH THE TOLERANCES AS SPECIFIED IN THE PROJECT SPECIFICATIONS - WITH NET OPENING SIZES AS INDICATED IN THESE SHOP DRAWINGS.
NET OPENING WIDTH SHALL BE FRAME WIDTH + 1/2"
NET OPENING HEIGHT SHALL BE FRAME HEIGHT + 1/2"
- CLEANING:**
USE ONLY A SOLUTION OF A MILD LIQUID SOAP IN WATER FOR ALL SURFACES, INCLUDING GLAZING AND SASH MATERIALS.



DRAWN BY:
ms
CHECKED:

NG
NICHOLAS
GESSLER
ARCHITECT
N.C.A.R.B. Certified
1728 NW Brown Road
3867 753-8021

SHEET NUMBER
A.8 of 8

All work shall comply with the standard building code, and all applicable local codes and ordinances.
Contractor shall verify all dimensions prior to commencing construction.

PROJECT NUMBER
2K530



BUILDING SYSTEM DESIGN CRITERIA
Loads Applied in Accordance with the
2001 FLORIDA BUILDING CODE

ORDER NO. 223680 DATE 10/26/05
REVISION 0

BUILDING(S) A
DESIGN LOCALE COLUMBIA CO., FL

LIVE LOAD FRAME 12 PSF
ROOF 20 PSF

WIND VELOCITY Δ 100 MPH (3 SECOND GUST)
IMPORTANCE FACTOR 1.0
EXPOSURE B ENCLOSED
INTERNAL PRESSURE COEFFICIENT +/- 0.18
COLLATERAL COMPONENT and CLADDING PRESSURE 19.1 PSF

DEAD LOAD The weight of the metal building components as it occurs.

COLLATERAL LOADS UNIFORM LOAD 5.0 PSF
CONCENTRATED LOAD See Drawings for Magnitude and

MEZZANINE Live Load = 100 psf; Dead Load = 58 psf; Sprinkler = 20 psf

BUILDING SYSTEM DESIGN CRITERIA
Loads Applied in Accordance with the
2001 FLORIDA BUILDING CODE

ORDER NO. 223680 DATE 10/26/05
REVISION 0



BUILDING(S) B,C,D
DESIGN LOCALE COLUMBIA CO., FL

LIVE LOAD FRAME 20 PSF
ROOF 20 PSF

WIND VELOCITY Δ 100 MPH (3 SECOND GUST)
IMPORTANCE FACTOR 1.0
EXPOSURE B ENCLOSED
INTERNAL PRESSURE COEFFICIENT +/- 0.18
COLLATERAL COMPONENT and CLADDING PRESSURE 19.1 PSF

DEAD LOAD The weight of the metal building components as it occurs.


COLLATERAL LOADS UNIFORM LOAD 5.0 PSF
CONCENTRATED LOAD See Drawings for Magnitude and



ANCHOR BOLT QUANTITIES
Framed Opening and Walk Door Anchorage Devices are NOT included in this Table


BOLT DIA.	QTY.	BOLT DIA.	QTY.
3/4"	76		
5/8"	16		

MBS METAL BUILDING SYSTEM
BLDG BUILDING
SL STEEL LINE EW ENDWALL
BL BASE LINE SW SIDEWALL
O GRID LINE
--- CENTER LINE
XX RECESSED OR RAISED COL. BASE
XX INDICATES DIMENSION OF COL. BASE ABOVE OR BELOW MBS BL










DESIGN CERTIFICATION
THESE DRAWINGS AND THE METAL BUILDING THEY REPRESENT ARE THE PRODUCT OF MESCO BUILDING SOLUTIONS, P.O. BOX 98828, SOUTH LAKE, TEXAS 76092, 817-488-8815.
THE ENGINEER WHOSE SEAL APPEARS HEREON IS EMPLOYED BY MESCO BUILDING SOLUTIONS AND IS NOT THE ENGINEER OF RECORD. THE STRUCTURAL DESIGN OF THE BUILDING SYSTEM MEETS THE SPECIFICATIONS INCLUDING THE DESIGN CRITERIA, DESIGN LOADS AND SERVICEABILITY REQUIREMENTS INCORPORATED BY THE BUYER INTO THE ORDER DOCUMENTS.
MESCO'S ENGINEER IS NOT RESPONSIBLE FOR OBSERVATION OR INSPECTION OF THE ERECTION OF THE BUILDING SYSTEM AND IS NOT ACTING AS THE PRIME DESIGN PROFESSIONAL. FOR THE CONSTRUCTION PROJECT UTILIZING THIS BUILDING SYSTEM, THE INFORMATION REQUIRED TO INTEGRATE THE BUILDING SYSTEM INTO THE CONSTRUCTION PROJECT IS GIVEN IN THE PROJECT DESIGN DATA.

ATTENTION FOUNDATION DESIGNER
The manufacturer has determined the required anchor bolt diameter assuming full allowable combined shear and tension can be developed in the bolt in accordance with Table J3.3 of the AISC 9th Edition of the Manual of Steel Construction, Allowable Stress Design assuming a threaded part made of ASTM-A36 Steel. It is the responsibility of the foundation designer to design an anchorage system using bolts of the stated diameter that develop sufficient strength to resist the reactions given on the anchor bolt drawings. This may require the addition of embedded angles, plates or other items to allow the bolt group to develop a single resistance cone.



SHOP LOCATED FRAMED OPENING SCHEDULE

Mark	Qty.	Jamb Depth	Opening Width	Mark	Qty.	Jamb Depth	Opening Width
◇				◇			
◇				◇			
◇				◇			




Rev. #	Description	Op.	Det.	Chk.	Date
1	ISSUED FOR CONSTRUCTION	srs			9-2-05
2	REVISED FOR CONSTRUCTION	srs			9-22-05
3	REVISED FOR CONSTRUCTION PER CO#2	JAA			10/26/05

Sheet Description ANCHOR BOLT LAYOUT	Operator SRS	Date 9-02-05
--	-----------------	-----------------

Buyer Simque Construction	Q Number	Order Number 22-3680
End Customer Rimrock Development, Inc.	Sheet Number A1	

DESIGN CRITERIA
Building Code Florida 2001
Live Load 12/20 psf
Wind Velocity 100 mph Δ

Designer Approval: _____
Designer Approval: _____



BUILDING SYSTEM DESIGN CRITERIA
Loads Applied in Accordance with the
2001 FLORIDA BUILDING CODE

ORDER NO.	223680	DATE	10/26/05
REVISION	0		
BUILDING(S)	A		
DESIGN LOCALE	COLUMBIA CO., FL		
LIVE LOAD	12 PSF		
FRAME	20 PSF		
ROOF	20 PSF		
WIND VELOCITY	100 MPH (3 SECOND GUST)	IMPORTANCE FACTOR	1.0
	EXPOSURE	ENCLOSURE	B
	INTERNAL PRESSURE COEFFICIENT	COLLATERAL COMPONENT and CLADDING PRESSURE	+/- 0.18
			19.1 PSF
DEAD LOAD	The weight of the metal building components as it occurs.		
COLLATERAL LOADS	5.0 PSF		
UNIFORM LOAD			
CONCENTRATED LOAD	See Drawings for Magnitude and		
MEZZANINE	Live Load= 100 psf; Dead Load = 58 psf; Sprinkler = 20 psf		

BUILDING SYSTEM DESIGN CRITERIA
Loads Applied in Accordance with the
2001 FLORIDA BUILDING CODE

ORDER NO.	223680	DATE	10/26/05
REVISION	0		
BUILDING(S)	B,C,D		
DESIGN LOCALE	COLUMBIA CO., FL		
LIVE LOAD	20 PSF		
FRAME	20 PSF		
ROOF	20 PSF		
WIND VELOCITY	100 MPH (3 SECOND GUST)	IMPORTANCE FACTOR	1.0
	EXPOSURE	ENCLOSURE	B
	INTERNAL PRESSURE COEFFICIENT	COLLATERAL COMPONENT and CLADDING PRESSURE	+/- 0.18
			19.1 PSF
DEAD LOAD	The weight of the metal building components as it occurs.		
COLLATERAL LOADS	5.0 PSF		
UNIFORM LOAD			
CONCENTRATED LOAD	See Drawings for Magnitude and		

BUILDING INFORMATION

SYSTEM:	1	AREA:	D
TYPE	SFS	ROOF PANEL	"ULTRA-DEK" 24Ga. GP
SLOPE	1/2:12	FRONT WALL PANEL	"OPEN TO BLD'G A"
WIDTH	8'-0"	BACK WALL PANEL	"OPEN FOR COLL. MAT'L"
HEIGHT	27'-10"	LEFT WALL PANEL	"OPEN FOR COLL. MAT'L"
LENGTH	26'-3"	RIGHT WALL PANEL	"OPEN FOR COLL. MAT'L"

General Notes

1. THE ERECTION DRAWING PACKAGE MAY CONSIST OF ERECTION DRAWINGS, DETAIL SHEETS, REFERENCE DRAWINGS, REFERENCE MANUALS, THIS TITLE SHEET DRAWING AND A BILL OF MATERIALS.
2. ALL DRAWINGS ARE TO BE USED IN CONJUNCTION WITH EACH OTHER. IF CONFLICTS OCCUR THE ERECTION DRAWINGS SHALL TAKE PRECEDENCE.

Abbreviations

BLDG = BUILDING	BEF = BEARING END FRAME	GA = GAUGE
SW = SIDEWALL	FEF = FULL END FRAME	UN = UNLESS NOTED
EW = ENDWALL	BUE = BUILT-UP END FRAME	psf = POUNDS PER SQUARE FOOT
FW = FRONT WALL	SL = STEEL LINE	mph = MILES PER HOUR
BW = BACK WALL	BL = BASE LINE	kip = 1000 POUNDS
LW = LEFT WALL	RL = RIDGE LINE	
RW = RIGHT WALL		

Symbols

BES = BOTTOM OF EAVESTRUT (LOW SIDE)	○ GRID LINE	◇ REFERENCES TO A DETAIL FOUND ON THE "DETAIL SHEETS"
BEH = BOTTOM OF EAVESTRUT (HIGH SIDE)	⬡ PARTITION COLUMN LINE OR FLOOR COLUMN LINE	

Design Certification

These drawings and the metal building they represent are the product of MESCO Building Solutions, (P.O. Box 93629, Southlake, Texas 76092, 817-488-8511). The engineer whose seal appears hereon is employed by MESCO Building Solutions and is not the Engineer of Record. The structural design of the building system meets the specifications including the design criteria, design loads and serviceability requirements incorporated by the buyer into the order documents. MESCO's engineer is not responsible for observation or inspection of the erection of the building system and is not acting as the prime design professional for the construction project utilizing this building system. The information required to integrate the building system into the construction project is given in the Project Design Data.

Rev.#	Description	Det.	Chk.	Date
0	ISSUED FOR CONSTRUCTION	KEB	DRS	10/07/05
1	ISSUED FOR CONSTRUCTION	MM	MM	10-26-05



Sheet Description	Buyer	Q Number	Order Number
TITLE SHEET	Simque Construction	-	22-3680
Operator	End Customer	Sheet Number	
KEB	Rimrock Development, Inc	T1 of 1	

BUILDING INFORMATION

SYSTEM:	1	AREA:	A
TYPE	SFS	ROOF PANEL	"ULTRA-DEK" 24Ga. GP
SLOPE	1/2:12	FRONT WALL PANEL	"PBR" 26GA. LS
WIDTH	40'-0"	BACK WALL PANEL	"OPEN FOR COLL. MAT'L"
HEIGHT	26'-0"	LEFT WALL PANEL	"OPEN FOR COLL. MAT'L"
LENGTH	100'-0"	RIGHT WALL PANEL	"OPEN TO BLD'G C"

ROOF ACCESSORIES

EAVE GUTTER

AT FRONT WALL

WALL ACCESSORIES

WALK DOORS PBR,PBA or PBX Panel

5 3070WH Mortise, Solid

FRAMED OPENNING

- 1 ZFO type# 2, 3' x 7' - A @ Front
- 1 ZFO type# 6, 6' x 5' - B @ Front

BUILDING INFORMATION

SYSTEM:	1	AREA:	B
TYPE	SFS	ROOF PANEL	"ULTRA-DEK" 24Ga. GP
SLOPE	1/2:12	FRONT WALL PANEL	"OPEN FOR COLL. MAT'L"
WIDTH	14'-0"	BACK WALL PANEL	"OPEN FOR COLL. MAT'L"
HEIGHT	27'-0"	LEFT WALL PANEL	"OPEN FOR COLL. MAT'L"
LENGTH	14'-0"	RIGHT WALL PANEL	"OPEN TO BLD'G A"

ROOF ACCESSORIES

EAVE GUTTER

AT FRONT WALL

Customer Service "Notice"

In the event of fabrication or design problems, shortages of material, damaged or wrong material customer services is available to assist you. Should one of these problems occur contact our customer service department at the numbers listed below. When contacting us please refer to the "Order Number" shown in the lower right hand corner of this sheet.

Customer Service: Telephone 1-800-556-3726
or Fax **817-329-2346**

Note: In order to receive reimbursement of costs, customer service must approve cost of materials or field work prior to procurement of materials or to work being performed. See the truck copy of the erection drawing package for further information and for sample forms of authorization to perform field work.

Special Notice for Buildings with GRAY PRIMER:

When Gray Primer is specified the customer is reminded that Gray Primer is intended as a PRIMER and that it should have minimal exposure to atmospheric conditions. The customer should also be reminded of the potential aesthetic issues that are specifically associated with Gray Primers such as: 1) Gray Primer will show rust spots/streaks due to imperfections in the application process and the properties associated with Gray Primers and 2) Abrasions caused by handling, loading, shipping, unloading, and during the erection process are unavoidable. As a result any rusting or abrasions on members with Gray Primer are NOT subject to customer rejection or claim for touch up to Mesco Building Solutions

TABLE OF CONTENTS

TITLE SHEET DRAWINGS	T1
ANCHOR BOLT DRAWINGS	A1
PROJECT DESIGN DATA	PD1
ERECTION DRAWINGS	E1 - E14
DETAILS/SECTIONS DRAWINGS	D1
REFERENCE DRAWINGS	
GENERAL INFORMATION Version 2000	
Care of Material, Pg.1	RG0101-0
Care of Material, Pg.2	RG0102-0
Fastener Identification	RG0103-0
Bolt & Nut Identification	RG0104-1
Pop Rivet Locations, Pg.1	RG0105-0
Pop Rivet Locations, Pg.2	RG0106-0
Pop Rivet Locations, Pg.3	RG0107-0
Dealer Responsibilities	RG0108-0
PBR ROOF EAVE AND RAKE	
Roll Formed Downspouts Pg.1	RR0305-0
Roll Formed Downspouts Pg.2	RR0306-0
WALL SYSTEM PBR,PBA,PBX, PBU Panel	
Sidewall Panel Installation	RW0101-1
Endwall Panel Installation	RW0102-1
Panel Base Installation	RW0103-1
Corner and Side Trim Installation	RW0104-1
WALL ACCESSORIES PBR,PBA,PBX Panel	
3070 & 4070 Walk Door Installation	RW0201-0
Walk Door Framing	RW0203-1
Walk Door Trim	RW0204-0
WALL F.O. PBR,PBA,PBX,PBU Panel	
Framed Opening Types	RM0101-0
Connection Details, Pg.1	RM0102-0
Connection Details, Pg.2	RM0103-0
Trim Details	RM0104-1
BRACING DETAILS	
Thru Web Type Bracing	RB0101-1
Roof Bridging Angle Details	RB0102-0

ULTRA-DEK INSTALLATION MANUALS

BUILDING INFORMATION

SYSTEM:	1	AREA:	C
TYPE	SFS	ROOF PANEL	"ULTRA-DEK" 24Ga. GP
SLOPE	1/2:12	FRONT WALL PANEL	"OPEN FOR COLL. MAT'L"
WIDTH	34'-0"	BACK WALL PANEL	"OPEN FOR COLL. MAT'L"
HEIGHT	26'-7"	LEFT WALL PANEL	"OPEN TO BLD'Gs A&D"
LENGTH	8'-0"	RIGHT WALL PANEL	"OPEN FOR COLL. MAT'L"

DESIGN CRITERIA

Building Code FBC 2001


Live Load 12/20 psf

Wind Velocity 100 mph


Designer Approval _____

Date _____






DETAIL 1
@ INTERIOR PURLINS



DETAIL 2
@ LOW SIDE EAVE



ROOF FRAME ASS'YS BLDG's A,B,C&D



⊠ = 1400# POINT LOAD

NOTE: THIS IS FOR ALUMINUM STRUCTURE (BY BUYER). ACTUAL SUPPORT AND ATTACHMENT TO BUILDING IS NOT BY MESCO. BUYER IS RESPONSIBLE FOR ALL WEATHERTIGHTNESS WHERE STRUCTURE ATTACHES TO BUILDING.

DESIGN CRITERIA
Building Code FLORIDA 2001
Live Load 12/20 psf
Wind Velocity 100 mph



Rev.#	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Simque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E1 of 14




Sheet Description
ERECTION DRAWING
Operator
MAM
Date
11-02-05

Buyer
Simque Construction
End Customer
Rimrock Development, Inc

Q Number
-
Order Number
22-3680
Sheet Number
E1 of 14


STEP 1 (EW TRANS.) 2 RSF1L 24 FS5PL 26 FS1ECZ 52 FS4CZ 3 PR13SS 312 ISL-B7 STEP 2 1200 ISL-B7 600 ISL-B7 50 CCP24AZI 100 FS1PL 17 FS14ASS 48 ISL-TWH	STEP 4 100 SL-M7 400 FS1ECZ STEP 6 538 PCL6L 1076 FS1PL STEP 9 (H.S. TRANS.) 36 BUP24 1080 ISL-B7 STEP 10 108 ISL-B7 STEP 12 72 CCP24AZO 576 FS1ECZ 1944 ISL-B7	STEP 13 (EW TRANS.) 1 RSF1L 12 FS5PL 14 FS1ECZ 28 FS4CZ 168 ISL-B7	STEP 14 (H.S. TRANS.) 144 ISL-TWH 864 ISL-B7 36 FS1ECZ 144 FS4CZ	STEP 1 (EW TRANS.) 1 RSF1L 12 FS5PL 8 FS1ECZ 29 FS4CZ 178 ISL-B7 5 FS1ECZ STEP 2 170 ISL-B7 84 ISL-B7 7 CCP24AZI 14 FS1PL 3 FS14ASS STEP 4 14 SL-M7 56 FS1ECZ	STEP 6 28 PCL6L 56 FS1PL STEP 9 (H.S. TRANS.) 7 BUP24 210 ISL-B7 STEP 10 21 ISL-B7 STEP 12 14 CCP24AZO 112 FS1ECZ 378 ISL-B7	STEP 14 (H.S. TRANS.) 28 ISL-TWH 168 ISL-B7 7 FS1ECZ 28 FS4CZ	STEP 2 96 ISL-B7 48 ISL-B7 4 CCP24AZI 8 FS1PL STEP 4 8 SL-M7 32 FS1ECZ STEP 6 44 PCL6L 88 FS1PL	STEP 9 (H.S. TRANS.) 4 BUP24 120 ISL-B7 STEP 10 12 ISL-B7 STEP 12 8 CCP24AZO 64 FS1ECZ 216 ISL-B7	BLD'Gs C&D STEP 13 (EW TRANS.) 2 RSF1L 24 FS5PL 17 FS1ECZ 68 FS4CZ 3 PR13SS 408 ISL-B7	STEP 14 (H.S. TRANS.) 16 ISL-TWH 96 ISL-B7 4 FS1ECZ 16 FS4CZ	BLD'G C ULTRA DEK ROOF (LOW FLOATING) THERMAL BLOCKS (NONE) 3" INSULATION (NOT BY MESCO)	STEP 1 (EW TRANS.) 1 RSF1L 12 FS5PL 5 FS1ECZ 16 FS4CZ 96 ISL-B7 5 FS1ECZ STEP 6 56 PCL6L 112 FS1PL	STEP 9 (H.S. TRANS.) 14 BUP24 420 ISL-B7 STEP 10 42 ISL-B7 STEP 12 28 CCP24AZO 224 FS1ECZ 756 ISL-B7	BLD'Gs C&D STEP 14 (H.S. TRANSITION) 56 ISL-TWH 336 ISL-B7 14 FS1ECZ 56 FS4CZ	BLD'G D ULTRA DEK ROOF (LOW FLOATING) THERMAL BLOCKS (NONE) 3" INSULATION (NOT BY MESCO)
---	--	--	---	---	---	--	--	--	--	---	---	---	---	---	---



ROOF PANEL ASS'YS BLDG's A,B,C&D

- NOTE: BLD'G A RIGHT EW OPEN TO BLD'G C FULL HEIGHT ; FULL WALL
- NOTE: BLD'G B RIGHT EW OPEN TO BLD'G A FULL HEIGHT ; FULL WALL
- NOTE: BLD'G C LEFT EW OPEN TO BLD'Gs A&D FULL HEIGHT ; FULL WALL
- NOTE: BLD'G D FRONT SW OPEN TO BLD'G A FULL HEIGHT ; FULL WALL
- NOTE: BLD'G D RIGHT EW OPEN TO BLD'G C FULL HEIGHT ; FULL WALL

NOTE:
REFER TO ULTRA-DEK SNAP SEAM ROOFING SYSTEM (TECHNICAL / ERECTION INFORMATION) FOR ULTRA-DEK PANEL INSTALLATION.
NOTE:
ROOF FASTENERS AND SEALANT ARE NOT SHOWN ON DETAILS FOR CLARITY. REFER TO ULTRA-DEK SNAP SEAM ROOFING SYSTEM (TECHNICAL / ERECTION INFORMATION) FOR FASTENER AND SEALANT INFORMATION AND LOCATIONS.
NOTE:
ROOF FASTENERS AND SEALANT SHALL BE INSTALLED IN ACCORDANCE WITH THE ULTRA-DEK SNAP SEAM ROOFING SYSTEM (TECHNICAL / ERECTION INFORMATION)




NOTE: DOWNSPOUTS NOT BY MESCO
NOTE: FIELD MODIFY GUTTER TO LENGTH (AS REQ'D)
PARAPET GUTTER ASSY
1 RPF1-0
2 RE7GP
25 PR26AL
TRANSITION TRIM ASSY #6
1 TT400GP
1 TT401GP
168 ISL-B7
15 PR13SS
2 TU6
168 ISL-TUR

Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Sinque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E2 of 14


DESIGN CRITERIA
Building Code FLORIDA 2001
Live Load 12/20 psf
Wind Velocity 100 mph

NOTE:
CARE MUST BE USED TO INSURE THAT
BRIDGING SLOTS LINE UP IN PURLINS

BRIDGING ANGLE SCHEDULE	
SEE REF.DWG. RB0102-0	
LOCATION	PARTS
△ A	12 LB2663Y4
△ B	7 LB4434Y4
△ C	49 LB5625Y4
△ D	9 LB3544Y4
△ E	6 LB3840Y4
△ F	6 LB3333Y4 6 CU11 12 S27CR-N
△ G	1 LB2747Y4 1 CU11 2 S27CR-N
△ H	2 LB3643Y4
△ I	2 LB3053Y4
△ J	2 LB2802Y4











ROOF BRACING ASS'YS BLDG's A,B,C&D



DESIGN CRITERIA
Building Code FLORIDA 2001
Live Load 12/20 psf
Wind Velocity 100 mph

Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
△	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTOR DRAWING	Simque Construction	-	22-3680
△					Operator	End Customer	Sheet Number	
					MAM	Rimrock Development, Inc	E3 of 14	
					Date			
					11-02-05			






DESIGN CRITERIA

Building Code **FLORIDA 2001**


Live Load **12/20 psf**

Wind Velocity **100 mph**

Rev.#	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Slimque Construction	-	22-3680
2					Operator MAM	End Customer Rimrock Development, Inc		Sheet Number E4 of 14




LEFT EW TRIM LAYOUT BLD'G A




RIGHT ENDWALL TRIM LAYOUT


ERECTOR NOTE:
INSTALL CLIP WITH SLOTTED
CONNECTION TO SPANDREL BEAM




LEFT EW ASS'Y BLD'G A
TOC= TOP OF COLUMN



RIGHT EW ASS'Y BLD'G A
TOC= TOP OF COLUMN




BACK SW ASS'Y BLD'G A
TOC= TOP OF COLUMN




LEFT EW ASS'Y BLD'G B
TOC= TOP OF COLUMN

PRIMARY FRAMING BOLT/NUT ASSEMBLY Assembly No. BN510BB Use "Snug Tight" Installation Method Part No. B510B Part No. N5B 	
PRIMARY FRAMING BOLT/NUT ASSEMBLY Assembly No. BN516BB Use "Snug Tight" Installation Method Part No. B516B Part No. N5B 	
PRIMARY FRAMING BOLT/NUT ASSEMBLY Assembly No. BN512BB Use "Snug Tight" Installation Method Part No. B512B Part No. N5B 	




LEFT EW ASS'Y BLD'G D
TOC= TOP OF COLUMN




RIGHT EW ASS'Y BLD'G C
TOC= TOP OF COLUMN

DESIGN CRITERIA	
Building Code	FLORIDA 2001
Live Load	12/20 psf
Wind Velocity	100 mph




Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	ORS	10/4/05	ERECTION DRAWING	Simque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E5 of 14
					Date			
					11-02-05			




NOTE:
AT LOCATIONS SHOWN, INSTALL FLANGE BRACES
THAT ARE AT ONE SIDE ONLY.

NOTE: SEE FLOOR ASS'Y FOR Pc MARKS & LOCATIONS

Frame Line: 2 & 3
BLD'G A
AssyQty = 2




DESIGN CRITERIA	
Building Code	FLORIDA 2001
Live Load	12/20 psf
Wind Velocity	100 mph






Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Stimque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E6 of 14






Frame Line: 4
BLD'G A
 AssyQty = 1


 <p>FA 8 BN616BB 1/2 x 8 x 2-4 1/16 Plate With (8) 3/4 Dia. x 2 A325</p>	 <p>FB 8 BN514BB 3/8 x 8 x 2-4 Plate With (8) 5/8 Dia. x 1 3/4 A325</p>	 <p>FC 8 BN820BB 5/8 x 0-10 x 2-4 9/16 Plate With (8) 1 Dia. x 2 1/2 A325</p>
--	--	---

DESIGN CRITERIA
 Building Code FLORIDA 2001
 Live Load 12/20 psf
 Wind Velocity 100 mph



Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Simque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E7 of 14






Frame Line: 5
BLD'GA
 AssyQty = 1

<p>FA 8 BN616BB 1/2 x 8 x 2-4 1/16 Plate With (8) 3/4 Dia. x 2 A325</p>	<p>FB 8 BN514BB 3/8 x 8 x 2-4 Plate With (8) 5/8 Dia. x 1 3/4 A325</p>	<p>FC 8 BN820BB 5/8 x 0-10 x 2-4 9/16 Plate With (8) 1 Dia. x 2 1/2 A325</p>	<p>FD 4 BN416BB 3/8 x 0-8 x 1-0 1/2 Plate With (4) 1/2 Dia. x 2 A325</p>	<p>FE 4 BN416BB 3/8 x 0-8 x 1-0 1/2 Plate With (4) 1/2 Dia. x 2 A325</p>
---	--	--	--	--

Rev. #	Description	Det.	Chk.	Date
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05




Sheet Description ERECTOR DRAWING	Date 11-02-05
Operator MAM	

Buyer Simque Construction	Order Number 22-3680
End Customer Rimrock Development, Inc	Sheet Number EB of 14

Q Number -	Order Number 22-3680
MEMA logo	Sheet Number EB of 14

DESIGN CRITERIA
 Building Code **FLORIDA 2001**
 Live Load **12/20 psf**
 Wind Velocity **100 mph**




NOTE: SEE FLOOR ASS'Y FOR Pc MARKS & LOCATIONS

NOTE: AT LOCATIONS SHOWN, INSTALL FLANGE BRACES THAT ARE AT ONE SIDE ONLY.

Frame Line: 6

BLD'G A

AssyQty = 1



FA
8 BN616BB
1/2 x 8 x 2-4 1/16 Plate With (8) 3/4 Dia. x 2 A325

FB
8 BN514BB
3/8 x 8 x 2-4 Plate With (8) 5/8 Dia. x 1 3/4 A325

FC
8 BN820BB
5/8 x 0-10 x 2-4 9/16 Plate With (8) 1 Dia. x 2 1/2 A325

Rev. #	Description	Det.	Chk.	Date
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05
2				
3				




Sheet Description	
Operator	MAM
Date	11-02-05

Buyer	
Buyer	Simque Construction
End Customer	Rimrock Development, Inc.


Q Number	Order Number
-	22-3680
Sheet Number	E9 of 14

DESIGN CRITERIA
Building Code FLORIDA 2001
Live Load 12/20 psf
Wind Velocity 100 mph







Frame Line: 1
BLD'G B
 AssyQty = 1




DESIGN CRITERIA
 Building Code FLORIDA 2001
 Live Load 12/20 psf
 Wind Velocity 100 mph

Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Simque Construction	-	22-3680
					Operator MAM	End Customer Rimrock Development, Inc		Sheet Number E10 of 14
								Date 11-02-05






Frame Line: 7
BLD'G C
 AssyQty = 1




DESIGN CRITERIA	
Building Code	FLORIDA 2001
Live Load	12/20 psf
Wind Velocity	100 mph







Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Simque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E11 of 14
					Date			
					11-02-05			




P.O. Box 93829, Southlake, TX, Zip 75093 817-488-8511




SECOND FLOOR FRAMING ASS'Y



SECOND FLOOR JOIST ASS'Y




32 MWH1
MWH1 = ANGLE 1x1x.109 for top & btm chord @ bar joist



SECOND FLOOR PANEL ASS'Y

"PBD" 26GA. 32" COVERAGE (GP) FLOOR DECK
PANEL = MPA-6GPK*



3 PA24000J*
FF = (3) Pcs OF 20'-0" PA24000J* PROVIDED TO BE FIELD MODIFY & FIELD LOCATE AROUND W.B. & COLUMNS (AS REQ'D) TO SUPPORT FLOOR DECK.

DESIGN CRITERIA
Building Code FLORIDA 2001
Live Load 12/20 psf
Wind Velocity 100 mph


Rev.#	Description	Det.	Chk.	Date
1	ISSUED FOR CONSTRUCTION	REB	DRS	10/4/05

ERECTOR DRAWING
Operator MAM Date 11-02-05

Buyer Simque Construction
End Customer Rtmrock Development, Inc


Q Number -
Order Number 22-3680
Sheet Number E12 of 14






SECTION A/E13


(TYP. @ JOIST TO WIND BENT COLUMN)




SECTION B/E13




SECTION C/E13




SECTION D/E13




SECTION E/E13




FLOOR JOIST ATTACHMENT TO FLOOR BEAM




FLOOR JOIST ATTACHMENT TO STIFFENER




FLOOR JOIST ATTACHMENT TO BRACKET




SECTION F/E13



FLOOR DECK SUPPORT @ COLUMN / W.B. COLUMN



FLOOR DECK SUPPORT @ EW COLUMN



SECTION G/E13

Rev. #	Description	Det.	Chk.	Date
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05
2				
3				
















Sheet Description	
Operator	MAM
Date	11-02-05

Buyer	Simque Construction
End Customer	Rimrock Development, Inc

Q Number	-	Order Number	22-3680
MEMA		Sheet Number	E13 of 14

DESIGN CRITERIA
 Building Code FLORIDA 2001
 Live Load 12/20 psf
 Wind Velocity 100 mph






Rev.#	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	DRS	10/4/05	ERECTION DRAWING	Simque Construction	-	22-3680
					Operator	End Customer		Sheet Number
					MAM	Rimrock Development, Inc		E14 of 14

DESIGN CRITERIA
Building Code FLORIDA 2001
Live Load 12/20 psf
Wind Velocity 100 mph

P:\0500 0706 0001\Revise\0500151207.rvt




DESIGN CRITERIA
 Building Code **FLORIDA 2001**
 Live Load **12/20 psf**
 Wind Velocity **100 mph**




Rev. #	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	ISSUED FOR CONSTRUCTION	KEB	GRS	10/4/05	DETAIL SHEET	Simque Construction	-	22-3680
					Operator MAM	End Customer Rimrock Development, Inc		Sheet Number D1 of 1
					Date 11-02-05			



11/20/05 07:28:20:03 Source: 60915 11/27/05 1/1



RB0101-0
Version 02-28-2003



RB0102-0



RG0101-0



RG0102-0

RECEIPT AND CARE OF MATERIALS

INTRODUCTION
This article has been prepared as a guideline for Buyer or Buyer's Receiving Agent who is responsible for receipt and care of materials manufactured by the Manufacturer.

SHIPPING DOCUMENTS
A complete set of Shipping Documents are provided by Manufacturer with each shipment of materials. The Shipping Documents include a Bill of Lading, a Shipping Manifest, and a Shipping List.

PACKAGING AND MARKING
Materials for the Building System are packaged for ease in loading, unloading and to prevent loss of materials during transit. Standard packaging as outlined below is suitable for transportation by Manufacturer truck, and any other packaging requirements must be specified by Buyer on the Contract Documents.

UNLOADING
Buyer is responsible for unloading materials at the delivery address or jobsite. If shipment is by truck, delivery is made to the nearest safe and accessible point to the job site. It is essential that the Buyer or Buyer's Receiving Agent be prepared with adequate workmen and equipment to meet and unload the shipment promptly at the scheduled time of delivery.

STORAGE
Substantial deterioration and damage can occur to materials during job site storage. Materials should always be assembled or erected promptly on receipt. If assembly must be delayed, materials must be stored under protection.

RECEIPT

It is the Buyer's responsibility to receive each shipment including verifying all quantities as shown on the Shipping Manifest and inspecting all pieces or packages for damage. Quantities are verified by marking the quantity received on the Shipping Manifest. All shortages of part or package must be noted by Buyer or Buyer's Receiving Agent on the Shipping Manifest.

IMPORTANT NOTICE
This material has been coated with a shop-applied primer. The primer is intended to protect the manufactured framing parts for only a short period of exposure to ordinary atmospheric conditions.

METAL BUILDING PANELS
Metal building panels are high quality construction materials. Proper care of these building components can enhance the appearance of a building and will assure full service life.

INTRODUCTION
Metal building panels are high quality construction materials. Proper care of these building components can enhance the appearance of a building and will assure full service life.

TYPES OF FINISHES
GALVALUME
Galvalume is the trade name for a patented steel sheet & coil product having a coating of corrosion resistant aluminum-zinc alloy.

PRE-PAINTED
Using galvalume steel as a substrate, pre-painted steel is given an additional rust inhibitor primer coat. This primer coat further increases the corrosion resistance.

MAINTENANCE
All panel finishes offered by the Manufacturer have excellent durability and provide an attractive appearance for the metal building's exterior. Periodic maintenance will extend the service life and add to the aesthetic value of the building panels.

RECEIPT OF MATERIALS
It is the responsibility of the Buyer to receive all shipments from the Manufacturer verifying the quantities received and inspecting the shipment for damage.

CLAIMS
Claims for shortages or damages made on the shipping manifest should be acknowledged with the signature of the Manufacturer's driver or the carrier's driver or agent.

PACKAGING

Packaging of Manufacturer panels is designed to protect materials and prevent material loss during transit. Standard packaging includes wrapping in waterproof paper in bundles not exceeding 3500 pounds in weight. Bundles are separated by configuration and color and loaded separated by configuration.

DAMAGE DURING CONSTRUCTION
The quality of workmanship in steel erection, construction practices, and handling methods used during the construction of the metal building can significantly affect the appearance and performance of the building panels.


UNLOADING, STACKING AND STORAGE
Proper unloading and stacking techniques can help prevent unnecessary damage, reduce handling time, and pay dividends in increased erection efficiency.

DAMAGE FROM CONDENSATION OR TRAPPED WATER
It is extremely important that the panels be checked at unloading, and then constantly monitored for evidence of trapped water or moisture condensation while awaiting erection.

RECEIPT OF MATERIALS
It is the responsibility of the Buyer to receive all shipments from the Manufacturer verifying the quantities received and inspecting the shipment for damage.


CLAIMS
Claims for shortages or damages made on the shipping manifest should be acknowledged with the signature of the Manufacturer's driver or the carrier's driver or agent.

Rev.#	Description	Del. Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
-	REFERENCE DRAWING			Operator	Simgue Construction	-	22-3680
				Date	End Customer		
				10-07-05	Rimrock Development, Inc		
						RG0102-0	




SELF-DRILLING STITCH FASTENERS

THESE FASTENERS DRILL & TAP IN ONE OPERATION
SOME OF THE COMMON USES FOR THESE FASTENERS ARE PANEL TO PANEL SIDELAPS, TRIMS TO TRIMS AND AS THE GUTTER SUPPORT FASTENER.




SELF-DRILLING STRUCTURAL FASTENERS

THESE FASTENERS DRILL & TAP IN ONE OPERATION
SOME OF THE COMMON USES FOR THESE FASTENERS ARE PANEL TO FRAMING AT EXTERIOR ROOF AND WALL PANEL WITH A MAXIMUM OF 4" OF BLANKET INSULATION.




SELF-TAPPING STRUCTURAL FASTENERS

THESE FASTENERS REQUIRE PRE-DRILLING A PILOT HOLE
THIS FASTENER IS THE TRANSLUCENT ROOF PANEL TO FRAMING FASTENER.




SELF-DRILLING STRUCTURAL FASTENERS

THESE FASTENERS DRILL & TAP IN ONE OPERATION
SOME OF THE COMMON USES FOR THESE FASTENERS ARE PANEL TO FRAMING AT SOFFIT, FACIA, BACK PANEL AND MINI-WHISE EXTERIOR PANEL, ALSO AT PANEL TO FRAMING AT LINER AND INTERIOR PARTITION PANELS.




SELF-DRILLING STRUCTURAL FASTENERS

THESE FASTENERS DRILL & TAP IN ONE OPERATION
SOME OF THE COMMON USES FOR THESE FASTENERS ARE PANEL TO FRAMING AT EXTERIOR ROOF AND WALL PANEL WITH OVER 4" OF BLANKET INSULATION.



SELF-TAPPING STRUCTURAL FASTENERS

THESE FASTENERS REQUIRE PRE-DRILLING A PILOT HOLE
SOME OF THE COMMON USES FOR THESE FASTENERS ARE THRU PANEL TO FRAMING AT ROOF TO WALL TRANSITIONS AND AT HIGH SIDE EAVE TRIMS.




SELF-DRILLING STRUCTURAL FASTENERS

THESE FASTENERS DRILL & TAP IN ONE OPERATION
SOME OF THE COMMON USES FOR THESE FASTENERS ARE PANEL TO FRAMING AT SOFFIT, FACIA, BACK PANEL AND MINI-WHISE EXTERIOR PANEL, ALSO AT PANEL TO FRAMING AT LINER AND INTERIOR PARTITION PANELS NOT POLAR WHITE OR UNPAINTED.




POP RIVET 1/8 X 3/16 GRIP

THESE POP RIVETS ARE USED AT TRIM ENDLAPS



POP RIVET 5/32 X 1/4"

THESE POP RIVETS ARE USED AT VALLEY AND PARAPET GUTTER ENDLAPS



RECOMMENDED INSTALLATION TOOLS & BITS


- RECOMMENDED TOOL - AN 1800 rpm MAXIMUM, 4 TO 6 AMP SCREW GUN EQUIPPED WITH A DEPTH LOCATING NOSE PIECE. USE ADEQUATE CORDAGE TO PREVENT VOLTAGE DROP AT TOOL.
- RECOMMENDED SOCKETS AND BITS: SELF-DRILLING SOCKETS - ONE PIECE 5/16" HEX SELF-TAPPING SOCKETS - ONE PIECE 3/8" HEX BITS - 1/8" PANEL OR TRIM TO FRAMING: #8 (.199) BITS - 1/8" PANEL OR TRIM TO FRAMING: #8 (.199) BIT SIZE FOR 1/8" POP RIVET IS #30 (.1285) BIT SIZE FOR 5/32" POP RIVET IS #20 (.161)

RECOMMENDED INSTALLATION GUIDELINES

- DO NOT USE IMPACT TOOLS OR NUT RUNNERS TO INSTALL SCREWS.
- REPLACE AND CLEAN SOCKETS OFTEN. THIS WILL ALLOW SCREWS TO SEAT PROPERLY IN THE SOCKET AND PREVENT "WOBBLING".
- ALWAYS DRIVE SCREW PERPENDICULAR TO THE WORK SURFACE. THIS WILL PREVENT SCREW "WALKING" OR PANEL/TRIM DAMAGE.
- INCORRECT FASTENER INSTALLATION CAN RESULT IN FASTENER FAILURE, WATER LEAKS, AND/OR PREMATURE DETERIORATION OF PANEL/SCREW.
- POP RIVETS REQUIRE CONNECTING PARTS TO BE PRE-DRILLED AND INSTALLED WITH AN ADEQUATE TOOL.


A307 HEX HEAD BOLT/NUT ASSEMBLIES

INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
SOME OF THE COMMON USES FOR THESE BOLT/NUT ASSEMBLIES ARE PURLIN, GIRT, EAVESTRUT AND FLANGE BRACE TO FRAME CONNECTIONS. ALSO END FRAME COLUMN TO END FRAME RAFTER CONNECTIONS.




A307 FINNECK BOLT/NUT ASSEMBLIES

INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
SOME OF THE COMMON USES FOR THESE BOLT/NUT ASSEMBLIES ARE HEADER TO JAMB AND JAMB TO GIRT AND JAMB TO BASE CLIP CONNECTIONS.




A490 HEX HEAD BOLT/NUT ASSEMBLIES

INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
THE MOST COMMON USE FOR THESE BOLTS IS THE MAIN FRAME COLUMN TO MAIN FRAME RAFTER CONNECTIONS.




A325 HEX HEAD BOLT/NUT ASSEMBLIES

INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
THE MOST COMMON USE FOR THESE BOLTS IS THE MAIN FRAME COLUMN TO MAIN FRAME RAFTER CONNECTIONS.




A325 HEX HEAD BOLT/NUT ASSEMBLIES


INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
THE MOST COMMON USE FOR THESE BOLTS IS THE MAIN FRAME COLUMN TO MAIN FRAME RAFTER CONNECTIONS.




Assembly No. BN720BB




Assembly No. BN410BB




Assembly No. BN416BB



Assembly No. BN510BB




Assembly No. BN512BB




A325 HEX HEAD BOLT/NUT ASSEMBLIES

INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
THE MOST COMMON USE FOR THESE BOLTS IS THE MAIN FRAME COLUMN TO MAIN FRAME RAFTER CONNECTIONS.




A354 HEX HEAD BOLT/A490 NUT ASSEMBLIES

INSTALLATION OF THESE BOLTS IS TO BE "SNUG TIGHT"
THE MOST COMMON USE FOR THESE BOLTS IS THE BUILT-UP COLUMN TO BUILT-UP RAFTER CONNECTIONS.




Assembly No. BN416CD




BOLT INSTALLATION INFORMATION

"SNUG TIGHT CONDITION" - SNUG TIGHT CONDITION IS DEFINED AS THE TIGHTNESS OBTAINED BY A FEW IMPACTS OF AN IMPACT WRENCH OR THE FULL EFFORT OF A MAN USING AN ORDINARY SPUD WRENCH.

POP RIVETS AT TRIM SPLICES



POP RIVETS AT TRIM SPLICES




NOTES: USE COLOR MATCH POP RIVETS FOR THE FOLLOWING COLORS: AG, BS, CW, DG, DS, FN, LS, PW, RR, AND ST. ALL OTHER COLORS USE STAINLESS STEEL POP RIVETS.

NOTES: WHERE TUBE SEALANT IS REQ'D. FOR TRIM LAPS, BRONZE SEALANT IS PROVIDED FOR BRONZE TRIM, WHITE TUBE SEALANT IS PROVIDED FOR ALL OTHER FINISH CODED TRIMS.

Rev. #	Description	Det.	Chk.	Date

Sheet Description		REFERENCE DRAWING	
Operator	Date	Operator	Date
KEB	10-07-05	KEB	10-07-05


Buyer	Q Number	Order Number
Simque Construction	-	22-3680
End Customer	Sheet Number	
Rimrock Development, Inc	RG0106-0	




POP RIVETS AT RAINWARE SPLICES

RG0107-0


RG0108-0




PART NO : RR
ELBOWS (6) POP RIVETS




PART NO : RG
GUTTER (10) POP RIVETS




PART NO : RT
DOWNSPOUT STRAP (4) POP RIVETS




PART NO : RE
GUTTER ENDCAPS (10) POP RIVETS




PART NO : RD
DOWNSPOUTS (6) POP RIVETS



PART NO : RK
KICKOUTS (6) POP RIVETS



PART NO : RR
RETURNS (6) POP RIVETS



3" MAX. SPACING, EACH LEG OF VALLEY
GUTTER, USE SELF-SEALING POP RIVET.

NOTES:
WHERE TUBE SEALANT IS REQ'D. FOR TRIM LAPS, BRONZE SEALANT IS PROVIDED FOR BRONZE TRIM/RAINWARE & WHITE TUBE SEALANT IS PROVIDED FOR ALL OTHER FINISH CODED TRIMS/RAINWARE.

NOTES:
USE COLOR MATCH POP RIVETS FOR THE FOLLOWING COLORS: AG, BS, CW, DG, DS, FN, LS, PW, RR, AND ST. ALL OTHER COLORS USE STAINLESS STEEL POP RIVETS.

DEALER / CONTRACTOR RESPONSIBILITIES

GENERAL NOTES

IT IS THE RESPONSIBILITY OF THE DEALER/CONTRACTOR TO INSURE THAT ALL PROJECT PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE REQUIREMENTS OF ANY GOVERNING BUILDING AUTHORITIES. THE SUPPLYING OF SEALED ENGINEERING DATA AND DRAWINGS FOR THE METAL BUILDING SYSTEM DOES NOT IMPLY OR CONSTITUTE AN AGREEMENT THAT MESCO METAL BUILDINGS OR ITS DESIGN ENGINEER IS ACTING AS THE ENGINEER OF RECORD OR DESIGN PROFESSIONAL FOR A CONSTRUCTION PROJECT.
THE DEALER/CONTRACTOR MUST SECURE ALL REQUIRED APPROVALS AND PERMITS FROM THE APPROPRIATE AGENCY AS REQUIRED.
APPROVAL OF MESCO'S DRAWINGS AND CALCULATIONS INDICATE THAT MESCO METAL BUILDINGS CORRECTLY INTERPRETED AND APPLIED THE REQUIREMENTS OF THE CONTRACT DRAWINGS AND SPECIFICATIONS. (SECT. 4.2.1 AISC CODE OF STANDARD PRACTICES, 9TH ED.)
WHERE DISCREPANCIES EXIST BETWEEN MESCO'S STRUCTURAL STEEL PLANS AND THE PLANS FOR OTHER TRADES, THE STRUCTURAL STEEL PLANS SHALL GOVERN. (SECT. 3.3 AISC CODE OF STANDARD PRACTICE 9TH ED.)
DESIGN CONSIDERATIONS OF ANY MATERIALS IN THE STRUCTURE WHICH ARE NOT FURNISHED BY MESCO METAL BUILDINGS ARE THE RESPONSIBILITY OF THE CONTRACTORS AND ENGINEERS OTHER THAN MESCO METAL BUILDINGS' ENGINEERS UNLESS SPECIFICALLY INDICATED.
THE DEALER/CONTRACTOR IS RESPONSIBLE FOR ALL ERECTION OF STEEL AND ASSOCIATED WORK IN COMPLIANCE WITH MESCO METAL BUILDINGS' "FOR CONSTRUCTION" DRAWINGS.
ALL BRACING AS SHOWN AND PROVIDED BY MESCO FOR THIS BUILDING IS REQUIRED AND SHALL BE INSTALLED BY THE ERECTOR AS A PERMANENT PART OF THE STRUCTURE.
TEMPORARY SUPPORTS, SUCH AS TEMPORARY GUYS, BRACES, FALSEWORK, CRIBBING OR OTHER ELEMENTS REQUIRED FOR THE ERECTION OPERATION WILL BE DETERMINED AND FURNISHED AND INSTALLED BY THE ERECTOR. THESE TEMPORARY SUPPORTS WILL SECURE THE STEEL FRAMING, OR ANY PARTIALLY ASSEMBLED STEEL FRAMING, AGAINST LOADS COMPARABLE IN INTENSITY TO THOSE FOR WHICH THE STRUCTURE WAS DESIGNED, RESULTING FROM WIND, SEISMIC FORCES AND ERECTION OPERATIONS, BUT NOT THE LOADS RESULTING FROM THE PERFORMANCE OF WORK BY OR THE ACTS OF OTHERS, NOR SUCH UNPREDICTABLE LOADS AS THOSE DUE TO TORNADO, EXPLOSION OR COLLISION. (SECT. 7.5.1 AISC CODE OF STANDARD PRACTICE, 9TH ED.)


THE STRUCTURE UNDER THIS PURCHASE ORDER HAS BEEN DESIGNED AND DETAILED FOR THE LOADS AND CONDITIONS STIPULATED IN THE PURCHASE ORDER AND SHOWN ON THESE DRAWINGS. ANY ALTERATIONS TO THE STRUCTURAL SYSTEM OR REMOVAL OF ANY COMPONENT PARTS, OR THE ADDITION OF OTHER CONSTRUCTION MATERIALS OR LOADS MUST BE DONE UNDER THE ADVICE AND DIRECTION OF A REGISTERED ARCHITECT, CIVIL OR STRUCTURAL ENGINEER.
MESCO METAL BUILDINGS WILL ASSUME NO RESPONSIBILITY FOR ANY LOADS NOT INDICATED.
THIS METAL BUILDING IS DESIGNED WITH MESCO METAL BUILDINGS' STANDARD PRACTICES WHICH ARE BASED ON PERTINENT PROCEDURES AND RECOMMENDATIONS OF THE FOLLOWING ORGANIZATIONS AND CODES:
1. AMERICAN INSTITUTE OF STEEL CONSTRUCTION: "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS"
2. AMERICAN IRON AND STEEL INSTITUTE: "SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS"
3. AMERICAN WELDING SOCIETY: "STRUCTURAL WELDING CODE" AWS D1.1.
4. METAL BUILDING MANUFACTURER'S ASSOCIATION: "LOW RISE BUILDING SYSTEMS MANUAL"
5. INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS: "UNIFORM BUILDING CODE"
6. SOUTHERN BUILDING CODE CONGRESS INTERNATIONAL: "STANDARD BUILDING CODE"
7. BUILDING OFFICIAL AND CODE ADMINISTRATORS INTERNATIONAL: "BOCA NATIONAL BUILDING CODE"
SHOP AND FIELD INSPECTIONS AND ASSOCIATED FEES ARE THE RESPONSIBILITY OF THE DEALER/CONTRACTOR, UNLESS STIPULATED OTHERWISE IN THE CONTRACT.

SAFETY COMMITMENT


MESCO METAL BUILDINGS HAS A COMMITMENT TO MANUFACTURE QUALITY BUILDING COMPONENTS THAT CAN BE SAFELY ERECTED. HOWEVER, THE SAFETY COMMITMENT AND JOB SITE PRACTICES OF THE ERECTOR ARE BEYOND THE CONTROL OF MESCO METAL BUILDINGS.
IT IS STRONGLY RECOMMENDED THAT SAFE WORKING CONDITIONS AND ACCIDENT PREVENTION PRACTICES BE THE TOP PRIORITY OF ANY JOB SITE.
LOCAL, STATE AND FEDERAL SAFETY AND HEALTH STANDARDS SHOULD ALWAYS BE FOLLOWED TO HELP INSURE WORKER SAFETY.
MAKE CERTAIN ALL EMPLOYEES KNOW THE SAFEST AND MOST PRODUCTIVE WAY OF ERECTING A BUILDING. EMERGENCY PROCEDURES SHOULD BE KNOWN TO ALL EMPLOYEES.
DAILY MEETINGS HIGHLIGHTING SAFETY PROCEDURES ARE ALSO RECOMMENDED. THE USE OF HARD HATS, RUBBER SOLE SHOES FOR ROOF WORK, PROPER EQUIPMENT FOR HANDLING MATERIAL, AND SAFETY NETS WHERE APPLICABLE, ARE RECOMMENDED.

RM0101-0


RM0102-0




FRAMED OPENING TYPE 1




FRAMED OPENING TYPE 2




FRAMED OPENING TYPE 3



FRAMED OPENING TYPE 4




FRAMED OPENING TYPE 5




FRAMED OPENING TYPE 6

SEE REFERENCE DRAWINGS RM0102 AND RM0103 FOR CONNECTION DETAILS




Rev.#	Description	Det.	Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
1	REFERENCE DRAWING				REFERENCE DRAWING	Simque Construction		22-3680
2					Operator	End Customer		Sheet Number
3					KEB	Rimrock Development, Inc		RM0102-0





RM0103-0

1. FRAMED OPENINGS ARE FIELD LOCATED. THE FRAMED OPENINGS MAY BE SHOWN ON THE ERECTION DRAWINGS IN THEIR GENERAL LOCATION.
2. FIELD CUT GIRTS AT FRAMED OPENINGS. IF GIRTS ABOVE THE FRAMED OPENING HEADS OR BELOW THE SILL MEMBERS MUST BE CUT. THE CUT PORTION MUST BE FIELD RELOCATED AT THE PROPER ELEVATION BETWEEN THE FRAMED OPENING JAMBS.






NOTE: PBR Wall Panel Shown. PBX, PBA and PBU Wall Panel Similar.


RM0104-1



RR0305-0




RR0306-0



Rev. #	Description	Det.	Chk.	Date

Sheet Description REFERENCE DRAWING	Buyer Simque Construction	Q Number -	Order Number 22-3680
Operator KEB	End Customer Rimrock Development, Inc	Sheet Number RR0306-0	Date 10-07-05









ENDWALL PANEL GENERAL NOTES:

1. SQUARE AND PLUMB BUILDING PRIOR TO INSTALLATION OF WALL PANELS.
2. MARK FOUNDATION AT BASE LINE AT 3 FT. INCREMENTS FOR THE WIDTH OF THE ENDWALL WHILE INSTALLING PANEL TO INSURE ALIGNMENT AND PANEL COVERAGE. REFER TO "DETAIL AT FOUNDATION" FOR MARK LOCATIONS.
3. BLOCK GIRTS TO LEVEL, IF REQUIRED, PRIOR TO INSTALLATION OF PANEL. LEAVE BLOCKING IN PLACE UNTIL PANEL INSTALLATION IS COMPLETE. REFER TO "DETAIL AT BLOCKING"
4. REFER TO ENDWALL PANEL INSTALLATION NOTES FOR PANEL INSTALLATION.
5. PRE DRILLING OF PANEL SIDELAP IS RECOMMENDED. REFER TO STANDARD DRAWINGS FOR RECOMMENDED FASTENER INSTALLATION.
6. THIS DRAWING IS TO BE USED IN CONJUNCTION WITH THE ERECTION DRAWINGS AND OTHER DRAWINGS OF THIS SERIES.


ENDWALL PANEL INSTALLATION NOTES:

1. ENDWALL START PANEL LOCATION FOR GABLE BLDG. CASE 1 IS LOCATED BY ALIGNING CENTER LINE OF PANEL WITH THE RIDGELINE OF THE BLDG. AS SHOWN IN ENDWALL START PANEL LOCATIONS.
2. ENDWALL START PANEL LOCATION FOR GABLE BLDG. CASE 2 IS LOCATED BY ALIGNING CENTER LINE OF THE MAJOR RIB WITH THE RIDGE LINE OF THE BLDG. AS SHOWN IN ENDWALL START PANEL LOC.
3. ENDWALL START PANEL LOCATION FOR SINGLE SLOPE ENDWALL IS LOCATED BY ALIGNING THE CENTER LINE OF THE MAJOR RIB WITH THE HIGH SIDE STEEL LINE AS SHOWN IN ENDWALL START PANEL LOCATIONS, SINGLE SLOPE ENDWALL.
4. REFER TO THE ERECTION DWGS FOR PANEL TYPE & CASE CONDITION OF YOUR ENDWALL.
5. INSTALL (2) FASTENERS PER PANEL THRU TO PANEL ANGLE TO TEMPORARILY HOLD PANEL IN PLACE UNTIL REMAINING FASTENERS CAN BE INSTALLED. REFER TO ERECTION DRAWINGS FOR FASTENER TYPE AND COLOR.
6. ATTACH PANEL TO FRAMING AT PANEL TO FRAMING FASTENER SPACING. REFER TO ERECTION DWGS. FOR FASTENER TYPE AND COLOR.
7. INSTALL NEXT PANEL LAPPING RIBS WITH PREVIOUSLY INSTALLED PANEL. SECURE PANEL TO PANEL AT LAPPED RIBS WITH FASTENERS AT STITCH FASTENER SPACING. REFER TO ERECTION DRAWINGS FOR FASTENER TYPE AND COLOR.
8. CONTINUE SHEETING ENDWALL CHECKING VERTICAL ALIGNMENT AND PANEL COVERAGE. PANEL MAY END AT MAJOR RIBS OR REQUIRE FIELD CUTTING. REFER TO ERECTION DWGS. FOR PANEL LAYOUT





SIDEWALL PANEL INSTALLATION NOTES

1. START FIRST SIDEWALL PANEL AT CORNER WITH THE CENTER LINE OF THE MAJOR RIB ALIGNED WITH THE ENDWALL STEEL LINE.
2. INSTALL ONE FASTENER AT CORNER OF EACH FRAMING MEMBER TO HOLD PANEL IN PLACE UNTIL REMAINING FASTENERS CAN BE INSTALLED.
3. ATTACH PANEL TO FRAMING MEMBERS AT PANEL TO FRAMING FASTENER SPACING. REFER TO ERECTION DRAWING FOR FASTENER TYPE AND COLOR.
4. INSTALL NEXT PANEL LAPPING RIBS. ATTACH PANEL TO PANEL USING FASTENERS AT STITCH FASTENER SPACING. REFER TO ERECTION DRAWINGS FOR FASTENER TYPE AND COLOR.
5. CONTINUE SHEETING SIDEWALL CHECKING VERTICAL ALIGNMENT AND COVERAGE. PANEL MAY END AT MAJOR RIB OR REQUIRE FIELD CUTTING. REFER TO ERECTION DRAWINGS FOR PANEL LAYOUT.



SIDEWALL PANEL GENERAL NOTES

1. SQUARE AND PLUMB BUILDING PRIOR TO INSTALLATION OF WALL PANELS.
2. MARK FOUNDATION AT BASE LINE AT 3 FT. INCREMENTS FOR THE LENGTH OF THE SIDEWALL TO USE WHILE INSTALLING PANEL TO INSURE PANEL COVERAGE. REFER TO DETAIL AT FOUNDATION.
3. BLOCK GIRTS TO LEVEL, IF REQUIRED, PRIOR TO INSTALLATION OF PANELS. LEAVE BLOCKING IN PLACE UNTIL PANEL INSTALLATION IS COMPLETE. REFER TO DETAIL AT BLOCKING.
4. REFER TO SIDEWALL PANEL INSTALLATION NOTES FOR PANEL INSTALLATION.
5. PRE DRILLING OF PANEL SIDELAP IS RECOMMENDED. REFER TO STANDARD DRAWING FOR RECOMMENDED FASTENER INSTALLATION.
6. THIS DRAWING IS TO BE USED IN CONJUNCTION WITH THE ERECTION DRAWINGS AND OTHER DRAWINGS OF THIS SERIES.



PANEL SIDELAPS






CORNER TRIM INSTALLATION NOTES:


1. Attach corner angle to wall framing members with one fastener at each member at each wall.
2. Install wall panels.
3. Install corner trim with pop rivets at 12" on center.

SIDE TRIM INSTALLATION NOTES:

1. Install side trim, prior to wall panel installation, to framing member with pop rivets at 12" on center.
2. Install wall panels.
3. Attach side trim to wall panel with pop rivets at 12" on center.



- BASE ANGLE INSTALLATION NOTES:**
1. Base angle is furnished as a standard component of the building unless one of the optional panel base members is specified. Base angle is in standard lengths of 25 feet.
 2. Base angle is omitted at all framed openings. See other reference drawings for base member cut outs.
 3. Attach base angle to foundation. Consult anchorage device manufacturer for recommended fastening to safely resist a lateral load of 168 lbs/ft of base angle. Suggested minimum fastening is 1/4" x 1 1/4" drive pin or expansion bolt at 4'-0" o.c. Minimum edge distance is 2"
- BASE GIRT INSTALLATION NOTES:**
1. Base girt is furnished as an optional component of the building.
 2. Web holes for clips and/or flange clips are provided in all frame and endwall columns and web holes for clips in framed opening joints for attachment of base girt. Field drill holes for base girt attachment in fixed base columns.
 3. In the case of personnel doors the base girt must be field cut at the door frame and either welded directly to the door frame or a clip must be welded to the door frame and a girt field drilled for a bolted connection.
- BASE CHANNEL INSTALLATION NOTES:**
1. Base channel is furnished as an optional component of the building. Base channel is furnished in 25' lengths and is to be field cut to length.
 2. Base channel is omitted at all framed openings. See other reference drawings for base member cut outs.
 3. Attach base channel to foundation. Consult anchorage device manufacturer for recommended fastening to safely resist a lateral load of 168 lbs/ft of base angle. Suggested minimum fastening is 1/4" x 1 1/4" drive pin or expansion bolt at 4'-0" o.c. Minimum edge distance is 2"
 4. Attach base angle to foundation. Consult anchorage device manufacturer for recommended fastening to safely resist a lateral load of 168 lbs/ft of base angle. Suggested minimum fastening is 1/4" x 1 1/4" drive pin at 4'-0" o.c. Minimum edge distance is 2 3/8"
 5. The aluminum base edge is to be field mitered at outside corners. The bronze or sandstone base edge is to be field cut at outside corners and then copped with a pre-formed, color matched corner member supplied with the order for each outside corner.
 6. Base edge is to be field mitered at inside corners.
 6. Base edge is to be field blocked at flush framed columns.




Rev. #	Description	Det.	Chk.	Date	Sheet Description REFERENCE DRAWING	Buyer Simque Construction	Order Number 22-3680
					Operator KEB	End Customer Rimrock Development, Inc	Sheet Number RW0104-1
					Date 10-07-05		




MATERIAL REQUIREMENTS FOR 3070 AND 4070 DOORS



RW0201-0




- NOTES:**
- ALL PARTS FOR LOCKSET INSTALLATION NOT SHOWN. REFERENCE LOCKSET PACKAGE FOR INSTRUCTIONS.
 - THIS DRAWING IS TO BE USED WITH R06-03 & 04 FOR 3070 OR 4070 DOOR INSTALLATION.
 - REFERENCE BILL OF MATERIAL FOR ITEMS PROVIDED WITH THE ASSEMBLY.
 - GLASS FOR THE NARROW LITE DOORS IS NOT PROVIDED BY THE BUILDING MANUFACTURER AND MAY BE 1/8", 3/16" OR 1/4" THICK PLASTIC OR TEMPERED GLASS. THE ACTUAL SIZE REQUIRED IS 6 5/8" X 29 7/16".





RW0203-1



- INSTALLATION NOTES**
- USING BILL OF MATERIALS AND REFERENCE DWGS. RW0201 or RW0202 LOCATE ALL MATERIALS REQ. TO INSTALL THE SIZE OF DOOR PROVIDED WITH THE ASSEMBLY.
 - AFTER DOOR LOCATION HAS BEEN ESTABLISHED FIELD CUT PANEL OPENING AS SHOWN IN INSTALLATION STEP 1 'PANEL PREPARATION'.
 - REMOVE PANEL BASE ANCHORAGE MATERIAL TO DIMENSIONS SHOWN IN INSTALLATION STEP 2 'BASE MEMBER CUT OUT'.
A) IF BASE GIRTS OR INTERMEDIATE GIRTS IS PROVIDED, FIELD CUT AS NOTED AND ATTACH TO DOOR FRAME WITH SCREWS AT LOCATIONS SHOWN ON ERECTION DWGS.
 - ASSEMBLE DOOR FRAME WITH BOLTS PROVIDED IN KIT. SQUARE FRAME AND ATTACH HEAD TO GIRT WITH SELF-DRILLING SCREWS AS SHOWN IN SECTION B. NOTE: DOOR FRAME MUST BE CENTERED IN PANEL CUT OUT TO ALLOW TRIM INSTALLATION TO WORK. ATTACH BASE OF DOOR FRAME TO ANCHOR POINTS AS SHOWN IN SECTION 'A'.
 - SEE REF. DWG. RW0204 FOR TRIM INSTALLATION. INSTALL HEAD TRIM BEFORE SIDE TRIM. INSTALL TRIMS AS SHOWN IN TRIM ASSEMBLY.
 - INSTALL WEATHERSTRIP/THRESHOLD AND/OR CLOSER IF REQUIRED.



INSTALLATION STEP 4: TRIM ASSEMBLY



INSTALLATION STEP 5: LOCKSETS


REFER TO INSTRUCTION PACKAGE PROVIDED WITH LOCKSETS FOR INSTALLATION.

NOTE: CYLINDRICAL PREP DOOR LEAF FOR USE WITH CYLINDRICAL LOCKSETS AND/OR PANIC DEVICE.
MORTISE PREP. DOOR LEAF FOR USE WITH MORTISE LOCKSETS ONLY.

INSTALLATION STEP 6: 6070 HARDWARE

6070 DOORS REQUIRE (1) ONE ACTIVE LEAF AND (1) INACTIVE LEAF. INACTIVE LEAF IS ALWAYS A CYLINDRICAL PREP. DOOR LEAF.

INSTALL CYLINDRICAL FILLER PLATE, ASTRAGAL, TOP AND BOTTOM SURFACE BOLTS TO INACTIVE LEAF.



Rev. #	Description	Det. Chk.	Date	Sheet Description	Buyer	Q Number	Order Number
▲				REFERENCE DRAWING	Simque Construction	-	22-3680
▲				Operator	End Customer		Sheet Number
▲				KEB	Rimrock Development, Inc		

