


[illegible]

BEARING WOOD INTERIOR WALL SCHEDULE					
MARK	STUD SPACING	CONNECTION & FASTENERS		LUMBER SPECIES	UPLIFT CAP (#/F)
		TOP	BOTTOM		
BW1	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW2	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SPF	402
BW3	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	571
BW4	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW5	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	439
BW6	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	665
BW7	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW8	12"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SPF	535
BW9	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	760
BW10	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW11	12"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	585
BW12	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	885

NOTE: 2 X 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS

* ALL LUMBER TO BE GRADE #2
** CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED
*** SPFS & SPSS CAN BE SUB. FOR SPFS W/ RESPECT TO STUD SIZE



- ### BEARING INTERIOR WALL DETAIL
- DOUBLE 2x4 TOP PLATE
DOUBLE 2x4 HEAD-
OVER OPENINGS W/ IN
BRG WALL SEE DET.
W/ROD FOR MORE INFO.
- 2x MID-SPAN BLOCKING
W/ (2) 12d TOENAILS @
EACH END FOR WALLS
TALLER THAN 8'-0"
- 2x P.T. W/ 1/2" A.B @ 32" O.C. W/ 7"
EMBEDMENT OR 1/2" A.T.R. W/ SIMPSON SET W/
MIN. 7" EMBEDMENT PAD STEP DOWN.
A.T. SIMPSON 1/2" TITEN HD @ 32" O.C.
W/ SAME EMBEDMENT
- SIMPSON SPH4
TOP AND BOTTOM
2x STUDS PER
PLAN, SCHEDULE
ABOVE
- EXTERIOR
SHEATHING FROM
TOP AND BOTTOM,
ATTACHED PER
NAILING
SCHEDULE
- CONNECTORS
TOP & BOTTOM
PER PLAN/
SCHEDULE ABOVE
SEE FOUNDATION
PLAN FOR MORE
INFO

GENERAL NOTES			
1.	SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED U.N.O.		
2.	ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.		
3.	CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.		
4.	CONTACT E.O.R. IF SP4 SPS OR SPFS S CONNECTIONS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.		
5.	IF "B.V" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE W/ROD/S3 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY)		
6.	IF "S.W" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 1/4" OSB PLYWOOD W/ 5d NAILS AT 1" O.C. IN FIELD AND EDGE TO (1) SIDE OF WALL.		
7.	ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ACT AS SHEARWALLS. SEE PLAN AND WALLS SECTIONS FOR STUD SPACING AND GRADE.		
8.	IF THE BEARING WALL IS INDICATED WITH THE B.V.L. B.W.L. B.W.T. B.W.D. THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE NAILS TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CAGED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.		

COLUMN SCHEDULE			
MARK	COLUMN SIZE	(BASE) CONN. & FASTENER	UPLIFT(LB)
C1	(3) 2 x 4 #2 SPF	(4) - 16d TOENAILS	0
C2	(3) 2 x 4 #2 SPF	DT122 W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145
C3	(3) 2 x 4 SYP #1 OR-	(4) - 16d TOENAILS	0
C4	(2) 2 x 4 SPF #2	DT122 W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145
C5	4 x 4 P.T. #2 SYP POST	ABU44 W/ 5/8" ATR** & (12) - 16d NAILS	G = 6665 U = 2200
C6	6 x 6 P.T. #2 SYP POST	ABU66 W/ 5/8" ATR** & (12) - 16d NAILS	G = 12000 U = 2300
C7	8 x 8 P.T. #2 SYP POST	ABU88 W/ (2) - 5/8" ATR** & (18) - 16d NAILS	G = 24335 U = 2320
C8	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (W/OUNNED) (F EXT.)	HOU5-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C9	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (W/OUNNED) (F EXT.)	HOU5-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C10	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (W/OUNNED) (F EXT.)	HOU5-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	6970
C11	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (W/OUNNED) (F EXT.)	HOU5-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
C12	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (W/OUNNED) (F EXT.)	HOU5-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
C13	5.25" x 7" P.L. 1.8E Rb-2400 PSI (W/OUNNED) (F EXT.)	HOU5-SDS2.5 W/ 7/8" ATR AND (20) 1/4" x 2 1/2" SDS WOOD SCREWS	7870

GENERAL COLUMN NOTES			
1.	SEE FLOOR PLAN FOR WALL WIDTH. STUD PICKS TO MATCH WALL WIDTH U.N.O.		
2.	ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.		
3.	NAIL BUILT UP STUDS PER DETAIL WFS7		
4.	MINIMUM BOLT EMBEDMENT:		
5.	EMBEDMENT FOR 1/2" ATR		
6.	EMBEDMENT FOR 5/8" ATR		
7.	EMBEDMENT FOR 7/8" ATR		
8.	IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)		
9.	SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION.		
10.	SAME NOMINAL SIZE PARALLEL COLUMNS (L&R) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOT IN THE PLANS		

COMMON NAIL vs. PNEUMATIC GUN NAILS:			
COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL	COMMON vs. GUN
8d	0.131" X 2 1/2"	0.131" X 2 1/2"	SEE PLAN RING SHANK ON ROOF
10d OR 12d	0.148" X 3"	0.131" X 3"	SEE PLAN
12d	0.148" X 3 1/4"	0.131" X 3 1/4"	SEE PLAN
12d	0.148" X 3 1/4"	0.131" X 3 1/4"	6" O.C. (COMMON) 6" O.C. (GUN NAIL)
10d	0.148" X 3"	0.131" X 3"	6" O.C. (COMMON) 6" O.C. (GUN NAIL)
16d	0.162" X 3 1/2"	0.131" X 3 1/2"	SEE PLAN

HEADER SCHEDULE		
(IF USED, SEE DET. "TOP" ON SHEET S-2 FOR ENERGY STAR INSULATION ON HEADERS)		
MARK	HEADER SIZE	REMARKS
H1	(2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H2	(2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H3	(2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H4	(2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H5	(2) - 1 3/4" X 11 1/4" LVL 2.0E FB-2600 PSI	ATTACH TOGETHER W/ (3) ROWS 14" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE
H6	(2) - 1 3/4" X 9 1/4" LVL 2.0E FB-2600 PSI	ATTACH TOGETHER W/ (3) ROWS 14" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE

HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS			
OPENING SIZE	2x4 WALL		2x6 OR 2x8 WALL
	JACKS EA. END	KINGS EA. END	JACKS EA. END
1'-0" - 3'-11"	(1)	(2)	(1)
4'-0" - 9'-11"	(2)	(3)	(2)
10'-0" - 16'-0"	(3)	(4)	(3)



GENERAL HEADER NOTES

- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
- IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. PLAN
- IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS
- ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WFS7
- FASTEN ALL MULTIPLE HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" O.C. ALONG EACH EDGE OR (3) ROWS IF 2X10 OR LARGER
- FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
- IF HEADER IS NOT SPECIFIED CONTACT E.O.R.

BEAM SCHEDULE		
MARK	BEAM SIZE	CONNECTIONS
BM1	(2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM2	(2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM3	(2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM4	(2) - 1 3/4" X 11 1/4" LVL 2.0E FB-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM5	(2) - 1 3/4" X 11 7/8" LVL 2.0E FB-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM6	(2) - 1 3/4" X 9 1/4" LVL 2.0E FB-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.

GENERAL BEAM NOTES

- VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)- SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
- BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.



FLOOR PLAN
SCALE: 1/4" = 1'-0"
ELEVATION "A" & "B"

NOTE:
○ INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND	
FRAMED WALL	
BEARING FRAME WALL	
FRAMED WALL W/ BRICK VENEER	
FRAMED WALL W/ SIDING OR STUCCO	

- ### GENERAL NOTES
- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
 - R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum 1/8" (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic conduit or pipe, 1 inch conduit, or other approved material and shall not have openings into the garage.
 - R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycomb core steel door, or 20 Minute fire rated door.
 - R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surface and any soffits protected on the enclosed side with 1/2" gypsum board.
 - Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
 - Bathroom exhaust fans must vent to the exterior of the building. Exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
 - R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also protect by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
 - R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 72 inches (910 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below or the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
 - R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
 - E.C. R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
 - M1502.4.5 Duct length
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
M1502.3 Duct termination.
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
 - Porch Ceilings: (See plan for the following options)
Option 1: Gypsum:
1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
The gypsum board shall be attached w/ Type "W" 1x4" drywall screws at 8" O.C. in field and edges.
Option 2: Plywood Base:
7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
 - Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

- * ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS	
1st FLOOR	2508 S.F.
TOTAL LIVING (AC)	2508 S.F.
GARAGE	543 S.F.
COVERED ENTRY	60 S.F.
COVERED PATIO/LANAI	193 S.F.
TOTAL AREA UNDER ROOF	3304 S.F.

COUNTY SEAL

Thursday, September 26, 2024

FDS ENGINEERS ASSOCIATES

2550 S. GULF BLVD. SUITE 200
PENSACOLA, FL 32509
904.200.1115
www.fdseng.com

Keese Associates
ARCHITECTURE DESIGN PLANNING
2200 W. 9TH AVE. SUITE 200
PENSACOLA, FL 32506
904.200.1115
www.keese.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 92
BLK:
SEC:
SUB:

Model Name / Number:
2508



Plan Issue Date:
Thursday, September 26, 2024

KA PROJECT NUMBER:
24-12151

Sheet: 2 Of:

FLOOR PLAN





















LOAD CALCULATIONS	
COOLING GREATER THAN HEATING	
GENERAL LIGHTING & RECEPTACLES	
3 WATTS PER SQUARE FOOT OF LIVING S.F. LIVING = 2,508 X 3 = 7524	
APPLIANCE CIRCUITS	
RANGE	8500
OVEN	NONE
MICRO / HOOD	1000
WATER HEATER	4500
WHIRL POOL	1250
WASHER	1500
DRYER	5000
DISHWASHER	1500
DISPOSAL	600
SMALL APPLIANCE CIRCUITS (3)	4500
BATH FANS (100 WATTS / EACH)	200
GEN LIGHT G & RECEPT. + APP. CIR. = 36,524	
SUBTRACT 100 % OF FIRST 10,000 = 10,000	
A = 26,524	
HVAC CIRCUITS	
A/C (AIR HANDLER & COMP.)	10,000
A/C (AUXILIARY HEAT STRIP)	10,000
B = 20,000	
CIRCUIT CALCULATIONS	
FIRST 10,000 AMPS @ 100%	= 10,000
+ 40% OF "A" = (40 X 26,524)	= 10,610
+ 100% OF "B" = (20,000)	= 20,000
TOTAL WATTAGE	= 40,610
WATTS DIVIDED BY 240 = AMPS	
CALCULATED SERVICE AMPS	= 170




PLUMBING RISER
NTS

ELECTRICAL PLAN
SCALE: 1/4" = 1'-0"

- ELECTRICAL NOTES:** UNLESS OTHERWISE NOTED.
- ELECTRICAL OUTLET HEIGHTS AS MEASURED FROM FINISHED FLOOR TO CENTER LINE OF THE BOX TO BE: 16" AFF (GENERAL), IN A FLOOD ZONE, ALL ELECTRICAL EQUIPMENT TO BE AT OR ABOVE DFE.
 - KITCHEN: 44" AFF
 - BATHROOM: 39" AFF
 - LAUNDRY ROOM: 36" AFF
 - EXTERIOR WATERPROOF: 12" AFF
 - GARAGE: GENERAL PURPOSE 42" AFF
 - RANGE: 2" AFF
 2. ALL TRIM PLATES AND DEVICES TO BE GANGED, WHERE POSSIBLE.
 3. ELECTRICAL SWITCHES TO BE AT 42" CENTERLINE ABOVE FINISHED FLOOR.
 4. ELECTRICAL PLAN IS INTENDED FOR BID PURPOSES ONLY. ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC), LATEST EDITION, BY A LICENSED ELECTRICAL CONTRACTOR WHO SHALL BE RESPONSIBLE FOR THE INSTALLATION & SIZING OF ALL ELECTRICAL WIRING & ACCESSORIES.
 5. SMOKE ALARMS SHALL COMPLY WITH NFPA 72 AND SECTION R314 AND SHALL BE LISTED IN ACCORDANCE WITH UL 217, COMBINATION SMOKE AND CARBON MONOXIDE ALARMS SHALL BE LISTED IN ACCORDANCE WITH UL 217 AND UL 2034.
 6. PROVIDE AFCI'S (ARC-FAULT CIRCUIT INTERRUPTERS) COMBINATION TYPE INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUITS IN ALL DWELLING UNITS PER NFPA 70 (CURRENT EDITION) AND THE NEC AND AS DEFINED IN UL 1699.
 7. PROVIDE TAMPER RESISTANT RECEPTACLES AS REQUIRED BY THE NFPA 70 (CURRENT EDITION).
 8. CARBON MONOXIDE PROTECTION: CARBON MONOXIDE ALARMS OR DETECTORS SHALL BE INSTALLED IN ALL DWELLING UNITS IN ACCORDANCE WITH FBC R315 AND NFPA 70. SUCH DEVICES SHALL BE LISTED BY THE APPROPRIATE STANDARD, EITHER ANSI/UL 2034, STANDARD FOR SINGLE AND MULTIPLE STATION CO ALARMS OR UL 2075, GAS AND VAPOR DETECTOR SENSOR, ACCORDING TO THE INSTALLATION.
 9. FBC'S 1.2 COMBINATION ALARMS: COMBINATION SMOKE/CARBON MONOXIDE ALARMS SHALL BE LISTED AND LABELED BY A NATIONALLY RECOGNIZED TESTING LABORATORY.
 10. KEEP ALL SMOKE DETECTORS MINIMUM OF 36" FROM BATHROOM DOORS.
 11. IN NEW CONSTRUCTION, SMOKE DETECTORS SHALL BE HARDWIRED INTO AN A/C ELECTRICAL POWER SOURCE AND SHALL BE EQUIPPED WITH A MONITORED BATTERY BACKUP.
 12. BATHROOM EXHAUST FANS MUST VENT TO THE EXTERIOR OF THE BUILDING, VENTILATION TO ATTIC SPACE AND SOFFITS IS NOT ACCEPTABLE.
 13. CHAPTER 45 PRIVATE SWIMMING POOLS — OUTDOOR SWIMMING POOLS SHALL BE PROVIDED WITH A BARRIER COMPLYING WITH R4501.17.1.1 THROUGH R4501.17.1.14.
 14. ADD GFCI PROTECTION TO RECEPTACLES IN LAUNDRY ROOMS AND UTILITY ROOMS OF DWELLINGS WHERE INSTALLED WITHIN 6' OF THE OUTSIDE EDGE OF A SINK. THIS WOULD INCLUDE THE RECEPTACLE INSTALLED FOR A WASHING MACHINE. RECEPTACLE OUTLETS SHALL NOT BE REQUIRED ON A WALL DIRECTLY BEHIND A RANGE OR SINK TO FULFILL THE REQUIREMENT OF AN OUTLET EVERY 24". THE WIDTH OF THE SINK OR RANGE IS NOT TO BE INCLUDED IN THE SPACING OF THE OUTLETS UNLESS THE DISTANCE FROM THE SINK OR RANGE IS GREATER THAN 12" FOR STRAIGHT COUNTER TOPS AND 18" FOR SINKS AND RANGES INSTALLED IN CORNER COUNTERS.
 15. WHERE MORE THAN ONE SMOKE ALARM IS REQUIRED TO BE INSTALLED WITHIN AN INDIVIDUAL DWELLING UNIT IN ACCORDANCE WITH SECTION R314.3, THE ALARM DEVICES SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTUATION OF ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE INDIVIDUAL DWELLING UNIT. PHYSICAL INTERCONNECTION OF SMOKE ALARMS SHALL NOT BE REQUIRED WHERE LISTED WIRELESS ALARMS ARE INSTALLED AND ALL ALARMS SOUND UPON ACTIVATION OF ONE ALARM.
 16. FOR ONE- AND TWO-FAMILY DWELLING UNITS, ALL SERVICE CONDUCTORS SHALL TERMINATE IN DISCONNECTING MEANS HAVING A SHORT-CIRCUIT CURRENT RATING EQUAL TO OR GREATER THAN THE AVAILABLE FAULT CURRENT, INSTALLED IN A READILY ACCESSIBLE OUTDOOR LOCATION. EACH DISCONNECT SHALL BE ONE OF THE FOLLOWING:
(1) SERVICE DISCONNECTS MARKED AS FOLLOWS:
EMERGENCY DISCONNECT.
SERVICE DISCONNECT.
(2) METER DISCONNECTS INSTALLED PER 230.82(3) AND MARKED AS FOLLOWS:
EMERGENCY DISCONNECT.
METER DISCONNECT.
NOT SERVICE EQUIPMENT.
(3) OTHER LISTED DISCONNECT SWITCHES OR CIRCUIT BREAKERS ON THE SUPPLY SIDE OF EACH SERVICE DISCONNECT THAT ARE SUITABLE FOR USE AS SERVICE EQUIPMENT AND MARKED AS FOLLOWS:
EMERGENCY DISCONNECT.
NOT SERVICE EQUIPMENT.
 17. ALL PERMANENTLY INSTALLED LUMINAIRES, EXCLUDING THOSE IN KITCHEN APPLIANCES, SHALL HAVE AN EFFICACY OF AT LEAST 45 LUMENS/PERWATT OR SHALL UTILIZE LAMPS WITH AN EFFICACY OF NOT LESS THAN 65 LUMENS/PERWATT.

ELECTRICAL LEGEND			
\$	SINGLE POLE SWITCH		SMOKE DETECTOR
\$2	DOUBLE POLE SWITCH		CARBON MONOXIDE/ SMOKE DETECTOR COMBO UNIT
\$3	THREE-WAY SWITCH		FLOOD LIGHT
\$4	FOUR-WAY SWITCH		FLUORESCENT LIGHTING
\$DM	DIMMER SWITCH		TRACK LIGHTING
	CEILING MOUNTED FIXTURE		CEILING FAN
	SCOUNCE (WALL MOUNTED) FIXTURE		CHIMES
	110 VOLT DUPLEX OUTLET		DOOR BELL CHIMES
	110 VOLT SPLIT SWITCHED OUTLET		DOOR BELL
	GROUND FAULT INTERRUPT		DISPOSAL
	WATER PROOF W/ GROUND FAULT		DISCONNECT SWITCH
	220 VOLT OUTLET		PREWIRE SPEAKER
	SPECIAL SERVICES OUTLET		JUNCTION BOX
	T.V. CABLE OUTLET		THERMOSTAT
	TELEPHONE CABLE OUTLET		LOW VOLTAGE LIGHTING
	RECESSED LIGHTING		INTERCOM SYSTEM
	WATER PROOF RECESSED LIGHTING		GARAGE DOOR PUSH BUTTON
	BATH FAN		
	BATH FAN W/ LIGHT		
	L.E.D. DISC LIGHT		



COUNTY SEAL

Thursday, September 26, 2024

ENGINEERS ASSOCIATES
FDS
www.fdseng.com

keesee
associates
ARCHITECTURE | DESIGN | PLANNING
22407 SE 23rd St., Suite 200
Boca Raton, FL 33433
954.980.2355
@keesee.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 92
BLK:
SEC:
SUB: Preserve of Laurel Lake
777 S.W. Rosemary Dr.
Lake City, FL


Model Name / Number:
2508

Plan Issue Date:
Thursday, September 26, 2024

KA PROJECT NUMBER:
24-12151


Sheet: 4 Of:

ELECTRICAL




LEFT ELEVATION "A"

SCALE: 3/16" = 1'-0"



RIGHT ELEVATION "A"

SCALE: 3/16" = 1'-0"



REAR ELEVATION

SCALE: 1/4" = 1'-0"



FRONT ELEVATION "A"

SCALE: 1/4" = 1'-0"

VENTILATION CALCULATION	
Formula = SF / 300 / 2 * 144 = net sq inches of venting needed equally for intake and exhaust	
Soffit product provides	4.12 net sq in / sf
Ridge vent provides	18.00 net sq in / lf
Off ridge vent provides	138.00 net sq in / sf
Overhang distance	2.00 ft
S.F. of Area to be vented (SF)	3304 s.f.
Total needed for exhaust for upper 1/3	793 net sq inches
Total needed for intake (soffit area, lower)	793 net sq inches
Number of Off Ridge Vents for upper 1/3 needed	6
L.F. of Ridge Vent needed (can be used in combo with ORV)	44
Lineal Feet of Soffit needed to meet required	96
Lineal S.F. provided by plan	251

COUNTY
SEAL

Thursday, September 26, 2024

www.fdseng.com

FDS
ENGINEERING ASSOCIATES
288 Seaboard Lane, Suite 200
Ocala, Florida 32751
352.607.8800
Certificate of Authorization No. 9481

☐ CARL A. BROWN, P.E. FL # 55126
☐ SCOTT A. LEWOWSKI, PE FL # 78750
☐ THIEN BAO DUONG, PE FL # 94452

keese
associates
ARCHITECTURE | DESIGN | PLANNING
23007 880 1335
www.keese.com

AA26003115
AIA
FDS
in
f
e
7

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 92
BLK:
SEC:
SUB: Preserve of Laurel Lake
777 S.W. Rosemary Dr.
Lake City, FL

Model Name / Number:
2508

Plan Issue Date:
Thursday, September 26, 2024

KA PROJECT NUMBER:
24-12151

Sheet: **5** OF

ELEVATIONS



HIP ROOF > 20 TO 27 DEG.
a=4ft [4:12]-[6:12]

GABLE ROOF > 20 TO 27 DEG
[4:12]-[6:12]

NOTE: 8d NAILS FOR WALL SHEATHING MUST BE MIN. 131" X 2 1/2".
DO NOT OVERDRIVE NAILS; FASTENERS SHALL NOT PENETRATE
SURFACE MORE THAN 1/8"



SCALE: 1/4" = 1'-0"


GENERAL CONNECTOR NOTES:

1. CONNECT ALL FLOOR TRUSSES TO INTERIOR BEARING WOOD WALLS / BEAMS w/ (2) 12d TOENAILS.
2. ALL TRUSSES TO BE CONNECTED AS PER TRUSS MANUFACTURER, U.L.O. ON PLAN.
3. G.C. MAY USE EITHER SMIPSON OR USP CONNECTIONS. SEE FRAMING PLAN FOR CONNECTOR CALL OUT.
4. FOR SINGLE PLY TRUSSES, SCAB ON FULL HEIGHT SYP #1 2"x4" TO TRUSS VERTICAL WEBB w/ (2) ROWS OF 10d NAILS @ 3" O.C. STAGGERED.
5. 12" MIN. A.T.R. EMBEDMENT @ CMU BOND BEAM U.L.O.
6. SCAB TRUSS CHORD w/ 4" O" 2 SYP #2 (MATCH CHORD LUMBER SIZE) w/ (2) ROWS 10d @ 4" FROM END & 4" O.C. STAGGERED. CENTER AT CONNECTOR LOCATION AS MUCH AS POSSIBLE.


1. SHINGLE OR METAL ROOFING SYSTEM (SEE ARCH.) SHEATHING - SEE [RSH] SCHEDULE THIS SHEET. FOR SHTG & FASTENERS ON PRE. ENGINEERED WOOD TRUSSES AT 2'-0" O.C. MAX. OR CONVENTIONAL FRAME ROOF. (SEE PLAN FOR SIZE AND SPACING. SEE ARCHITECTURAL PLAN FOR TYPICAL ROOF SLOPE AND OTHER INFORMATION.)

TILE ROOFING SYSTEM (SEE ARCH.) SEE [RSH] SCHEDULE THIS SHEET


IF ROOF TRUSS LAYOUT SHOWS TRUSS ID'S, THIS LAYOUT HAS BEEN PROVIDED BY THE CLIENT/ DESIGNER OR ARCHITECT TO USE FOR THE DESIGN OF THIS PROJECT. OTHERWISE A GENERIC LAYOUT HAS BEEN DETERMINED, BUT PRIOR TO CONSTRUCTION OR TRUSS FABRICATION, FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS ARE TO BE SUBMITTED TO ENGINEER OF RECORD (E.O.R.) FOR REVIEW AND APPROVAL. AT THIS TIME THE E.O.R. IS REQUIRED TO REVERSE THIS LAYOUT AND PROVIDE A REVISION PER A REVIEW OF THE FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS. ADDITIONAL FEE'S MAY APPLY, STARTING CONSTRUCTION OR TRUSS FABRICATION PRIOR TO THIS REVIEW IS NOT ADVISED. AND THE E.O.R. IS NOT RESPONSIBLE FOR ADDITIONAL COSTS DUE TO REVISIONS OF THE PLAN. IF CONVENTIONAL FRAMING IS SHOWN, NO TRUSS APPROVAL IS REQUIRED, UNLESS LAYOUT IS REWID W/OUT WRITING APPROVAL FROM FDS.




TB15 EXTERIOR NON-BEARING WALL DETAIL N.T.S.




WC04 GARAGE HEADER ANCHOR 3/4" = 1'-0"




WC05 SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.




WF64 EXTERIOR NON BRG. WALL DETAIL N.T.S.




WF43 EXTERIOR ANGLED WALL DETAIL N.T.S.




WC03 WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"




CD11 COMMON BEAM ATTACHMENT N.T.S.




CD25 BEAM TO WALL CONNECTION N.T.S.




WF66 TYPICAL BEARING WALL N.T.S.




WC09 WALL STEP @ CORNER N.T.S.




WC06 EXTERIOR FRAME CORNER 3/4" = 1'-0"



RD01 VALLEY FLASHING DETAIL N.T.S.



CD26 GIRDER BASE CONNECTION 1/2" = 1'-0"



WF68 CORNER CONNECTION N.T.S.

COUNTY
SEAL

Thursday, September 26, 2024


FDS
ENGINEERING ASSOCIATES
255 Seaboard Lane, Suite 200
Norfolk, Virginia 23502
Tel: 757.646.2304
Fax: 757.646.2305
www.fdseng.com

Keese Associates
ARCHITECTURE | DESIGN | PLANNING
2407 S.W. 23rd St.
Miami, FL 33135
Tel: 305.850.2323
www.keese.com


DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

INVENTORY
LOT: 92
BLK:
SEC:
SUB: Preserve of Laure Lake
777 S.W. Rosemary Dr.
Lake City, FL


Model Name / Number:
2508
Plan Issue Date:
Thursday, September 26, 2024
KA PROJECT NUMBER:
24-12151
Sheet: **S-2** Of:
TYPICAL FRAMING DETAILS



WF39 TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



WF09 WALL HEADER DETAIL N.T.S.



WF67 WALL FRAMING 3/4" = 1'-0"

COUNTY
SEAL

Thursday, September 26, 2024

To the best of the Engineer's knowledge, information, and belief, the design and construction of the above project complies with the applicable building codes and standards, and the Engineer is not providing any warranty or representation for the design and construction of the project.

FDS
ENGINEERING ASSOCIATES
255 Seaboard Lane, Suite 200
Maitland, Florida 32751
Tel: 407.960.2204
Fax: 407.960.2204
Certificate of Authorization No. 9361

☐ CARL A. BROWN, P.E.
☐ SCOTT A. LEWIS, P.E.
☐ THIEN BAO DUONG, P.E.

keese
associates
ARCHITECTURE | DESIGN | PLANNING
25407 YSBO 2355
g@keese.com

AA2000115

AD

BD

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
**100 WEST GARDEN STREET
PENSACOLA FL 32502**

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 92
BLK:
SEC:
SUB: Preserve of Laure Lake
777 S.W. Rosemary Dr.
Lake City, FL












Model Name / Number:
2508

Plan Issue Date:
Thursday, September 26, 2024

KA PROJECT NUMBER:
24-12151

Sheet: **S-2.1** Of:

**TYPICAL FRAMING
DETAILS**



COUNTY SEAL

keese associates
ARCHITECTURE | DESIGN | PLANNING
225 S. Duval Street, Suite 200
Pensacola, FL 32502
352.407.5205
govee@keese.com

FDS
ENGINEERING ASSOCIATES
225 S. Duval Street, Suite 200
Pensacola, Florida 32502
352.407.5205
Certificate of Authorization No. 9-181

AA2003115

FL # 86126
FL # 78750
FL # 94452

□ CARL A. BROWN, P.E.
□ SCOTT A. LEWIS, P.E.
□ THEN BAO DUONG, P.E.

AD

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
**100 WEST GARDEN STREET
PENSACOLA FL 32502**

**DIVISION LOCATION:
GAINESVILLE**

Job Information:

INVENTORY

LOT: 92
BLK:
SEC:
SUB: Preserve of Laurel Lake
777 S.W. Rosemary Dr.
Lake City, FL


Model Name / Number:
2508

Plan Issue Date:
Thursday, September 26, 2024


KA PROJECT NUMBER:
24-12151

Sheet: **S-3** Of:


TYPICAL WALL DETAILS




GE05 GABLE END BRACING - FRAME WALL N.T.S.




GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




GE24 GABLE @ VAULT N.T.S.




WF72 LEDGER N.T.S.




WF73 KNEEWALL @ DORMER N.T.S.





GE21 SECTION @ DUTCH GABLE 3/4"=1'-0"



LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.



GE23.1 GABLE END OVERHANG 1/2"=1'-0"



SR01 SECTION AT SHED ROOF 3/4"=1'-0"

COUNTY
SEAL

Thursday, September 26, 2024

To the best of the Engineer's knowledge, information, and belief, the design and construction of the project complies with the applicable provisions of the Florida Building Code, and the design and construction of the project complies with the applicable provisions of the Florida Building Code, and the design and construction of the project complies with the applicable provisions of the Florida Building Code.

FDS
ENGINEERING ASSOCIATES
2555 South Lake Road, Suite 200
Tampa, Florida 33629
Tel: 813.288.8800
Fax: 813.288.8801
www.fdseng.com

keesee
associates
ARCHITECTURE | DESIGN | PLANNING
22401 SW 235th St., Suite 200
Maitland, FL 32751
Tel: 407.580.2355
www.keesee.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 92
BLK: SEC:
SUB: Preserve of Laurel Lake
777 S.W. Rosemary Dr.
Lake City, FL




Model Name / Number:
2508

Plan Issue Date:
Thursday, September 26, 2024

KA PROJECT NUMBER:
24-12151

Sheet: **S-4.1** Of:

ROOF FRAMING AND BRACING DETAILS



THESE DETAILS ARE GENERIC AND MEANT TO SHOW
GENERAL FLASHING AND WATERPROOFING METHODS
TO BE USED.

SELF-ADHERED FLASHING PRODUCTS DETAILS

TWO LAYERS OF FELT OR ONE LAYER OF HOUSE WRAP AND ONE LAYER OF FELT ARE REQUIRED BEHIND STUCCO. FBC R703.2

DETAIL INSTRUCTIONS

REFER TO THE NUMBER MARKED AS (#) IN EACH DETAIL THAT
CORRESPONDS TO THE NUMBERED ITEMS IN THE LIST OF
INSTRUCTIONS BELOW:

1. INSTALL SELF-ADHERED FLASHING IN ORDER AS SHOWN BY NUMBERS.
2. INSTALL FLASHING AND WEATHER RESISTIVE BARRIER TO FORM WATER SHEDDING LAPS.
3. SELF-ADHERED FLASHING CAN BE SUBSTITUTED FOR BUILDING PAPER.
4. SPLIT THE RELEASE PAPER USING THE RIPCORD (SPLIT RELEASE ON DEMAND, EMBEDDED IN THE ADHESIVE LAYER) - FOR EASE OF INSTALLATION AND TO MINIMIZE SCORING CUTS.
5. REMOVE ALL RELEASE PAPER PER STANDARD INSTALLATION INSTRUCTIONS AND ADHERE TO SUBSTRATE USING A SQUARE PIECE OF FLASHING MATERIAL (6" X 6" MINIMUM).
6. FOLD AS SHOWN BY ARROWS.
7. ANGLE OF CORNER MAY VARY, ADJUST FOLDING OF THE FLASHING ACCORDINGLY TO FIT TIGHT TO CORNER.
8. MECHANICALLY FASTEN AS NECESSARY.

FLASHING REQUIREMENTS

R703.1 GENERAL. EXTERIOR WALL SHALL PROVIDE THE BUILDING WITH A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE. THE EXTERIOR WALL ENVELOPE SHALL INCLUDE FLASHINGS AS DESCRIBED IN SECTION R703.4. A WATER-RESISTIVE BARRIER IS DESCRIBED AS A MATERIAL, BEHIND AN EXTERIOR WALL COVERING THAT IS INTENDED TO RESIST LIQUID WATER THAT HAS PENETRATED THROUGH THE EXTERIOR WALL COVERING FROM THE EXTERIOR TO THE INTERIOR OF THE BUILDING. A WATER-RESISTIVE BARRIER IS DESCRIBED AS A MATERIAL OR ASSEMBLY OF MATERIALS APPLIED ON THE EXTERIOR SIDE OF EXTERIOR WALLS FOR THE PURPOSE OF PROVIDING A WEATHER-RESISTIVE BARRIER, INSULATION, OR FOR AESTHETICS, INCLUDING BUT NOT LIMITED TO, VEINERS, SIDING, EXTERIOR INSULATION AND FINISH SYSTEMS, ARCHITECTURAL TRIM AND EMBELLISHMENTS SUCH AS CORNICES, SOFFITS, AND FASCIAS.

R703.2 WATER-RESISTIVE BARRIER. ONE LAYER OF NO. 15 ASPHALT FELT, FREE FROM HOLES AND BREAKS, COMPLYING WITH ASTM D226 FOR TYPE I FELT OR OTHER APPROVED WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS. SUCH FELT OR MATERIAL SHALL BE APPLIED HORIZONTALLY, WITH THE UPPER LAYER LAPPED OVER THE LOWER LAYER NOT LESS THAN 2 INCHES (51 MM). WHERE JOINTS OCCUR, FELT SHALL BE LAPPED NOT LESS THAN 6 INCHES (152 MM). THE FELT OR OTHER APPROVED MATERIAL SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MEET THE REQUIREMENTS OF THE EXTERIOR WALL ENVELOPE AS DESCRIBED IN SECTION R703.1.

R703.7.3 WATER-RESISTIVE BARRIIS SHALL BE INSTALLED AS REQUIRED IN SECTION R703.2 AND, WHERE APPLIED OVER WOOD-BASED SHEATHING, SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE AT LEAST EQUIVALENT TO TWO LAYERS OF GRADE D PAPER. THE INDIVIDUAL LAYERS SHALL BE INSTALLED INDEPENDENTLY SUCH THAT EACH LAYER PROVIDES A SEPARATE CONTINUOUS PLANE AND ANY FLASHING (INSTALLED IN ACCORDANCE WITH SECTION R703.4) INTENDED TO DRAIN TO THE WATER-RESISTIVE BARRIER IS DIRECTED BETWEEN THE LAYERS.

EXCEPTION: WHERE THE WATER-RESISTIVE BARRIER THAT IS APPLIED OVER WOOD-BASED SHEATHING HAS A WATER RESISTANCE EQUAL TO OR GREATER THAN THAT OF 60-MINUTE GRADE D PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING, SUBSTANTIALLY NONWATER-ABSORBING LAYER OR DESIGNED DRAINAGE SPACE.

R703.4 FLASHING. APPROVED CORROSION-RESISTANT FLASHING SHALL BE APPLIED SINGLE-FRAMING IN A MANNER TO PREVENT ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS. SELF-ADHERED FLASHING SHALL BE APPLIED TO THE EXTERIOR WALLS OF THE BUILDING. FLASHING SHALL BE APPLIED TO THE JUNCTION WITH THE BUILDING WALL WITH A SEALANT COMPLYING WITH AAMA 800 OR ASTM C920 CLASS 25 GRADE NS OR GREATER FOR JOINT EXPANSION AND CONTRACTION, ASTM C1281, AAMA 812, OR OTHER APPROVED STANDARD AS APPROPRIATE FOR THE APPLICATION. FLASHING MEMBRANES USED AS FLASHING IN EXTERIOR WALLS SHALL COMPLY WITH AAMA 754. THE FLASHING SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH. APPROVED CORROSION RESISTANT FLASHINGS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS:

1. EXTERIOR WINDOW AND DOOR OPENINGS, FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER RESISTIVE BARRIER COMPLYING WITH SECTION 703.2 FOR SUBSEQUENT DRAINAGE. MECHANICAL ATTACHMENT OF FLASHINGS SHALL COMPLY WITH ASTM 752. FLASHING AT EXTERIOR WINDOW AND DOOR OPENING SHALL BE INSTALLED IN ACCORDANCE WITH ONE OR MORE OF THE FOLLOWING:
 - 1.1 THE PENETRATION MANUFACTURER'S INSTALLATION AND FLASHING INSTRUCTIONS, OR FOR APPLICATIONS NOT ADDRESSED IN THE PENETRATION MANUFACTURER'S INSTRUCTIONS, IN ACCORDANCE WITH THE FLASHING MANUFACTURER'S INSTRUCTIONS, WHERE FLASHING INSTRUCTIONS OR DETAILS ARE NOT PROVIDED, PAN FLASHING SHALL BE INSTALLED AT THE SILL OF EXTERIOR WINDOW AND DOOR OPENINGS. PAN FLASHING SHALL BE SEALED, OR SLOPED IN SUCH A MANNER AS TO DIRECT WATER TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER RESISTIVE BARRIER FOR SUBSEQUENT DRAINAGE. OPENINGS USING PAN FLASHING SHALL INCORPORATE FLASHINGS OR PROTECTION AT THE HEAD AND SIDES.
 - 1.2 IN ACCORDANCE WITH THE FLASHING DESIGN OR METHOD OF A REGISTERED DESIGN PROFESSIONAL.
 - 1.3 IN ACCORDANCE WITH OTHER APPROVED METHODS.
 - 1.4 IN ACCORDANCE WITH FMA/AMA 100, FMA/AMA 200, FMA/WDMA 250, FMA/AMA/WDMA 300 OR FMA/AMA/WDMA 400.
2. AT THE INTERSECTION OF CHIMNEYS OR OTHER MASONRY CONSTRUCTION WITH FRAME OR STUCCO WALLS, WITH PROJECTING LIPS OR BOTH SIDES UNDER STUCCO COPIES.
3. UNDER AND AT THE ENDS OF MASONRY, WOOD OR METAL COPINGS AND SILLS.
4. CONTINUOUSLY ABOVE ALL PROJECTING WOOD TRIM.
5. WHERE EXTERIOR PORCHES, DECKS OR STAIRS ATTACH TO A WALL OR FLOOR ASSEMBLY OF WOOD-FRAME CONSTRUCTION.
6. AT WALL AND ROOF INTERSECTIONS.
7. AT BUILT-IN GUTTERS.

















FIGURE 3: CORNER DETAIL

FLASHING INSTALLATION

WHERE ROOF MEETS VERTICAL WALL

FLASHING DETAIL AT CRICKET
/ KNEEWALL INTERSECTION