


SUOB FILESIPLAN REVIEMFL20099-CLANCYDETAILSIFL20099 S-1 .dwg, 5/30/2020 7:47:23 AM



NOTE
7/16" O.S.B. NAILED WITH 8D 6"
O.C. IN FIELD \$ 4" O.C. ON EDGES

Triple 3-1/3" hidden vent soffit has a 9.19 sq. inches/sq. foot rating

NOTE

Simpson Strong-Tie Co. Strong-Drive SDWC TRUSS Screws may be used for uplift connection in lieu of straps. Strong-Drive SDWC TRUSS Screws to be installed per manufacturer's specifications.

Simpson Strong-Tie Co. Titen HD Heavy-Duty Screw Anchors 5/8" x 8", maximum spacing of 42" o.c., may be used in lieu of 5/8"x10" anchor bolts with 3"x3"x1/8" washer. Titen HD Heavy-Duty Screw Anchors shall be installed per manufacturer's specifications.

ROOF SHEATHING FASTENING

- 4" O.C. GABLE END
- 6" O.C. EDGES (ALL ZONES)6" O.C. INTERMEDIATE FRAMING (ZONE 3)
- 12" O.C. INTERMEDIATE FRAMING (ZONE 5)

 12" O.C. INTERMEDIATE FRAMING (ZONE 1 \$ 2)

 CEE SIGNED PROS. 1 \$ 2017, SIGNED PROS. 2 \$

SEE FIGURE R803.2.3.1, SECTION R803.1, 2017 FLORIDA BUILDING CODE - RESIDENTIAL, SIXTH EDITION FOR ROOF SHEATHING NAILING ZONES

ROOF NOTES

ROOF PITCH LESS THEN 4/12 DBL LAYER OF UNDERLAYMENT IS REQUIRED

OVERLAP ROOFING UNDERLAYMENT 4'(MIN) OVER HIPS AND RIDGES

BUTTON CAP NAILS ARE USED TO FASTEN UNDERLAYMENT TO ROOF DECK
WHEN SHINGLES NOT INSTALLED SAME DAY

DRIP EDGE INSTALLED OVER THE UNDERLAYMENT AT RAKES AND UNDER THE UNDERLAYMENT AT EAVES


ALL ROOF PENETRATIONS ARE PROPERLY FLASHED W/ FLASHING OF THE


CORRECT SIZE FOR THE PENETRATION


METAL ROOFING ATTACHED W/ CORRECT FASTENERS PER CODE AND


MANUFACTURERS SPECS


I" SPACE IS MAINTAINED BETWEEN THE END OF THE GUTTER AND THE WALL
CLADDING
















THIS FIGURE SHOWS A TRUSS GABLE END USING THE L-BENT STRAP METHOD IN ORDER TO SHOW STRAPS, COMPRESSION BLOCKS ARE NOT SHOWN.
THE METHODOLOGY FOR A CONVENTIONALLY FRAMED GABLE END IS SIMILAR.
NOT ALL DETAILS ARE SHOWN.

GABLE END BRACING
NOT TO SCALE





PREPARED FOR
BRYAN ZECHER CONSTRUCTION
386.752.8653
bczecher@comcast.net

CLANCY RESIDENCE

PROJECT NO. FL20099

MAY 29, 2020

REVISION DATE

REVIEWFL20099-CLANCYDETAIISFL20099 S-2.dwg, 5/29/2020 3:39:31 PM