

MIKE TODD CONSTRUCTION
CGC 006209
129 NE COLBURN AVENUE
LAKE CITY, FLORIDA 32055
PHONE 386-755-4387 FAX 386-755-1220

SCOPE OF WORK

MAY 21,2013

BRYANT'S TOWING
1165 E. DUVAL ST.
Lake City, Florida 32055

FOR FURNISHING ALL PERMITS, ENGINEERING, LABOR, EQUIPMENT AND MATERIAL REQUIRED TO PERFORM THE FOLLOWING DESCRIBED WORK:

1. PREPARE EXTERIOR WALLS AND ROOF AREA FOR NEW TRUSSES AND METAL ROOF. FASTEN 2 X 8 PT TOP PLATE TO CONCRETE WALL CAP WITH 5/8" TAPCON THREADED FASTENERS, 48" ON CENTER. A 2 X 6 PT SIDE PLATE TO BE SECURED TO MASONRY SIDE WALL WITH 1/4" TAPCON FASTENERS, 12" ON CENTER. 2 X 6 SECURED TO 2 X 8 WITH 3" WOOD SCREWS, 16" ON CENTER. TRUSS STRAPS INSTALLED TO MEET TRUSS ENGINEERING UPLIFT REQUIREMENTS.
2. INSTALL SINGLE SLOPE, WOOD TRUSS SYSTEM ACCORDING TO ENGINEERED DRAWINGS PROVIDED. WOOD TRUSSES TO BE DESIGNED SO THAT EXISTING MANSARD SLOPE SHALL CONTINUE ON NEW ROOF DESIGN. CONSTRUCTION OF NEW MANSARD SYSTEM ACCORDING TO CURRENT BUILDING CODES AND PRACTICES.
3. MANSARD AREAS TO BE STRIPPED WITH 1 X 4, #2 PINE, 24" ON CENTER AND COVERED WITH 29ga PAINTED METAL
4. INSTALL NEW 29ga METAL ROOFING PANELS, INCLUDING ALL FLASHING AND TRIM, ROOFING INSTALLED OVER 1 X 4, # 2 PINE, 24" ON CENTER.
5. ALL DUMP FEES AND TRASH REMOVAL IS INCLUDED.
6. REMOVE ALL DAMAGED STOREFRONT GLASS AND REPLACE WITH NEW GLASS AS REQUIRED.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Our workers are fully covered by Workman's Compensation Insurance

Authorized
Signature


