DATE 07/13/2009

Columbia County Building Permit

This Permit Must Be Prominently Posted on Premises During Construction

PERMIT
000027941

APPLICANT DENNIS O'NEIL PHONE 454-2476

ADDRESS 235 NE 2ND AVE HIGH SPRINGS FL 32643

OWNER EDWARD & KYLE BUNNELL PHONE 386 462-7006

ADDRESS 1002 SW GRASSY LANE FT. WHITE FL 32038

CONTRACTOR DENNIS O'NEIL PHONE 454-2476

LOCATION OF PROPERTY 47S, TL ON GRASSY LANE, TO THE END

TYPE DEVELOPMENT SFD ADDITION ESTIMATED COST OF CONSTRUCTION 13500.00

HEATED FLOOR AREA 270.00 TOTAL AREA 270.00 HEIGHT ____ STORIES 1

FOUNDATION CONC WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB

LAND USE & ZONING A-3 MAX. HEIGHT ____

Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00

NO. EX.D.U. 1 FLOOD ZONE X DEVELOPMENT PERMIT NO. ____

PARCEL ID 10-6S-16-03814-113 SUBDIVISION SOUTH FORK

LOT 14 BLOCK ____ PHASE ____ UNIT 0 TOTAL ACRES 20.00

Culvert Permit No.	Culvert Waiver	Contractor's License Number	Applicant/Owner/Contractor
		CGC061581	Dem O'Neil

Driveway Connection	Septic Tank Number	LU & Zoning checked by	Approved for Issuance	New Resident
EXISTING	09-378	BK	WR	N

COMMENTS: NOC ON FILE

Check # or Cash 19465

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power ____ date/app. by Foundation ____ date/app. by Monolithic ____ date/app. by

Under slab rough-in plumbing ____ date/app. by Slab ____ date/app. by Sheathing/Nailing ____ date/app. by

Framing ____ date/app. by Insulation ____ date/app. by

Rough-in plumbing above slab and below wood floor ____ date/app. by Electrical rough-in ____ date/app. by

Heat & Air Duct ____ date/app. by Peri. beam (Lintel) ____ date/app. by Pool ____ date/app. by

Permanent power ____ date/app. by C.O. Final ____ date/app. by Culvert ____ date/app. by

Pump pole ____ date/app. by Utility Pole ____ date/app. by M/H tie downs, blocking, electricity and plumbing ____ date/app. by

Reconnection ____ date/app. by RV ____ date/app. by Re-roof ____ date/app. by

BUILDING PERMIT FEE $ 70.00 CERTIFICATION FEE $ 1.35 SURCHARGE FEE $ 1.35

MISC. FEES $ 0.00 ZONING CERT. FEE $ 50.00 FIRE FEE $ 0.00 WASTE FEE $ ____

FLOOD DEVELOPMENT FEE $ ____ FLOOD ZONE FEE $ 25.00 CULVERT FEE $ ____ **TOTAL FEE** 147.70

INSPECTORS OFFICE ____ CLERKS OFFICE CN

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS OT THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permits Application Application # _____

Property ID Number 10-6S-16-03814-113 HX Septic Permit No. 08-0378-M

Subdivision Name SouthFork Lot 14 Block _____ Unit _____ Phase _____

Construction of Room ADDITION Cost of Construction 20,000.00

Mobile Home Permit - New or Used (Circle One) Year _____ Length _____ Width _____

Name of the Authorized Person Signing the Permit DENNIS ONeil ✓

Phone 386 454 2476 Fax 386 454 4244

Address 235 NE 2ND St. HIGH SPRINGS, FL.

Owners Name EDWARD BUNNELL Phone 727 515 0043

911 Address 1002 SW Grassy LN. FT. WHITE FL.

Relationship to Property Owner _____ Is this Home Replacing an Existing Home _____

Contractors Name ONeil Construction of High Springs INC Phone 386 454 2476

Company Name Dennis ONeil Fax 386 454 4244

Address 235 NE 2ND Ave HIGH SPRINGS, FL. 32643

Fee Simple Owner Name & Address EDWARD BUNNELL 1002 SW Grassy LN. Ft White

Bonding Co. Name & Address N/A

Architect/Engineer Name & Address N/A

Mortgage Lenders Name & Address N/A

Driving Directions to the Property ~~From High Springs take HWY 27 to Ft White J-R~~ South ~~On HWY 47 Go Passed~~ Bethany Farms Turn Left on Grassy Lane Go 1 mile to End. Property is At End of Road.

Lot Size _____ Total Acreage 20 Building across lot numbers _____

Actual Distance of Structure from Property Lines - Front/Road 510 Left Side 560 Right Side 690 Rear 22'

Number of Stories 1 Heated Floor Area (Addition) 270 Total Floor Area 270 Roof Pitch 6/12

Circle the correct power company - FL Power & Light - (Clay Elec) - Suwannee Valley Elec.

Progress Energy - Slash Pine Electric

Do you currently have an (Existing Drive) (Currently using) or Private Drive (Blue Road Sign) or need a Culvert Permit (Putting in a Culvert) or Culvert Waiver (No Culvert but do not need a Culvert)

left message 7/10/09

Both Pages Must be Submitted to obtain a Building Permit.

Revised 12-30-08

Columbia County Building Permits Application Application #_____

TIME LIMITATIONS OF *APPLICATIONS* : An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

TIME LIMITATIONS OF *PERMITS*: Every permit issued shall become invalid unless the work authorized by such permit is commenced within 180 days after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of 180 days after the time work is commenced. A valid permit receives an approved inspection every 180 days. Work shall be considered not suspended, abandoned or invalid when the permit has received an approved inspection within 180 days of the previous approved inspection.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment: According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUILDING PERMITEE: YOU ARE HEREBY NOTIFIED: as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

OWNERS CERTIFICATION: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning. I further understand the above written responsibilities in Columbia County for obtaining this Building Permit.

_____
Owners Signature

CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit including all application and permit time limitations.

_____
Contractor's Signature (Permitee)

Contractor's License Number CGC061581
Columbia County
Competency Card Number_____

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 7th **day of** July **20**09

Personally known ____ **or Produced Identification**_____

_____
State of Florida Notary Signature (For the Contractor)

SEAL:

NOTARY PUBLIC
SANDRA J WEBB
Notary Public, State of Florida
Commission# DD623026
My comm. expires Dec. 17, 2010

Both Pages Must be Submitted to obtain a Building Permit.

Revised 12-30-08

Site Plan
Lot 13 + 14



Parcel 10-65-16-03814-113 HX
Bunnell Edward D + M Kyle

1002 SW Grassy Ln
Ft. White FL 32038

Site Plan
Lot 13 & 14



Parcel 10-65-16-03814-113 HX
Bunnell Edward D & M Kyle

1002 SW Grassy Ln
Ft. White FL 32038

Documentary Stamp 409.50
Intangible Tax ______
P. DeWitt Cason
Clerk of Court
By ______ D.C.

Recording Fees: $______
Documentary Stamps: +______
Total: $

Prepared By And Return To
SOUTHEAST TITLE GROUP, LLP
Address: 2015 So First Street
Lake City, Fl 32050
SE File #99Y-02041KW/KIM WATSON
Property Appraisers Parcel I.D. Number(s):
Grantee(s) S.S.#(s): [redacted]

99-03597

FILED AND RECORDED IN PUBLIC RECORDS OF COLUMBIA COUNTY, FL
1999 MAR -3 PM 4:13
RECORD VERIFIED
P. DeWitt Cason
CLERK OF COURTS
COLUMBIA COUNTY, FL
BY ______

WARRANTY DEED

THIS WARRANTY DEED made and executed the 26th day of February, 1999, by **GLENN FARMS, INC.** , a corporation existing under the laws of Florida , and having its principal place of business at P.O. BOX 66, FT. WHITE, FLORIDA 32038, hereinafter called the Grantor, to **EDWARD D. BUNNELL** and **M. KYLE BUNNELL, HIS WIFE**, whose post office address is: 1626 PALMWOOD DR., CLEARWATER, FL. 33756, hereinafter called the Grantee:

(Wherever used herein the terms "first party" and "second party" shall include singular and plural, heirs, legal representatives, and assigns of individuals, and the successors and assigns of corporations, wherever the context so admits or requires.)

WITNESSETH: That the Grantor, for and in consideration of the sum of TEN DOLLARS ($10.00) and other valuable considerations, receipt whereof is hereby acknowledged, by these presents does grant, bargain, sell, alien, remise, release, convey and confirm unto the Grantee all that certain land situate, lying and being in COLUMBIA County, State of Florida, viz:

SEE EXHIBIT "A" ATTACHED FOR FULL LEGAL DESCRIPTION

Subject to Restrictions, Reservations and Easements of Record.

TOGETHER with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining.

TO HAVE AND TO HOLD the same in fee simple forever.

AND the Grantor hereby covenants with said Grantee that the Grantor is lawfully seized of said land in fee simple; that the Grantor has good right and lawful authority to sell and convey said land, and hereby warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances

IN WITNESS WHEREOF, the said Grantor has caused these presents to be executed in its name, and its corporate seal to be hereunto affixed, by its proper officers thereunto duly authorized, the day and year first above written.

Signed, sealed and delivered
in the presence of:

Witness Signature
Printed Name: Bonita Hall

Witness Signature
Printed Name: Susan R. Sweet

GLENN FARMS, INC.

BY: ______
Vice President

Address: P.O. BOX 66
FT. WHITE, FLORIDA 32038

ATTEST: ______
Secretary

(CORPORATE SEAL)

OFFICIAL RECORDS
BK 0875 PG 1915

\F\WDCOR.DEE

STATE OF Fla
COUNTY OF Columbia

I hereby certify that on this day, before me, an officer duly authorized in the state aforesaid and in the county aforesaid to take acknowledgements, personally appeared Joel Glenn and _____ well known to me to be the VICE President and _____ respectively of the corporation named as Grantor in the foregoing deed, who are personally known to me and who took an oath that they severally acknowledged executing the same in the presence of two subscribing witnesses freely and voluntarily under authority duly vested in them by said corporation, and that the seal affixed thereto is the true corporate seal of said corporation.

Witness my hand and official seal in the county and state aforesaid this 26th day of February, 1999.

Bonita Hadwin
Notary Public Sign Above
Print Name: _____
My Commission #: _____
My Commission expires: _____

NOTARY PUBLIC STATE OF FLORIDA
BONITA HADWIN
COMMISSION # CC 476215
EXPIRES AUG 10, 1999
BONDED THRU
ATLANTIC BONDING CO., INC.

BK 0875 PG 1916
OFFICIAL RECORDS

EXHIBIT "A"

PARCEL 13

A PART OF THE S 1/2 OF SECTION 10, TOWNSHIP 6 SOUTH, RANGE 16 EAST, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGIN AT THE NE CORNER OF THE SE 1/4 OF THE SE 1/4 OF SAID SECTION 10 AND RUN THENCE S 88°43'47" W, A DISTANCE OF 691.15 FEET; THENCE S 00°22'55"W, A DISTANCE OF 661.88 FEET; THENCE N 88°37'18" E, A DISTANCE OF 81.00 FEET; THENCE N 81°52'29" E, A DISTANCE OF 626.25 FEET; THENCE N 00°32'31" W, A DISTANCE OF 586.75 FEET TO THE POINT OF BEGINNING, COLUMBIA COUNTY, FLORIDA.

PARCEL 14

A PART OF THE S 1/2 OF SECTION 10, TOWNSHIP 6 SOUTH, RANGE 16 EAST, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGIN AT THE SE CORNER OF THE SE 1/4 OF THE SE 1/4 OF SAID SECTION 10 AND RUN THENCE N 00°32'31" W, A DISTANCE OF 743.12 FEET; THENCE S 81°52'29" W, A DISTANCE OF 626.25 FEET; THENCE S 00°57'17" E, A DISTANCE OF 666.81 FEET; THENCE N 88°52'16" E, A DISTANCE OF 616.00 FEET TO THE POINT OF BEGINNING, COLUMBIA COUNTY, FLORIDA.

TOGETHER WITH AND SUBJECT TO AN EASEMENT FOR INGRESS AND EGRESS. A PART OF THE SOUTH 1/2 OF SECTION 10, TOWNSHIP 6 SOUTH, RANGE 16 EAST, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCE AT THE SW CORNER OF SAID SECTION 10 AND RUN THENCE N 88°52'16" E, ALONG THE SOUTH LINE OF SAID SECTION 10, A DISTANCE OF 46.86 FEET TO THE EAST RIGHT-OF-WAY OF STATE ROAD NO. 47; THENCE N 00°20'30" W, ALONG SAID EAST RIGHT-OF-WAY 627.05 FEET TO THE POINT OF BEGINNING; THENCE N 00°02'30" W, STILL ALONG SAID RIGHT-OF-WAY A DISTANCE OF 60.00 FEET; THENCE N 88°53'29" E, A DISTANCE OF 629.67 FEET; THENCE N 00°24'41" W, A DISTANCE OF 681.60 FEET, THENCE N 88°53'26" E, A DISTANCE OF 60.00 FEET, THENCE S 00°24'41" W, A DISTANCE OF 681.60 FEET; THENCE N 88°53'29" E, A DISTANCE OF 629.35 FEET; THENCE N 88°58'12" E, 650.99 FEET, THENCE N 01°01'48" W, A DISTANCE OF 589.75 FEET; THENCE S 87°47'54" W, A DISTANCE OF 36.83 FEET THENCE N 00°25'25" W, A DISTANCE OF 739.98 FEET, THENCE N 88°25'30" E, A DISTANCE OF 60.01 FEET, THENCE S 00°25'25" E, A DISTANCE OF 679.29 FEET, THENCE N 87°47'54" E, A DISTANCE OF 36.18 FEET, THENCE S 01°01'48" E, A DISTANCE OF 650.81 FEET; THENCE N 88°37'18" E, A DISTANCE OF 2603.18 FEET, THENCE S 00°17'09" E, A DISTANCE OF 60.01 FEET; THENCE S 88°37'18" W, A DISTANCE OF 2632.46 FEET, THENCE S 88°58'12" W, 681.09 FEET, THENCE S 88°53'29" W, 1319.83 FEET TO THE POINT OF BEGINNING, COLUMBIA COUNTY, FLORIDA.

Subject to: That certain Mortgage from Glenn Farms, Inc. to Capital City Bank, dated March 17, 1998, filed March 18, 1998, in O.R. Book 855, page 601. Termination of Financial Statement in O.R. Book 855, page 619.

Subject to: Restrictions as recorded in O.R. Book 867, page 1096.

Subject to: Easement as recorded in O.R. Book 867, page 1108. (Columbia Southfork)

Subject to: Easement granted to Clay Electric in O.R. Book 859, page 213.

Columbia County Property Appraiser

DB Last Updated: 4/27/2009

2009 Preliminary Values

Tax Record | Property Card | Interactive GIS Map

Print

Parcel: 10-6S-16-03814-113 HX

Search Result: 1 of 2 Next >>

Owner & Property Info

Owner's Name	BUNNELL EDWARD D & M KYLE		
Site Address	GRASSY		
Mailing Address	1002 SW GRASSY LN FT WHITE, FL 32038		
Use Desc. (code)	SINGLE FAM (000100)		
Neighborhood	010616.02	**Tax District**	3
UD Codes	MKTA02	**Market Area**	02
Total Land Area	20.020 ACRES		
Description	BEG NE COR OF SE1/4 OF SE1/4, RUN W 691.15 FT, S 661.88 FT, E 81 FT, CONT E 626.25 FT, N 586.75 FT TO POB. (AKA LOT 13 SOUTHFORK S/D UNREC) & ALSO BEG SE COR OF SE1/4 OF SE1/4, RUN N 743.12 FT, W 626.25 FT, S 666.81 FT, E 616 FT TO POB. (AKA LOT 14 SOUTHFORK S/D UNR) ORB 875-1919,		

GIS Aerial

Property & Assessment Values

Mkt Land Value	cnt: (1)	$100,580.00
Ag Land Value	cnt: (0)	$0.00
Building Value	cnt: (1)	$85,941.00
XFOB Value	cnt: (4)	$56,712.00
Total Appraised Value		$243,233.00

Just Value		$243,233.00
Class Value		$0.00
Assessed Value		$224,565.00
Exemptions	(code: HX)	$50,000.00
Total Taxable Value		County: $174,565.00 | City: $174,565.00 Other: $174,565.00 | School: $199,565.00

Sales History

Sale Date	Book/Page	Inst. Type	Sale Vlmp	Sale Qual	Sale RCode	Sale Price
2/26/1999	875/1915	WD	V	Q		$58,500.00

Building Characteristics

Bldg Item	Bldg Desc	Year Blt	Ext. Walls	Heated S.F.	Actual S.F.	Bldg Value
1	SINGLE FAM (000100)	2004	CB Stucco (17)	1643	2051	$85,941.00
	Note: All S.F. calculations are based on exterior building dimensions.					

Extra Features & Out Buildings

Code	Desc	Year Blt	Value	Units	Dims	Condition (% Good)
0190	FPLC PF	2004	$1,600.00	0000001.000	0 x 0 x 0	(000.00)
0040	BARN,POLE	2004	$12,312.00	0002736.000	38 x 72 x 0	(000.00)
0060	CARPORT F	2006	$3,600.00	0000720.000	24 x 30 x 0	(000.00)
0030	BARN,MT	2006	$39,200.00	0002800.000	40 x 70 x 0	(000.00)

Land Breakdown

0907.09

NOTICE OF COMMENCEMENT

Inst 200912011222 Date 7/7/2009 Time 2:08 PM
DC,P DeWitt Cason,Columbia County Page 1 of 1 B 1176 P 1621

Tax Parcel Identification Number 10-6S-16-03814-113 HX

THE UNDERSIGNED hereby gives notice that improvements will be made to certain real property, and in accordance with Section 713.13 of the Florida Statutes, the following information is provided in this **NOTICE OF COMMENCEMENT**.

1. Description of property *(legal description)*: LOT 14 SOUTHFORK S/D UNR ORD 875-1919
   a) Street *(job)* Address: 1002 SW Grassy LN Ft. White FL.
2. General description of improvements: ROOM ADDITION

3. 0wner Information
   a) Name and address: EDWARD BUNNELL
   b) Name and address of fee simple titleholder (if other than owner) SAME
   c) Interest in property OWNER
4. Contractor Information
   a) Name and address: ONeil Construction of High Springs INC.
   b) Telephone No.: 386 454 2476 Fax No. (Opt.) 386 454 4244
5. Surety Information
   a) Name and address: N/A
   b) Amount of Bond:
   c) Telephone No.: Fax No. (Opt.)
6. Lender
   a) Name and address: N/A
   b) Phone No.
7. Identity of person within the State of Florida designated by owner upon whom notices or other documents may be served:
   a) Name and address: EDWARD Bunnell
   b) Telephone No.: 497 3078 Fax No. (Opt.)

8. In addition to himself, owner designates the following person to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes:
   a) Name and address: ONeil Construction P.O. Box 1633 High Springs
   b) Telephone No.: 386 454 2476 Fax No. (Opt.) 386-454-4244

9. Expiration date of Notice of Commencement **(the expiration date is one year from the date of recording unless a different date is specified)**:

WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY; A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.

STATE OF FLORIDA
COUNTY OF COLUMBIA

10. Den Oneil
Signature of Owner or Owner's Authorized Office/Director/Partner/Manager

DENNIS ONEIL / ONEIL CONSTRUCTION
Print Name

The foregoing instrument was acknowledged before me , a Florida Notary, this 25 day of June, 20 09, by:
Edward D. Bunnell as (type of authority, e.g. officer, trustee, attorney fact) for (name of party on behalf of whom instrument was executed).

Personally Known ____ OR Produced Identification ✓ Type B540-224-68-253-0

Notary Signature Ann M. Raulerson Notary Stamp or Seal:

ANN MARIE RAULERSON
Commission DD 645666
Expires July 5, 2010
Bonded Thru Troy Fain Insurance 800-385-7019

---AND---

11. Verification pursuant to Section 92.525, Florida Statutes. Under penalties of perjury, I declare that I have read the foregoing and that the facts stated in it are true to the best of my knowledge and belief.

Signature of Natural Person Signing (in line #10 above)

0907-09

STATE OF FLORIDA
DEPARTMENT OF HEALTH

APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Bunnell

Permit Application Number 09-0378M

---------- PART II - SITEPLAN ----------

Scale: Each block represents 10 feet and 1 inch = 40 feet.



Notes: _____

Site Plan submitted by: Don Ohl Agent

Plan Approved ✓ Not Approved____ Date____

By Mark S Zambo Columbia County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT

COLUMBIA COUNTY INSPECTION SHEET

P M
10-21-09

DATE 10/19/2009 TAKEN BY JL **INSPECTION DATE:** 10.19.09

BUILDING PERMIT # 000027941 **CULVERT / WAIVER PERMIT #** _____ **WAIVER** _____

PARCEL ID # 10-6S-16-03814-113 ZONING A-3

TYPE OF DEVELOPMENT SFD ADDITION

SETBACKS: FRONT 30.00 REAR 25.00 SIDE 25.00 HEIGHT _____

FLOOD ZONE X SEPTIC 09-378 NO. EXISTING D.U. 1

SUBDIVISION SOUTH FORK Lot 14 Block ___ Unit 0 Phase ___

OWNER EDWARD & KYLE BUNNELL PHONE 386 462-7006

ADDRESS 1002 SW GRASSY LANE FT. WHITE FL 32038

CONTRACTOR DENNIS O'NEIL PHONE 454-2476

LOCATION 47S, TL ON GRASSY LANE, TO THE END

COMMENTS: NOC ON FILE

NO release sent to ETT 8/31/10

INSPECTION(S) REQUESTED:

___ Temp Power _____ ___ Foundation _____ ___ Set backs _____

___ Mono Slab 07/21/2009 HD ___ Under Slab Rough-in _____ ___ Slab _____

___ Sheathing/Nailing 08/07/2009 WR ___ Insulation 08/24/2009 HD ___ Framing 08/24/2009 HD

___ Above slab Rough-in _____ ___ Electrical Rough-in 08/24/2009 HD

___ Heat & A/C 08/24/2009 HD ___ Beam (Lintel) 07/29/2009 HD ✓ ~~Perm~~ Power _____

✓ CO Final OK ___ Culvert _____ ___ Reconnection _____

___ Pool _____ ___ MH Perm Power _____ ___ Utility Pole _____

___ RV Power _____ ___ Re-Roof _____ ___ Other _____

INSPECTORS:

APPROVED ✓ NOT APPROVED _____ BY 303 POWER CO. CLAY

INSPECTORS COMMENTS: ~~Locked~~ O.K. 2nd visit

left message 10/22/09

Schafer Engineering, LLC

14705 Main St. Alachua FL 32615

Prepared for:

O'NEIL CONSTRUCTION
THE BUNNELL ADDITION
COLUMBIA COUNTY, FLORIDA

By:

Schafer Engineering, LLC

386-462-1340 / 352-375-6329

NO COPIES ARE TO BE PERMITTED

SCHAFER ENGINEERING, LLC

June 25, 2009

SUMMARY: Wind Load Analysis for O'Neal Construction \ The Bunnell Bedroom Addition
Wind Speed: 110 M.P.H. \ No Copies Permitted \ 2007 FBC \ Designed For One Use Only

Foundation:
20" wide x 10" deep stemwall footing with (2) #5 rebar continuous minimum. CMU walls must have #5 dowels at 72" o.c. maximum with a standard 90 degree ACI hook in footing and a 4" slab on grade. Monolithic slab to be 12" wide x 20" deep minimum with (2) #5 rebar continuous with 12" minimum coverage on face of foundation. It is assumed that ideal soil conditions and pad preparation are provided.

Walls:
8" CMU block with vertical #5 reinforcing bar in fully grouted cells at 72" o.c. maximum spacing. Wall heights are 8' maximum. Provide an 8" x 8" bond beam with 1-#5 rebar horizontal continuous at the top course. Install pre-cast, pre-engineered lintels or pre-engineered steel lintels spanning over all openings. One #5 rebar each corner. One #5 rebar each side of door and window openings. Two #5 rebar in openings wider than 12'-0". One #5 rebar where girders or girder trusses bear on masonry wall.

Shearwalls:

Transverse: 15'-0"	Allowable pounds per foot unit shear on shearwalls: 314 plf
Longitudinal: 23'-0"	Unit shear transferred from diaphragm: Trs 146 plf Long: 83 plf

Trusses:
Pre-engineered Pre-fabricated trusses with the bracing system designed by the manufacturer. Trusses must be installed and anchored according to the truss engineering requirements.

Roof Sheathing:
7/16" osb minimum attached to the top chords of the trusses with 8d/113 gauge ring shank nails spaced at 4" o.c. edges and 6" interior.

6-25-09

Bruce Schafer P. E. #48984
7104 N. W. 42nd Lane \ Gainesville, Florida 32606

SCHAFER ENGINEERING, LLC

7104 N. W. 42ND LANE

GAINESVILLE, FLORIDA 32606



TYPICAL GABLE END BRACING

6-25-09

48984
7104 NW 42nd Ln
Gainesville, Fl

ASCE 7-05

User Input Data		
Structure Type	Building	
Basic Wind Speed (V)	110	mph
Structural Category	II	
Exposure	B	
Struc Nat Frequency (n1)	1	Hz
Slope of Roof (Theta)	26.6	Deg
Type of Roof	Gabled	
Eave Height (Eht)	8.00	ft
Ridge Height (RHt)	12.75	ft
Mean Roof Height (Ht)	10.88	ft
Width Perp. to Wind (B)	15.00	ft
Width Parallel to Wind (L)	18.00	ft
Damping Ratio (beta)	0.01	

Red values should be changed only through "Main Menu"

Calculated Parameters		
Type of Structure		
Height/Least Horizontal Dim	0.73	
Flexible Structure	No	

Calculated Parameters		
Importance Factor	1	
Hurricane Prone Region (V>100 mph)		
Table C6-4 Values		
Alpha =	7.000	
zg =	1200.000	
At =	0.143	
Bt =	0.840	
Am =	0.250	
Bm =	0.450	
Cc =	0.300	
l =	320.00	ft
Epsilon =	0.333	
Zmin =	30.00	ft

Gust Factor Category I: Rigid Structures - Simplified Method			
Gust1	For rigid structures (Nat Freq > 1 Hz) use 0.85	0.85	
Gust Factor Category II: Rigid Structures - Complete Analysis			
Zm	Zmin	30.00	ft
lzm	Cc * (33/z)^0.167	0.3048	
Lzm	l*(zm/33)^Epsilon	309.99	ft
Q	(1/(1+0.63*((B+Ht)/Lzm)^0.63))^0.5	0.9400	
Gust2	0.925*((1+1.7*lzm*3.4*Q)/(1+1.7*3.4*lzm))	0.8896	
Gust Factor Category III: Flexible or Dynamically Sensitive Structures			
Vhref	V*(5280/3600)	161.33	ft/s
Vzm	bm*(zm/33)^Am*Vhref	70.89	ft/s
NF1	NatFreq*Lzm/Vzm	4.37	Hz
Rn	(7.47*NF1)/(1+10.302*NF1)^1.667	0.0552	
Nh	4.6*NatFreq*Ht/Vzm	0.71	
Nb	4.6*NatFreq*B/Vzm	0.97	
Nd	15.4*NatFreq*Depth/Vzm	3.91	
Rh	1/Nh-(1/(2*Nh^2)*(1-Exp(-2*Nh)))	0.6577	
Rb	1/Nb-(1/(2*Nb^2)*(1-Exp(-2*Nb)))	0.5750	
Rd	1/Nd-(1/(2*Nd^2)*(1-Exp(-2*Nd)))	0.2231	
RR	((1/Beta)*Rn*Rh*Rb*(0.53+0.47*Rd))^0.5	1.1509	
gg	+(2*LN(3600*n1))^0.5+0.577/(2*LN(3600*n1))^0.5	4.19	
Gust3	0.925*((1+1.7*lzm*(3.4^2*Q^2+GG^2*RR^2)^0.5)/(1+1.7*3.4*lzm))	1.34	

Gust Factor Summary			
Main Wind-force resisting system:		**Components and Cladding:**	
Gust Factor Category:	I	Gust Factor Category:	I
Gust Factor (G)	0.89	Gust Factor (G)	0.89

ASCE 7-05

6.5.12.2.1 Design Wind Pressure - Buildings of All Heights (Non-flexible)

Elev.	Kz	Kzt	Kd	qz	Pressure (lb/ft^2)	
					Windward Wall*	
ft			1.00	lb/ft^2	+GCpi	-GCpi
15	0.70	1.00	1.00	21.70	12.24	18.65

Figure 6-3 - External Pressure Coefficients, Cp

Loads on Main Wind-Force Resisting Systems



Variable	Formula	Value	Units
Kh	2.01*(15/zg)^(2/Alpha)	0.57	
Kht	Topographic factor (Fig 6-2)	1.00	
Qh	.00256*(V)^2*ImpFac*Kh*Kht*Kd	17.80	psf

Wall Pressure Coefficients, Cp	
Surface	Cp
Windward Wall (See Figure 6.5.12.2.1 for Pressures)	0.80

Roof Pressure Coefficients, Cp	
Roof Area (sq. ft.)	-
Reduction Factor	1.00

Description	Cp	Pressure (psf)	
		+GCpi	-GCpi
Leeward Walls (Wind Dir Parallel to 15 ft wall)	-0.46	-10.49	-4.08
Leeward Walls (Wind Dir Parallel to 18 ft wall)	-0.50	-11.12	-4.71
Side Walls	-0.70	-14.29	-7.88
Roof - Normal to Ridge (Theta>=10)			
Windward - Max Negative	-0.30	-8.00	-1.60
Windward - Max Positive	0.17	-0.49	5.92
Leeward Normal to Ridge	-0.60	-12.71	-6.30
Overhang Top	-0.30	-4.80	-4.80
Overhang Bottom	0.80	0.71	0.71
Roof - Parallel to Ridge (All Theta)			
Dist from Windward Edge: 0 ft to 5.44 ft	-0.98	-18.78	-12.37
Dist from Windward Edge: 5.44 ft to 10.88 ft	-0.86	-16.80	-10.39
Dist from Windward Edge: 10.88 ft to 21.76 ft	-0.54	-11.78	-5.38
	0.00	0.00	0.00

ASCE 7-05

* Horizontal distance from windward edge

Figure 6-4 - External Pressure Coefficients, GCpf

Loads on Main Wind-Force Resisting Systems w/ Ht <= 60 ft

Kh =	2.01*(15/zg)^(2/Alpha)	=	0.57
Kht =	Topographic factor (Fig 6-2)	=	1.00
Qh =	0.00256*(V)^2*ImpFac*Kh*Kht*Kd	=	17.80

Case A						
Surface	**GCpf**	**+GCpi**	**-GCpi**	**qh (psf)**	**Min P (psf)**	**Max P (psf)**
1	0.55	0.18	-0.18	21.70	8.03	15.84
2	-0.10	0.18	-0.18	21.70	-5.99	1.82
3	-0.45	0.18	-0.18	21.70	-13.61	-5.79
4	-0.39	0.18	-0.18	21.70	-12.38	-4.57
5	0.00	0.18	-0.18	21.70	-3.91	3.91
6	0.00	0.18	-0.18	21.70	-3.91	3.91
1E	0.73	0.18	-0.18	21.70	11.88	19.69
2E	-0.19	0.18	-0.18	21.70	-7.93	-0.12
3E	-0.58	0.18	-0.18	21.70	-16.59	-8.78
4E	-0.53	0.18	-0.18	21.70	-15.50	-7.69
5E	0.00	0.18	-0.18	21.70	-3.91	3.91
6E	0.00	0.18	-0.18	21.70	-3.91	3.91

* p = qh * (GCpf - GCpi)



ASCE 7-05

Figure 6-4 - External Pressure Coefficients, GCpf

Loads on Main Wind-Force Resisting Systems w/ Ht <= 60 ft

Kh =	2.01*(15/zg)^(2/Alpha)	=	0.57
Kht =	Topographic factor (Fig 6-2)	=	1.00
Qh =	0.00256*(V)^2*ImpFac*Kh*Kht*Kd	=	17.80

Case B						
Surface	**GCpf**	**+GCpi**	**-GCpi**	**qh (psf)**	**Min P (psf)**	**Max P (psf)**
1	-0.45	0.18	-0.18	21.70	-13.67	-5.86
2	-0.69	0.18	-0.18	21.70	-18.88	-11.07
3	-0.37	0.18	-0.18	21.70	-11.94	-4.12
4	-0.45	0.18	-0.18	21.70	-13.67	-5.86
5	0.40	0.18	-0.18	21.70	4.77	12.59
6	-0.29	0.18	-0.18	21.70	-10.20	-2.39
1E	-0.48	0.18	-0.18	21.70	-14.32	-6.51
2E	-1.07	0.18	-0.18	21.70	-27.13	-19.31
3E	-0.53	0.18	-0.18	21.70	-15.41	-7.60
4E	-0.48	0.18	-0.18	21.70	-14.32	-6.51
5E	0.61	0.18	-0.18	21.70	9.33	17.14
6E	-0.43	0.18	-0.18	21.70	-13.24	-5.43

* p = qh * (GCpf - GCpi)



Figure 6-5 - External Pressure Coefficients, GCp

Loads on Components and Cladding for Buildings w/ Ht <= 60 ft

ASCE 7-05





Gabled Roof
10 < Theta <= 45

a = 1.5 ==> 3.00 ft

Component	Width (ft)	Length (ft)	Area (ft^2)	Zone	GCp Max	GCp Min	Wind Press (lb/ft^2) Max	Wind Press (lb/ft^2) Min
	16	7	112.00	5	0.81	-1.03	17.71	-21.53
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					
	0	0	0.00					

Note: * Enter Zone 1 through 5, or 1H through 3H for overhangs.

Table 6-7 Internal Pressure Coefficients for Buildings, Gcpi

Condition	Gcpi Max +	Gcpi Max -
Open Buildings	0.00	0.00

ASCE 7-05

Partially Enclosed Buildings	0.55	-0.55
Enclosed Buildings	0.18	-0.18
Enclosed Buildings	**0.18**	**-0.18**

Table 6-8 External Pressure Coefficients for Arched Roofs, Cp

r (Rise-to-Span Ratio) = 0.3

Condition	Variable	Cp		
		Windward Quarter	Center Half	Leeward Quarter
Roof on Elevated Structure	Cp	0.13	-1	-0.5
	P (+GCpi) - psf	-1.22	-19.04	-11.12
	P (-GCpi) -psf	5.18	-12.63	-4.71
Roof Springing from Ground	Cp	0.42	-1	-0.5
	P (+GCpi) - psf	3.45	-19.04	-11.12
	P (-GCpi) -psf	3.45	-19.04	-11.12

Table 6-9 Force Coefficients for Monoslope Roofs over Open Buildings, Cf

Variable	Description	Value	
L	Roof dimension normal to wind direction	18.00	ft
B	Roof dimension parallel to wind direction	15.00	ft
L/B	Ratio of L to B	1.200	
Theta	Slope of Roof	26.6	Deg
Cf	Force Coefficient	1.16	
X	Distance to center of pressure from windward edge	0.41	ft

Note: All outlets AFCI

Note: Tie Electric into Existing 200 AMP Panel



Floor Plan

1/4" = 1'

270 Sq. Ft.

Bunnell Addition

Sheet 1

ONEIL CONSTRUCTION

Plans By: Jamie O'Neill



Foundation PLan

1/4" = 1'

Note: Pretreat Soil for termites



Footer Detail

Bunnell Addition

Sheet 2



Front Elevation
1/4" = 1'

Bunnell Addition
Sheet 3



Rear Elevation

1/4" = 1'

Bunnell Addition

Sheet 4

Note: Fire blocking to cut off all Vertical + Horizontal Draft openings

Note: Roof Sheating Nail @ 4" O.C. edge and 6" interior 8d/113 guage ring Shank



Typical Wall Section

Bunnell Addition

Sheet 5

Note: Left Elevation is Existing House



Right Elevation

1/4" = 1'

Bunnell Addition

Sheet 6

Julius Lee Engineering

RE: 308847 - ONEIL CONST. - BUNNELL ADDITION

1109 Coastal Bay Blvd.
Boynton Beach, FL 33435

Site Information:
Project Customer: O'NEIL CONST. Project Name: 308847 Model: BUNNELL ADDITION
Lot/Block: Subdivision:
Address: 1002 SW GRASSY LANE
City: COLUMBIA CTY State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.
Name: O'NEIL CONST. License #: QB0010656
Address: 235 NE 2ND ST
City: HIGH SPRINGS, State: FL

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):
Design Code: FBC2007/TPI2002 Design Program: MiTek 20/20 7.1
Wind Code: ASCE 7-05 Wind Speed: 110 mph Floor Load: N/A psf
Roof Load: 32.0 psf

This package includes 2 individual, dated Truss Design Drawings and 0 Additional Drawings.
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.
This document processed per section 16G15-23.003 of the Florida Board of Professionals Rules

In the event of changes from Builder or E.O.R. additional coversheets and drawings may accompany this coversheet. The latest approval dates supersede and replace the previous drawings.

No.	Seal#	Truss Name	Date
1	I4047618	T01	6/30/09
2	I4047619	T01G	6/30/09

The truss drawing(s) referenced above have been prepared by MiTek Industries, Inc. under my direct supervision based on the parameters provided by Builders FirstSource (Lake City).

Truss Design Engineer's Name: Julius Lee

My license renewal date for the state of Florida is

NOTE: The seal on these drawings indicate acceptance of professional engineering responsibility solely for the truss components shown. The suitability and use of this component for any particular building is the responsibility of the building designer, per ANSI/TPI-1 Chapter 2.

JULIUS S.K. LEE LICENSE No 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

June 30,2009

Julius Lee

Job	Truss	Truss Type	Qty	Ply	ONEIL CONST. - BUNNELL ADDITION	
308347	T01	COMMON	9	1	Job Reference (optional)	I4047618

Builders FrstSource, Lake City, FL 32055 — 7.130 s Apr 28 2009 MiTek Industries, Inc. Tue Jun 30 15:17:20 2009 Page 1



Plate Offsets (X,Y): [2:0-1-12,0-1-8], [4:0-1-12,0-1-8]

LOADING (psf)		SPACING	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plates Increase	1.25	TC	0.42	Vert(LL)	-0.05	2-6	>999	360	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.30	Vert(TL)	-0.11	2-6	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.08	Horz(TL)	0.01	4	n/a	n/a		
BCDL	5.0	Code FBC2007/TPI2002		(Matrix)		Wind(LL)	0.04	2-6	>999	240	Weight: 59 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=585/0-1-8 (input: 0-7-8), 4=585/0-1-8 (input: 0-7-8)
Max Horz 2=101(LC 6)
Max Uplift 2=-291(LC 6), 4=-291(LC 7)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-610/392, 3-4=-610/392
BOT CHORD 2-6=-99/457, 4-6=-99/457
WEBS 3-6=0/257

NOTES (8-9)
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
5) All bearings are assumed to be SYP No.2 .
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 291 lb uplift at joint 2 and 291 lb uplift at joint 4.
7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
8) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
9) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869: Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard



June 30,2009

Julius Lee Engineering
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	ONEIL CONST. - BUNNELL ADDITION	I4047619
306847	T01G	GABLE	1	1	Job Reference (optional)	

Builders FrstSource, Lake City, FL 32055 — 7.130 s Apr 28 2009 MiTek Industries, Inc. Tue Jun 30 15:17:21 2009 Page 1



Plate Offsets (X,Y): [2:0-3-8,Edge], [2:0-2-8,Edge], [10:0-3-8,Edge], [10:0-2-8,Edge]

LOADING (psf)		SPACING	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plates Increase	1.25	TC	0.54	Vert(LL)	-0.04	11	n/r	120	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.06	Vert(TL)	-0.07	11	n/r	90		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.07	Horz(TL)	0.00	10	n/a	n/a		
BCDL	5.0	Code FBC2007/TPI2002		(Matrix)							Weight: 75 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 15-0-0.
(lb) - Max Horz 2=108(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 14 except 2=-428(LC 6), 10=-446(LC 7), 15=-217(LC 6), 16=-188(LC 6), 13=-215(LC 7), 12=-194(LC 7)
Max Grav All reactions 250 lb or less at joint(s) 14 except 2=498(LC 1), 10=498(LC 1), 15=252(LC 10), 16=299(LC 1), 13=252(LC 11), 12=299(LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 5-15=-235/260, 4-16=-271/259, 7-13=-235/260, 8-12=-271/259

NOTES (13-14)
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1-2002.
4) All plates are 2x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
9) All bearings are assumed to be SYP No.2 .
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14 except (jt=lb) 2=428, 10=446, 15=217, 16=188, 13=215, 12=194.
11) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
12) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
13) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
14) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869: Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard
1) Regular: Lumber Increase=1.25, Plate Increase=1.25

JULIUS S.K. LEE LICENSE No 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

June 30,2009

Continued on page 2

Julius Lee Engineering
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	ONEIL CONST. - BUNNELL ADDITION
308347	T01G	GABLE	1	1	I4047619
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055 — 7.130 s Apr 28 2009 MiTek Industries, Inc. Tue Jun 30 15:17:22 2009 Page 2

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-6=-114(F=-60), 6-11=-114(F=-60), 2-10=-10

JULIUS S.K. LEE
LICENSE
No 34869
STATE OF FLORIDA
PROFESSIONAL ENGINEER

June 30,2009

Julius Lee Engineering
1109 Coastal Bay Blvd.
Boynton, FL 33435

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MiTek 20/20 software or upon request.**

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION

Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI1: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ER-5243, 9604B, 9730, 95-43, 96-31, 9667A
NER-487, NER-561
95110, 84-32, 96-67, ER-3907, 9432A

Julius Lee Engineering
1109 Coastal Bay Blvd.
Boynton, FL 33435

⚠ General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI1.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.

COLUMBIA COUNTY BUILDING DEPARTMENT
RESIDENTIAL CHECK LIST REQUIRMENTS

MINIMUM PLAN REQUIREMENTS FOR THE FLORIDA BUILDING CODE RESIDENTIAL 2007 ONE (1) AND TWO (2) FAMILY DWELLINGS

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

ALL BUILDING PLANS MUST INDICATE COMPLIANCE with the Current 2007 FLORIDA BUILDING CODES RESIDENTIAL. ALL PLANS OR DRAWINGS SHALL PROVIDE CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FIGURE R301.2(4) of the FLORIDA BUILDING CODES RESIDENTIAL (Florida Wind speed map) **SHALL BE USED.**

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE -------- 100 MPH
ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE --------110 MPH
NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

	GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL			Items to Include- Each Box shall be Circled as Applicable		
				Yes	No	N/A
1	Two (2) complete sets of plans containing the following:					
2	All drawings must be clear, concise, drawn to scale, details that are not used shall be marked void					
3	Condition space (Sq. Ft.) 270		Total (Sq. Ft.) under roof 270	IIIIIII	IIIIIII	IIIII

Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal shall be affixed to the plans and documents as per the FLORIDA BUILDING CODES RESIDENTIAL R101.2.1

Site Plan information including:

4	Dimensions of lot or parcel of land	✓		
5	Dimensions of all building set backs	✓		
6	Location of all other structures (include square footage of structures) on parcel, existing or proposed well and septic tank and all utility easements.	✓		
7	Provide a full legal description of property.	✓		

Wind-load Engineering Summary, calculations and any details required

	GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable		
8	Plans or specifications must show compliance with FBCR Chapter 3	IIIIII YES	IIIII NO	IIIIII N/A
9	Basic wind speed (3-second gust), miles per hour	✓		
10	(Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated)	✓		
11	Wind importance factor and nature of occupancy	✓		
12	The applicable internal pressure coefficient, Components and Cladding	✓		
13	The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component, cladding materials not specifally designed by the registered design professional.	✓		

Elevations Drawing including:

14	All side views of the structure	✓		
15	Roof pitch	✓		
16	Overhang dimensions and detail with attic ventilation	✓		
17	Location, size and height above roof of chimneys			✓
18	Location and size of skylights with Florida Product Approval			✓
18	Number of stories			
20A	Building height from the established grade to the roofs highest peak	✓		

Floor Plan including:

20	Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches, deck, balconies	✓		
21	Raised floor surfaces located more than 30 inches above the floor or grade			✓
22	All exterior and interior shear walls indicated	✓		
23	Shear wall opening shown (Windows, Doors and Garage doors)	✓		
24	Emergency escape and rescue opening shown in each bedroom (net clear opening shown)	✓		
25	Safety glazing of glass where needed			✓
26	Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 of FBCR)			✓
27	Stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails (see FBCR SECTION 311)			✓
28	Identify accessibility of bathroom (see FBCR SECTION 322)			✓

All materials placed within opening or onto/into exterior walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the plan (see Florida product approval form)

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable

FBCR 403: Foundation Plans

		YES	NO	N/A
29	Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.	✓		
30	All posts and/or column footing including size and reinforcing			✓
31	Any special support required by soil analysis such as piling.			✓
32	Assumed load-bearing valve of soil 2000 Pound Per Square Foot	✓		
33	Location of horizontal and vertical steel, for foundation or walls (include # size and type)	✓		

FBCR 506: CONCRETE SLAB ON GRADE

34	Show Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)	✓		
35	Show control joints, synthetic fiber reinforcement or welded fire fabric reinforcement and Supports	✓		

FBCR 320: PROTECTION AGAINST TERMITES

36	Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or submit other approved termite protection methods. **Protection shall be provided by registered termiticides**	✓		

FBCR 606: Masonry Walls and Stem walls (load bearing & shear Walls)

37	Show all materials making up walls, wall height, and Block size, mortar type	✓		
38	Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement	✓		

Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer or Architect

Floor Framing System: First and/or second story

39	Floor truss package shall including layout and details, signed and sealed by Florida Registered Professional Engineer			✓
40	Show conventional floor joist type, size, span, spacing and attachment to load bearing walls, stem walls and/or priers			✓
41	Girder type, size and spacing to load bearing walls, stem wall and/or priers			✓
42	Attachment of joist to girder			✓
43	Wind load requirements where applicable			✓
44	Show required under-floor crawl space			✓
45	Show required amount of ventilation opening for under-floor spaces			✓
46	Show required covering of ventilation opening			✓
47	Show the required access opening to access to under-floor spaces			✓
	Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges &			✓

48	intermediate of the areas structural panel sheathing			✓
49	Show Draftstopping, Fire caulking and Fire blocking			✓
50	Show fireproofing requirements for garages attached to living spaces, per FBCR section 309			✓
51	Provide live and dead load rating of floor framing systems (psf).			✓

FBCR CHAPTER 6 WOOD WALL FRAMING CONSTRUCTION

	GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable		
		YES	NO	N/A
52	Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls			
53	Fastener schedule for structural members per table FBCR 602.3 are to be shown			
54	Show Wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural members, showing fastener schedule attachment on the edges & intermediate of the areas structural panel sheathing			
55	Show all required connectors with a max uplift rating and required number of connectors and oc spacing for continuous connection of structural walls to foundation and roof trusses or rafter systems			
56	Show sizes, type, span lengths and required number of support jack studs, king studs for shear wall opening and girder or header per FBCR Table 502.5 (1)			
57	Indicate where pressure treated wood will be placed			
58	Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing edges & intermediate areas			
59	A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail			

FBCR :ROOF SYSTEMS:

60	Truss design drawing shall meet section FBCR 802.10 Wood trusses	✓		
61	Include a layout and truss details, signed and sealed by Florida Professional Engineer	✓		
62	Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters	✓		
63	Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details	✓		
64	Provide dead load rating of trusses	✓		

FBCR 802:Conventional Roof Framing Layout

65	Rafter and ridge beams sizes, span, species and spacing			✓
66	Connectors to wall assemblies' include assemblies' resistance to uplift rating			✓
67	Valley framing and support details			✓
68	Provide dead load rating of rafter system			✓

FBCR Table 602,3(2) & FBCR 803 ROOF SHEATHING

69	Include all materials which will make up the roof decking, identification of structural panel sheathing, grade, thickness	✓		
70	Show fastener Size and schedule for structural panel sheathing on the edges & intermediate areas	✓		

FBCR ROOF ASSEMBLIES FRC Chapter 9

71	Include all materials which will make up the roof assembles covering	✓		
72	Submit Florida Product Approval numbers for each component of the roof assembles covering	✓		

FBCR Chapter 11 Energy Efficiency Code for residential building

Residential construction shall comply with this code by using the following compliance methods in the FBCR chapter11 Residential buildings compliance methods. *Two of the required forms are to be submitted, showing dimensions condition area equal to the total condition living space area*

	GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable		
		YES	NO	N/A
73	Show the insulation R value for the following areas of the structure	✓		
74	Attic space	✓		
75	Exterior wall cavity	✓		
76	Crawl space			✓

HVAC information

77	Submit two copies of a Manual J sizing equipment or equivalent computation study			✓
78	Exhaust fans locations in bathrooms			✓
79	Show clothes dryer route and total run of exhaust duct			✓

Plumbing Fixture layout shown

80	All fixtures waste water lines shall be shown on the foundation plan			✓
81	Show the location of water heater			✓

Private Potable Water

82	Pump motor horse power			✓
83	Reservoir pressure tank gallon capacity			✓
84	Rating of cycle stop valve if used			✓

Electrical layout shown including

85	Switches, outlets/receptacles, lighting and all required GFCI outlets identified	✓		
86	Ceiling fans	✓		
87	Smoke detectors & Carbon dioxide detectors	✓		
88	Service panel, sub-panel, location(s) and total ampere ratings			
89	On the electrical plans identify the electrical service overcurrent protection device for the main electrical service. This device shall be installed on the exterior of structures to serve as a disconnecting means for the utility company electrical service. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground. Indicate if the utility company service entrance cable will be of the overhead or underground type.			

90	Appliances and HVAC equipment and disconnects			✓
91	Arc Fault Circuits (AFCI) in bedrooms		✓	

Disclosure Statement for Owner Builders *If you as the applicant will be acting as an owner/builder under section 489.103(7) of the Florida Statutes, submit the required owner builder disclosure statement form.*

Notice Of Commencement

A notice of commencement form **recorded** in the Columbia County Clerk Office is required to be filed with the building department Before Any Inspections can be preformed.

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

		YES	NO	N/A
92	**Building Permit Application** A current Building Permit Application form is to be completed and submitted for all residential projects	✓		
93	**Parcel Number** The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested	✓		
94	**Environmental Health Permit or Sewer Tap Approval** A copy of a approved Columbia County Environmental Health (386) 758-1058			
95	**City of Lake City** A permit showing an approved waste water sewer tap			✓
96	**Toilet facilities shall be provided for all construction sites**	✓		
97	**Town of Fort White** (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White an approval land use development letter issued by the Town of Fort is required to be submitted with the application for a building permit.			✓
98	**Flood Information:** All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting a application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.5.2 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.5.3 of the Columbia County Land Development Regulations			✓
99	CERTIFIED FINISHED FLOOR ELEVATIONS will be required on any project where the base flood elevation (100 year flood) has been established			✓
100	A development permit will also be required. Development permit cost is **$50.00**			✓
101	**Driveway Connection:** If the property does not have an existing access to a public road, then an application for a culvert permit (**$25.00**) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (**$50.00**). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.			✓
102	**911 Address:** If the project is located in an area where a 911 address has not been issued, then application for a 911address must be applied for and **received** through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125	✓		

Section R101.2.1 of the Florida Building Code Residential:

The provisions of Chapter 1, Florida Building Code, Building shall govern the administration and enforcement of the Florida Building Code, Residential.

Section 105 of the Florida Building Code defines the:

Time limitation of application.

An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

Single-family residential dwelling.

Section 105.3.4 A building permit for a single-family residential dwelling must be issued within 30 working days of application therefor unless unusual circumstances require a longer time for processing the applicati or unless the permit application fails to satisfy the Florida Building Code or the enforcing agency's laws or ordinances.

Permit intent.

Section 105.4.1: A permit issued shall be constructed to be a license to proceed with the work and not as authority to violate, cancel, alter or set aside any of the provisions of the technical codes, nor shall issuance o a permit prevent the building official from thereafter requiring a correction of errors in plans, construction or violations of this code. Every permit issued shall become invalid unless the work authorized by such permit is commenced within six months after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of six months after the time the work is commenced.

If work has commenced.

Section 105.4.1.1: If work has commenced and the permit is revoked, becomes null and void, or expires because of lack of progress or abandonment, a new permit covering the proposed construction shall be obtained before proceeding with the work.

New Permit.

Section 105.4.1.2: If a new permit is not obtained within 180 days from the date the initial permit became nu and void, the building official is authorized to require that any work which has been commenced or completed be removed from the building site. Alternately, a new permit may be issued on application, providing the work in place and required to complete the structure meets all applicable regulations in effect at the time the initial permit became null and void and any regulations which may have become effective between the date of expiration and the date if issuance of the new permit.

Work Shall Be:

Section 105.4.1.3: Work shall be considered to be in active progress when the permit has received an approved inspection within 180 days. This provision shall not be applicable in case of civil commotion or strike or when the building work is halted due directly to judicial injunction, order or similar process.

The Fee:

Section 105.4.1.4: The fee for renewal reissuance and extension of a permit shall be set forth by the administrative authority.

When the submitted application is approved for permitting the applican will be notified by phone as to the date and time a building permit will b prepared and issued by the Columbia County Building & Zoning Department

PRODUCT APPROVAL SPECIFICATION SHEET

Location:_____ **Project Name:**_____

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are **applying for a building permit on or after April 1, 2004**. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS			
1. Swinging			
2. Sliding			
3. Sectional			
4. Roll up			
5. Automatic			
6. Other			
B. WINDOWS			
1. Single hung			
2. Horizontal Slider			
3. Casement			
4. Double Hung			
5. Fixed			
6. Awning			
7. Pass -through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11 Dual Action			
12. Other			
C. PANEL WALL			
1. Siding			
2. Soffits			
3. EIFS			
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS			
1. Asphalt Shingles			
2. Underlayments			
3. Roofing Fasteners			
4. Non-structural Metal Rf			
5. Built-Up Roofing			
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

Category/Subcategory (cont.)	Manufacturer	Product Description	Approval Number(s)
13. Liquid Applied Roof Sys			
14. Cements-Adhesives – Coatings			
15. Roof Tile Adhesive			
16. Spray Applied Polyurethane Roof			
17. Other			
E. SHUTTERS			
1. Accordion			
2. Bahama			
3. Storm Panels			
4. Colonial			
5. Roll-up			
6. Equipment			
7. Others			
F. SKYLIGHTS			
1. Skylight			
2. Other			
G. STRUCTURAL COMPONENTS			
1. Wood connector/anchor			
2. Truss plates			
3. Engineered lumber			
4. Railing			
5. Coolers-freezers			
6. Concrete Admixtures			
7. Material			
8. Insulation Forms			
9. Plastics			
10. Deck-Roof			
11. Wall			
12. Sheds			
13. Other			
H. NEW EXTERIOR ENVELOPE PRODUCTS			
1.			
2.			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) the performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

I understand these products may have to be removed if approval cannot be demonstrated during inspectic

Contractor or Contractor's Authorized Agent Signature

Print Name

Date

PRODUCT APPROVAL SPECIFICATION SHEET

Location: 1002 SW Grassy Ln. Columbia County **Project Name:** Bunnell Addition

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are **applying for a building permit on or after April 1, 2004**. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS			
✓ 1. Swinging	Therma Tru	Fiberglass	8838.1
2. Sliding			
3. Sectional			
4. Roll up			
5. Automatic			
6. Other			
B. WINDOWS			
1. Single hung			
2. Horizontal Slider			
3. Casement			
4. Double Hung			
✓ 5. Fixed	Magnolia	Fixed Window	10303.1
6. Awning			
7. Pass -through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11 Dual Action			
12. Other			
C. PANEL WALL			
1. Siding			
2. Soffits			
3. EIFS			
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS			
✓ 1. Asphalt Shingles	Owens Corning		FL. 10674
✓ 2. Underlayments	Woodland	#30 LB. FELT	D4869
3. Roofing Fasteners			
4. Non-structural Metal Rf			
5. Built-Up Roofing			
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

Category/Subcategory (cont.)	Manufacturer	Product Description	Approval Number(s)
13. Liquid Applied Roof Sys			
14. Cements-Adhesives – Coatings			
15. Roof Tile Adhesive			
16. Spray Applied Polyurethane Roof			
17. Other			
E. SHUTTERS			
1. Accordion			
2. Bahama			
3. Storm Panels			
4. Colonial			
5. Roll-up			
6. Equipment			
7. Others			
F. SKYLIGHTS			
1. Skylight			
2. Other			
G. STRUCTURAL COMPONENTS			
1. Wood connector/anchor			
2. Truss plates			
3. Engineered lumber			
4. Railing			
5. Coolers-freezers			
6. Concrete Admixtures			
7. Material			
8. Insulation Forms			
9. Plastics			
10. Deck-Roof			
11. Wall			
12. Sheds			
13. Other			
H. NEW EXTERIOR ENVELOPE PRODUCTS			
1.			
2.			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) the performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

I understand these products may have to be removed if approval cannot be demonstrated during inspection

Dennis ONeil

Contractor or Contractor's Authorized Agent Signature

Dennis ONeil 7/6/09

Print Name Date

1002 SW Grassy LN. Columbia County

Location

Permit # **(FOR STAFF USE ONLY)**

Website:

STEPDOWN CORNER SET

TOP CHORD 2X4 SO. PINE #2 or Better
BOT CHORD 2X4 SO. PINE #2 or Better
WEBS 2X4 SO. PINE #3 or Better

120 MPH MAX

Setback 7' or Less

PROVIDE UPLIFT CONNECTIONS AT BEARINGS AS INDICATED.
UPLIFT: 400# or Less
BRG LOC: *
UPLIFT BASED ON 7.2 PSF TOTAL DEAD LOAD. WIND SPEED=120 "C" MPH. MEAN HGT=28 FT. ENCLOSED. (ASCE 7-02)

PROVIDE UPLIFT CONNECTIONS AT BEARINGS AS INDICATED. TILE
UPLIFT: 400# or Less
BRG LOC: *
UPLIFT BASED ON 15.0 PSF TOTAL DEAD LOAD. WIND SPEED=120 "C" MPH. MEAN HGT (of jacks)=28 FT. ENCLOSED. (ASCE 7-02)

PROVIDE UPLIFT CONNECTIONS AT BEARINGS AS INDICATED.
UPLIFT: 400# or Less
BRG LOC: *
UPLIFT BASED ON 7.2 PSF TOTAL DEAD LOAD. WIND SPEED=120 "B" MPH. MEAN HGT (of jacks)=28 FT. ENCLOSED. (ASCE 7-02)



* (3) 16d TOENAILS

** SEE EOR FOR TIE DOWN



END AND CORNER JACKS



HIPJACK

UPLIFT VALUES DO TAKE INTO ACCOUNT PORCHES EXPOSED
BC LIVE LOAD IS NON CONCURRENT 10*

CORNER SET SETBACK
7'0" MAX

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W,H/S/K) ASTM A653 GRADE 40/60 (W,K/H,S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (I) SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.

JULIUS LEE CONS. ENGINEERS, P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2181
NO. 34869
STATE OF FLORIDA
PROFESSIONAL ENGINEER

SHINGLE		
TC	LL	20 MAX PSF
TC	DL	7 MAX PSF
BC	LL	10* MAX PSF
BC	DL	5 MAX PSF
TILE		
TC	LL	20 MAX PSF
TC	DL	20 MAX PSF
BC	LL	10* MAX PSF
BC	DL	5 MAX PSF
DUR. FAC.		1.25
SPACING		2' MAX

REF	7'MAX STBK CS
DATE	Jun./27/2008
DRWG	
-ENG	

REVIEWED
By julius lee at 10:52 am, Jun 27, 2008

ASCE 7-02: 130 MPH WIND SPEED, 15' MEAN HEIGHT, ENCLOSED, I = 1.00, EXPOSURE C

MAX GABLE VERTICAL LENGTH

2X4 GABLE VERTICAL SPACING	SPECIES	BRACE GRADE	NO BRACES	(1) 1X4 "L" BRACE *		(1) 2X4 "L" BRACE *		(2) 2X4 "L" BRACE **		(1) 2X6 "L" BRACE *		(2) 2X6 "L" BRACE **	
				GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B
24" O.C.	SPF HF	#1 / #2	3' 4"	5' 10"	6' 0"	6' 11"	7' 1"	8' 3"	8' 6"	10' 10"	11' 2"	12' 11"	13' 3"
		#3	3' 3"	4' 11"	4' 11"	6' 6"	6' 6"	8' 3"	8' 3"	10' 1"	10' 1"	12' 11"	12' 11"
		STUD	3' 3"	4' 11"	4' 11"	6' 5"	6' 5"	8' 3"	8' 3"	10' 0"	10' 0"	12' 11"	12' 11"
		STANDARD	3' 3"	4' 2"	4' 2"	5' 6"	5' 6"	7' 5"	7' 5"	8' 8"	8' 8"	11' 6"	11' 6"
	SP DFL	#1	3' 8"	5' 10"	6' 3"	6' 11"	7' 5"	8' 3"	8' 11"	10' 10"	11' 8"	12' 11"	13' 11"
		#2	3' 7"	5' 10"	6' 3"	6' 11"	7' 5"	8' 3"	8' 11"	10' 10"	11' 8"	12' 11"	13' 11"
		#3	3' 6"	5' 0"	6' 0"	6' 8"	6' 8"	8' 3"	8' 8"	10' 4"	10' 4"	12' 11"	13' 7"
		STUD	3' 6"	5' 0"	5' 0"	8' 7"	6' 7"	8' 3"	8' 8"	10' 3"	10' 3"	12' 11"	13' 7"
		STANDARD	3' 4"	4' 3"	4' 3"	5' 8"	5' 8"	7' 8"	7' 8"	8' 10"	8' 10"	12' 0"	12' 0"
16" O.C.	SPF HF	#1 / #2	3' 10"	6' 8"	6' 10"	7' 11"	8' 1"	9' 6"	9' 8"	12' 6"	12' 9"	14' 0"	14' 0"
		#3	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
		STUD	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 6"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
		STANDARD	3' 9"	5' 2"	6' 2"	6' 10"	6' 10"	9' 2"	9' 2"	10' 7"	10' 7"	14' 0"	14' 0"
	SP DFL	#1	4' 3"	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"
		#2	4' 2"	6' 8"	7' 2"	7' 11"	8' 6"	9' 6"	10' 2"	12' 6"	13' 5"	14' 0"	14' 0"
		#3	4' 0"	6' 2"	6' 2"	7' 11"	8' 2"	9' 6"	9' 11"	12' 6"	12' 8"	14' 0"	14' 0"
		STUD	4' 0"	6' 1"	6' 1"	7' 11"	8' 1"	9' 5"	9' 11"	12' 5"	12' 5"	14' 0"	14' 0"
		STANDARD	3' 10"	5' 3"	5' 3"	6' 11"	6' 11"	9' 4"	9' 4"	10' 10"	10' 10"	14' 0"	14' 0"
12" O.C.	SPF HF	#1 / #2	4' 5"	7' 4"	7' 7"	8' 9"	8' 11"	10' 6"	10' 8"	13' 8"	14' 0"	14' 0"	14' 0"
		#3	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	13' 8"	14' 0"	14' 0"
		STUD	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	13' 8"	14' 0"	14' 0"
		STANDARD	4' 2"	6' 11"	6' 11"	7' 10"	7' 10"	10' 6"	10' 6"	12' 3"	12' 3"	14' 0"	14' 0"
	SP DFL	#1	4' 8"	7' 4"	7' 11"	8' 9"	9' 5"	10' 5"	11' 2"	13' 8"	14' 0"	14' 0"	14' 0"
		#2	4' 7"	7' 4"	7' 11"	8' 9"	9' 5"	10' 6"	11' 2"	13' 8"	14' 0"	14' 0"	14' 0"
		#3	4' 4"	7' 2"	7' 2"	8' 9"	9' 2"	10' 5"	10' 11"	13' 6"	14' 0"	14' 0"	14' 0"
		STUD	4' 4"	7' 1"	7' 1"	8' 9"	9' 2"	10' 6"	10' 11"	13' 8"	14' 0"	14' 0"	14' 0"
		STANDARD	4' 3"	6' 1"	6' 1"	8' 0"	8' 0"	10' 5"	10' 8"	12' 6"	12' 6"	14' 0"	14' 0"

BRACING GROUP SPECIES AND GRADES:

GROUP A:

SPRUCE-PINE-FIR		HEM-FIR	
#1 / #2	STANDARD	#2	STUD
#3	STUD	#3	STANDARD

DOUGLAS FIR-LARCH	SOUTHERN PINE
#3	#3
STUD	STUD
STANDARD	STANDARD

GROUP B:

HEM-FIR
#1 & BTR
#1

SOUTHERN PINE	DOUGLAS FIR-LARCH
#1	#1
#2	#2





REFER TO CHART ABOVE FOR MAX GABLE VERTICAL LENGTH.

GABLE TRUSS DETAIL NOTES:

LIVE LOAD DEFLECTION CRITERIA IS L/240.

PROVIDE UPLIFT CONNECTIONS FOR 136 PLF OVER CONTINUOUS BEARING (5 PSF TC DEAD LOAD).

GABLE END SUPPORTS LOAD FROM 4' 0" OUTLOOKERS WITH 2' 0" OVERHANG, OR 12" PLYWOOD OVERHANG.

ATTACH EACH "L" BRACE WITH 10d NAILS.
* FOR (1) "L" BRACE: SPACE NAILS AT 2" O.C. IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.
** FOR (2) "L" BRACES: SPACE NAILS AT 3" O.C. IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.

"L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

GABLE VERTICAL PLATE SIZES

VERTICAL LENGTH	NO SPLICE
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 8"	2X4
GREATER THAN 11' 8"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR PEAK, SPLICE, AND HEEL PLATES.

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

REVIEWED
By julius lee at 12:00 pm, Jun 11, 2008

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR, SUITE 200, MADISON, WI 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

MAX. TOT. LD. 60 PSF

MAX. SPACING 24.0"

REF	ASCE7-02-GAB13015
DATE	11/26/03
DRWG	MITEK STD GABLE 15 E HT
-ENG	

ASCE 7-02: 130 MPH WIND SPEED, 30' MEAN HEIGHT, ENCLOSED, I = 1.00, EXPOSURE C

MAX GABLE VERTICAL LENGTH

2X4 GABLE VERTICAL SPACING	SPECIES	BRACE GRADE	NO BRACES	(1) 1X4 "L" BRACE *		(1) 2X4 "L" BRACE *		(2) 2X4 "L" BRACE **		(1) 2X6 "L" BRACE *		(2) 2X6 "L" BRACE **	
				GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B
24" O.C.	SPF HF	#1 / #2	3' 2"	5' 6"	5' 6"	6' 6"	6' 9"	7' 10"	8' 0"	10' 3"	10' 7"	12' 3"	12' 7"
		#3	3' 1"	4' 5"	4' 5"	5' 10"	5' 10"	7' 10"	7' 10"	9' 1"	9' 1"	12' 3"	12' 3"
		STUD	3' 1"	4' 5"	4' 5"	5' 10"	5' 10"	7' 10"	7' 10"	9' 1"	9' 1"	12' 3"	12' 3"
		STANDARD	2' 11"	3' 9"	3' 9"	6' 0"	5' 0"	6' 9"	6' 9"	7' 10"	7' 10"	10' 7"	10' 7"
	SP DFL	#1	3' 8"	5' 8"	5' 11"	6' 8"	7' 0"	7' 10"	8' 5"	10' 3"	11' 1"	12' 3"	13' 2"
		#2	3' 6"	5' 6"	5' 11"	6' 8"	7' 0"	7' 10"	8' 1"	10' 3"	11' 1"	12' 3"	13' 2"
		#3	3' 3"	4' 6"	4' 6"	6' 0"	6' 0"	7' 10"	8' 1"	9' 4"	9' 4"	12' 3"	12' 8"
		STUD	3' 3"	4' 6"	4' 6"	5' 11"	5' 11"	7' 10"	8' 0"	9' 3"	9' 3"	12' 3"	12' 8"
		STANDARD	3' 0"	3' 10"	3' 10"	5' 1"	5' 1"	6' 11"	6' 11"	8' 0"	8' 0"	10' 10"	10' 10"
16" O.C.	SPF HF	#1 / #2	3' 8"	6' 4"	6' 6"	7' 6"	7' 8"	8' 11"	9' 2"	11' 9"	12' 1"	14' 0"	14' 0"
		#3	3' 7"	5' 5"	5' 5"	7' 2"	7' 2"	8' 11"	8' 11"	11' 2"	11' 2"	14' 0"	14' 0"
		STUD	3' 7"	5' 6"	6' 5"	7' 2"	7' 2"	8' 11"	8' 11"	11' 1"	11' 1"	14' 0"	14' 0"
		STANDARD	3' 7"	4' 6"	4' 6"	6' 2"	6' 2"	8' 3"	8' 3"	9' 7"	9' 7"	12' 11"	12' 11"
	SP DFL	#1	4' 0"	6' 4"	6' 10"	7' 6"	8' 1"	8' 11"	9' 7"	11' 9"	12' 8"	14' 0"	14' 0"
		#2	3' 11"	6' 4"	6' 10"	7' 6"	8' 1"	8' 11"	9' 7"	11' 9"	12' 8"	14' 0"	14' 0"
		#3	3' 9"	5' 7"	6' 7"	7' 4"	7' 4"	8' 11"	9' 5"	11' 5"	11' 6"	14' 0"	14' 0"
		STUD	3' 8"	5' 6"	5' 6"	7' 3"	7' 3"	8' 11"	9' 5"	11' 4"	11' 4"	14' 0"	14' 0"
		STANDARD	3' 8"	4' 9"	4' 9"	6' 3"	6' 3"	8' 5"	8' 5"	9' 9"	9' 9"	13' 3"	13' 3"
12" O.C.	SPF HF	#1 / #2	4' 0"	6' 11"	7' 2"	8' 3"	8' 6"	9' 10"	10' 1"	12' 11"	13' 4"	14' 0"	14' 0"
		#3	3' 11"	6' 3"	6' 3"	8' 3"	8' 3"	9' 10"	9' 10"	12' 11"	12' 11"	14' 0"	14' 0"
		STUD	3' 11"	6' 3"	6' 3"	8' 3"	8' 3"	9' 10"	9' 10"	12' 10"	12' 10"	14' 0"	14' 0"
		STANDARD	3' 11"	5' 4"	5' 4"	7' 1"	7' 1"	9' 6"	9' 6"	11' 1"	11' 1"	14' 0"	14' 0"
	SP DFL	#1	4' 5"	6' 11"	7' 6"	8' 3"	8' 11"	9' 10"	10' 7"	12' 11"	13' 11"	14' 0"	14' 0"
		#2	4' 4"	6' 11"	7' 6"	8' 3"	8' 11"	9' 10"	10' 7"	12' 11"	13' 11"	14' 0"	14' 0"
		#3	4' 2"	6' 5"	6' 5"	8' 3"	8' 6"	9' 10"	10' 4"	12' 11"	13' 3"	14' 0"	14' 0"
		STUD	4' 2"	6' 4"	6' 4"	8' 3"	8' 5"	9' 10"	10' 4"	12' 11"	13' 1"	14' 0"	14' 0"
		STANDARD	4' 0"	5' 6"	5' 6"	7' 3"	7' 3"	9' 9"	9' 9"	11' 4"	11' 4"	14' 0"	14' 0"

BRACING GROUP SPECIES AND GRADES:

GROUP A:

SPRUCE-PINE-FIR		HEM-FIR	
#1 / #2	STANDARD	#2	STUD
#3	STUD	#3	STANDARD

DOUGLAS FIR-LARCH	SOUTHERN PINE
#3	#3
STUD	STUD
STANDARD	STANDARD

GROUP B:

HEM-FIR
#1 & BTR
#1

SOUTHERN PINE	DOUGLAS FIR-LARCH
#1	#1
#2	#2





REFER TO CHART ABOVE FOR MAX GABLE VERTICAL LENGTH.

GABLE TRUSS DETAIL NOTES:

LIVE LOAD DEFLECTION CRITERIA IS L/240.

PROVIDE UPLIFT CONNECTIONS FOR 180 PLF OVER CONTINUOUS BEARING (6 PSF TC DEAD LOAD).

GABLE END SUPPORTS LOAD FROM 4' 0" OUTLOOKERS WITH 2' 0" OVERHANG, OR 12" PLYWOOD OVERHANG.

ATTACH EACH "L" BRACE WITH 10d NAILS.
* FOR (1) "L" BRACE: SPACE NAILS AT 2" O.C. IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.
** FOR (2) "L" BRACES: SPACE NAILS AT 3" O.C. IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.

"L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

GABLE VERTICAL PLATE SIZES

VERTICAL LENGTH	NO SPLICE
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR PEAK, SPLICE, AND HEEL PLATES.

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

REVIEWED
By julius lee at 12:00 pm, Jun 11, 2008

JULIUS LEE'S CONS. ENGINEERS P.A.
1456 SW 4th AVENUE
DELRAY BEACH, FL. 33444-2161
No: 34869
STATE OF FLORIDA

MAX. TOT. LD. 60 PSF

MAX. SPACING 24.0"

REF	ASCE7-02-GAB13030
DATE	11/26/03
DWG	MITEK STD GABLE 30' E MT
-ENG	

TYPICAL ATTIC TRUSS BRACING



GABLE END TRUSS DETAIL



MINIMUM BC BRACING ON GABLE TRUSS. OTHER PERMANENT BRACING DESIGNS BY ARCHITECT OR EOR

TYPICAL ALTERNATE BRACING DETAIL FOR EXTERIOR FLAT GIRDER TRUSS



REVIEWED
By julius lee at 11:59 am, Jun 11, 2008

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

TYPICAL WALL GIRDER VERTICAL WEB BRACING DETAIL





JULIUS LEE'S
CONS. ENGINEERS P.A.
1456 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

PIGGYBACK DETAIL

TOP CHORD 2X4 #2 OR BETTER
BOT CHORD 2X4 #2 OR BETTER
WEBS 2X4 #3 OR BETTER

REFER TO SEALED DESIGN FOR DASHED PLATES.

SPACE PIGGYBACK VERTICALS AT 4' OC MAX.

TOP AND BOTTOM CHORD SPLICES MUST BE STAGGERED SO THAT ONE SPLICE IS NOT DIRECTLY OVER ANOTHER.

PIGGYBACK BOTTOM CHORD MAY BE OMITTED. ATTACH VERTICAL WEBS TO TRUSS TOP CHORD WITH 1.5X3 PLATE.

ATTACH PURLINS TO TOP OF FLAT TOP CHORD. IF PIGGYBACK IS SOLID LUMBER OR THE BOTTOM CHORD IS OMITTED, PURLINS MAY BE APPLIED BENEATH THE TOP CHORD OF SUPPORTING TRUSS.

REFER TO ENGINEER'S SEALED DESIGN FOR REQUIRED PURLIN SPACING.

THIS DETAIL IS APPLICABLE FOR THE FOLLOWING WIND CONDITIONS:

110 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, 1 MI FROM COAST CAT I, EXP C, WIND TC DL=5 PSF, WIND BC DL=5 PSF

110 MPH WIND, 30' MEAN HGT, FBC ENCLOSED BLDG, LOCATED ANYWHERE IN ROOF WIND TC DL=5 PSF, WIND BC DL=5 PSF

130 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, CAT II, EXP. C, WIND TC DL=6 PSF, WIND BC DL=6 PSF

FRONT FACE (E,*) PLATES MAY BE OFFSET FROM BACK FACE PLATES AS LONG AS BOTH FACES ARE SPACED 4' OC MAX.

JOINT TYPE	SPANS UP TO			
	30'	34'	38'	52'
A	2X4	2.5X4	2.5X4	3X5
B	4X8	5X8	5X8	5X8
C	1.5X3	1.5X4	1.5X4	1.5X4
D	5X4	5X5	5X5	5X8
E	4X8 OR 3X8 TRULOX AT 4' OC, ROTATED VERTICALLY			

ATTACH TRULOX PLATES WITH (6) 0.120" X 1.375" NAILS, OR EQUAL, PER FACE PER PLY. (4) NAILS IN EACH MEMBER TO BE CONNECTED. REFER TO DRAWING 160 TL FOR TRULOX INFORMATION.



WEB BRACING CHART	
WEB LENGTH	REQUIRED BRACING
0' TO 7'9"	NO BRACING
7'9" TO 10'	1x4 "T" BRACE. SAME GRADE, SPECIES AS WEB MEMBER, OR BETTER, AND 80% LENGTH OF WEB MEMBER. ATTACH WITH 8d NAILS AT 4" OC.
10' TO 14'	2x4 "T" BRACE. SAME GRADE, SPECIES AS WEB MEMBER, OR BETTER, AND 80% LENGTH OF WEB MEMBER. ATTACH WITH 16d NAILS AT 4" OC.



ATTACH PIGGYBACK WITH 3X8 TRULOX OR ALPINE PIGGYBACK SPECIAL PLATE.

* PIGGYBACK SPECIAL PLATE

ATTACH TEETH TO THE PIGGYBACK AT THE TIME OF FABRICATION. ATTACH TO SUPPORTING TRUSS WITH (4) 0.120" X 1.375" NAILS PER FACE PER PLY. APPLY PIGGYBACK SPECIAL PLATE TO EACH TRUSS FACE AND SPACE 4' OC OR LESS.



THIS DRAWING REPLACES DRAWINGS 634,016 634,017 & 847,045

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI. 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

REVIEWED
By julius lee at 11:59 am, Jun 11, 2008

JULIUS LEE'S
CONS. ENGINEERS P.A.
1400 SW 4th AVENUE
DELRAY BEACH, FL. 33444-2161

No: 34869
STATE OF FLORIDA

MAX LOADING
55 PSF AT 1.33 DUR. FAC.
50 PSF AT 1.25 DUR. FAC.
47 PSF AT 1.15 DUR. FAC.
SPACING 24.0"

REF PIGGYBACK
DATE 09/12/07
DRWG MITEK STD PIGGY
-ENG JL

VALLEY TRUSS DETAIL

TOP CHORD 2X4 SP #2 OR SPF #1/#2 OR BETTER.
BOT CHORD 2X3(*) OR 2X4 SP #2N OR SPF #1/#2 OR BETTER.
WEBS 2X4 SP #3 OR BETTER.

* 2X3 MAY BE RIPPED FROM A 2X6 (PITCHED OR SQUARE).

** ATTACH EACH VALLEY TO EVERY SUPPORTING TRUSS WITH: (2) 16d BOX (0.135" X 3.5") NAILS TOE-NAILED FOR FBC 2004 110 MPH, ASCE 7-02 110 MPH WIND OR (3) 16d FOR ASCE 7-02 130 MPH WIND. 15' MEAN HEIGHT, ENCLOSED BUILDING, EXP. C, RESIDENTIAL, WIND TC DL=5 PSF.

UNLESS SPECIFIED ON ENGINEER'S SEALED DESIGN, APPLY 1X4 "T"-BRACE, 80% LENGTH OF WEB, VALLEY WEB, SAME SPECIES AND GRADE OR BETTER, ATTACHED WITH 8d BOX (0.113" X 2.5") NAILS AT 6" OC, OR CONTINUOUS LATERAL BRACING, EQUALLY SPACED, FOR VERTICAL VALLEY WEBS GREATER THAN 7'9".

MAXIMUM VALLEY VERTICAL HEIGHT MAY NOT EXCEED 12'0".

TOP CHORD OF TRUSS BENEATH VALLEY SET MUST BE BRACED WITH:
PROPERLY ATTACHED, RATED SHEATHING APPLIED PRIOR TO VALLEY TRUSS INSTALLATION
OR
PURLINS AT 24" OC OR AS OTHERWISE SPECIFIED ON ENGINEERS' SEALED DESIGN
OR
BY VALLEY TRUSSES USED IN LIEU OF PURLIN SPACING AS SPECIFIED ON ENGINEERS' SEALED DESIGN.

*** NOTE THAT THE PURLIN SPACING FOR BRACING THE TOP CHORD OF THE TRUSS BENEATH THE VALLEY IS MEASURED ALONG THE SLOPE OF THE TOP CHORD.

++ LARGER SPANS MAY BE BUILT AS LONG AS THE VERTICAL HEIGHT DOES NOT EXCEED 12'0".

BOTTOM CHORD MAY BE SQUARE OR PITCHED CUT AS SHOWN.









SUPPORTING TRUSSES AT 24" OC MAXIMUM SPACING.

THIS DRAWING REPLACES DRAWING A105

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

«WARNING» TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI. 53719) AND WTCA (WOOD TRUSS COUNCIL AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

REVIEWED
By julius lee at 11:59 am, Jun 11, 2008

JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

TC LL	20	20	PSF	REF VALLEY DETAIL
TC DL	7	15	PSF	DATE 11/26/03
BC DL	5	5	PSF	DRWG VALTRUSS1103
BC LL	0	0	PSF	-ENG JL
TOT. LD.	32	40	PSF	
DUR.FAC.	1.25	1.25		
SPACING		24"		

TOE-NAIL DETAIL

TOE-NAILS TO BE DRIVEN AT AN ANGLE OF APPROXIMATELY THIRTY DEGREES WITH THE PIECE AND STARTED APPROXIMATELY ONE-THIRD THE LENGTH OF THE NAIL FROM THE END OF THE MEMBER.

PER ANSI/AF&PA NDS-2001 SECTION 12.4.1 - EDGE DISTANCE, END DISTANCE, SPACING: "EDGE DISTANCES, END DISTANCES AND SPACINGS FOR NAILS AND SPIKES SHALL BE SUFFICIENT TO PREVENT SPLITTING OF THE WOOD."

THE NUMBER OF TOE-NAILS TO BE USED IN A SPECIFIC APPLICATION IS DEPENDENT UPON PROPERTIES FOR THE CHORD SIZE, LUMBER SPECIES, AND NAIL TYPE. PROPER CONSTRUCTION PRACTICES AS WELL AS GOOD JUDGEMENT SHOULD DETERMINE THE NUMBER OF NAILS TO BE USED.

THIS DETAIL DISPLAYS A TOE-NAILED CONNECTION FOR JACK FRAMING INTO A SINGLE OR DOUBLE PLY SUPPORTING GIRDER.

MAXIMUM VERTICAL RESISTANCE OF 16d (0.162"X3.5") COMMON TOE-NAILS

NUMBER OF TOE-NAILS	SOUTHERN PINE		DOUGLAS FIR-LARCH		HEM-FIR		SPRUCE PINE FIR	
	1 PLY	2 PLIES	1 PLY	2 PLIES	1 PLY	2 PLIES	1 PLY	2 PLIES
2	197#	256#	181#	234#	156#	203#	154#	199#
3	296#	383#	271#	351#	234#	304#	230#	298#
4	394#	511#	361#	468#	312#	406#	307#	397#
5	493#	639#	452#	585#	390#	507#	384#	496#

ALL VALUES MAY BE MULTIPLIED BY APPROPRIATE DURATION OF LOAD FACTOR.





ALTERNATIVE CONDITION

THIS DRAWING REPLACES DRAWING 784040

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

"WARNING" TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

REVIEWED
By Julius lee at 11:59 am, Jun 11, 2008

JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

TC LL	PSF	REF	TOE-NAIL
TC DL	PSF	DATE	09/12/07
BC DL	PSF	DRWG	CNTONAIL1103
BC LL	PSF	-ENG	JL
TOT. LD.	PSF		
DUR. FAC.	1.00		
SPACING			

1/2" DIAMETER BOLT SPACING FOR LOAD APPLIED PARALLEL TO GRAIN.

* GRADE AND SPECIES AS SPECIFIED ON THE ALPINE DESIGN.

BOLT HOLES SHALL BE A MINIMUM OF 1/32" TO A MAXIMUM OF 1/16" LARGER THAN BOLT DIAMETER.

TYPICAL LOCATION OF 1/2" DIAMETER THRU BOLTS. BOLT QUANTITIES AS NOTED ON SEALED DESIGN MUST BE APPLIED IN ONE OF THE PATTERNS SHOWN BELOW.

WASHERS REQUIRED UNDER BOLT HEAD AND NUT



2X6 DETAIL



2X8 DETAIL

THIS DRAWING REPLACES DRAWING A628.016

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

«WARNING» TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI. 53719) AND WTCA (WOOD TRUSS COUNCIL AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

REVIEWED
By julius lee at 11:59 am, Jun 11, 2008

JULIUS LEE'S CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

TC LL	PSF	REF	BOLT SPACING
TC DL	PSF	DATE	11/26/03
BC DL	PSF	DRWG	CNBOLTSP1103
BC LL	PSF	-ENG	JL
TOT. LD.	PSF		
DUR. FAC.			
SPACING			

TRULOX CONNECTION DETAIL

11 GAUGE (0.120" X 1.375") NAILS REQUIRED FOR TRULOX PLATE ATTACHMENT. FILL ROWS COMPLETELY WHERE SHOWN (⊕).

* NAILS MAY BE OMITTED FROM THESE ROWS.

THIS DETAIL MAY BE USED WITH SO. PINE, DOUGLAS-FIR OR HEM-FIR CHORDS WITH A MINIMUM 1.00 DURATION OF LOAD OR SPRUCE-PINE-FIR CHORDS WITH A MINIMUM 1.15 DURATION OF LOAD. CHORD SIZE OF BOTH TRUSSES MUST EXCEED THE TRULOX PLATE WIDTH.

TRULOX PLATE IS CENTERED ON THE CHORDS AND BENT BETWEEN NAIL ROWS.

REFER TO ENGINEER'S SEALED DESIGN REFERENCING THIS DETAIL FOR LUMBER, PLATES, AND OTHER INFORMATION NOT SHOWN.



MINIMUM 3X6 TRULOX PLATE





MINIMUM 5X6 TRULOX PLATE

TRULOX PLATE SIZE	REQUIRED NAILS PER TRUSS	MAXIMUM LOAD UP OR DOWN
3X6	9	350#
5X6	15	990#

REVIEWED
By julius lee at 11:58 am, Jun 11, 2008

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

THIS DRAWING REPLACES DRAWINGS 1,158,989 1,158,989/R 1,154,844 1,152,217 1,152,017 1,159,154 & 1,151,524

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

REF	TRULOX
DATE	11/26/03
DRWG	CNTRULOX1103
-ENG	JL

STRONG BACK DETAIL
SYSTEM-42 OR FLAT TRUSS



ALTERNATE DETAIL FOR STRONG BACK WITH VERTICAL NOT LINING UP



REVIEWED
By julius lee at 11:58 am, Jun 11, 2008

JULIUS LEE LICENSE NO. 34869 STATE OF FLORIDA PROFESSIONAL ENGINEER

JULIUS LEE'S
CONS. ENGINEERS P.A.
1456 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161

No: 34869
STATE OF FLORIDA

MULTIPLE-MEMBER CONNECTIONS FOR SIDE-LOADED BEAMS

Maximum Uniform Load Applied to Either Outside Member (PLF)

Connector Type	Number of Rows	Connector On-Center Spacing	Connector Pattern					
			Assembly A 	Assembly B 	Assembly C 	Assembly D 	Assembly E 	Assembly F 
			3½" 2-ply	5¼" 3-ply	5¼" 2-ply	7" 3-ply	7" 2-ply	7" 4-ply
10d (0.128" x 3") Nail[1]	2	12"	370	***280***	280	***245***		
	3	12"	555	***415***	415	***370***		
½" A307 Through Bolts[2][4]	2	24"	505	380	520	465	860	340
		19.2"	635	475	655	580	1,075	425
		16"	760	570	785	695	1,290	505
SDS ¼" x 3½"[4]	2	24"	680	***510***	510	***455***		
		19.2"	850	***640***	640	***565***		
		16"	1,020	***765***	765	***680***		
SDS ¼" x 6"[3][4]	2	24"				***455***	***465***	***455***
		19.2"				***565***	***580***	***565***
		16"				***680***	***695***	***680***
USP WS35 [4]	2	24"	480	***360***	360	***320***		
		19.2"	600	***450***	450	***400***		
		16"	715	***540***	540	***480***		
USP WS6 [3][4]	2	24"				***350***	***525***	***350***
		19.2"				***440***	***660***	***440***
		16"				***525***	***790***	***525***
3⅜" TrussLok[4]	2	24"	635	***475***	475	***425***		
		19.2"	795	***595***	595	***530***		
		16"	955	***715***	715	***635***		
5" TrussLok[4]	2	24"		***500***	500	***445***	***480***	***445***
		19.2"		***625***	625	***555***	***600***	***555***
		16"		***750***	750	***665***	***725***	***665***
6¾" TrussLok[4]	2	24"				445	620	445
		19.2"				555	770	555
		16"				665	925	665

(1) Nailed connection values may be doubled for 6" on-center or tripled for 4" on-center nail spacing.

(2) Washers required. Bolt holes to be 9⁄16" maximum.

(3) 6" SDS or WS screws can be used with Parallam® PSL and Microllam® LVL, but are not recommended for TimberStrand® LSL.

(4) 24" on-center bolted and screwed connection values may be doubled for 12" on-center spacing.

General Notes

- Connections are based on NDS® 2005 or manufacturer's code report.
- Use specific gravity of 0.5 when designing lateral connections.
- Values listed are for 100% stress level. Increase 15% for snow-loaded roof conditions or 25% for non-snow roof conditions, where code allows.
- ***Bold Italic*** cells indicate **Connector Pattern** must be installed on both sides. Stagger fasteners on opposite side of beam by ½ the required **Connector Spacing**.
- Verify adequacy of beam in allowable load tables on pages 16–33.
- 7" wide beams should be side-loaded only when loads are applied to both sides of the members (to minimize rotation).
- Minimum end distance for bolts and screws is 6".
- Beams wider than 7" require special consideration by the design professional.

Uniform Load Design Example



First, check the allowable load tables on pages 16–33 to verify that three pieces can carry the total load of 715 plf with proper live load deflection criteria. Maximum load applied to either outside member is 415 plf. For a 3-ply 1¾" assembly, two rows of 10d (0.128" x 3") nails at 12" on-center is good for only 280 plf. Therefore, use three rows of 10d (0.128" x 3") nails at 12" on-center (good for 415 plf).

Alternates:
Two rows of ½" bolts or SDS ¼" x 3½" screws at 19.2" on-center.

Point Load—Maximum Point Load Applied to Either Outside Member (lbs)

Connector Type	Number of Connectors	Connector Pattern: Assembly A	Assembly B	Assembly C	Assembly D	Assembly E	Assembly F
							
		3½" 2-ply	5¼" 3-ply	5¼" 2-ply	7" 3-ply	7" 2-ply	7" 4-ply
10d (0.128" x 3") Nail	6	1,110	***835***	835	***740***		
	12	2,225	***1,670***	1,670	***1,485***		
	18	3,335	***2,505***	2,505	***2,225***		
	24	4,450	***3,335***	3,335	***2,965***		
SDS Screws ¼" x 3½" or WS35 ¼" x 6" or WS6(1)	4	1,915	1,435(4)	1,435	***1,275***	***1,860(2)***	***1,405(2)***
	6	2,870	2,150 (4)	2,150	***1,915***	***2,785(2)***	***2,110(2)***
	8	3,825	2,870 (4)	2,870	***2,550***	***3,715(2)***	***2,810(2)***
3⅜" or 5" TrussLok™	4	2,545	1,910 (4)	1,910	***1,695***	***1,925(3)***	***1,775(3)***
	6	3,815	2,860 (4)	2,860	***2,545***	***2,890(3)***	***2,665(3)***
	8	5,090	3,815 (4)	3,815	***3,390***	***3,855(3)***	***3,550(3)***

(1) 6" SDS or WS screws can be used with Parallam® PSL and Microllam® LVL, but are not recommended for TimberStrand® LSL.

See General Notes on page 38

(2) 6" long screws required.

(3) 5" long screws required.

(4) 3½" and 3⅜" long screws must be installed on both sides.

Connections

4 or 6 or Screw Connection



8 Screw Connection



Nail Connection



There must be an equal number of nails on each side of the connection

Point Load Design Example



First, verify that a 3-ply 1¾" x 14" beam is capable of supporting the 3,000 lb point load as well as all other loads applied. The 3,000 lb point load is being transferred to the beam with a face mount hanger. For a 3-ply 1¾" assembly, eight 3⅜" TrussLok™ screws are good for 3,815 lbs with a face mount hanger.

MULTIPLE-MEMBER CONNECTIONS FOR TOP-LOADED BEAMS

1¾" Wide Pieces

- Minimum of three rows of 10d (0.128" x 3") nails at 12" on-center.
- Minimum of four rows of 10d (0.128" x 3") nails at 12" on-center for 14" or deeper.
- If using 12d–16d (0.148"–0.162" diameter) nails, the number of nailing rows may be reduced by one.
- Minimum of two rows of SDS, WS, or TrussLok™ screws at 16" on-center. Use 3⅜" minimum length with two or three plies; 5" minimum for 4-ply members. 6" SDS and WS screws are not recommended for use with TimberStrand® LSL. For 3- or 4-ply members, connectors must be installed on both sides. Stagger fasteners on opposite side of beam by ½ of the required connector spacing.
- Load must be applied evenly across entire beam width. Otherwise, use connections for side-loaded beams.

3½" Wide Pieces

- Minimum of two rows of SDS, WS, or TrussLok™ screws, 5" minimum length, at 16" on-center. 6" SDS and WS screws are not recommended for use with TimberStrand® LSL. Connectors must be installed on both sides. Stagger fasteners on opposite side of beam by ½ of the required connector spacing.
- Load must be applied evenly across entire beam width. Otherwise, use connections for side-loaded beams.
- Minimum of two rows of ½" bolts at 24" on-center staggered.



Multiple pieces can be nailed or bolted together to form a header or beam of the required size, up to a maximum width of 7"

6/12 PITCH
2'-0" O/H

ALL FLAT CEILINGS





BEARING HEIGHT SCHEDULE

PLATE1 "

NOTES:

1) REFER TO HIB 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING.) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED.

2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V10S FOR ALTERNATE BRACING REQUIREMENTS.

3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.

4) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.

5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.

6) SY42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.

7) ALL ROOF TRUSS HANGERS TO BE SIMPSON HTU26 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSS HANGERS TO BE SIMPSON THA422 UNLESS OTHERWISE NOTED.

8) BEAM/HEADER/LINTEL (HDR) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VOIDS ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS. REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Requested Delivery Date _____

Approved by _____ Date: _____

Builders FirstSource

Bunnell
PHONE: 904-437-3349 FAX: 904-437-3994

Jacksonville
PHONE: 904-772-6100 FAX: 904-772-1973

Lake City
PHONE: 386-755-6896 FAX: 386-755-7973

Sanford
PHONE: 407-322-0059 FAX: 407-322-5553

BUILDER: O'NEIL CONST.

LEGAL ADDRESS: BUNNELL ADDITION

MODEL: | REVISION:

SCALE: NTS

DATE: 6-30-09 | DRAWN BY: K.L.H. | JOB #: 308847