ABBREVIATIONS

Children of the Control of the Contr	A STATE OF THE STA
A/C	AIR COOLING UNIT
ADJ	ADJACENT
AFF	ABOVE FINISHED FLOOR
AHU	AIR HANDLING UNIT
ALUM	ALUMINUM
BLK	BLOCK
ВОТ	воттом
BRG	BEARING
CJ	CONTROL JOINT
CLG	CEILING
COL	COLUMN
CONC	CONCRETE
CONT	CONTINUOUS
CPT	CARPET
DIA	DIAMETER
DN	DOWN
DWG	DRAWING
EA	EACH
ELEC	ELECTRIC
EQ	EQUAL
FF	FINISH FLOOR
FTG	FOOTING
НВ	HOSE BIB
HDR	HEADER
HGT	HEIGHT
MAX	MAXIMUM
MIN	MINIMUM
NTS	NOT TO SCALE
OPNG	OPENING
SIM	SIMILAR
TYP	TYPICAL
VLT	VAULT
UNO	UNLESS NOTED OTHERWISE

area taulation 'a'

GARAGE	401 SF
FRONT PORCH	21 SF
REAR PATIO	72 SF
FLOOR 1 LIVING	1,607 SF
TOTAL LIVING	1,607 SF

area tabulation 'b'

Off Col tollo of the	12900	
GARAGE	401	SF
FRONT PORCH	108	SF
REAR PATIO	72	SF
FLOOR 1 LIVING	1,607	SF
TOTAL LIVING	1,607	SF

Covington

38' - 1607 - LH

INDEX

ARCHITECTURAL

CS COVER SHEET

EXTERIOR ELEVATIONS

SLAB PENETRATION PLAN

FLOOR PLANS

SECTIONS & DETAILS

INTERIOR DETAILS

ROOF PLAN

ELECTRICAL PLANS

CONSTRUCTION DETAILS

Florida Region (Frame)

REVISIONS

NUMBER	DATE	DESCRIPTION
01	03.04.202	Added Elevations A1& B1
02	06.14.21	Added outlet to O.Suite & noted outlets to meet 6' max from wall break & 12' max between outlet spacing at habitable rooms (E1.1)

Florida Building Code - Residential, 7th Edition (2020)
Provide temporary toilet facilities on site (Plumbing Sec 311.1).
Provide professional termite treatment of soil per R318. 3. Meet 2017 N.E.C. on all electrical work.

4. Provide passed compaction test to 95% density per R403.

5. Garage door(s) & windows to meet required wind load Sec R301.2.1.

6. All stairs, hand/guard rails to meet Sec R312. 7. Meet emergency egress requirements for bedrooms per R310.
3. Meet tempered glass requirements of Sec R308.4. Roof shingles must meet Section 905.
 Install smoke detectors in & outside sleeping rooms & at each level er Sec R314 & NFPA 72. Install carbon monoxide alarms per R315. 11. Install 4" high house address number of SFR, identification shall be legible & placed in a position that is visible from the street R319.

12. Meet all 2020 Florida Building Code Requirements.



BUILDING CODE COMPLIANCE

ALL CONSTRUCTION TO COMPLY WITH LOCAL CODES AND ORDINANCE CURRENTLY IN USE WITH THE LOCAL JURISDICTION.

PRODUCT: NEW SINGLE FAMILY DETACHED

OCCUPANCY CLASSIFICATION:

RESIDENTIAL R-3

CONSTRUCTION CLASS:

UNPROTECTED

CONSTRUCTION TYPE:

TYPE VB **EMERGENCY ESCAPE:**

> EGRESS OR RESCUE WINDOWS FROM SLEEPING ROOMS SHALL HAVE MINIMUM OF 5.7 SQUARE FEET

APPLICABLE CODES:

FOLLOW ALL APPLICABLE STATE AND LOCAL CODES. FLORIDA STATE SUPPLEMENTS AND AMENDMENTS.

2020 Florida Building Code, Residential, 7th Edition

2017 National Electrical Code, NFPA 70







Lot 043 Reserve at Jewel Lake 33-3S-16-02439-243 Lake City, FL 32024

Century Communities.

RELEASE DATE: 01.11.202 PLAN NUMBER: 33811607


COVINGTON


SHEET NO:

Keynotes | Legend


CORROSION RESISTANT ROOF TO WALL FLASHING AT ALL ROOF / WALL INTERSECTIONS. CORROSION RESISTANT SCREEN LOUVERED VENTS, SIZE AS NOTED.

BRICK WAINSCOT WITH SLOPED BRICK ROWLOCK CAP.
 STONE WAINSCOT WITH SLOPED STONE CAP.
 3 1/2" VINYL TRIM SURROUND





FRONT ELEVATION 'B1' 1/8" = 1'-0" @ 11x17 1/4" = 1'-0" @ 22x34










Lot 043 Reserve at Jewel Lake 33-3S-16-02439-243 Lake City, FL 32024


Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

SHE	MODEL:	PLAN NUMBER:
ET NO:	COVINGTON	33811607
	DRAWING TITLE:	RELEASE DATE:
_	EXTERIOR ELEVATIONS	01.11.2021

1.1-B1







Reviewed for Code Compliance HEET NO:

1/8" = 1'-0" @ 11x17

1/4" = 1'-0" @ 22x34

EXAMINER - LICENSE NO.

COVINGTON

Lot 043

Reserve at Jewel Lake 33-3S-16-02439-243

Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

RELEASE DATE: 01.11.2021


DRAWING TITLE:

EXTERIOR ELEVATIONS

33811607

GENERAL SLAB FOUNDATION NOTES

- PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL PLUMBING LOCATIONS.
- REFER TO EXTERIOR ELEVATIONS FOR BRICK/STONE LOCATIONS.
- GARAGE SLAB SHALL SLOPE TOWARD GARAGE DOOR OPENING.



SLAB PENETRATION PLAN 'B1' - Cul R42707 SHEET NO:

1/8" = 1'-0" @ 11x17 EXAMINER - LICENSE NO.

1/4" = 1'-0" @ 22x34

2.1-B

COVINGTON

Lot 043

Reserve at Jewel Lake 33-3S-16-02439-243 Lake City, FL 32024

Century Communities expressly reserves its common law

RELEASE DATE: 01.11.2021

SLAB PENETRATION PLAN

33811607

NOTES & LEGENDS

- 1. REFER TO ENGINEERING STRUCTURAL DRAWINGS (S-#) FOR BEARING WALL LOCATIONS AND FOR ALL BEAM & HEADER SIZES AND BEARING WALL LOCATIONS
- 2. ALL BEARING WALLS SHALL BE 16" O.C. WALL CONST. W/ DOUBLE TOP PLATE U.N.O.
- 3. ALL INTERIOR NON BEARING DOOR & WINDOW HEADERS SHALL BE (1) 2x4 OR (1) 2x6 W/VERTICAL CRIPPLERS @ 2'-0" O.C. TO MATCH WALL WIDTH UNLESS NOTED OTHERWISE.
- 4. (2) HOSE BIBS SHALL BE INSTALLED, LOCATION TO BE DETERMINED BY PLUMBING CONTRACTOR

OPTIONAL WINDOW 2X4 FRAME WALL

2X6 FRAME WALL BALLOON FRAME WALL


(PER STRUCTURALS)

KEYNOTES

- A1 GARAGE CEILING 5/8" TYPE X DRYWALL, VERTICAL SURFACE WALLS - 1/2" DRYWALL
- A2 22"X30" ATTIC ACCESS CONSTRUCTED WITH GYP. BD. (5/8" TYPE X
- AT GARAGE) WITH DOOR TRIM FRAME ACCESS SUPPORT A3 PROVIDE 6" MIN. FLAT CLG AT ANGLED CLG CONDITION
- A4 PULL DOWN STAIRS 25.5" x 54"
- A5 TEMPERED SAFETY GLASS PER IRC R308.4 A6 HOUSE TO GARAGE DOOR SEPARATION. PROVIDE APPROVED 20
- MINUTE RATED DOOR PER IRC 302.5.1 A7 A/C CONDENSER PAD. REFER TO SITE PLAN FOR FINAL LOCATION.
- VERIFY CONNECTION TO CONC. PAD W/ MANUF. SPECS A8 5/8" TYPE X DRYWALL AT ACCESSIBLE AREAS UNDER STAIRS
- D1 DRYWALL SOFFIT 12" DROP FROM CEILING LINE
- D2 DRYWALL SOFFIT 8" DROP FROM CEILING LINE
- K1 39" KNEE WALL WITH CAP PER SPECS
- K2 38" KNEE WALL WITH 1x CAP
- K3 46" KNEE WALL WITH CAP PER SPECS
- K4 34 1/2" KNEE WALL
- K5 42" KNEE WALL WITH 1x CAP K6 KNEE WALL WITH 1x CAP 42" ABOVE STAIR NOSING OR LANDING
- P1 30" X 60" SHOWER ENCLOSURE PER SPECS
- P2 30"X60" TUB PER SPECS
- S1 BOX STAIR WITH 38" KNEE WALL & 1X CAP
- S2 1X CAPPED STRINGER, TOP AT 3" ABOVE TREAD

area tabulation 'b'

area tone ar	0.1
GARAGE	401 SF
FRONT PORCH	108 SF
REAR PATIO	72 SF
FLOOR 1 LIVING	1,607 SF
TOTAL LIVING	1,607 SF



ATTIC VENT CALCULATION

ATTIC VENTILATION TO COMPLY W/ F.B.C RESIDENTIAL CODE. THE REQUIRED NET FREE VENTILATING AREA OF NOT LESS THAN 1/150 OF THE SPACE VENTILATED. AREA MAY BE REDUCED TO 1/300 PROVIDED THAT 50 PERCENT (BUT NOT MORE THAN 80%) OF THE REQ'D VENTILATING AREA IS PROVIDED IN THE UPPER PORTION OF THE SPACE TO BE VENTILATED AT LEAST 3 FEET ABOVE EAVE OR CORNICE WITH THE BALANCE OF THE REQ'D VENTILATION PROVIDED BY THE EAVE OR CORNICE VENTS.

MANUFACTURE SELECTED TO VERIFY THE NET FREE VENTILATION OF THE VENT PRODUCT SELECTED AND TO MAINTAIN THE REQUIRED VENTILATION.

DO NOT LOCATE VENTS ON ROOF PLANE(S) FACING STREET.


ROOF VENTIL	ATION CAL	CULATIONS	
ROOF AREA	2,388 SF		
TOTAL NET FREE AREA REQ'D (1 TO 300)	1146.2 SQ. IN.		
MAIN HOUSE INLET (SOFFIT) VENTILATION	160.0 LF x	6.4 SQ. IN / LINEAR FT =	1024.0 SQ. IN
POD VENT(S) REQUIRED WITH BASE HOUSE	8	VENTS AT 70.0 SQ. IN EA. =	560.0 SQ. IN.
LOWER VENTING PROVIDED (573.1 SQ. IN. REQ'D)	1024.0 SQ. IN		
UPPER VENTING PROVIDED (573.1 SQ. IN. REQ'D)	560.0 SQ. IN		

NOTE: TYPICAL VENTILATION INCLUDES:

SOFFIT VENTS

(AREA: 6.4 SQ. IN PER FOOT - VERIFY WITH MANUFACTURE) 2. LOMANCO 770* ATTIC VENT LOCATED 12" MIN. FROM RIDGE

(AREA: 70 SQ. IN. - VERIFY W MANUFACTURE)
*(1) LOMANCO 770D VENT AT 140 S.I. EA.CAN BE USED IN PLACE OF (2) 770 VENTS.







Lot 043 Reserve at Jewel Lake 33-3S-16-02439-243 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

mpliand Science		
MODEL:	PLAN NUMBER:	PERSONALARIS
COVINGTON	33811607	Century C
DRAWING TITLE:	RELEASE DATE:	Commu
ROOF PLAN	01.11.2021	nities.
		William .

6.1-B




110v RECEPTACLE SWITCH 110v SWITCHED RECEPTACLE \$3 3 WAY SWITCH 110v ABOVE COUNTER RECEPTACLE. GFI PROTECTED AT KITCHEN, BATH & LAUNDRY \$4 4 WAY SWITCH 110v DEDICATED RECEPTACLE FOR SECURITY/STRUCTURED WIRING PANEL WALL MOUNTED LIGHT GFI OUTLET LED DOWNLIGHT VP=VAPOR PROTECTED 220v RECEPTACLE DISCONNECT 110v FLOOR RECEPTACLE -CEILING FIXTURE OUTLET B = BRACE FOR FUTURE FAN • • CHIME H = HANGING P = OPT. PENDANT BATH EXHAUST FAN S SMOKE DETECTOR CEILING FAN PREWIRE WITH BRACING FOR FUTURE FAN C SMOKE/CARBON MONOXIDE ALARM

- PROVIDE ADDITIONAL EXTERIOR WEATHERPROOF RECEPTACLE WITHIN 15 FEET OF CONDENSING UNITS
- INSTALL GFCI AND ARC FAULT CIRCUIT IINTERRUPTER PROTECTION PER NEC SECTIONS 210.52G
- ALL GARAGE OUTLETS SHALL BE ON A DEDICATED CIRCUIT
- DWGS. ARE DIAGRAMMATICAL & INDICATE THE GENERAL ARRANGEMENT OF THE ELECTRICAL WORK. ANY DISCREPANCIES ON
- THE DOCUMENTS SHALL BE CALLED TO THE ARCHITECT'S ATTENTION PRIOR TO THE COMMENCEMENT OF WORK. DO NOT SCALE ELECTRICAL DRAWINGS.

KEYNOTES

- E1 ELECTRICAL PANEL PER SPECS
- E2 INSTALL OUTLET UNDER SINK FOR FUTURE DISPOSAL
- E3 DOOR CHIME TRANSFORMER LOCATION
- E4 MECHANICAL ROOMS TO INCLUDE KEYLESS LIGHT, PLUG AND DISCONNECT FOR AIR HANDLER
- E5 COACH LIGHT ONLY IF REQUIRED BY LOCAL MUNICIPALITY



FIRST FLOOR ELECTRICAL PLAN 'B'

1/8" " = 1'-0" @ 11x17

1/4" " = 1'-0" @ 22x34

Lot 043 Reserve at Jewel Lake 33-3S-16-02439-243 Lake City, FL 32024

Century Communities expressly reserves its common law copyright in these plans. Plans are not to be copied, reproduced, or changed, in any manner whatsoever, nor are they to be assigned to a third party without written permission and consent of Century Communities.

Money Money Market Mark	PLAN NUMBER:
COVINGTON	33811607
DRAWING TITLE:	RELEASE DATE:
FIRST FLOOR ELECTRICAL	01.11.2021

EXAMINER - LICENSE NO.

E1.1

REVISION SUMMARY DESIGNER REVISION DESCRIPTION **ABBREVIATIONS** P.T. Pressure Treated Above Rad. Radius Foot / Feet Req'd. Required A.F.F. Above Finished Floor Footing Rm. Room Galvanized General Contractor G.F.I. Ground Fault Interrupter S.F. Square Ft. B/Beam Bottom of Beam SHT Sheet S.L. Side Lights S.P.F. Spruce Pine Fir Height Sq. Square S.Y.P. Southern Yellow Pine K/Wall Kneewall Thik'n. Thicken L.F. Linear Ft T.O.B. Top of Block T.O.M. Top of Masonry T.O.P. Top of Plate Minimum Trans. Transom Window Typ. Typical U.N.O. Unless Noted Otherwise Mono Monolithic Electrica Vert. Vertical Elevation V.L. Versalam O.C. On center VTR Vent through Roof W Washer Expansion W/ With F.B.C. Florida Bldg. Code W.A. Wedge Anchor Fin. Fir. Finished Floor PLF Pounds per linear foot Wd Wood Flr. Floor Fdn. Foundation TERMITE SPECIFICATIONS SECTION R318 PROTECTION AGAINST TERMITES

CENTURY COMPLETE 38-1607 COVINGTON B LH

GENERAL STRUCTURAL NOTES

TERMITE PROTECTION SHALL BE PROVIDED BY REGISTERED TERMITICIDES, INCLUDING SOIL APPLIED PESTICIDES, BAITING SYSTEMS, AND PESTICIDES APPLIED TO WOOD, OR OTHER APPROVED METHODS OF TERMITE PROTECTION LABELED FOR USE A PREVENTIVE TREATMENT TO NEW CONSTRUCTION (SEE SECTION 202, REGISTERED TERMITICIDE). UPON COMPLETION OF THE APPLICATION OF THE TERMITE PROTECTIVE TREATMENT, A CERTIFICATE OF COMPLIANCE SHALL BE SSUED TO THE BUILDING DEPARTMENT BY THE LICENSED PEST CONTROL COMPANY THAT CONTAINS IE FOLLOWING STATEMENT: "THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. TREATMENT IS IN ACCORDANCE WITH RULES AND LAWS ESTABLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES."

CONSTRUCTION.

- METHOD OF TREATMENT SHALL BE APPROVED BY THE GOVERNING JURISDICTION "LIQUID BORATE OR BOR-A-COR" PRODUCT METHODS MUST BE DETERMINED AT PERMIT STAGE AND PRODUCT APPROVAL DATA MUST BE ON FILE WITH THE BUILDING DEPARTMENT.
- PRESSURE TREATED LUMBER THAT HAS BEEN CUT OR DRILLED THAT EXPOSES UNTREATED PORTIONS OF WOOD ARE REQUIRED TO BE FIELD TREATED TO PREVENT INSECT INFESTATION. OPTIONAL BORATE APPLIED TO ALL FRAME MEMBERS WITHIN 24" A.F.F.

-- NOTICE TO BUILDER AND ALL SUBCONTRACTORS--

I IS THE INTENT OF THE ENGINEER LISTED IN THE TITLEBLOCK OF THESE DOCUMENTS THAT THESE DOCUMENTS BE ACCURATE, PROVIDING LICENSED PROFESSIONALS CLEAR INFORMATION. EVERY ATTEMPT HAS BEEN MADE TO PREVENT ERROR. THE BUILDER AND ALL SUBCONTRACTORS ARE

- REVIEW ALL THE INFORMATION CONTAINED IN THESE DOCUMENTS, PRIOR TO THE COMMENCEMENT OF ANY WORK. THE ENGINEER ARE NOT RESPONSIBLE FOR ANY PLAN ERRORS. OMISSIONS, OR MISINTERPRETATIONS UNDETECTED AND NOT REPORTED TO THE ENGINEER
- PRIOR TO CONSTRUCTION. SHALL STRICTLY OBSERVE ALL APPLICATION CODES DURING THE COURSE OF CONSTRUCTION INCLUDING ALL STATE, CITY, AND COUNTY BUILDING, ZONING, ELECTRICAL, MECHANICAL, PLUMBING AND FIRE CODES. CONTRACTOR SHALL VERIFY ALL CODE REQUIREMENTS PRIOR TO
- THE ARCHITECT / ENGINEER SHALL NOT BE RESPONSIBLE FOR SAFETY PROCEDURES, THE MEANS AND METHODS OF CONSTRUCTION, TECHNOLOGIES, OR THE CONTRACTION TO CARRY OUT THE WORK IN ACCORDANCE WITH THE DRAWINGS AND SPECIFICATIONS OR RELATED CODES.
- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESPONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS
- DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO
- ALL CONSTRUCTION MUST BE IN ACCORDANCE TO THE INFORMATION FOUND IN THESE DOCUMENTS. ANY QUESTIONS REGARDING THE INFORMATION FOUND IN THESE PLANS SHOULD BE DIRECTED TO OUR QUALITY ASSURANCE MANAGER AT 321-972-0491 IMMEDIATELY. NO BACK CHARGES WILL BE CONSIDERED FOR REIMBURSEMENT BY THE THE ENGINEER WITHOUT ADVANCED NOTIFICATION AND APPROVAL BY THE ENGINEER. PAYMENTS WILL BE MADE IN ACCORDANCE TO THE TERMS OF THE AGREEMENT.

CAST IN PLAE REINFORCED CONCRETE

- ALL CONCRETE SHALIAVE A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 2500 PSI (SLABS) 3000 PSI (COLUMNS AND BEAMS), A SLUMP OF 5" PLUS OR MINUS 1", AI HAVE 2 TO 5% AIR ENTRAINMENT, AND A MAXIMUM WATER/CEMENT RATIO OF 0.63 HOOKS SHALL BE PRIDED AT DISCONTINUOUS ENDS OF ALL TOP BARS OF BEAMS.
- HORIZONTAL FOOTINBARS SHALL BE BENT 25" AROUND CORNERS OR CORNER BARS WITH A 25" LAP PROVIDED EA WAY CONCRETE COVER M 3" WHEN EXPOSED TO EARTH OR 1 1/2" TO FORM U.N.O.
- FIBER MESH LENGTHALL BE 1/2" TO 2", DOSAGE AMOUNT SHALL BE FROM 1.0 TO 1.5 LBS PER CUBIC YARD IN ACCORDANCE WITH THE MANUFACTURER'S AT SHALL COMPLY WITH ASTM C1116 LE REINFORCING STL / STIRRUPS AND TIES SHALL BE NEW DOMES A615M GRADE 60 U.N REINFORCING FOR FOOTING SHALL BE SUPPORTED ON PRE-CAST CONCRETE PADS, STEEL WIRE OR PLASTIC SUPPORT. TOP REINFORCING SHALLE POSITIVELY SUPPORTED BY TEMPORARY STRINGERS. DOWELS FOR COLUMNS & FILLED CELLS SHALL BE SECURED IN
- PLACE BY USING ADDONAL CROSS- REINFORCING TIED TO FOOTING REINFORCING. SPLICES IN REINFORCING WHERE PERMITTED SHALL BE AS PER DETAIL MS05/D1.
 HIGH STRENGTH SIMON SET EPOXY-TIE WAS USED IN THE DESIGN OF THIS PRODUCT. IF CONTRACTORS WISH TO USE A DIFFERENT EPOXY, THEY

 4. SUBMIT SHOP DRAWINGS IS.
 MEMBERS, CONNECTION AND TOLERANCES.

 4. SUBMIT SHOP DRAWINGS IS.
 MEMBERS, CONNECTION AND TOLERANCES.
- WHERE PROJECT IS BE LOCATED IN KNOWN RADON GAS PREVALENT AREAS, APPENDIX "F" OF THE FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL IS TO BMPLEMENTED. F303.4 CONCRETE STRENGTH IN THESE AREAS ARE TO BE A MINIMUM OF 3000 P.S.I. THEREFORE, ANY AND ALL NOTES ON THESPLANS THAT INDICATE 2500 P.S.I. SHALL BE REPLACED WITH 3000 P.S.I. FOR THE CONCRETE STRENGTH.

MASONRY

- HOLLOW LOAD BEARS UNITS SHALL BE NORMAL WEIGHT, GRADE N, TYPE 2, CONFORMING TO ASTM C90-014, WITH A MINIMUM NET COMPRESSIVE STRENGTH OF 2000 F (fm = 2000 PSI)
- MORTAR SHALL BE TE "S", CONFORMING TO ASTM C270-14A. COARSE GROUT SHA CONFORM TO ASTM C476-10 WITH A MAXIMUM AGGREGATE SIZE OF 3/8" AND A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 3000 PSI SLIP 8" TO 11". CONTINUOUS MASONRY INSPECTIONS ARE REQUIRED DURING CONSTRUCTION GRADE 60 U.N.O. VEFCAL REINFORCEMENT SHALL BE AS NOTED ON THE DRAWINGS WITH THE CELLS FILLED WITH COARSE GROUT.
- GRADE 60 U.N.O. VERCAL REINFORCEMENT SHALL BE HELD IN POSITION AT THE TOP AND BOTTOM AND AT A MAXIMUM SPACING OF 192 DIA OR 10FT WHICH EVER IS LESSEINFORCING SHALL BE PLACED IN THE CENTER OF THE MASONRY CELL WITH MIN 1/2" CLEARANCE TO INSIDE FACE. REINFORCING STEELHALL BE LAPPED PER DETAIL MS05/D1, UNLESS OTHERWISE NOTED ON THE DRAWINGS. GROUT STOPS SHALLE PROVIDED BELOW BOND BEAM. PLASTIC SCREEN, METAL LATH STRIP OR CAVITY CAPS MAY BE USED TO PREVENT THE
- FLOW OF GROUT IN CELLS BELOW. THE USE OF FELT PAPER AS A STOP IS PROHIBITED. TEMPORARY BRACINAND SHORING OF WALL TO PROVIDE STABILITY DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TYPICAL FILLED CELIEINFORCING SIZE AND SPACING SHALL BE ABOVE AND BELOW ALL WALL OPENINGS
- DO NOT APPLY UNIFOM LOADS TO MASONRY WALLS FOR (3) DAYS AND NO CONCENTRATED LOADS FOR (7) DAYS. PER CODE ACI 318-14 CONSOLIDATE POUREXCEEDING 12" IN HEIGHT BY MECHANICAL VIBRATION, AND RECONSOLIDATE BY MECHANICAL VIBRATION AFTER INITIAL WATER LOSS AND SELEMENT HAS OCCURRED. GROUT SHALL BE FLUSH WITH TOP OF WALL.

- ALL EXTERIOR WOOLTUDS WALLS, BEARING WALLS, SHEAR WALLS, AND MISC. STRUCTURAL WOOD FRAMING MEMBERS, (I.E. BLOCKING OR GABLE END BRACING) SHALIE EITHER AS SPECIFIED IN PLAN OR IN DETAILS. IF CONFLICTS OCCUR BETWEEN PLAN AND DETAILS, THE STRONGEST MATERIAL SHALL BE; ED. AT A MINIMUM, ALL WOOD STRUCTURAL FRAMING MEMBERS SHALL BE SPF #2.
- ALL LUMBER SPECIFD ON DRAWINGS ARE INTENDED FOR DRY USE ONLY (MOISTURE CONTENT 19% OR LESS), U.N.O. ALL WATERPROOFING AND FIRE SAFETY SYSTEMARE THE RESPONSIBILITY OF THE CONTRACTOR AND ARE TO BE DESIGNED AND DETAILED BY OTHERS ANY WOOD FRAME IERIOR BEARING WALL STUDS THAT HAVE HOLES IN THE CENTER OF THE STUD UP TO 1" DIA. SHALL HAVE STUD PROTECTION SHIELDS. ALL HOLE3VER 1" IN DIA. FOR PLUMBING LINES, ETC. SHALL BE REPAIRED WITH SIMPSON HSS2 STUD SHOES, TYP., U.N.O. MANY OF THE NEW P.SSURE TREATED WOODS USE CHEMICALS THAT ARE CORROSIVE TO STEEL. IT IS THE CONTRACTOR'S RESPONSIBILITY TO
- VERIFY THE TYPE OFOOD TREATMENT AND TO SELECT APPROPRIATE CONNECTORS THAT RESIST CORROSION. FOR EXAMPLE, ACQ-C, ACQ-D, CBA-A OR CA-B REQUE HOT-DIPPED GALVANIZED OR STAINLESS STEEL FASTENERS. DOT SODIUM BORATE (SBX) DOES NOT. ALL EXPOSED WOODR WOOD IN CONTACT WITH EARTH OR CONCRETE TO BE PRESSURE TREATED. UNTREATED WOOD SLL NOT BE IN DIRECT CONTACT WITH CONCRETE OR MASONRY. SEAT PLATES SHALL BE PROVIDED AT BEARING LOCATIONS
- WITHOUT WOODEN TO PLATES. SEE PLAN FOR STUDACK AND BEAM NAILING PATTERNS
- ALL ENGINEERED LUSER TO HAVE THE FOLLOWING MIN VALUES U.N.O. PARALLAM COLLNS: 1.8E Fb = 2400 PSI
- MICROLAM (LVL)EAMS: 2.0E Fb= 2600 PS GLULAM BEAMS: P/SP 24F-V5 LAYUP (1.7E FB=2400 PSI) MIN. SEE PLAN NOTE FOR DITIONAL ROOF, WALL, SHEAR WALL AND FLOOR SHEATHING REQUIREMENTS ALONG W/ NAILING INFORMATION OTHERWISE: ROOF DECK: PLYOOD C-C/C-D, EXTERIOR OR OSB
- FLOOR SHEATHII: T&G A-C GROUP 1 APA RATED (48/24) SHEATHING SHALL FINISH FLUSH TO EXTERIOR WALL FACE. WALL SHEATHIN 1/8" STRUCTURAL I OSB EXPOSURE 1 OR 15/30" RATED OSB EXPOSURE 1 (SPECIFIC GRAVITY, G=0.50, MIN.). A MINIMUM 1/8" SPACE IS RECOMMENDEBETWEEN PANELS AT EDGE AND END JOINTS TO ALLOW FOR EXPANSION. PER R604.3 SHEATHING SHALL NOT BE USED AS WEATHER RESISNCE BARRIER UNLESS SPECIFIED.
- LATH AND LATH ATTAIMENTS SHALL BE OF CORROSION-RESISTANT MATERIALS. EXPANDED METAL OR WOVEN WIRE LATH SHALL BE ATTACHED TO WOOD SHEATHING WH 11/2" LONG, 11 GAGE NAILS HAVING A 7/16" HEAD, OR 1 1/2" LONG, 16 GAGE STAPLES, SPACED IN ACCORDANCE WITH ASTM C1062 OR C1787, OR AS OTRWISE APPROVED (REF. 2020 FBC-R-R703.7.1).

STRUCTURAL STEEL

- MATERIAL SPECIFICATIONS, WIDE FLANGE SECTIONS: ASTM A992, GRADE 50, Fy=50 KSI TUBE STEEL (HSS): ASTM A500, GRADE B, Fy = 46 KSI PIPE STEEL: ASTM F3125, TYPE EE OR S, Fy = 35 KSI ALL OTHER STRUCTURAL & MISC. STEEL: A36 Fy=36 KSI STRUCTURAL CONNECTIONS: ALL STRUCTURAL
- 2. STRUCTURAL BOLTS SMALLLER THAN 5/8" DIA. TO BE A307 THREADED ROD SHALL CONFORM TO A36 OR A307 ANCHOR BOLTS SHALL CONFORM TO ASTM F1554 ALL BOLTS CALAST IN CONCRETE: ASTM A36 OR ASTM A-307 SHOP AND FIELD WELDS: E70XX ELECTRODES STEEL REINFORCEMENT SHOP DRAWINGS TO BE PROVIDED TO ENGINEER OF RECORD BEFORE FABRICATION FOR REVIEW AND APPROVAL
- STRUCTURAL CONNECTIONONS: ALL STRUCTURAL BOLTS TO BE A325N U.N.O. ALL A325N BOLTS SHALL BE BROUGHT TO A "SNUG-TIGHT" CONDITION , AS DEFINED IN THE SPECIFICACATION. SLIP CRITICAL (SC) BOLTS MUST BE FULLY TENSIONED PER SPECIFICATION STRUCTURAL BOLTS SMALLER THAN 5/8" DIA. TO BE A307 THREADECED ROD SHALL CONFORM TO A36 OR A307 ANCHOR BOLTS SHALL CONFORM TO ASTM F1554 ALL BOLTS CAST IN CONCRETE: ASTM A36 OR ASTM A-307 S7 SHOP AND FIELD WELDS: E70XX ELECTRODES STEEL REINFORCEMENT SHOP DRAWINGS TO BE PROVIDED TO ENGINEER OF RECORD BEFORE FABRICATION FOR REVIEW AND APPROVAL. WELDED CONNECTIONS: ELECTRODES - E70XX UNO (LOW HYDROGEN). FILLET WELDS SHALL BE 3/16" UNO.
- STRUCTURAL STEEL SHALL LL RECEIVE SHOP COAT OF PRIMER (COLOR AS DIRECTED BY ARCHITECT) EXCEPT FOR AREAS WHICH WILL RECEIVE SPRAY-ON FIRE PROTECTICTION...
- 6. A CERTIFIED TESTING AGE SENCY SHALL BE ENGAGED TO PERFORM INDUSTRY STANDARD INSPECTIONS TO ENSURE CONFORMANCE WITH PLANS AND SPECIFICATIONS (IF PROVINCED). SUBMIT REPORTS TO ARCHITECT AND ENGINEER.

PRE ENGINEER RED WOOD TRUSSES

- 1. ALL PREFABRICATED WOO)OD TRUSSES SHALL BE SECURELY FASTENED TO THEIR SUPPORTING WALLS OR BEAMS WITH HURRICANE CLIPS OR
- ANCHORS PER STRUCTURIFICATION FOR PREFABRICATED WOOD TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF THE "NATIONAL DESIGN SPECIFICATION FOR PREFABRICATED WOOD TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF THE "NATIONAL DESIGN SPECIFICATION FOR PROPERTY PRODUCTS ASSOCIATION. STRESS-GRADE LUMBER A, AND ITS FASTENERS" AS RECOMMENDED BY THE NATIONAL FOREST PRODUCTS ASSOCIATION.
- 3. TRUSS MEMBERS AND COPONNECTIONS SHALL BE PROPORTIONED (WITH A MAXIMUM ALLOWABLE STRESS INCREASE FOR LOAD DURATION OF 25%) TO WITHSTAND THE LIVE LOALADS GIVEN IN THE NOTES AND TOTAL DEAD LOAD.
- BRIDGING FOR PRE-ENGININEERED TRUSSES SHALL BE AS REQUIRED BY THE TRUSS MANUFACTURER UNLESS NOTED ON THE PLANS. TRUSS ELEVATIONS AND S) SECTIONS ARE FOR GENERAL CONFIGURATION OF TRUSSES ONLY. WEB MEMBERS ARE NOT SHOWN, BUT SHALL BE
- DESIGNED BY THE TRUSS IS MANUFACTURER IN ACCORDANCE WITH THE FRAMING DESIGN LOADS:

 DESIGN SPECIFICATIONS F: FOR LIGHT WEIGHT METAL PLATE CONNECTED WOOD TRUSSES PER THE TRUSS PLATE INSTITUTE TPI LATEST EDITION. PRE-ENGINEERED WOOD T) TRUSSES SHALL BE DESIGNED BY THE MANUFACTURER IN ACCORDANCE WITH SPECIFIED LOADS AND GOVERNING CODES . SUBMITTALS SHALL INCLUIUDE TRUSS FRAMING PLANS AND DETAILS SHOWING MEMBER SIZES, BRACING, ANCHORAGE, CONNECTIONS, TRUSS LOCATIONS, AND PERMANENET BRACING AND/OR BRIDGING AS REQUIRED FOR ERECTION AND FOR THE PERMANENT STRUCTURE. EACH SUBMITTAL SHALL BE SIGNED AND SEFEALED BY A FLORIDA REGISTERED STRUCTURAL ENGINEER. SUBMIT 3 COPIES FOR REVIEW AND APPROVAL PRIOR TO
- 8. THE TRUSS MANUFACTURERER SHALL DETERMINE ALL SPANS WORKING POINTS, BEARING POINTS, AND SIMILAR CONDITIONS. TRUSS SHOP DRAWINGS SHALL SHOW ALL TRUSSESES, ALL BRACING MEMBERS, AND ALL TRUSS TO TRUSS HANGERS.

UPLIFT CONNECCTORS

1. UPLIFT CONNECTORS SUC JCH AS HURRICANE CLIPS, TRUSS ANCHORS AND ANCHOR BOLTS ARE ONLY REQUIRED ON MEMBERS IN WALLS THAT ARE EXPOSED TO UPLIFT OR LALATERAL FORCES. INTERIOR LOAD BEARING WALLS ARE NOT ALWAYS EXPOSED TO UPLIFT FORCES. THE MEMBERS OF THESE WALLS WOULD NOT OT NEED TO HAVE CONNECTORS APPLIED. PLEASE COORDINATE THE TRUSS ENGINEER FOR THE LOCATION OF THESE

FIELD REPAIR NOTES

- 1. MISSED "J" BOLTS FOR WOOOD BEARING WALLS MAY BE SUBSTITUTED WITH 1/2" DIA. EPOXY ANCHORS WITH 7" EMBEDMENT. SIMPSON "SET" EPOXY ADHESIVE BINDER FOLLOVOWING ALL MANUFACTURER'S RECOMMENDATIONS OR SIMPSON 1/2" TITEN HD BOLTS WITH MINIMUM 7" EMBEDMENT. SEE PLAN FOR EMBEDMENT DEDEPTH AT FLOOR STEPS.
- 2. FOR MISSED VERT. DOWELELS, DRILL A 3/4" DIAMETER HOLE 6" DEEP AT THE LOCATION OF THE OMITTED REBAR AND INSTALL A 32" LONG #5 BAR INTO THE EPOXY FILLED HOLE. USE A TWO PART EMBEDMENT EPOXY (SIMPSON HIGH STRENGTH EPOXY-TIE ANCHORING ADDESIVE) MIXED PER THE MANUFACTURER'S INSTRUCUCTIONS. ASSURE THAT ALL DUST AND DEBRIS FROM DRILLING ARE REMOVED FROM THE HOLE BY BRUSHING AND USING COMPRESSED AIR PRIOR TO APPLYING THE EPOXY. ALLOW THE EPOXY TO CURE TO THE MANUFACTURER'S SPECIFICATIONS, THEN FILL THE CELL IN THE NORMAL WAY DURINGNG BOND BEAM POUR.
- 3. FOR MORTAR JOINTS LESSS THAN 1/4", PROVIDE (1) #5 VERT. IN CONC. FILLED CELL EACH SIDE OF THE JOINT (BAR DOES NOT HAVE TO BE CONT. TO 4. MISSED LINTEL STRAPS FCFOR MASONRY CONSTRUCTION MAY BE SUBSTITUTED WITH (1) SIMPSON MTSM16 TWIST STRAP W/ (4) 1/4"x 21/4" TITENS TO

MASONRY AND (7)-10d NAILAILS TO TRUSS FOR UPLIFTS LESS THAN 860 LBS (USE (2) MTSM16 FOR UPLIFTS LESS THAN 1660#). IF CORNER STRAP IS

MISSED, CONTRACTOR IS IS TO INSTALL (2) SIMPSON HGAM10 W/ (4) 1/4" x 1 1/2" SDS SCREWS AND (5) 1/4" x 2 1/4" TITENS ONE EACH SIDE OF TRUSS.

NO MORE THAN 10 STRAPS PS MAY BE SUBSTITUTED OR NO MORE THAN 3 IN A ROW WITHOUT APPROVAL FROM EOR. IF GIRDER TRUSS CONNECTIONS ARE MISSED, CONTACT THE EOR FOR SUBSTITUTION. 6. IF MISSED, MSTAM36 OR M MSTAM40 STRAP IS MISSED FOR 2ND FLOOR JAMB STUD CONNECTION, CONTRACTOR MAY INSTALL SIMPSON HTT5 W/ (26) 16d x 21/2" NAILS AND 5/8" 5" ANCHOR BOLT SET IN SIMPSON HIGH STRENGTH EPOXY W/ MIN 6" EMBEDMENT AND MIN 3" EDGE DISTANCE. CONTACT EOR IF STRAPS ARE MISSED UNUNDER GIRDER JAMB STUD LOCATIONS.

STRUCTURAL DESIGN CRITERIA

CODE CRITERIA

- FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL
- FLORIDA FIRE PREVENTION CODE 7TH EDITION (2020)
- NFPA 70-17. NATIONAL ELECTRICAL CODES. (NEC 2017)
- BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE (ACI 318-14

- NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION 2018 EDITION

- AMERICAN SOCIETY OF CIVIL ENGINEERS: ASCE/SEI 7-1

TOP CHORD DI

BOTTOM CHORD LI

GENERAL ROOF LOADING

		SHINGLE ROOF (PSF)	METAL ROOF (PSF)	TILE ROOF (PSF)	HEAVY ROOF (PSF
	TOP CHORD LL TOP CHORD DL	20 10	20 10	20 15	20 25
1	BOTTOM CHORD LL* BOTTOM CHORD DL	0 10	0 10	0 10	0 10
1	TOTAL (PSF)	40	40	45	55
	BOTTOM CHORD LL (OPT) ATTICS W/ LIMITED STORAGE ATTICS W/ HEAVY STORAGE * ATTICS W/ NO STORAGE	20 50 10			

NOTE: LL REDUCTIONS ARE ALLOWED PER CODE BUT ONLY WITH WRITTEN APPROVAL FROM EOR OR INDICATED ON PLAN

GENERAL FLOOR LOADING

10 (PSF)

0 (PSF)

BOTTOWI CHORD DL	3 (PSF)		
SPECIAL FLOOR LOADING			
GAME ROOM / READING ROOMS BALCONIES / DECKS BALCONIES OVER 100 SQ:FT LIGHT STORAGE GUARDRAILS AND HANDRAILS GUARDRAIL IN-FILL COMPONENTS STAIRS / NON SLEEPING ROOMS SLEEPING ROOMS LIBRARIES - STACK ROOMS HABITABLE ATTICS SERVED W/ FIXED STAIRS PASSENGER VEHICLE GARAGES	60 (PSF) 40(PSF) 100(PSF) 125(PSF) 200(LBS)(d) 50 (LBS)(f) 40 (PSF) 30 (PSF) 150(PSF) 30(PSF)	COMMENTS: d. A SINGLE CONCENTRATED LOAI APPLIED IN ANY DIRECTION AT A POINT ALONG THE TOP. f. BALUSTERS AND PANELS FILLER SHALL BE DESIGNED TO WITHST A HORIZONTALLY APPLIED NORI LOAD OF 50 POUNDS ON AN ARE EQUAL TO 1 SQ. FT.	
DEEL EC.	TION CD	ITEDIA	

ADJACENT TRUSSES

WIND LOADING CRITERIA WIND SPEED (ALLOWABLE 101.0 MPH **EXPOSURE CATEGORY BUILDING CATEGORY** BUILDING TYPE ENCLOSURE CLASSIFICATION ENCLOSED

INTERNAL PRESSURE COEFFICIENT NOTE: MEAN ROOF HEIGHT FOR TYPICAL SINGLE STORY HOME IS 15FT, AND FOF 2 STORY HOME IS 30FT

ASCE 7-16 WALL DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS

FOR MEAN ROOF HEIGHT ≤ 60 ft

WIND AREA (SQ FEET)	(+) VALUE DENOTES PRESSURE (-) VALUE DENOTES SUCTION		WIND PRESSURE AND SUCTION DIAGRAM
AREA	4	5	
10 - 19.99	(+) 25.5 (-) 26.6	B (+) 25.5 (-) 33.6	
20 - 49.99	C (+) 24.4 (-) 26.6	(+) 24.4 (-) 30.8	
50 - 99.99	(+) 22.8 (-) 23.8	(+) 22.8 (-) 28.0	5
> 100	G (+) 21.7 (-) 23.8	(+) 21.7 (-) 26.6	4 5 5 a
GAR	AGE DOORS*	SOFFIT	
9'-0" x 7'-0	" 16'-0" x 7'-0"		10 3
(+) 22.5 (-) 25.5	J (+) 21.7 (K	(+) 25.5 (-) 33.6	DIAGRAM

GENERAL PRESSURE NOTES

- MULTIPLY THE ABOVE PRESSURES BY 1.67 TO GET ULTIMATE WIND
- "a" = END ZONE IS ONLY WITHIN 4'-0" OF ALL EXTERIOR BUILDING CORNERS. INDICATED PRESSURES CAN BE INTERPOLATED FOR OTHER DOOR SIZES, OTHERWISE USE LOAD ASSOCIATED WITH THE LOWER EFFECTIVE AREAS. DESIGNATED AREAS WHERE THE ULTIMATE WIND SPEED IS 140 MPH OR GREATER AND IS CONSIDER TO BE IN THE WIND-BOURNE DEBRIS AREA. CONTRACTOR TO PROVIDED ADDITIONAL INFO AS REQUIRED FOR PERMITTING.

SHEET INDEX


S0	NOTES & SCHEDULES	9
S1	FOUNDATION PLAN B	
S2	ROOF FRAMING PLAN B	Reviews
SN	NOTES & SCHEDULES	Reviewed for Code Universal Engineeri
D1	FOUNDATION DETAILS	
D2	FRAMING DETAILS	EXAMINER - LICENSE N
D3	FRAMING DETAILS	LICENSEN
D4	FRAMING DETAILS	
D5	FRAMING DETAILS	







LOT 43 RESERVE AT JEWEL LAKE 33-3S-16-02439-243 LAKE CITY, FL 32024



FOUNDATION PLAN B

SSCALE: 1/4" = 1'-0" @ 22x34 SSCALE: 1/8" = 1'-0" @ 11x17

FOL	JNDATION LEGEND			
SYMBOL F#.#	DESIGN DESCRIPTION INDICATES CONCRETE FOOTING W/ MINIMUM SOIL BEARING CAPACITY OF 2000 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SN FOR DESIGN SPECIFICATIONS.		RY	
	INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE 1/8" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12'x12' SQUARE MAXIMUM		D S	
#"	INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET D1		CEI	
0'-0" FIN. FLR.	4" 2500 PSI CONC. SLAB W/ REINF. PER SO W/6 MIL VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES. SEE FOUNDATION SCHEDULE ON SN INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT, AND UPLIFT CONNECTION SCHEDULE ON SN FOR	THE ENGINEERS KNOW, EDGE, INFORMATION, AND PRICING A BLUDNE TRICING HANDS AND SECRETARIANS CONTAMED SHAWKINGS COMPT WHITH THE 200 FLORIGA BLUDNE AND SELECTION, EXPRESSES SHAWTHER AND SELL AND	igust 2 - 2021*	
2. SEE ARCH	CONNECTION TO SLAB TES: CORNER FRAMING PER DETAIL FM19/D1 HITECTURAL PLANS FOR ALL SLAB STEP F SHOW SHOWN WITHIN THESE DOCUMENTS.	TO THE BEST OF BELLEF, THE SY WITHIN THESE COOLE-RESUBLE SO ONLY FOR DRAWING PAGE OF FURTHER REVIEW FURTHER REVIEW FOR THE REVIEW FOR THE PREVIEW FOR THE PREV	DATE: Aussian sauce	
F	LAN KEY NOTES	l ses	Suite 200 2751 77-880-2304 tion No. 9161 FL # 56126 PE - FL #87864	
BUILDER NOTE: ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN		ENGINEERING ASSOCIATES 258 Southhall Lane, Suite 200 Maittand, FL 32751 O: 321-972-0491 F: 407-880-2304 Certificate Of Authorization No. 9161 CARL A. BROWN, PE - FL #56126 □ LUIS PABLO TORRES, PE - FL #87864		
	SIONAL FOR CLARIFICATION PRIOR TO MMENCEMENT OF CONSTRUCTION			
CVMDOL	WALL TYPE			
SYMBOL	DESIGN DESCRIPTION 2x_INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.			
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN			
	2x WOOD FRAME EXTERIOR WALL)7)20	
		PLAN NUMBER: 33811607	RELEASE DATE: 08.03.2020	


Reviewed for Code Compliance
Universal Engineering Science

SHEF
NO:

EXAMINER - LICENSE NO.


COVINGTON PLAN FOUNDATION PLAN


S1



ROOF FRAMING PLAN B

SCALE: 1/4" = 1'-0" @ 22x34 SCALE: 1/8" = 1'-0" @ 11x17





- GC/ BUILDER, SEE ARCH PLANS FOR ROUGH OPENING LOCATIONS AND ADDITIONAL INFORMATION REQ'D FOR DOOR/WINDOW
- INSTALLATION ALONG w/ DIMENSIONS NOT SHOWN ON FOUNDATION CONSULT W/ MANUFACTURER SPECIFICATIONS PRIOR TO POURING OR RECESSING DOOR SILLS OR SLIDING GLASS DOOR SILLS.
- NO WOOD STAKES PERMITTED IN FOUNDATION. PENDING SITE CONDITIONS, FOUNDATION MAY HAVE TO BE STEPPED
- DOWN SEE FM18/D1 FOR ADDITIONAL INFORMATION, G.C. TO DETERMINE STEP LOCATIONS, IF REQUIRED. STEEL BENDS AND LAP SPLICE SEE FM18/D1 AND FM19/D1 ALL EQUIPMENT AND/OR APPLIANCES HAVING AN IGNITION SOURCE
- SHALL BE ELEVATED A MIN OF 18". CONTRACTOR TO PROVIDE SUCH PLATFORM W/ EITHER MASONRY OR WOOD CONSTRUCTION ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 2000 PSF (SEE SOILS REPORT AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS). IF SOIL CONDITIONS ON THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY, THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF FOUNDATION DESIGN. SOIL
- COMPACTED IN 12" LIFTS TO AT LEAST 95% OF MAX, DRY DENSITY AS DETERMINED BY ASTM D 1557 (MODIFIED PROCTOR). 10. R.403.1.4 MINIMUM DEPTH: EXTERIOR FOOTINGS SHALL BE PLACED NOT LESS THAN 12 INCHES (305mm) BELOW THE FINISHED GRADE OF

TO BE FREE OF ORGANIC MATERIAL AND COHESIVE SOILS.

COLUMN SCHEDULE							
MARK	COLUMN SIZE	FIRST FLOOR BASE CONNECTIONS, SEE PLAN FOR SECOND FLOOR CONNECTIONS	UPLIFT(lb				
C1	(3) 2x #2 SPF	(4)12d TOENAILS	NO UPLIFT				
C2	(3) 2x #2 SPF	DTT2Z W/1/2" ATR & (8) 1/4" X 1 1/2" SDS SCREWS	1835				
C3	(3) 2x #1 SYP	(4)12d TOENAILS	NO UPLIFT				
C4	(3) 2x #1 SYP	DTT2Z w/ ½" ATR & (8) ¼" x 1½" SDS SCREWS	1835				
C5	4x4 P.T.#2 SYP POST	ABU44 w/ 5/8" ATR & (12)16d NAILS FIRST/SECOND FLOOR CONN.	G = 6665 U = 1782				
C6	6x6 P.T. #2 SYP POST	ABU66 w/ 5/8" ATR & (12)16d NAILS FIRST/SECOND FLOOR CONN.	G = 12000 U = 2070				
C7	8x8 P.T. #2 SYP POST	ABU88 w/(2) ⁵ / ₈ " ATR & (18)16d FIRST/SECOND FLOOR CONN.	G = 24335 U = 2088				
C8	3.5" x 3.5" P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDU5-SDS2.5 w/ 5%" ATR AND (14) 1/4"x21/2" SDS WOOD SCREWS	5080				
C9	3.5" x 5.25" P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDU5-SDS2.5 w/ 5/8" ATR AND (14) 1/4"x2 1/2" SDS WOOD SCREWS	5080				
C10	3.5" x 7" P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDU8-SDS2.5 w/ ⁷ / ₈ " ATR AND (20) ¹ / ₄ "x2 ¹ / ₂ " SDS WOOD SCREWS	6372				
C11	5.25" x 5.25" P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDU8-SDS2.5 w/ 7/8" ATR AND (20) 1/4"x2 1/2" SDS WOOD SCREWS	7082				

GENERAL COLUMN NOTES

2x4 STUDS,

Fb=2400 PSI

Fb=2400 PSI

5.25" x 5.25" P.L. 1.8E

5.25" x 7" P.L. 1.8E

- ALL STRUCTURAL LUMBER TO BE SYP#2 OR SPF#2 UNO ON PLAN. MINIMUM BOLT EMBEDMENT: 5" EMBEDMENT FOR 1/2" ATR. 6"

- REQ'D. SEE PLANS FOR BASE CONNECTION
- EMBEDMENT FOR 5/8" ATR. 8" EMBEDMENT FOR 7/8" ATR. P.L. COL. TO BRG DIRECTLY ON FOUNDATION. CUT BASE PLATE AS REQ'D. G.C. TO PROVIDE MOISTURE BARRIER IF COL. IS CALLED OUT ON 2ND FLOOR, THE BASE CONNECTION IS NOT VALUES HAVE BEEN REDUCED FOR NARROW FACE APPLICATION. CONNECTIONS SHALL BE INSTALLED ON NARROW OR WIDE FACE PER SIMPSON TC-SCLCLM 2x TOP PLATE WITH 2-ROWS

OF 12d @ 3" O.C., TYPICAL


HDU8-SDS2.5 w/ 1/8" ATR AND

HDU8-SDS2.5 w/7/8" ATR AND


(20) 1/4"x2 1/2" SDS WOOD SCREWS

(20) 1/4"x2 1/2" SDS WOOD SCREWS

7082





(2) 2x HEADER (U.N.O.) SEE FLOOR PLAN FOR MIBIZE. SEE HD/SN FOR CONNECTION INFO. IF HEADER IS WITHIN A WALV NO UPLIFT AS INDICATED IN THE WOOD BEARING WALL SCHEDULE, THE CINECTORS INDICATED IN WF09 & HD CAN BE IGNORED.



SEE FOUNDATION w/ 4 1/2" MIN. EMBEDMENT (IF AT STEP, - FOR FOOTING 7" MIN PAST LOWER SLAB.) ONLY IF -TYPE & SIZE INDICATED WOOD BEARING BEANG WALL DETAIL WALL OR SHEAR WALL, SEE PLAN FOR BEARING WALL / SHEAR WALL LOCATION GENERAL BEARING WALL NOTES ALL STRUCTURAL LUMBER DESIGNATED AS 9 SHALL BE SYP #2 AND ALL


- STRUCTURAL LUMBER DESIGNATED AS SPF ALL BE SPF #2 U.N.O. SEE FLOOR PLAN FOR WALL SIZE, ASSUME 25TUDS USED UNO CONNECTIONS TO BE INSTALLED TO EACH SO AS INDICATED CONTACT E.O.R. IF SP4's, SP6's OR SP8's COECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIMENTS. IF "BW" IS INDICATED ON SECOND FLOOR BA CONNECTION TO BE IGNORED. SEE WF06 AND FB06 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR
- 2ND FLOOR TO FIRST FLOOR CONNECTIONS.OTE: THIS IS FOR 2 STORY IF "SW" IS INDICATED ON PLAN THE WALL IS CISIDERED A SHEAR WALL AND REQUIRES MIN. 7/16" OSB / PLYWOOD w/8d N/S @ 4" O.C. IN FIELD AND EDGE
- TO ONE SIDE OF WALL. U.N.O. ON PLANS. ALL 2x EXTERIOR WALLS w/ SHEATHING ATTAIED PER NAILING SCHEDULE TB13/SN ACTS AS SHEAR WALLS, SEE PLAN A) WALL SECTIONS FOR STUD SPACING AND GRADE. ALL TOP PLATES AND SILL PLATES SHALL BE E SAME SPECIES AS THE WOO
- IF THE BEARING WALL IS INDICATED WITH THIW1 BW4 BW7 BW10 THESE WALLS ARE ONLY SUPPORTING THE FLOOR UD AND DO NOT HAVE UPLIFT THE STUDS ARE TOE NAILED TO THE PLATE A THE 2X PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN TIBEARING WALL SCHEDULE.





HEADER SCHEDULE

TALL THEN USE SIMPSON CS18 INSTALLED FROM BOTTOM OF HEADER, UP STUD, OVER TOP PLATE & BACK DOWN OTHER SIDE OF WALL TO BOTTOM OF HEADER -



OPENINGS GREATER THAN 4'-0" PROVIDE (2) 2x SILL PLATE w/ A35 CLIPS EACH SIDE. NO TOP PLATE SPLICES SHALL OCCUR OVER OR WITHIN 2 FEET OF HEADER.

HOLD DOWN CONNECTIONS NOT REQUIRED AT

BEARING WALLS WITHOUT UPLIFT.


SIMPSON LSTA30 / USP LSTA30 SIMPSON SP4 / USP SPT4 SIMPSON SP6 / USP SPT6 SIMPSON SP8 / USP SPT8 SIMPSON HTS20 / USP HTW20 SIMPSON SP2 / USP SPT24 SIMPSON A35 / USP MPA1 SIMPSON HTT4 / USP HTT45

TYPICAL FRAMING CONNECTIONS AT OPENINGS

BEAM SCHEDULE

MARK	BEAM SIZE	FASTENING SCHEDULE		
BM1>	(2) 2x8 SYP #2 w/ 7/16" OSB FLITCH PLATE	(2) ROWS OF 12d @ 12" O.C. TYP. EACH SIDE	NN PLAN	N N N N N N N N N N N N N N N N N N N
BM2	(2) 2x10 SYP #2 w/ 7/16" OSB FLITCH PLATE.		U.N.O. ON FRAMING PLAN	U.N.O. ON FRAMING PLAN
вмз	(2) 2x12 SYP #2 w/ 7/16" OSB FLITCH PLATE.		ш	£
BM4	(2) 1 3/4"x11 1/4" LVL 2.0E Fb=2600	(2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C TYP. EACH SIDE OR (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE) HTS20) HTW20
BM5	(2) 1 3/4"x11 7/8" LVL 2.0E Fb=2600		ON CONNECTOR (2) LSTA18 OR (2) HTS20 LUMN: (2) HETA16	CONNECTOR (2) LSTA18 OR (2) HTW20
BM6	(2) 1 3/4"x16" LVL 2.0E Fb=2600		SIMPSON CONNECTOR POST: (2) LSTA18 OR (2 CMU COLUMN: (2) HETA	USP CONNECTOR
ВМ7	(3) 2x10 SYP #2 w/ (2) 7/16" OSB FLITCH PLATES		SIMPS WOOD POST: CMU CC	WOOD POST:
BM8	(3) 1 3/4"x9 1/4" LVL 2.0E Fb=2600		WOO	WOOI
8M10				

SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.



SIMPSONN - CONNECTOR SCHEDULE CONNECTOR & FASTENERS SPF SYP H2.5A w/ (10)8d NAILS 535 565 H10A w/(18)10d x 1 1/2' 0A-2₄-2 w/(18)10d x 1 1/2" AT 2 PLY TRUSSES 930 1080 MTS S12 w/(14)10d x 1 1/2" (AT EXTERIOR 850 990 OC/CATION INCLUDE (3) 12d TOENAILS) 1TSTS20 w/(24)10d x 1 1/2" (AT EXTERIOR 1125 1310 LOCOCATION INCLUDE (3)12d TOENAILS HTS20 w/(48)10d x 1 1/2" (AT EXTERIOR 2250 2620 OCATION INCLUDE (6)12d TOENAILS FRAME TO (2) LGT2 w/ (32) 16d SINKERS & (14) 3500-M 4060-M MASONRY 1/4" x 2 1/4" TITEN (2 PLY TRUSS) FRAME R (28) 16d SINKERS FOR FRAME (EA) 2) LGT3 w/ (24) 1/4" x 3" SDS SCREWS 4730-M 6570-M MASONRY 4 & (8) 3/8" x 5" TITEN (2 PLY TRUSS) FRAME 5010-F 6960-F R (52) 16d SINKERS FOR FRAME (EA) HU41/410 OPT HUC410 w/ (18) 16d & (10) 10d BEAM HU46 OPT HUC46 w/ (6) 10d NAILS & MASONRY / (12) 1/4" x 2 3/4" TITEN (TO MAS.) U#1135 U#1135 FRAME OR (12) 16d & (6) 10d (FOR FRAME) SYP-F SYP-M H10S w/ (24) 10d x1 1/2" NAILS 770 910 T w/ (16) 1/4"x3" SDS WOOD SCREWS & ^{J4-}J4-SDS2.5 w/ (10) 1/4"x2 1/2" SDS WOOD 3285 4565 FRAME SCREWS & (1) 5/8" A.T.R. (2.(2) HTT5 w/ (52) 16d"x2 1/2" NAILS & 8750 10180 FRAME (2) 5/8"\$ A.T.R. (SEE NOTE #4)


GENERAL CONNECTOR NOTOTES: CONNECT ALL FLOOR THE TRUSSES TO INTERIOR BEARING WOOD WALLS / BEAMS W/ (2) 12d TOENAILS. ALL TRUSS TO TRUSS (S CONNECTIONS ARE PROVIDED BY TRUSS MANUFACTURER, U.N.O ON PLAN. G.C. MAY USE EITHER SIMPSON OR USP CONNECTIONS, SEE FRAMING PLAN FOR CONNECTOR CALL

FOR SINGLE PLY TRUS JSSES, SCAB ON FULL HEIGHT SYP #1 2"x4" TO TRUSS VERTICAL WEB w/ (2) ROWS OF 10d NAILS @ 3" O.C. C. STAGGERED.

MINIMUM A.T.R. EMBED EDMENT: 5" EMBEDMENT FOR 1/2" A.T.R. 6" EMBEDMENT FOR 5/8" A.T.R. 8"

MINIMAL CONNECTOTOR UNO ON FRAMING PLAN

- CONNECTION FOR ALL, LL ROOF / FLOOR TRUSSES TO MASONRY WALLS/ LINTELS/ ICF WALLS UNO ON CONNECTION AT 24" OF OR 32" O.C. PENDING VERTICALS FOR ALL FLOOR TRUSSES PARALLEL TO
- MASONRY WALLS SEE IE DETAIL FB12/D3 FOR MORE INFORMATION CONNECTION FOR ALL L HIP JACK (CORNER JACK) TO MASONRY WALLS/ICF WALLS/LINTELS CONNECTION FOR ALL L CONTINUOUS RIM BOARD TO TOP OF MASONRY AT 32" O.C MAX. W/ (2) AT EACH CORNER. G.C. TCTO VERIFY LOCATION DOES NOT CONFLICT w/TJI (IF APPLICABLE) LAYOUT CONNECT ALL FLOOR TO TRUSSES TO INTERIOR BEARING WOOD WALL/BEAMS W/ (2) 12d TOENAILS
- MINIMAL CONNECTOTOR UNO ON FRAMING PLAN CONNECTION FOR JAC, CK TRUSS TO WOOD WALL OR BEAM
- MINIMAL CONNECTOTOR UNO ON FRAMING PLAN CONNECTION FOR ALL L TRUSSES TO INTERIOR/EXTERIOR BEARING WOOD WALLS AND/OR BEAMS/AS



_ 15/32" OSB EXPOSURE 1 (2)- 2x TOP PLATE BEYOND SOLID 2x BLOCKING @ ALL SHEATHING (SEE SECTION X-X) **EXPOSURE 1** SHEATHING -2x STUDS BEYOND. SEE PLAN PROVIDE BLOCKING AS REQUIRED PER SECTION X-X IF NOT FULL HEIGHT SHEET FLOOR SYSTEM -2x4 P.T. BASE PLATE BEYOND SEE 2x RIBBON OR BLOCKING -BETWEEN FLOOR SYSTEM

HORIZONTAL WALL ELEVATION DIAGRAM AT ALL PANEL BLOCKING LOCATIONS SHALL BE MIN 2 X 4 #2 SPF TURNED VERTICAL W/ 7/16" FLITCH PLATE TO W/ (2) 12 TOENAILS EA. END. NAIL FLITCH PLATE TO VERTICAL W/ (4) 8d SPACING (2) 8d NAILS @ 3" O.C. STAGGERED FOR SHEATHING VERTICAL BLOCKING

DOUBLE NAIL EDGE SPACING

ALL SHEATHING MAY BE INSTALLED VERTICALLY OR HORIZONTALLY. ATTACH PER NAILING SCHEDULE. PANEL EDGES WILL NEED TO BE TTACHED TO STUD AND OR BLOCKING AT ALL EDGES. A MINIMUM 1/8" PACE IS RECOMMENDED BETWEEN PANELS AT EDGES AND END IOINTS TO ALLOW FOR EXPANSION. FASTENERS SHALL NOT ENETRATE SURFACE MORE THAN 1/8".

- A NAIL AT BASE 2 ROWS @ 4" O.C. w/ 8d COMMON NAIL.
- (B) NAIL AT TOP PLATE TWO ROWS @ 4" O.C. w/ 8d COMMON NAIL.
- (C) NAIL OPENING PERIMETER w/ (2) ROWS @ 4" O.C. w/ 8d COMMON NAIL.
- NAIL INTERIOR AT 6" O.C. w/ 8d COMMON NAIL.
- E STAGGER ALL VERTICAL JOINTS & NAIL @ 4" O.C. w/ 8d COMMON NAIL


SINGLE NAIL EDGE SPACING

- F PLYWOOD SPLICES @ HEADER NAIL SHEATHING TO HEADER W/ 8d COMMON NAILS @ 4" O.C. (2) ROWS @ TOP & BOTT.
- (2) 8d NAILS @ 3" O.C. TO EACH TRUSS END OR @ VERTICAL MEMBER IF

OTE: 8d NAILS FOR WALL SHEATHING MUST BE MIN .131" X 2 1/2". DO NOT OVERDRIVE NAILS: FASTENERS SHALL NOT PENETRATE URFACE MORE THAN 1/8"

TB13 WALL SHEATHING INSTALL & NAILING SCHEDULE






OVINGTON

PER PLAN TOP SPLICE 2x4 BEYOND AGAINST 2x8 STUD -AT ALL EXTERIOR CONDITIONS -ATTACH 2x STUDS TO TOP PLATE w/ 4-16d NAILS (2 ON EA SIDE) 2x8 STUDS, PER PLAN (SIM w/2x6 STUDS) - DOUBLE 2x8 PROVIDE 2x4 ON TOP OF 2x8 TO BLOCK OUT TOP PLATE ATTACH w/ 2-ROWS OF 12d @ 3" O.C. (SOLID BLOCK w/ 2x6) TOP PLATE TRANSITION OF 12d @ 3" O.C., TYPICAL PIPE OR DUCT W/ PENETRATION -THRU TOP PLATE W/ MORE THAN 50% OF TOP PLATE WIDTH INSTALL SIMPSON PSPN516Z

- 2x TOP PLATE WITH 2-ROWS w/12-16d NAILS TOP AND BOTTOM AT ALL EXTERIOR CONDITIONS -ATTACH 2X STUDS TO TOP PLATE W/ (4) 16d NAILS (2 ON EA. SIDE) TYP BOTTOM SPLICE OVER STUD SCALE: 3/4" = 1'-0" @ 22x34



2-2x4 LAMINATIONS w/

THE LAST LAMINATION

3-2x LAMINATION/ 2-ROWS OF -ROW OF STAGGERED 10d STAGGERED 16d MMON WIRE NAILS (ONE INTO EACH (TSIDE FACE) COMMON WIRE NAILS D = 0.148", L= 3") OR EQUAL (D = 0.162", L= 3-1/ OR EQUAL


SCALE: 3/8" = 1'-0" @ 11x17


4-2x LAMINATIONROVIDE 1/4" 9x51/2" LAG SCREWS AT ME SPACING AS


ADJACENT NAILS ARE DRIVEN FROM OPPCTE SIDES OF THE COLUMN. ALL NAILS PENETRATE AT LEAST 3/4" OF THIHICKNESS OF





REFER TO NDS SECTION 15.3 FOR ADDITIOL INFO.
















INTERIOR BEARING STEP-DOWN
SHEARWALL w/UPLIFT

SCALE: 3/4" = 1'-0" @ 22x34
SCALE: 3/8" = 1'-0" @ 11x17



UPLIFT VALUES - (DOUBLE SIDE PLYWOOD DOUBLES VALUE BELOW) SHEATHING I-SIDE - 860 LBS. PER TRUSS/JOIST/RAFTER





SCALE: 3/4" = 1'-0" SCALE: 3/8" = 1'-0" @ 11x17



WWW.FDSENG.COM

LOT 43 RESERVE AT JEWEL LAKE 33-3S-16-02439-243 LAKE CITY, FL 32024

> RELEASE DATE: 08.03.2020

PLAN NUMBER: 33811607