

## FBC APPROVED PRODUCT LIST

CATEGORY	SUBCATEGORY	MANUFACTURER & PRODUCT	APPROVAL NUMBER	MAX ALLOWABLE WINDSPEED (MPH)
STRUCTURAL COMPONENT	ROOF DECK	CARPORTS ANYWHERE, HAMPTON RIB ROOF PANEL	27402.1	180
STRUCTURAL COMPONENT	STRUCTURAL WALL	CARPORTS ANYWHERE, HAMPTON RIB WALL PANEL	27403.1	180
STRUCTURAL COMPONENT	STRUCTURAL WALL	CARPORTS ANYWHERE, RESI-LAP SIDING WALL PANEL	27403.2	180
PANEL WALLS	WALL LOUVER (FLOOD VENT)	FLOOD SOLUTIONS, LLC. FS & FS HEX	17888.1	N/A
EXTERIOR DOOR	SWINGING	ELIXER DOOR & METAL CO. SERIES 407 VINYL STEEL OUT-SWINGING REGULAR DOOR - BLANK (NO WINDOW)	17996.5	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC SERIES 3100: +42.5/-46	21450.3	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 3652: +36/-40	21460.6	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC., SERIES 780 MAX 3'x12' +35/-45	21460.8	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC, SERIES 750 MAX 6'x12' +19.9/-24.4	21460.9	140
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC. SERIES 750: MAX 8'x12' +24.4/-27	21460.10	160
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC., SERIES 750: MAX 10'x12' +19.4/-22.7	21460.11	140
EXTERIOR DOOR	SINGLE HUNG	CGI WINDOWS AND DOORS MODEL SH-4100A	23358.2	180
WINDOW	SINGLE HUNG	POCOHONTAS ALUMINUM COMPANY INC MODEL 100VS	12940	150

## POST/TRUSS MAXIMUM SPACINGS

ULTIMATE WINDSPEED (MPH)	STRUCTURE WIDTH (FT)	MAXIMUM POST/TRUSS SPACING (FT)
120-150	6-24	5.0
120-150	>24-30	4.0
>160	ALL	4.0
NOTES:		
1. NOT APPLICABLE FOR STRUCTURES WITH A MEAN ROOF HEIGHT OVER 20 FEET AND/OR ROOF PITCH STEEPER THAN 6:12		
2. APPLICABLE ONLY FOR ANY MATERIALS LISTED ON THE APPROVED PRODUCTS CHART AND FRAMING INDICATED IN THE GENERAL NOTES AND DETAILS		
3. 5' O.C. REQUIRES VERTICAL ROOF		

## GROUND ANCHOR LENGTH

(ALL BUILDING WIDTHS ≤ 30')		WIND SPEED (MPH)			
SOIL TYPE		≤ 140	145-155	160-170	175-180
VERY DENSE AND/OR CEMENTED SAND, COARSE GRAVEL, COBIES PRELOADED SILTS, CLAYS AND CORAL	30	30'	48	48	
MEDIUM DENSE COARSE SANDS, SANDY GRAVEL, VERY STIFF SILTS AND CLAYS	30	48'	48"	60"	
LOOSE TO MEDIUM DENSE SANDS, FIRM TO STIFF CLAYS, SILTS AND ALLUVIAL FILL	48	48	60"	60"	
LOOSE SANDS, FIRM CLAYS SILTS AND ALLUVIAL FILL	48	60'	60	60'	

NOTES:  
SUB-GRADE SOILS:  
-TO BE TERMITE TREATED PER SECTION 1816  
-ANY FILL DIRT COMPAKTED TO MINIMUM 95%

CONCRETE:  
-MINIMUM 2,500 PSI COMPRESSIVE STRENGTH AT 28 DAYS

-ALL OPEN AREAS OF CONCRETE OUTSIDE OF THE PROPOSED STRUCTURE SHALL BE DESIGNED TO SLOPE AWAY FROM THE STRUCTURE

REINFORCING STEEL (REBAR) REQUIREMENTS:

-MINIMUM GRADE 40 STEEL

-REBAR MAY BE BENT IN SHOP OR FIELD PROVIDED:

-THE REBAR IS BENT COLD

-THE DIAMETER OF THE BEND MEASURED ON THE INSIDE DOES NOT EXCEED 6-BAR DIAMETERS: AND

-REINFORCEMENT PARTIALLY EMBEDDED IN CONCRETE SHALL NOT BE FIELD BENT EXCEPT IN CASES WHERE DOWELS NEED TO BE BENT TO ALIGN WITH A VERTICAL CELL. THESE REBAR MAY BE BENT NOT TO EXCEED TO SLOPE OF 1" HORIZONTALLY TO 6" VERTICALLY.

-COVER:

-3" COVER MINIMUM WHERE THE CONCRETE IS CAST AGAINST AND PERMANENTLY IN CONTACT WITH SOIL OR WEATHER, AND 12" ELSEWHERE. REBAR EMBEDDED IN GROUTED CELLS SHALL HAVE A MINIMUM CLEAR DISTANCE OF 1" FOR FINE GROUT, AND 2" FOR COARSE GROUT BETWEEN REBAR AND ANY FACE OF A CELL. REBAR USED IN MASONRY WALLS SHALL HAVE A MASONRY COVER (INCLUDING GROUT) OF NOT LESS THAN 2" FOR MASONRY UNITS WITH FACE EXPOSED TO EARTH OR WEATHER, AND 12" FOR MASONRY UNITS NOT EXPOSED TO EARTH OR WEATHER.

GALVANIZATION:


-METAL ACCESSORIES FOR USE IN EXTERIOR WALL CONSTRUCTION AND NOT DIRECTLY EXPOSED TO WEATHER SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A 153, CLASS B-2. METAL PLATE CONNECTORS, SCREWS, BOLTS, AND NAILS EXPOSED DIRECTLY TO WEATHER SHALL BE STAINLESS STEEL OR HOT DIPPED GALVANIZED

THESE PLANS PERTAIN ONLY TO THE STRUCTURE, INCLUDING MAIN WIND FORCE RESISTING SYSTEM, COMPONENTS AND CLADDING, AND BASE RAIL ANCHORAGE. OTHER DESIGN ISSUES, INCLUDING BUT NOT LIMITED TO PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, FINISH FLOOR ELEVATION AND SLOPE, OR OTHER LOCAL ZONING REQUIREMENTS ARE THE RESPONSIBILITY OF OTHERS.


THESE STRUCTURES ARE DESIGNED AS NON-HABITABLE UTILITY/STORAGE BUILDINGS (RISK CATEGORY I) CAPABLE OF SUPPORTING DEAD LOAD OF THE STRUCTURE AND APPLICABLE LIVE AND WIND LOADS. IMPROVEMENTS NOT SPECIFICALLY ADDRESSED HEREIN, INCLUDING DOORS, WINDOWS, OR OTHER COMPONENTS NOT LISTED IN THE FBC APPROVED PRODUCTS LIST (THIS SHEET), AND NOT PROVIDED AND INSTALLED BY CARPORTS ANYWHERE, INC., WHICH EXERT ADDITIONAL LOADS ON THE STRUCTURE SHALL BE AT THE OWNER'S RISK. CARPORTS ANYWHERE NOR THE ENGINEERING DESIGN SHALL NOT BE RESPONSIBLE FOR STRUCTURAL DAMAGE OR FAILURE DUE TO THE APPLICATION OF ADDITIONAL LOADS.

BASE RAIL GROUND ANCHOR REQUIREMENTS: ONE WITHIN 6" OF EVERY POST LOCATION, AND BOTH SIDES OF OPENINGS WHERE BASE RAIL IS ABSENT. GROUND ANCHORS ARE NOT REQUIRED FOR CONCRETE FOOTING AND/OR CONCRETE SLAB CONSTRUCTION. SEE GROUND ANCHOR SCHEDULE (THIS SHEET) FOR SPECIFIC TYPE GROUND ANCHOR REQUIREMENTS.


ANY FILL DIRT NEEDED FOR THE FOUNDATION IS TO BE COMPAKTED TO 95%.




## CONCRETE FOUNDATION/BASE RAIL ANCHOR DETAIL




## CONCRETE FOUNDATION/BASE RAIL ANCHOR DETAIL



## GROUND ANCHOR BASE RAIL DETAIL



## POST TO BASE RAIL CONNECTION



## END POST TO BASE RAIL CONNECTION



### CODE INFORMATION


CODE VERSION	FBC 2023 8th Edition ASCE-7-22		
MANUFACTURER	CARPORTS ANYWHERE		
BUILDING TYPE	UTILITY STRUCTURE		
CONSTRUCTION TYPE	II-B		
RISK CATEGORY	1		
FIRE PROTECTION	NONE		
FIRE SUPPRESSION SYSTEM	NONE		
OCCUPANCY	UTILITY U		
BASIC WIND SPEED	V <sub>z</sub> : 120-180 mph		
EXPOSURE	B/C		
ENCLOSURE	ENCLOSED		
INTERNAL PRESSURE COEFFICIENT	+/- 0.18		
IMPORTANCE FACTOR	1.0		
ROOF DEAD LOAD	10PSF		
ROOF LIVE LOAD	20PSF OR 300lb POINT LOAD		
FLOOR DEAD LOAD	10PSF		
FLOOR LIVE LOAD	60PSF		
"R" RATING OF WALLS FLOOR, ROOF	N/A		
MODULES PER BUILDING	1		
HURRICANE PROTECTION USAGE	NO		
HURRICANE SHELTER USAGE	NO		
SQUARE FOOTAGE			
REVISIONS			
REV	DESCRIPTION	DATE	BY
1	HEADER SPLICE, FILL COMPACTION	8/16/22	MTB
2	PRODUCT #'s, NOTES	1/30/23	MTB
3	FOOTER HEIGHT	2/23/23	MTB
4	2023 FBC	2/19/23	MTB

Drawn By: MTB  
Date: 5/27/20  
Location: FLORIDA

### ENCLOSED GENERIC ENGINEERING

GENERAL NOTES

1. THIS BUILDING IS EXEMPT FROM THE FBC ENERGY CONSERVATION CODE PER SECTION C101.4.2.
2. ALL STEEL TUBING SHALL BE 60 KSI STEEL.
3. PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, AND/OR OTHER LOCAL CODE REQUIREMENTS ARE THE RESPONSIBILITY OF THE OWNER.
4. FIELD FRAMING CONNECTIONS SECURED WITH #12-14x3/4" SELF-DRILLING SCREWS.
5. ALL SHOP FRAMING CONNECTIONS ARE TO BE WELDED NO WELDING ON SITE. ALL WELDING DONE IN SHOP BY A CERTIFIED WELDER.
6. CONCRETE EXPANSION ANCHORS ARE TO BE MINIMUM 1/2"x6.5", 2,500LB TENSILE STRENGTH.
7. 14GA. FRAMING IS 2.5"x2.5" TUBE STEEL. NIPPLES ARE 2.25"x2.25" TUBE STEEL. 12GA. FRAMING IS 2.25"x2.25" TUBE STEEL. NIPPLES ARE 2.0"x2.0" TUBE STEEL.



TITLE: PRODUCTS, ANCHORING SPACING & CONCRETE DETAILS

Sheet: CA-1 OF 3



















**CODE INFORMATION**

CODE VERSION	FBC 2023 6th Edition, ASCE-7-22
MANUFACTURER	CARPORTS ANYWHERE
BUILDING TYPE	UTILITY STRUCTURE
CONSTRUCTION TYPE	II-B
RISK CATEGORY	I
FIRE PROTECTION	NONE
FIRE SUPPRESSION SYSTEM	NONE
OCCUPANCY	UTILITY U
BASIC WIND SPEED	Vw: 120-180mph
EXPOSURE	B/C
ENCLOSURE	ENCLOSED
INTERNAL PRESSURE COEFFICIENT	+/- 0.1B
IMPORTANCE FACTOR	1.0
ROOF DEAD LOAD	10PSF
ROOF LIVE LOAD	20PSF OR 300lb POINT LOAD
FLOOR DEAD LOAD	10PSF
FLOOR LIVE LOAD	50PSF
"R" RATING OF WALLS, FLOOR, ROOF	N/A
MODULES PER BUILDING	1
HURRICANE PROTECTION USAGE	NO
HURRICANE SHELTER USAGE	NO
SQUARE FOOTAGE	

**REVISIONS**

REV	DESCRIPTION	DATE	BY
1	HEADER SPLICE, FILL COMPACTION	8/16/22	MTB
2	PRODUCT #'S, NOTES	1/30/23	MTB
3	FOOTER HEIGHT	2/23/23	MTB
4	2023 FBC	2/19/23	MTB

Drawn By:	MTB
Date:	5/27/20
Location:	FLORIDA
ENCLOSED GENERIC ENGINEERING	
GENERAL NOTES	
1. THIS BUILDING IS EXEMPT FROM THE FBC ENERGY CONSERVATION CODE PER SECTION C101.4.2.	
2. ALL STEEL TUBING SHALL BE 50 KSI STEEL.	
3. PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, AND/OR OTHER LOCAL CODE REQUIREMENTS ARE THE RESPONSIBILITY OF THE OWNER.	
4. FIELD FRAMING CONNECTIONS SECURED WITH #12-14x3/4" SELF-DRILLING SCREWS.	
5. ALL SHOP FRAMING CONNECTIONS ARE TO BE WELDED, NO WELDING ON SITE, ALL WELDING DONE IN SHOP BY A CERTIFIED WELDER.	
6. CONCRETE EXPANSION ANCHORS ARE TO BE MINIMUM 1/2"x6.6", 2,500LB TENSILE STRENGTH.	
7. 14GA. FRAMING IS 2.5"x2.5" TUBE STEEL, NIPPLES ARE 2.0"x2.0" TUBE STEEL.	


**BOX EAVE RAFTER TO POST CONNECTION DETAIL**

**40' BOX EAVE RAFTER TO POST CONNECTION DETAIL**

**TRUSSSED RAFTER CONNECTION DETAIL**

**LEAN-TO TO TRUSS CONNECTION**

**NON-STRUCTURAL HEADER OR WINDOW RAIL TO POST DETAIL**

**SIDE WALL ROLL-UP DOOR/FRAME OUT HEADER DETAIL**

**ROOF PANEL CONNECTION VERTICAL SHEATHING OPTION**

**LEAN-TO TO TRUSS CONNECTION**

**HEADER CONNECTION DETAIL OPTION 1**

**SIDE WALL HEADER SPLICE DETAIL**

**HEADER CONNECTION DETAIL OPTION 2**

**POST TO TRUSS CONNECTION**

**HYDROVENT DETAIL (OPTIONAL)**

**INTERMEDIATE POST TO HEADER/BASE RAIL/OR WINDOW RAIL DETAIL**

**DOOR FRAME TO POST CONNECTION**

**ROLL-UP DOOR TO POST CONNECTION**

**EAVE & RIDGE REINFORCED ROOF PANEL CONNECTION (RIDGE 3r AND EAVE 3e)**

mph	Exp. B	Exp. C
120	n/r	n/r
150	n/r	30"
165	30"	24"
180	24"	12"


**CODE INFORMATION**

CODE VERSION	FBC 2023 8th Edition, ASCE-7-22
MANUFACTURER	CARPORTS ANYWHERE
BUILDING TYPE	UTILITY STRUCTURE
CONSTRUCTION TYPE	II-B
RISK CATEGORY	I
FIRE PROTECTION	NONE
FIRE SUPPRESSION SYSTEM	NONE
OCCUPANCY	UTILITY U
BASIC WIND SPEED	V <sub>at</sub> : 120-180mph
EXPOSURE	B/C
ENCLOSURE	ENCLOSED
INTERNAL PRESSURE COEFFICIENT	+/- 0.18
IMPORTANCE FACTOR	1.0
ROOF DEAD LOAD	10PSF
ROOF LIVE LOAD	20PSF OR 300lb POINT LOAD
FLOOR DEAD LOAD	10PSF
FLOOR LIVE LOAD	50PSF
'R' RATING OF WALLS FLOOR ROOF	N/A
MODULES PER BUILDING	1
HURRICANE PROTECTION USAGE	NO
HURRICANE SHELTER USAGE	NO
SQUARE FOOTAGE	

**REVISIONS**

REV	DESCRIPTION	DATE	BY
1	HEADER SPLICE, FILL COMPACTION	8/16/22	MTB
2	PRODUCT #'s, NOTES	1/30/23	MTB
3	FOOTER HEIGHT	2/23/23	MTB
4	2023 FBC	12/19/23	MTB

Drawn By: MTB






Date: 5/27/20

Location: FLORIDA

**ENCLOSED GENERIC ENGINEERING**

**GENERAL NOTES**

1. THIS BUILDING IS EXEMPT FROM THE FBC ENERGY CONSERVATION CODE PER SECTION C101.4.2.
2. ALL STEEL TUBING SHALL BE 50 KSI STEEL.
3. PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, AND/OR OTHER LOCAL CODE REQUIREMENTS ARE THE RESPONSIBILITY OF THE OWNER.
4. FIELD FRAMING CONNECTIONS SECURED WITH #12-14x3/4" SELF-DRILLING SCREWS
5. ALL SHOP FRAMING CONNECTIONS ARE TO BE WELDED, NO WELDING ON SITE. ALL WELDING DONE IN SHOP BY A CERTIFIED WELDER.
6. CONCRETE EXPANSION ANCHORS ARE TO BE MINIMUM 1/2"x5.5", 2,500LB TENSILE STRENGTH.
7. 14GA. FRAMING IS 2.5"x2.5" TUBE STEEL. NIPPLES ARE 2.25"x2.25" TUBE STEEL. 12GA. FRAMING IS 2.25"x2.25" TUBE STEEL. NIPPLES ARE 2.0"x2.0" TUBE STEEL.



## FBC APPROVED PRODUCT LIST

CATEGORY	SUBCATEGORY	MANUFACTURER & PRODUCT	APPROVAL NUMBER	MAX ALLOWABLE WINDSPEED (MPH)
STRUCTURAL COMPONENT	ROOF DECK	CARPORTS ANYWHERE, HAMPTON RIB ROOF PANEL	27402.1	180
STRUCTURAL COMPONENT	STRUCTURAL WALL	CARPORTS ANYWHERE, HAMPTON RIB WALL PANEL	27403.1	180
STRUCTURAL COMPONENT	STRUCTURAL WALL	CARPORTS ANYWHERE, RESI-LAP SIDING WALL PANEL	27403.2	180
PANEL WALLS	WALL LOUVER (FLOOD VENT)	FLOOD SOLUTIONS, LLC, FS & FS HEX	17588.1	N/A
EXTERIOR DOOR	SWINGING	ELIXER DOOR & METAL CO. SERIES 407 VINYL STEEL OUT-SWINGING REGULAR DOOR - BLANK (NO WINDOW)	17996.5	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 3100: +42.6/-45	21450.3	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 3652: +36/-40	21450.6	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 750: MAX 3'x12' +35/-45	21450.8	180
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 750: MAX 6'x12' +19.9/-24.4	21450.9	140
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 750: MAX 8'x12' +24.4/-27	21450.10	160
EXTERIOR DOOR	ROLL-UP	JANUS INTERNATIONAL GROUP LLC, SERIES 750: MAX 10'x12' +19.4/-22.7	21450.11	140
EXTERIOR DOOR	SINGLE HUNG	CGI WINDOWS AND DOORS MODEL SH-4100A	23358.2	180
WINDOW	SINGLE HUNG	POCOHONTAS ALUMINUM COMPANY INC. MODEL 100VS	12940	150

## POST/TRUSS MAXIMUM SPACINGS

ULTIMATE WINDSPEED (MPH)	STRUCTURE WIDTH (FT)	MAXIMUM POST/TRUSS SPACING (FT)
120-150	6-24	5.0
120-150	>24-30	4.0
>180	ALL	4.0

NOTES:  
1. NOT APPLICABLE FOR STRUCTURES WITH A MEAN ROOF HEIGHT OVER 20 FEET AND/OR ROOF PITCH STEEPER THAN 6:12.  
2. APPLICABLE ONLY FOR ANY MATERIALS LISTED ON THE APPROVED PRODUCTS CHART AND FRAMING INDICATED IN THE GENERAL NOTES AND DETAILS.  
3. 5' O.C. REQUIRES VERTICAL ROOF.

## GROUND ANCHOR LENGTH

(ALL BUILDING WIDTHS ≤ 30')		WIND SPEED (MPH)			
SOIL TYPE	≤ 140	145-155	160-170	175-180	
VERY DENSE AND/OR CEMENTED SAND, COARSE GRAVEL, COBBLES, PRELOADED SILTS CLAYS AND CORAL	30	30'	48"	48	
MEDIUM DENSE COARSE SANDS, SANDY GRAVEL, VERY STIFF SILTS AND CLAYS	30'	48'	48"	60"	
LOOSE TO MEDIUM DENSE SANDS, FIRM TO STIFF CLAYS, SILTS AND ALLUVIAL FILL	48	48"	60"	60"	
LOOSE SANDS, FIRM CLAYS SILTS AND ALLUVIAL FILL	48	60	60'	60"	

NOTES:  
SUB-GRADE SOILS.  
-TO BE TERMITE TREATED PER SECTION 1816  
-ANY FILL DIRT COMPAKTED TO MINIMUM 95%

CONCRETE:  
-MINIMUM 2,500 PSI COMPRESSIVE STRENGTH AT 28 DAYS

-ALL OPEN AREAS OF CONCRETE OUTSIDE OF THE PROPOSED STRUCTURE SHALL BE DESIGNED TO SLOPE AWAY FROM THE STRUCTURE

### REINFORCING STEEL (REBAR) REQUIREMENTS:

-MINIMUM GRADE 40 STEEL

-REBAR MAY BE BENT IN SHOP OR FIELD PROVIDED

-THE REBAR IS BENT COLD

-THE DIAMETER OF THE BEND MEASURED ON THE INSIDE DOES NOT EXCEED 6-BAR DIAMETERS: AND  
-REINFORCEMENT PARTIALLY EMBEDDED IN CONCRETE SHALL NOT BE FIELD BENT EXCEPT IN CASES WHERE DOWELS NEED TO BE BENT TO ALIGN WITH A VERTICAL CELL THESE REBAR MAY BE BENT NOT TO EXCEED TO SLOPE OF 1" HORIZONTALLY TO 6" VERTICALLY.

-COVER:

-3" COVER MINIMUM WHERE THE CONCRETE IS CAST AGAINST AND PERMANENTLY IN CONTACT WITH SOIL OR WEATHER, AND 12" ELSEWHERE. REBAR EMBEDDED IN GROUTED CELLS SHALL HAVE A MINIMUM CLEAR DISTANCE OF 1" FOR FINE GROUT, AND 1" FOR COARSE GROUT BETWEEN REBAR AND ANY FACE OF A CELL. REBAR USED IN MASONRY WALLS SHALL HAVE A MASONRY COVER (INCLUDING GROUT) OF NOT LESS THAN 2" FOR MASONRY UNITS WITH FACE EXPOSED TO EARTH OR WEATHER, AND 12" FOR MASONRY UNITS NOT EXPOSED TO EARTH OR WEATHER.

### GALVANIZATION:


-METAL ACCESSORIES FOR USE IN EXTERIOR WALL CONSTRUCTION AND NOT DIRECTLY EXPOSED TO WEATHER SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A 153, CLASS B-2. METAL PLATE CONNECTORS, SCREWS, BOLTS, AND NAILS EXPOSED DIRECTLY TO WEATHER SHALL BE STAINLESS STEEL OR HOT DIPPED GALVANIZED.

THESE PLANS PERTAIN ONLY TO THE STRUCTURE, INCLUDING MAIN WIND FORCE RESISTING SYSTEM, COMPONENTS AND CLADDING, AND BASE RAIL ANCHORAGE OTHER DESIGN ISSUES, INCLUDING BUT NOT LIMITED TO PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, FINISH FLOOR ELEVATION AND SLOPE, OR OTHER LOCAL ZONING REQUIREMENTS ARE THE RESPONSIBILITY OF OTHERS.


THESE STRUCTURES ARE DESIGNED AS NON-HABITABLE UTILITY/STORAGE BUILDINGS (RISK CATEGORY I) CAPABLE OF SUPPORTING DEAD LOAD OF THE STRUCTURE AND APPLICABLE LIVE AND WIND LOADS. IMPROVEMENTS NOT SPECIFICALLY ADDRESSED HEREIN, INCLUDING DOORS, WINDOWS, OR OTHER COMPONENTS NOT LISTED IN THE FBC APPROVED PRODUCTS LIST (THIS SHEET), AND NOT PROVIDED AND INSTALLED BY CARPORTS ANYWHERE, INC., WHICH EXERT ADDITIONAL LOADS ON THE STRUCTURE SHALL BE AT THE OWNER'S RISK. CARPORTS ANYWHERE NOR THE ENGINEERING DESIGN SHALL NOT BE RESPONSIBLE FOR STRUCTURAL DAMAGE OR FAILURE DUE TO THE APPLICATION OF ADDITIONAL LOADS.

BASE RAIL GROUND ANCHOR REQUIREMENTS: ONE WITHIN 6" OF EVERY POST LOCATION, AND BOTH SIDES OF OPENINGS WHERE BASE RAIL IS ABSENT. GROUND ANCHORS ARE NOT REQUIRED FOR CONCRETE FOOTING AND/OR CONCRETE SLAB CONSTRUCTION. SEE GROUND ANCHOR SCHEDULE (THIS SHEET) FOR SPECIFIC TYPE GROUND ANCHOR REQUIREMENTS.


ANY FILL DIRT NEEDED FOR THE FOUNDATION IS TO BE COMPAKTED TO 95%.





## CONCRETE FOUNDATION/BASE RAIL ANCHOR DETAIL



## CONCRETE FOUNDATION/BASE RAIL ANCHOR DETAIL



## GROUND ANCHOR BASE RAIL DETAIL



## END POST TO BASE RAIL CONNECTION



### CODE INFORMATION

CODE VERSION	FBC 2023 8th Edition ASCE-7-22
MANUFACTURER	CARPORTS ANYWHERE
BUILDING TYPE	UTILITY STRUCTURE
CONSTRUCTION TYPE	II-B
RISK CATEGORY	1
FIRE PROTECTION	NONE
FIRE SUPPRESSION SYSTEM	NONE
OCCUPANCY	UTILITY U
BASIC WIND SPEED	Vet: 120-180mph
EXPOSURE	B/C
ENCLOSURE	ENCLOSED
INTERNAL PRESSURE COEFFICIENT	+/- 0.18
IMPORTANCE FACTOR	1.0
ROOF DEAD LOAD	10PSF
ROOF LIVE LOAD	20PSF OR 300lb POINT LOAD
FLOOR DEAD LOAD	10PSF
FLOOR LIVE LOAD	50PSF
'R' RATING OF WALLS, FLOOR, ROOF	N/A
MODULES PER BUILDING	1
HURRICANE PROTECTION USAGE	NO
HURRICANE SHELTER USAGE	NO
SQUARE FOOTAGE	

### REVISIONS

REV	DESCRIPTION	DATE	BY
1	HEADER SPLICE, FILL COMPACTION	8/16/22	MTB
2	PRODUCT #'S, NOTES	1/30/23	MTB
3	FOOTER HEIGHT	2/23/23	MTB
4	2023 FBC	2/19/23	MTB

Drawn By: MTB  
Date: 5/27/20  
Location: FLORIDA  
ENCLOSED GENERIC ENGINEERING  
GENERAL NOTES  
1. THIS BUILDING IS EXEMPT FROM THE FBC ENERGY CONSERVATION CODE PER SECTION C101.4.2.  
2. ALL STEEL TUBING SHALL BE 60 KSI STEEL.  
3. PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, AND/OR OTHER LOCAL CODE REQUIREMENTS ARE THE RESPONSIBILITY OF THE OWNER.  
4. FIELD FRAMING CONNECTIONS SECURED WITH #12-14x3/4" SELF-DRILLING SCREWS.  
5. ALL SHOP FRAMING CONNECTIONS ARE TO BE WELDED. NO WELDING ON SITE. ALL WELDING DONE IN SHOP BY A CERTIFIED WELDER.  
6. CONCRETE EXPANSION ANCHORS ARE TO BE MINIMUM 1/2x6.5", 2,600LB TENSILE STRENGTH.  
7. 14GA. FRAMING IS 2.6"x2.6" TUBE STEEL. 12GA. FRAMING IS 2.25"x2.25" TUBE STEEL. NIPPLES ARE 2.0"x2.0" TUBE STEEL.

12/19/23  
M


Matthew T. Baldwin P.E.  
Florida License #64608

Sheet: CA-1 OF 3


PRODUCTS, ANCHORING, SPACING, & CONCRETE DETAILS

## CODE INFORMATION


CODE VERSION	FBC 2023 BH Edition ASCE-7-22		
MANUFACTURER	CARPORTS ANYWHERE		
BUILDING TYPE	UTILITY STRUCTURE		
CONSTRUCTION TYPE	II-B		
RISK CATEGORY	1		
FIRE PROTECTION	NONE		
FIRE SUPPRESSION SYSTEM	NONE		
OCCUPANCY	UTILITY U		
BASIC WIND SPEED	V <sub>3s</sub> : 120-180 mph		
EXPOSURE	B/C		
ENCLOSURE	ENCLOSED		
INTERNAL PRESSURE COEFFICIENT	+/- 0.18		
IMPORTANCE FACTOR	1.0		
ROOF DEAD LOAD	10 psf		
ROOF LIVE LOAD	20 psf or 300 lb point load		
FLOOR DEAD LOAD	10 psf		
FLOOR LIVE LOAD	50 psf		
'R' RATING OF WALLS, FLOOR, ROOF	N/A		
MODULES PER BUILDING	1		
HURRICANE PROTECTION USAGE	NO		
HURRICANE SHELTER USAGE	NO		
SQUARE FOOTAGE			
REVISIONS			
REV	DESCRIPTION	DATE	BY
1	HEADER SPLICE, FILL COMPACTION	8/16/22	MTB
2	PRODUCT #'s, NOTES	1/30/23	MTB
3	FOOTER HEIGHT	2/23/23	MTB
4	2023 FBC	12/19/23	MTB




BOX EAVE Rafter TO  
POST CONNECTION DETAIL




40' BOX EAVE Rafter TO  
POST CONNECTION DETAIL




TRUSSeD RAFTER  
CONNECTION DETAIL




LEAN-TO TO TRUSS  
CONNECTION




NON-STRUCTURAL HEADER OR  
WINDOW RAIL TO POST DETAIL




SIDE WALL ROLL-UP  
DOOR/FRAME OUT  
HEADER DETAIL



ROOF PANEL CONNECTION  
VERTICAL SHEATHING OPTION





LEAN-TO TO TRUSS  
CONNECTION




HEADER  
CONNECTION  
DETAIL  
OPTION 1


Drawn By: MTB  
Date: 5/27/20  
Location: FLORIDA  
ENCLOSED GENERIC ENGINEERING  
GENERAL NOTES  
1. THIS BUILDING IS EXEMPT FROM THE FBC ENERGY CONSERVATION CODE PER SECTION C101.4.2.  
2. ALL STEEL TUBING SHALL BE 50 KSI STEEL.  
3. PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, AND/OR OTHER LOCAL CODE REQUIREMENTS ARE THE RESPONSIBILITY OF THE OWNER.  
4. FIELD FRAMING CONNECTIONS SECURED WITH #12-14x3/4" SELF-DRILLING SCREWS.  
5. ALL SHOP FRAMING CONNECTIONS ARE TO BE WELDED. NO WELDING ON SITE. ALL WELDING DONE IN SHOP BY A CERTIFIED WELDER.  
6. CONCRETE EXPANSION ANCHORS ARE TO BE MINIMUM 1/2"x6.5", 2,500 LB TENSILE STRENGTH.  
7. 14GA. FRAMING IS 2.6"x2.6" TUBE STEEL. 12GA. FRAMING IS 2.25"x2.25" TUBE STEEL. NIPPLES ARE 2.0"x2.0" TUBE STEEL.




HEADER CONNECTION  
DETAIL OPTION 2




POST TO TRUSS  
CONNECTION




HYDROVENT DETAIL  
(OPTIONAL)




INTERMEDIATE POST TO  
HEADER/BASE RAIL/Or  
WINDOW RAIL DETAIL




DOOR FRAME TO POST  
CONNECTION



ROLL-UP DOOR TO  
POST CONNECTION



26 GAUGE ROOF SHEATHING SECURED WITH  
(1) #12-14x3" SELF-DRILLING SCREWS PER  
MANUFACTURER'S PRODUCT APPROVAL



1" 16 GAUGE FURRING CHANNEL  
48" O.C. MAX. SECURED WITH  
(2) #12-14x1" SELF-DRILLING  
SCREWS TO EACH RAFTER.

mph	Exp. B	Exp. C
120	n/r	n/r
150	n/r	30"
165	30"	24"
180	24"	12"

A Distance in inches  
EAVE & RIDGE REINFORCED ROOF PANEL CONNECTION  
(RIDGE 3r AND EAVE 3e)

DETAILS

Matthew T. Baldwin P.E.  
Florida License #64608

Sheet: CA-2 OF 3

12/19/23



#### CODE INFORMATION

CODE VERSION	FBC 2023 8th Edition, ASCE-7-22
MANUFACTURER	CARPORTS ANYWHERE
BUILDING TYPE	UTILITY STRUCTURE
CONSTRUCTION TYPE	II-B
RISK CATEGORY	I
FIRE PROTECTION	NONE
FIRE SUPPRESSION SYSTEM	NONE
OCCUPANCY	UTILITY U
BASIC WIND SPEED	Vut: 120-180mph
EXPOSURE	B/C
ENCLOSURE	ENCLOSED
INTERNAL PRESSURE COEFFICIENT	+/- 0.18
IMPORTANCE FACTOR	1.0
ROOF DEAD LOAD	10PSF
ROOF LIVE LOAD	20PSF OR 300lb POINT LOAD
FLOOR DEAD LOAD	10PSF
FLOOR LIVE LOAD	50PSF
'R' RATING OF WALLS, FLOOR, ROOF	N/A
MODULES PER BUILDING	1
HURRICANE PROTECTION USAGE	NO
HURRICANE SHELTER USAGE	NO
SQUARE FOOTAGE	

#### REVISIONS

REV	DESCRIPTION	DATE	BY
1	HEADER SPLICE, FILL COMPACTION	8/16/22	MTB
2	PRODUCT #'s, NOTES	1/30/23	MTB
3	FOOTER HEIGHT	2/23/23	MTB
4	2023 FBC	2/19/23	MTB

Drawn By: MTB  
Date: 5/27/20  
Location: FLORIDA

#### ENCLOSED GENERIC ENGINEERING

GENERAL NOTES

1. THIS BUILDING IS EXEMPT FROM THE FBC ENERGY CONSERVATION CODE PER SECTION C101.4.2.
2. ALL STEEL TUBING SHALL BE 50 KSI STEEL.
3. PLUMBING, ELECTRICAL, INGRESS/EGRESS, PROPERTY SET-BACKS, AND/OR OTHER LOCAL CODE REQUIREMENTS ARE THE RESPONSIBILITY OF THE OWNER.
4. FIELD FRAMING CONNECTIONS SECURED WITH #12-14x3/4" SELF-DRILLING SCREWS.
5. ALL SHOP FRAMING CONNECTIONS ARE TO BE WELDED, NO WELDING ON SITE. ALL WELDING DONE IN SHOP BY A CERTIFIED WELDER.
6. CONCRETE EXPANSION ANCHORS ARE TO BE MINIMUM 1/2"x5.5", 2,500LB TENSILE STRENGTH.
7. 14GA. FRAMING IS 2.6"x2.6" TUBE STEEL. NIPPLES ARE 2.26"x2.26" TUBE STEEL. 12GA. FRAMING IS 2.26"x2.26" TUBE STEEL. NIPPLES ARE 2.0"x2.0" TUBE STEEL.


CM

12/19/23


Matthew T. Baldwin P.E  
Florida License #64608

LAYOUT VIEWS


Sheet: CA-3 OF 3




TYPICAL POST/TRUSS FRAMING SECTION -  
BOX EAVE, UP TO & INCLUDING 24' WIDE




TYPICAL POST/TRUSS FRAMING SECTION -  
BOX EAVE, 24'-1" TO 30' WIDE




TYPICAL SIDE WALL FRAMING -  
BOX EAVE/BOW FRAME, HORIZONTAL ROOF




TYPICAL SIDE WALL FRAMING -  
BOX EAVE, VERTICAL ROOF




TYPICAL SIDE WALL ELEVATION -  
BOW FRAME, HORIZONTAL WALLS & ROOF



TYPICAL SIDE WALL ELEVATION -  
BOX EAVE, HORIZONTAL WALLS (OR LAP) & ROOF



TYPICAL END ELEVATION



TYPICAL SIDE WALL ELEVATION